



Model: **HNT Conversion**

5/25/21

Bill to Address

Ship to Address

Same as Billing

Customer Name: Texas City Police Department
Address: 9th Ave N
City: Texas City **ST:** TX **Zip:** 77590
Quote #: JJ210525A
PO #:

Customer Name: Texas City Police Department
Address: 9th Ave N
City: Texas City **ST:** TX **Zip:** 77590
Contact Name: Capt. Rex Spotted Bear
Phone #: 409-502-8871
Email: rspottedbear@texascitytx.gov

- Signed PO Signed Drawings Signed Quote
 Chassis Invoice Any misc. documents pertinent to order
 Handwritten Order

Ship VIA:

Body Price:	70,676.00
Freight:	0.00
Chassis Price:	
Total Price:	\$70,676.00

Salesman Name: Jeremy Johnson

TAG Plant: TAG D

Chassis Specifications

Year, Make, & Model: Ford E450 **GVWR:** 14,050
Wheelbase: 158" **CA:** 100" **Frame Width:** 42" **Engine:** gas
VIN#: Drop Ship Chassis Bought Chassis
Chassis ETA: **Dealer Name:**

General Specifications

Base Body:	Supreme body IA15084096
Negotiation Room	Permently seal back doors. Install plywood over back wall to make surface smooth. Cut down side benches to approx. 78" to fit into room. Lower backrest on wall (this may make it more difficult to hold seat cushions up). Build a bulkhead approx. 78" from back wall with a sliding pocket door. Cover walls and ceiling with gray carpet for sound deadening.
HVAC	Install a 13,500 btu cool and 55600 btu heat HVAC unit in the center of the ceiling of the negotiation room.
Table	Install a 48" long 36" high table against the back wall. Table should have fold down sides to assist in getting in and out.
Cabinets	Install 16" h x 12" deep upper cabinets with fold up doors on each side of room. The cabinets will be installed against the ceiling.
White boards	Install (3) 60" x 36" white boards in negotiation room. One on each side wall below cabinets and one on back wall just above the table.
Phone Jack	Install an interior/exterior phone jack in back wall directly under table. This is a phone jack only and P.D. must supply phone and equipment. Type of phone jack will be determined by current equipment.
Intelligence Room	Remove existing engine driven HVAC system including secondary compressor, condensor and evaporator. Remove existing cabinets in front of body.
Carpet	Cover walls and ceiling with gray carpet for sound dampening. This includes side door pocket
Work stations	Install a two person workstation on streetside starting at bulkhead wall. Install a laminated work top 24" deep x 30" high for two people. In stall a two drawer cabinet under work top in the center. Directly behind work top install a 18"w x 24" d x80" high single door cabinet with 4 adjustable shelves. Install 16" x 12" deep cabinet with fold up doors over work stations. Include (2) rollers chairs.
HVAC	Install a 13,500 btu cool and 55600 btu heat HVAC unit in the center of the ceiling of the intelligence room.
Power and Wiring	Note: 120 volt power will only work with generator working. All non-OEM 12 volt circuits will be connected to auxillary batteries.

Generator	Install a Onan 7K gas generator with remote start, hour meter and battery charger. Install in under body compartment on the streetside just in front of rear wheels
Invertor	Orion-Tr smart charger with auxilliary batteries and seperator. Install auxillary batteries in external box on streetside behind rear tires. Connect smart charger with land line through existing auto-eject.
Power center	Install a (8) breaker load center with breakers in the cabinet on the streetside near generator.
120 power & Outlets	Breaker 1 negotiation room A/C - Breaker 2 intelligence room A/C - breaker 3 work table - breaker 4 negotiation table - brealer 5 existing outside outlet - breaker 6 outlet in cabinet - breaker 7 outlets on streetside wall for future table and refridgerator - breaker 8 open
Wire Troughs	Run two wire troughs from negotiation table throught cabinet to front work stations. One trough will be for 120 volt and one will be for electronics.
Outlets & USB	Install (2) dual outlets with USB on work top. Install (2) dual outlets with USB on top of negotiation table. Install (1) dual outlet in cabinet. Install (1) dual outlet on back wall above negotiation table. Install (2) dual outlets on streetside wall behind stepwell. One for future refridgerator and one for future fold down desk. Re-Install outside outlets.
Monitor - Chargers	Install two wall mount monitors at the front work stations. Each work station will have a secure docking station for a laptop.
IT wiring	Run HDMI and CAT6 from each monitor and laptop station to rear negotiation table
Lighting	Install (2) 48" LED dimmable light bars on each side of the A/C in the front compartment. Light will have switch by side door. Install (2) LED dimmable light bars on each side of the A/C in the rear compartment with switch by the sliding door. Install (2) 24" LED dimmable light bars under upper cabinets over work stations with switch at the work station.
Radio	Re-intall existing radio on front wall over work station
Exterior - Camera	Install a back up camera with color monitor
Emergency & Scene Lights	Remove existing scene and emergency lights and replace with similar size LED lights. Install new lights in same locations so that the same wires can be used.
50" Smart Board TV	Install a 50" Smartboard television
Relief Area	Install a beverage counter wirectly behind stepwell with a mini freidge mounted underneath.
Fold Down Desk	Install a fold down desk from wall directly in front of bulkhead on the curbside.
Upper Cabinets	Install 16" h x 12" deep upper cabinets with fold up doors on the curbside wall against the ceiling. Run cabinets from door pocket to bulkhea.
Electric Awning	Install a 14" 12 volt electric awning on the curbside of the body.

Thank you for considering The Armored Group!

Jeremy Johnson
Global Fleet Manager/Tactical Vehicle Specialist
Office: (602) 840-2271
Cell: (817) 291-4956
Fax: (602) 840-6162
Email: jeremy@armoredcars.com

State and/or Federal taxes may be applicable at time of invoicing.

All prices are firm for 30 days from date of quotation.

Prices will be reviewed and are subject to revision after this date.

Payment terms are 50% down and balance due prior to shipment unless prior credit arrangements have been made.

Order Acceptance By: _____
Texas City Police Department

Date: _____