



Gowan, Inc.
5550 Airline Dr.
Houston, TX 77076-4998
Cell: 281-984-8142
Office: 713-696-5448
Fax: 713.237.9208
TACLA1 7399C, MPL 37572

Date: September 21, 2021

TO: City of Texas City
301 – 6th Street North (2nd Floor)
P.O. Drawer 2608
Texas City, Texas 77592-2608

Quote SER33-12244

ATTENTION: Glen Riske

Choice Partners 18/060JN-11

RE: Reymisa Cooling tower Library Replacement

Gowan will supply the labor, tools, equipment and supervision to replace current cooling tower with fiberglass Reymisa Tower w/external heat exchanger. The duration of this job will be 1 week from start to finish. During this time the library will be without cooling. The work will be scheduled and performed in coordination with customer needs. This work is to be performed during Gowan's normal operating hours

Scope includes:

- LOTO Electrical to cooling tower and Demo (by others)
- Isolate Valves to tower to prevent leakage
- Demo Tower and necessary piping
- Clean base for installation
- Set new steel base
- Set new exchanger, pump and tower on base
- Install ladder and railing on tower
- Install Pipping
- Hook pipping up to existing building loop
- Fill tower and loop
- Mount VFD for tower speed control
- Hook up electrical (by Others)
- Test operations
- Open valves and remove LOTO
- Turn A/C units on in Library and make sure they are all running
- Clean work Area.
- Dispose of old tower as per EPA regulations

Work Performed by Others:

- Electrical
- Crane (Gowan can assist in the rigging)

REYMSA COOLING TOWER

All-Fiberglass Construction, UV Gel-Coat Protection, Seamless Molded Basins

Hot Side: 200 GPM @ 100/90/80

Cold Side: 200 GPM @ 86/96/80

External Plate & Frame Heat Exchanger (SST)

(1) 5 hp DIRECT DRIVE Motor

(1) 3 hp Condenser Pump Motor

Vibration Cut Out Switch

Mechanical Brass Make-Up Valves

Galvanized Steel Safety Cage/Aluminum Ladder

Galvanized Steel Catwalk w/ Handrails

Steel Base Support System (galvanized)

15-Year Cooling Tower Structure Warranty; 7-Year Tower Motor Warranty

See Attached Submittals.

Base: \$99,452.00 Plus tax if applicable

Price:

Quote Asbestos or Mold Abatement/Containment

Excludes Hazardous Material Disposal or Removal

Quote Exclusions (if checked)

- Crane
- Insulation beyond point listed
- Detail Construction Drawings
- Patching, Painting, & Signage
- Electrical
- Any work not outlined above
- Other, Overtime Labor

With the signature below we hereby authorize *Gowan, Inc.* to proceed with the above described work.

The price is firm and will remain in effect for 10 days

GOWAN, INC.

Chris Lamb

TITLE _____

Chris Lamb
Account Executive

This proposal is "Regulated by The Texas Department of Licensing and Regulation", P. O. Box 12157, Austin, Texas 78711, 1.800.803.9202, 512.463.6599,