

ADDENDUM TO PIPELINE ROAD CROSSING PERMIT
SAN ANTONIO WATER SYSTEM
PRIMROSE OAKS SOUTH WATER MAIN REPLACEMENT

This attachment is provided as an addendum to the Atascosa County Application for a Pipeline Road Crossing Permit.

San Antonio Water System (SAWS), on the Primrose Oaks South Water Main Replacement project, proposes to install new upsized water mains to better serve the Primrose Oaks and Oaks South subdivisions. The following limited summary of work is proposed to be completed under this permit:

- Installation of a new 12-inch PVC water line along Stacey Road, between Post Oak Road and Oaks South Road, where it will connect to an existing 12-inch water line. The installation will be completed with open cut trenching.
 - o Due to telecommunications lines present in the right-of-way on both sides of the road, the proposed water line must be installed under the pavement.
 - o The water line is proposed to be located approximately 19 feet from the right-of-way edge and approximately 4-6 feet from the edge of pavement. The variation in the distance from edge of pavement is due to a meandering pavement edge.
- For pavement restoration, the pipeline trench will be restored with a Type B Hot Mix Asphaltic Concrete (HMAC) material with a depth of 12 inches.
- Following trench restoration, the full southern half of Stacey Road (the east-bound driving lane) will be restored with a chip seal surface treatment. All roadway impacts will be limited to this southern half of the roadway, as there are no services or other crossings.

Throughout the completion of this pipeline installation in Stacey Road, the County Commissioners and staff will be kept up to date on the schedule and progress.