

QUOTE # 25036

DATE: February 25, 2025

EXPIRATION DATE March 25, 2025

BILL Justin Vasquez
TO Atascosa County Jail
1108 Campbell Ave
Jourdanton, TX 78026
jvasquez@co.atascosa.tx.us
830-580-2595

SHIP SASL to
TO Deliver/Install

SALESPERSON	JOB	PAYMENT TERMS	DUE DATE
Brooks Quillian	Magistrate Video	50% down upon approval 50% due upon completion	Net 30

Scope of Work:

OVERVIEW

- Design and install a video system that captures the Judge and Inmate during Magistrate sessions with video and audio that will be sent to a display mounted in the Lobby area.
- When the Magistrate is not in session, the Lobby display will be utilized for digital signage.

SYSTEM

- Install a Samsung 65" UHD display in the lobby on the wall to the left of the entryway.
- Install a Panasonic AW-UE4WG 4K ePTZ, HDMI, USB, POE 111-degree camera on the ceiling in the Magistrate office at a suitable location that will capture all parties involved in the Magistrate session.
 - The camera will receive power and LAN via POE, and HDMI over fiber cable to the IDF.
 - The camera has a built-in stereo microphone to capture session audio.
- Install a NUC PC with Windows 11 in the IDF which will serve as a digital signage source for the lobby display.
- Install an Inogeni CAM230 USB/HDMI switcher in the IDF and connect the NUC and the Panasonic camera.
- Install an Inogeni remote interface located in the Magistrate office which will allow the selection of the live camera view or the NUC that is being displayed in the Lobby with the simple push of a button.
- Install a 5-Port Netgear unmanaged POE switch in the IDF to connect all devices and then to the facility LAN.

OTHER

- SASL will fully program all aspects of the system and provide training to the end user(s) to ensure proper operation of the equipment and successful execution of court sessions.
- IT personnel will be required for some aspects of the network configuration.
- Quote includes all equipment, tech materials, logistics, installation, and programming.

Equipment	\$5,604.00
Installation Services	\$3,130.00
Total	\$8,734.00

Signature of Approval

It All Starts With Design.

Bill of Materials:

Qty	Make	Model	Description
			VIDEO
DISPLAY			\$993.00
1	Samsung	BE65D-H	65In BED Series Commercial TV Crystal UHD Display, 300nit, 16/7
1	Chief	LSM1U	Large height adjustable fixed wall mount - Black
1	SnapOne	WB-200-2	WattBox® Power Conditioner 2 Outlets
CONTENT / CAMERA			\$1,994.00
1	Panasonic	AW-UE4WG	4K PTZ, HDMI, USB, POE 111 Deg Streaming PTZ - White
1	SASL	NUC	NUC14MKN15, Celeron N150, 16GB DDR5 Mem, 256GB PCIe Gen 4 2280 M.2 SSD, Windows 11 Pro
DISTRIBUTION / SWITCHING			\$2,156.00
1	Inogeni	CAM230	CAM230 USB and HDMI Multi-Camera Switcher
1	Inogeni	REMOTECAM	CAM230/CAM300 Remote Control Keypad
1	Inogeni	HD2USB3	HDMI to USB3 Capture Card
1	Liberty	DL-HD50C	Digitalinx Series HDMI 1.4 Extender Set Over POC w/ Loop Output, IR & CEC
1	Netgear	GS305P-300NAS	5PT GE UNMANAGED SWCH W/POE+
1	Kramer	CP-AOCH/60F-164	4K Active Optical UHD Pluggable HDMI Cable Plenum rated

Terms and Conditions

1. **Payment Schedule:** SASL intends to invoice per phase and project progress.
 - a. Down Payment to Order Materials – 50%
 - b. Remaining balance due upon completion – 50%
2. **Payment** is due within 30 days of the invoice date, unless otherwise noted. A delayed payment may result in project delays.
3. **Installation Labor and Materials:**
 - a. SASL Tech Materials will be provided, as required, to complete all audio and video connections, properly secure equipment, and wire management parts to provide a tidy cabling plant.
 - b. All work shall be installed as indicated and specified, and in accordance with acknowledged industry professional standards and practices, and manufacturer’s recommendations.
 - c. San Antonio Sound & Light shall provide all tools and equipment needed to install the systems.
4. **Non-Equipment Deliverables**
 - a. System Technical Drawings: One-Line Schematic, Rack Elevation, Mechanical Plate Details, AV Floor Plan, AV Reflected Ceiling Plan, Control Narrative and GUI Layouts (Per the Proposal scope of work)
 - b. System Equipment Tables with connection details, IP Address and Physical MAC address of all devices (As Required)
 - c. Control System Source Code: All uncompiled source code and programming software be made available to the customer. (As Required)
5. **Warranty and Insurance:**
 - a. San Antonio Sound & Light offers a one-year warranty on workmanship in all installed systems. After 1 year, much of the equipment may still be under the manufacturer’s warranty. In the event of equipment failure, SASL will assist in diagnosing the problem and getting any equipment sent for repair, but a service fee will be charged.
 - b. SASL carries worker’s compensation, auto and general liability insurance. Certificates are available on request.
 - c. Owner Furnished Equipment is not covered under SASL’s warranty.
6. **COVID Related price changes, delays, and increased shipping cost:** SASL is experiencing price increases and equipment delays from most manufactures. Global supply chain shortages often cause delays on equipment deliveries. SASL will always do our best to mitigate any potential price changes and will advise clients of any known delays as soon as possible. The shipping price in the proposal is an estimate. Final shipping charges will be applied to the invoice. Pricing on this quote will be honored up to the quote’s stated expiration date.

It All Starts With Design.

