

May 6, 2024

Work Order for contract by and between Burnet County, Precinct 4 & D.I.J. Construction

Work to be performed prior to September 30, 2024.

CR 421: +/-1.1 miles

Project scope: Continuous double yellow thermoplastic striping, yellow reflective centerline markers and one stop bar.

Quantities:

+/- 5,808 LF of double yellow striping at 0.70 cents/LF = \$4,065.60

Yellow Reflective markers (RPM) every 40' = 145 markers @ \$3.15 each = \$456.75

1 - White 24" stop bar @ \$100/each

Total for CR 421 approximately = \$4,622.35

TOTAL WORK ORDER NTE = \$4,500.00 out of 4920 "Contract Labor"

Joe Don Dockery
Burnet County Commissioner
Precinct 4
Cell 512-715-2911
jdockery@burnetcountytexas.org