

September 4, 2025

Work Order for contract by and between Burnet County, Precinct 4 & D.I.J. Construction

Work to be performed prior to September 30, 2025.

CR 411 North end: +/-5400 linear feet

Project scope: Continuous single yellow thermoplastic striping and yellow reflective centerline markers.

Quantities:

+/- 5,400 LF of single yellow striping at \$0.50/LF = \$2,700.00

Yellow Reflective markers (RPM) every 40' = 135 markers @ \$5.00 each = \$675.00

Total for CR 411 approximately = \$3,375.00

TOTAL WORK ORDER NTE = \$3,375.00 out of 4920 "Contract Labor"

Joe Don Dockery
Burnet County Commissioner
Precinct 4
Cell 512-715-2911
jdockery@burnetcountytexas.org