

December 15, 2025

Work Order for contract by and between Burnet County, Precinct 4 & D.I.J. Construction

Work to be performed prior to September 30, 2026.

CR 414: +/-14,000 linear feet

Project scope: Continuous double yellow thermoplastic striping, white shoulder striping, and yellow reflective centerline markers and 4 stop bars.

Quantities:

+/- 14,000 LF of double yellow striping at \$1.00/LF = \$14,000.00

+/- 28,000 LF of white shoulder striping at \$0.50/LF = \$14,000.00

Yellow Reflective markers (RPM) every 40' = 350 markers @ \$5.00 each = \$1,750.00

4 stop bars = 4 x 24" x 12' white stop bars = \$547.20

Total for CR 414 approximately = \$30,279.20

TOTAL WORK ORDER NTE = \$30,500 out of 4920 "Contract Labor"

Joe Don Dockery
Burnet County Commissioner
Precinct 4
Cell 512-715-2911
jdockery@burnetcountytexas.org