



Proposal for Burnet County IDF Clean Up

DESCRIPTION	MANUFACTURER	PART#	QTY	U
BACKBONE FIBER OPTICS				
Reroute & Dress In Existing Fiber	CCI	Labor	1	LOT
BACKBONE HPC COPPER				
Cable, 4 pr, UTP, Cat 6A, CMP, Blue	Panduit	PUP6XHD04BU-G	2,000	FT
Patch Panel, 24 Port, Flat, Modular, Black	Panduit	CPPL24WBLY	4	EA
Data Jack, Cat 6A, 10Ghz, T568A/B, Black (PP)	Panduit	CJ6X88TGBL	96	EA
HORIZONTAL UTP COPPER				
Patch Panel, 24 Port, Flat, Modular, Black	Panduit	CPPL24WBLY	3	EA
Data Jack, Cat 6A, 10Ghz, T568A/B, Black (PP)	Panduit	CJ6X88TGBL	78	EA
RACK AND WIRE MANAGEMENT				
Runway, Ladder, Radius Drop, Black	CPI	12100-718	2	EA
Runway, Ladder, Elevation Kit, Black	CPI	10506-716	3	EA
Runway, Wall Angle Support Kit, 18"W, Black	CPI	11421-718	2	EA
Runway, Ladder, Splice Kit, Butt, Black	CPI	11301-701	2	EA
Runway, Ladder, Ground Kit	CPI	40164-001	2	EA
Runway, Ladder, Universal, 18", Black Tube	CPI	10250-718	3	EA
Rack & Stack Existing Equipment From Old Rack To New Rack	CCI	Labor	1	LOT
GROUNDING				
Cable, Ground, #6 AWG, Stranded, Green	WIRE	THHN-6-STR-GRN-CUT REEL	30	FT
Ground Lugs, Compression, 6 AWG W/2 X1/4" Holes	Burndy	YA6CL2TC14	2	EA
TESTING				