



Preliminary Development Plan

Amendment

For

Costco Chandler Business Center

Located at the Southwest Corner of Pecos Road and Alma School Road

By:

Kimley-Horn and Associates, Inc.

Case No: PLH24-0024

Submitted: January 8, 2025

TABLE OF CONTENTS

A. INTRODUCTION	2
B. SITE, SURROUNDING AREA, AND EXISTING ZONING	3
C. PROPOSED PRELIMINARY DEVELOPMENT PLAN	3
1. 3	
2. 3	
3. 4	
D. DEVELOPMENT STANDARDS	4
<i>Exhibit 1 – Site Context</i>	5
<i>Exhibit 2 – Chandler General Plan</i>	6
<i>Exhibit 3 – Site Plan</i>	7
<i>Exhibit 4 – Building Elevations</i>	8
Exhibit 5 - Fuel Canopy Elevations	9
<i>Exhibit 5 – Landscape Plan</i>	10

PREPARED BY:


PROJECT TEAM

Developer	Engineering	Representation
Costco	Kimley-Horn	Gallagher & Kennedy
Therese Garcia	Bryan Wright	Rodney Q. Jarvis
730 Lake Drive	1001 W. Southern Ave.,	2575 E. Camelback Road,
	Unit 131	Suite 1100,
Issaquah, WA 98027	Mesa, AZ 85210	Phoenix, AZ 85016
ThereseGarcia@costco.com	Bryan.Wright@Kimley-Horn.com	Rod.Jarvis@gknet.com

A. INTRODUCTION

Costco Wholesale is the developer and operator of the proposed Costco Chandler Business Center which consists of approximately 170,500 sf of retail development on +/-18.65 gross acres located at the southwest corner of Pecos Road and Alma School Road in Chandler, Arizona. As shown in **Exhibit 1, Site Context**, the project site is made up of one existing parcel APN: 303-26-003P. The property is currently being utilized for agricultural uses. This request is to amend the zoning and preliminary development plan of the subject property from Planned Area Development (PAD) for an office park with ancillary retail and restaurant uses, including a Mid-Rise Overlay for building Height up to 75 feet to Planned Area Development (PAD) for the Costco Business Center and Fuel Center based upon the C-2 Community Commercial District.

This use is appropriate for this area and site which is currently zoned for retail use and office space. With the proposed reduced building square footage, removal of the parking garage, and substantial landscaping, this use better suits the area and supports the needs of local small business as well as residents. Approval of this proposal will allow for a new commercial corner that will complement the existing commercial uses, parks, schools, residential, employment and religious uses that surround it.



B. SITE, SURROUNDING AREA, AND EXISTING ZONING

The Site is designated on the City's General Plan as Neighborhoods. The Neighborhood designation allows for a variety of non-residential uses. **See Exhibit 2, Chandler General Plan.** The site is currently zoned PAD and designated for an Office Park with ancillary retail and restaurant uses, including a Mid-Rise Overlay for building Height up to 75 feet. This office park has not been developed and the Site is currently use for agricultural purposes. This request will allow for the development of the site in a manner that is less impactful from a peak hour traffic aspect while also serving local small business and residents through the Business Center and Fuel Center. The Site is bounded by multifamily use Camden Pecos Ranch Apartments to the west, multifamily use The Casitas at San Marcos to the north, the Banner Medical Office complex to the east, and Loop 202 to the south. This location also provides excellent access to the freeway.

C. PROPOSED PRELIMINARY DEVELOPMENT PLAN

1. Site Layout

The proposed Preliminary Development Plan is designed to be mindful of the existing neighbors as well as provide an inviting and convenient destination for local business owners and residents. The proposed building is planned to be approximately 170,500 square feet and be located in the southwest corner of the Site. This is a significant reduction from the Office Park use previously approved that allowed for 400,000 square feet of office space with ancillary retail spaces as well as a four-story parking garage located only 20 feet from the existing multifamily use to the west. The proposed plan provides a 60-foot setback from the western property line to the building face. The proposed use also has a maximum height of 36 feet for buildings. The previously approved use had a maximum height of 75 feet. The location of the Fuel Center was carefully coordinated with city staff to manage queueing for the fuel dispensers. Proper circulation and adequate storage lengths along with the proposed signal improvements were analyzed in the decision of placing the Fuel Center at the southeast corner of the project. The location of the Fuel Center provides appropriate visibility while reducing the potential for traffic conflicts offsite. **See Exhibit 3, Site Plan.**

2. Architecture

The overall theme for the building is a contemporary design focused on clean, simple lines that is attractive and consistent with the design standards for the City of Chandler while also being recognizable as a Costco Business Center. **See Exhibit 4, Building Elevations.** The architecture features undulating roof heights, alternating materials and horizontal relief to break up the massing. Pedestrian elements such as trellis and shade structures at seating areas were incorporated to enhance the pedestrian experience. Variations in the neutral colors including Taupe, Sandstone, and Bronze have been utilized to match the desert background and are consistent and appropriate within the context of the area. See Exhibit X, Color & Materials Board.

3. Landscaping

The landscaping for the project has been designed per the development requirements of the City to create an attractive appearance for the overall development and community. See Exhibit 5, Landscape Plan. The southwest corner of the intersection of South Pecos Road and West Alma School Road will have a 50' landscape buffer consisting of earthen berms, a screening hedge, meandering trees and unique cacti and succulent species. The enhanced landscape corner treatment at South Alma School Road and West Pecos Road will be a palette of palms, accent shrubs and succulents, earthen berms, boulders, and rock creating an impactful landscape statement for the neighborhood. The site landscape design will create appropriate shade and buffer areas within and along the perimeters of the site while providing an attractive appearance for the overall development. The site parking field and perimeter will be planted with a sustainable, colorful, and attractive plant palette to draw interest to and through the Site. The west property line adjacent to the multi-family development, Dissimilar Buffer, will be planted with screening trees at twenty feet (20') on center and interspersed with dense shade trees planter at forty feet (40') on center, creating a dense screen between the proposed development and the adjacent use.

D. DEVELOPMENT STANDARDS

Below are the proposed Costco Chandler Business Center PAD development standards compared to the previously approved (March 31, 2016) Santan Office Campus DVR15-0041.

Table 1 – PAD Comparison

	Previous Approval	2024 Proposal
Proposed Use	Office Park with Mid-Rise Overlay	Costco Business Center
Parcels	303-26-003P	303-26-003P
Acreage	±18.65Acres	±18.65 Acres
Building Height Allowed	75' (4-Stories)	36' (1-Story)
Zoning	PAD	PAD
Underlying Zoning	C-2	C-2
Min. Rear Building Setback	0'	60'

EXHIBIT 1 – SITE CONTEXT





EXHIBIT 2 – CHANDLER GENERAL PLAN

Figure 5: Future Land Use Plan Map



Future Land Use Plan Map

Neighborhoods
This category allows a range of residential densities and a variety of non-residential uses such as commercial, institutional, public facilities, and commercial offices based upon location and other criteria as described in the text of the general plan.

Regional Commercial
Major regional commercial uses such as shopping malls, power centers, large single-use retail, and other commercial centers. As described in the general plan text, these locations are eligible for consideration of urban-style mixed-use developments. Other supportive land uses that may be allowed include large offices and mixed residential densities.


Employment
Major employers, knowledge-based employers, industrial/business parks, and industrial support uses. A compatible mix of supporting commercial uses and residential densities as an integral component may be considered as described in the General Plan text, growth area policies, and area plans.

Recreation/Open Space
Public parks and open spaces shown are greater than approximately five acres. Refer to the Parks and Open Space Map for more information.

Growth Areas
Targeted areas suitable for planned multimodal transportation and infrastructure expansion and improvements designed to support economic growth with a planned concentration of a variety of uses such as residential, office, commercial, tourism, and industrial. A.R.S. §9-461.05

1. Downtown Chandler
2. North Arizona Avenue
3. Chandler Airport
4. South Price Road Corridor
5. Medical/Regional Retail
6. I-10/Loop 202





PROJECT DATA

PROJECT ADDRESS: SWC OF W. PECOS RD & S. ALMA SCHOOL RD CHANDLER, AZ

SITE DATA:

TOTAL SITE AREA: 18.57 ACRES (808,909 SF)
INCLUDES:
SITE AREA: 16.37 ACRES
FUTURE EXPANSION AREA: 2.20 ACRES

JURISDICTION: CITY OF CHANDLER

ZONING: PLANNED AREA DEVELOPMENT

SETBACKS: REQUIRED ACTUAL
FRONT: 50' FRONT: TBD
SIDE: 5' SIDE: TBD
REAR: 20' REAR: TBD

BOUNDARIES INFORMATION: THIS PLAN HAS BEEN PREPARED BY MG2 CORPORATION USING A SURVEY BY INNOVATION GROUP, INC DATED 10.26.15

BUILDING DATA:

TOTAL BUILDING FOOTPRINT AREA: 140,740 SF
FUTURE TOTAL: 170,462 SF

INCLUDES:
WAREHOUSE MAIN LEVEL: 133,686 SF
FUTURE BUILDING ADDITION: 29,722 SF
OPEN CANOPY FOOTPRINT AREA: 6,985 SF

PARKING DATA:

TOTAL PARKING: 603 STALLS


INCLUDES:
10' WIDE STALLS: 579 STALLS
10' WIDE LOADING ZONE STALLS: 12 STALLS
ACCESSIBLE STALLS (2 PER 100): 12 STALLS

NUMBER OF STALLS PER 1000 SF OF BUILDING AREA: 4.28 STALLS

TRUCK STALLS: 32 STALLS

JURISDICTIONAL PARKING REQUIRED (1 PARKING STALL PER 250 SF): 536 STALLS

NOTES:
EXISTING CONDITIONS TO BE FIELD VERIFIED.



SWC OF W PECOS RD & S ALMA SCHOOL RD CHANDLER, AZ




23-5956-01
OCTOBER 2, 2024

PRELIMINARY
SITE PLAN

DD11-12

MG2 is the registered proprietor of the MG2 logo and the MG2 logo is a registered trademark of MG2 Corporation. All other trademarks are the property of their respective owners.






Exhibit 4 - building elevations



ELEVATION MATERIAL PERCENTAGES

MATERIAL	ELEVATION			
	WEST	NORTH	EAST	SOUTH
SMOOTH FACE CMU "BUFF"	2,918 SF 21%	1,709 SF 18%	2,550 SF 15%	2,022 SF 21%
CONCRETE "NATURAL"			1,585 SF 9%	
VERTICAL RIB ARCHITECTURAL METAL PANEL "TAUPE" AND "SANDSTONE"	10,725 SF 79%	7,636 SF 82%	13,153 SF 76%	7,773 SF 79%

*CALCULATION DOES NOT INCLUDE EXTERIOR DOORS OR TIRE CENTER DOORS



SIGN TABLE						
IDENTITY	QUANTITY	SIGN	SIZE	AREA (EACH)	TOTAL SF	
A	1	COSTCO BUSINESS CENTER	4'-0" C	105 SF	105 SF	
B	2	COSTCO BUSINESS CENTER	6'-0" C	223 SF	446 SF	
TOTAL SIGN AREA:					551 SF	





EXHIBIT 5 – FUEL CANOPY ELEVATIONS



1 EAST / WEST ELEVATION
SCALE: 1" = 10'



2 SOUTH / NORTH ELEVATION
SCALE: 1" = 10'



3 CONTROLLER / DATA HUT
SCALE: 1" = 10'



3 CANOPY SIGNS
SCALE: 1/4" = 1'

SIGN TABLE					
IDENTITY	QUANTITY	SIGN	SIZE	AREA (EACH)	TOTAL SF
A	4	CANOPY SIGN	8'-6 5/8" X 2'-5 1/4"	21 SF	84 SF
TOTAL SIGN AREA:					84 SF

