

DATE: 12/6/2017

FACILITIES MAINTENANCE



JOB

Treasures Walls North wall 10' x West wall 20'

Column1	AMOUNT
Hollow Metal Frame + Door Stan Greer quote	\$2,225.50
2 Bundle Metal Track 3 5/8 20 gauge	\$130.00
3 Bundle Metal Studs 3 5/8 20 gauge	\$195.00
10 Sheets 5/8 drywall	\$105.00
500 ft 12-2 MC/w ground	\$300.00
6- 20 Amp outlets	\$47.99
500 ft Roll drywall tape	\$71.92
8- boxes drywall mud	\$71.92
1 5gal paint	\$153.00
1 day to run electric 2 guys 1 day framing 2guys 2 days hang & tape drywall 2guys 2 days finish drywall & texture 2guys 1 day trim, electric & paint 2guys	7 days total for 2 guys \$2,800.00
TOTAL	\$6,100.33

Reference only

