



**COCHISE COUNTY  
PROCUREMENT DEPARTMENT**

1415 Melody Lane, Building C, Bisbee, AZ 85603  
Phone: (520) 432-8390 | Fax: (520) 432-8397

**25-04-SWD-01**

**Attachment 2 – Scope of Work**

In accordance with 25-04-SWD-01, The Contractor shall provide to the satisfaction of Cochise County (“County”) all labor, materials, transportation, and expertise to reconstruct the transfer station located at 90 West 9<sup>th</sup> Street, Douglas, AZ 85607. The following tasks are to be completed:

Task 1: Cut and remove existing sheets, approximately 12 feet up from the current foundation. Approximately 120 linear feet.

Task 2: Remove existing damaged drip edge at the base.

Task 3: Remove existing four bay doors and frames.

Task 4: Remove existing man door.

Task 5: Remove damaged down spouts and frames.

Task 6: Install C channel at the base ensuring the screws have an adequate backing to fasten on to.

Task 7: Install new sheets- approximately 12 feet up from the current foundation. Approximately 120 linear feet.

Task 8: Install new down spout where the existing ones were removed.

Task 9: Install 20-foot corner trim.

Task 10: Build new day frames for all 4 bay door openings. All frames will be built out of new 2"x 8" C Channel.

Task 11: Install all 4 new non-insulated chain hoisted bay doors. Quantity (4) at 10 feet wide x 16 feet high.

Additional information:

- All colors to be chosen by the customer and decided prior to start of project.
- Cochise County will keep all material from demolition.
- All equipment and materials must be hoisted mechanically to the roof from the parking lot.
- Contractor will be responsible for all applicable OSHA Safety Standards for roofing contractors.
- All material used must match existing material.