

Foothills Parking Lot Reconstruction Bid Sheet

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
109.10000	Mobilization/Demobilization	L.SUM	1		
205.01150	Excavation	CU.YD.	106		
301.01000	Subgrade Preparation	SQ.YD.	634		
310.03001	Aggregate Base Course	CU.YD.	71		
321.00200	Asphalt Concrete Pavement (MARSHAL 1/2 MIX)	TON	591		
340.01210	Concrete Sidewalk, MAG Det 230	SQ.FT.	1016		
340.01150	Concrete Single Curb, MAG Det 222, Type B	L.FT.	168		
340.01358	Concrete A.D.A. Curb Ram	L.SUM	1		
350.01850	Remove Concrete Single Curb	L.FT.	481		
350.01900	Remove Concrete Sidewalk	SQ.FT.	616		
350.01909	Remove Concrete Stairs, Sidewalk & Rail	L.SUM	1		
350.03010	Remove Light Pole	EACH	1		
350.07501	Removal of Asphalt Concrete Pavement	SQ.YD.	4326		
351.46000	Relocate Sign	EACH	1		
401.00000	Traffic Control	L.SUM	1		
461.01100	4 in White Traffic Paint Stripe	L.FT.	2708		
461.01510	Paint Symbol, Arrow (ADOTm-10a Standard Drawing)	EACH	10		
461.01512	Paint Symbol, Right Turn Arrow	EACH	1		
461.01516	Paint Symbol, Divided Arrow (ADOTm-10a Standard Drawing)	EACH	4		
461.01711	Paint Legend, YIELD	EACH	2		
462.01530	Painted Symbol, Handicap Parking	EACH	4		
464.03000	Sign Post, Perforated	EACH	5		
465.01002	Flat Sheet Aluminum Sign Panel, High Intensity Grade	SQ.FT.	5		
510.10001	Brick Retaining Wall, Max Height 3 Feet	L.FT.	74		
520.01035	Safety Rail, Height 3 ft - 6 in (MAG Det 145)	L.FT.	106		

Bid Total