



A. Scope of Work

B. Scope of Services / Preconstruction Services Tasks

A. Scope of Work

Utility Potholing - Vacuum Excavation & Backfill

Mobilization	Mobilization for vacuum excavation truck and crew.
Core & Reinstatement	Cost to core and reinstate asphalt core per approved MAG standards in ADOT ROW. This will be used if ADOT inspector allows it.
Utility Potholing - Daily Rate	Daily rate for vacuum excavation of existing utilities, inclusive of slurry backfill or native backfill. Utilities whose owners require 6" of sand above utility is also included in this rate.

Traffic Control for Utility Potholing

Mid-Block Closure Equipment (Taxable)	Traffic control equipment.
Setup or Pickup Mid-Block Closure - Each Direction	Labor to install / remove mid-block lane closures.
Flaggers - 2 Each @ 10 Hours Per Day	Labor for flaggers to flag sidewalks when utility potholing is ongoing.
Traffic Control Plan (Taxable)	Traffic control plans required to perform utility potholing.
Flags (Taxable)	Traffic control equipment.
Sand Bags (Taxable)	Traffic control equipment.

Survey - As-Built Utilities

Survey & as-built all utilities after potholing	Survey and as-built all utilities after potholing is complete.
---	--

Asphalt Repair & Patching

Furnish & Install AC Hot-Mix for potholes in ADOT ROW	Cost to cover trucking, material purchase, and labor to place AC hot-mix patch for potholes within ADOT ROW. Cost also includes labor to sawcut 2'x2' area if ADOT requires.
---	--

B. Scope of Services / Preconstruction Services Tasks



	Cost Breakdown			Total Cost
	Quantity	Unit	Rate	
Utility Potholing - Vacuum Excavation & Backfill	Total =			\$32,177.00
Mobilization	2	EA (Allowance)	\$1,898.00	\$3,796.00
Core & Reinstatement	15	EA (Allowance)	\$275.00	\$4,125.00
Utility Potholing - Daily Rate	4	DAYS (Allowance)	\$6,064.00	\$24,256.00
Traffic Control for Utility Potholing	Total =			\$7,770.47
Mid-Block Closure Equipment (Taxable)	5	EA (Allowance)	\$60.00	\$327.54
Setup or Pickup Mid-Block Closure - Each Direction	10	EA (Allowance)	\$220.00	\$2,200.00
Flaggers - 2 Each @ 10 Hours Per Day	100	HRS (Allowance)	\$50.00	\$5,000.00
Traffic Control Plan (Taxable)	2	EA (Allowance)	\$65.00	\$141.94
Flags (Taxable)	12	EA (Allowance)	\$2.50	\$32.75
Sand Bags (Taxable)	25	EA (Allowance)	\$2.50	\$68.24
Survey - As-Built Utilities	Total =			\$900.00
Survey & as-built all utilities after potholing	1	LS (Allowance)	\$2,000.00	\$900.00
Asphalt Repair & Patching	Total =			\$6,000.00
Furnish & Install AC Hot-Mix for potholes in ADOT ROW	1	LS (Allowance)	\$6,000.00	\$6,000.00
			Subtotal =	\$46,847.47
Summary				
Total =				\$46,847.47



QUOTE

Safe Site Utility Services LLC

Company Address	7623 N 73rd Dr Glendale, Arizona 85303	Created Date	12/7/2023
Phone	(602) 606-8882	Quote Number	00002980
Email:	Bids@safesitellc.com	Opportunity	OP23-4397
Licenses:	AZ: ROC 211956 / NV: NSC 0078575	Expiration Date	3/3/2024

Customer Information

Opportunity Name	City of Flagstaff Drainage CMAR	Phone	480-486-3012
Contact Name	George Lane-Roberts	Email	george@banicki.com
Account Name	J Banicki Construction, Inc.	Billing Address	Accounts Payable 4720 E Cotton Gin Loop S-240 Phoenix, AZ 85040

Work Site Info

Site Address 2601 N Fort Valley Rd, Flagstaff, AZ 86001

Scope of Work

1. Safe Site will verify 811 markings and assess the success probability of test hole locations indicated by client prior to excavation utilizing various geophysical locating means. Test hole locations may be adjusted or eliminated based on the results of this investigation and upon discussion with, and approval of client
2. Safe Site will supply a vacuum excavation crew on the project site for digging test holes and documenting utility locations.
3. Upon exposure of a target utility, Safe Site will record utility type, size, material, and depth of cover of each.
4. If Line Item charges for Survey are shown in Fees Section then Safe Site will provide survey and a CAD map file by a Registered Land Surveyor to document the locations and elevations of potholed utilities. If no Line Item for Survey is shown then pricing assumes Survey and CAD will be provided by others.
5. Safe Site will provide a Test Hole Summary Report detailing this information.
6. Safe Site will indicate the locations of exposed utilities by marking the ground surface using PK nails or stake chasers (nylon brushes).

Terms and Conditions

1. Client will provide available utility location information as well as project datum information to Safe Site to aid in facilitating this project.
2. A "Test Hole" will be considered one excavation up to 8 feet deep with lateral "belling" of up to a width of 4 feet. Excavating in excess of 12 feet in depth will be considered out of scope.
3. Test Holes will be backfilled per owner/agency specifications.
4. Asphalt on concrete pavement surfaces will be restored per method indicated in Fees section. If local authority requires a different restoration, any additional costs will be passed on to Client. These charges, if applicable, will be determined during the permitting stage and any fee charge will be presented to Client. Coring pavement in excess of 12" thickness will result in an additional fee of \$100 per hole.
5. Pricing assumes test hole locations are accessible within 15' with vacuum truck. Further distances, such as rear of lots, will be considered out of scope and additional fees will be presented to Client for approval.

6. Should caliche, tree roots, concrete, rocks in excess of 6" diameter, or other materials encumber vacuum excavation, work will be halted for that test hole and referred back to Client for alternative solutions which may include authorization to continue work at Hourly Rate.
7. Traffic control costs are included where applicable.
8. Expected Permitting/Bonding costs, if any, have been included in this proposal. Any out of ordinary costs incurred due to governing agency requirements will be presented to Client for approval as additional fee amount.
9. If excavation spoils are determined to be potentially hazardous waste by an enforcement agency having jurisdiction, then the cost of testing and disposal will be passed through to client. Work will cease until Client has been notified and agreement on how to proceed has been reached.
10. Safe Site will exercise due diligence in identifying and locating all utilities. However, due to factors beyond our control including lack of maps, inaccuracy of maps, lack of aboveground indications of utilities, the presence of unknown and non-electromagnetically conductive utilities and soil conditions being non-conductive to GPR scans, Safe Site cannot guarantee that all utilities will be found.
11. Payment terms are Net 30 days unless other arrangements have been made.
12. New Customer Policy - Payment will be required by credit card for the first job completed or if the job is over \$1000, we will require a 35% retainer to be paid prior to commencement of work. We prefer payment is made via ACH/Wire Transfer, otherwise credit card transactions would require an additional 3% Fee. After the first job completed, invoicing terms will be standard Net 30 Days.

Site Specific Details

Description	<p>Provide utility potholing services under day rate to include up to 8 hours on site per day. Perform approx. 28 utility test holes (potholes) for utility conflicts.</p> <p>Hotel and Per Diem for overnight stays & Backfill are included in Day Rate.</p> <p>Safe Site will core and reinstate utility test holes performed in asphalt per MAG 212B Specs.</p> <p>Safe Site will pin utility locations, document findings and provide un-stamped report.</p> <p>Safe Site will provide slurry backfill and associated sand when necessary.</p> <p>Client will provide permit and traffic control. Survey, if needed will be provided by others.</p> <p>Utility Designating & Mapping</p> <p>Designate & Map site utilities within the area depicted on the map provided and as directed by client. Utility locations will be captured using GPS data collectors and a 2D CAD and PDF map will be provided.</p> <p>Daily Rate to include up to 8 hours on site per day.</p> <p>Hotel and Per Diem are included in Day Rate.</p>
Additional Terms	<p>-Additional hours on site or dumping beyond 8 hours will be billed at \$320 per hour.</p> <p>-Mobilization Fee applies for each trip required.</p> <p>-Our designation markings are for design / pre-construction purposes only. Prior to digging Client must request a locate through 811 as required by law so that the public utilities can be marked by the utility owners.</p>

Project Fee

Product	Line Item Description	Sales Price	Quantity	Total Price
1 Technician - Port to Port Mobilization	Roundtrip (Utility Designating & Mapping)	\$2.00	292.00	\$584.00
AC Surface Restoration - Core & Reinstate	Per Core & Reinstatement (Min. of 3)	\$275.00	15.00	\$4,125.00
Lump Sum Mobilization	Roundtrip from Glendale Yard	\$1,898.00	1.00	\$1,898.00
Utility Locating	Utility Designating (Daily Rate)	\$1,555.00	2.00	\$3,110.00
Utility Mapping	GPS Data Collection & CAD Deliverable (Daily Rate)	\$1,310.00	1.00	\$1,310.00
Utility Potholing	Day Rate as Described	\$6,064.00	4.00	\$24,256.00

Total Price \$35,283.00

ACCEPTANCE STATEMENT AND AUTHORIZATION TO PROCEED

This Acceptance becomes a part of the Proposal Letter.

The Proposal is hereby accepted according to the Scope of Work and Terms and Conditions contained therein. Safe Site Utility Services, LLC is authorized to proceed with the work described therein. Payment will be made according to the payment terms specified in the Proposal. Any unpaid balance remaining beyond the due date will be subject to interest at an annual rate of 18% (1.5% per month).

For acceptance and scheduling of these services please sign, scan, and return this page to bids@safesitellc.com or fax to Safe Site @ 602-391-2934.

Client Name: _____
By:

Signature

Date

Printed Name

Title



Quail Construction LLC
 7200 E 31st Place
 Yuma, AZ 85365
 928-314-1212

QUOTATION

Quote Date	Quote ID
12/8/2023	SM-120823-001

Valid Through: 3/8/2024

J Banicki Construction Inc.

George Lane-Roberts
 4720 E Cotton Gin Loop #240
 Phoenix, AZ 85040
 Phone: 480-486-3012

Job Location:

Schultz Creek Drainage, Ft. Valley Road
 Flagstaff

Quote Created By: S. Miller

Email: george@banicki.com

Bid Line#	Item Description	Price	UOM	Qty/Day	Days	Total Qty.	Total
1	Mid-Block Closure (daytime Equip) *	\$60.00	Per Day	1	5	5	\$300.00
2	Setup or Pickup (Mid-Block)	\$220.00	Per Each	2	5	10	\$2,200.00
3	Flaggers (Qty: 2 @ 10 Hrs each)	\$50.00	Per Hour	20	5	100	\$5,000.00
4	Traffic Control Plan *	\$65.00	Per Each	2	1	2	\$130.00
5	Flag w/dowel *	\$2.50	Per Each	12	1	12	\$30.00
6	Sand Bag (filled) *	\$2.50	Per Each	25	1	25	\$62.50

Note: The * indicates taxable items.

5 Working Days- Rental shown on Quote. Invoiced per actual.
 Contractor to determine actual rental duration & Quantities.
 Will be invoiced per actual (+ or -).

Equipment Daily Rates include the following:
 Devices, signs, stands for Daytime hours only.

Initial Setup or Final Pickup does NOT include standby time.

Note:
 Any additional labor not quoted above will be invoiced
 at hourly Rates: This includes and is not limited to Standby,
 Flagging, Shadow, job Maintenance.

Additional Rates:
 1 Man/1 Truck- \$75 per/hour
 2 Man/1 Truck-\$110 per/hour
 Certified Flagger - \$50 per/hour
 Message Boards - \$50 Per Each/Day

Scope: All rental periods are based on calendar days.
 Hourly labor is charged port to port from branch location to job site.

EQUIPMENT	\$300.00
ONE TIME CHARGES	\$222.50
LABOR	\$7,200.00
SUBTOTAL	\$7,722.50
SALES TAX (9.181%)	\$47.97
QUOTE TOTAL	\$7,770.47

Quote For: J Banicki Construction Inc. - Quote ID: SM-120823-001 (cont.)

S. Miller
Quail Construction LLC

12/8/2023

Date

Accepted By:

Signature

Print Name

Title

Company



December 11, 2023

J. Banicki Inc.
6423 S. Ash Avenue
Tempe, AZ 85283
Attn.: George-Lane Roberts

RE: Hwy. 180 Box Culvert Extension
Pot Hole Locations

Mr. Roberts,

Matrix Land Surveying, Inc. is pleased to submit this proposal for professional surveying services on the above-referenced project. We propose to provide the following services.

LIST OF SERVICES

- Verify existing horizontal and vertical control
- Locate pothole locations
- Provide Points file of locations

We agree to provide the above-listed professional surveying services for a **FIXED FEE** of ***NINE HUNDRED DOLLARS (\$900.00)***.

This Fee is based upon the following:

- 48-Hour Notice for scheduled work
- Contractor to schedule work to maximize efforts for each site visit
- One-Time Only staking of all items listed
- Horizontal and vertical control exists prior to commencement of our services

Thank you for considering Matrix Land Surveying, Inc. for this project. We look forward to working with you. If you have any questions regarding this proposal, please do not hesitate to contact me.

Sincerely,

William D. Nigro, R.L.S.