

Case No. PZ-24-00009: Subdivision Process  
Amendment for Adoption to Flagstaff City Code

**CHAPTER 11-20**  
**SUBDIVISION AND LAND SPLIT REGULATIONS**

Divisions:

- 11-20.10 Title and Authority
- 11-20.20 Purpose and Intent
- 11-20.30 ~~Applicability Purpose and Intent~~
- 11-20.40 Subdivision Procedures and Requirements
- ~~11-20.50~~ ~~11-20.50~~ ~~Conceptual Plat~~
- ~~11-20.60~~ ~~Preliminary Plat~~
- ~~11-20.70~~ ~~Final Plat~~
- ~~11-20.80~~ ~~Development Master Plans~~
- ~~11-20.90~~ ~~Modified Subdivision Process~~
- ~~11-20.100~~ Land Splits and Combinations
- ~~11-20.60~~ ~~11-20.110~~ Boundary Adjustments
- ~~11-20.70~~ ~~11-20.120~~ Subdivision Design Standards and Requirements
- ~~11-20.80~~ ~~11-20.130~~ Minimum Required Subdivision Improvements
- ~~11-20.90~~ ~~11-20.140~~ Modifications
- ~~11-20.100~~ ~~11-20.150~~ Reversion to Acreage
- ~~11-20.110~~ ~~11-20.160~~ Vacation of Streets and Easements
- ~~11-20.120~~ ~~11-20.170~~ Violations
- ~~11-20.130~~ ~~11-20.180~~ Appeals

Formatted: Font: Bold

Formatted: Border: Bottom: (No border)

**11-20.10**  
**Title and Authority**

Sections:

11-20.10.010 Title and Authority

11-20.10.020 Short Title

**11-20.10.010 Title and Authority**

These regulations shall be known and referred to as the Subdivision and Land Split Regulations for the City of Flagstaff, Arizona, as provided for by A.R.S. § 9-46~~32~~.

**11-20.10.020 Short Title**

The City of Flagstaff Subdivision and Land Split Regulations shall also be known as the "Subdivision Regulations".

Formatted: Left

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

**11-20.20**  
**Purpose and Intent**

Sections:

11-20.20.010 Purpose and Intent

**11-20.20.010 Purpose and Intent**

A. The purpose of the City of Flagstaff Subdivision and Land Split Regulations is to facilitate orderly growth and harmonious development, and to protect and promote public health, safety and welfare. These Subdivision Regulations reflect policies developed by the City in its General Plan to help regulate the need for expanded public services, including transportation, education, water, sewer, and other utilities that is influenced by the sale of subdivided land. The preservation of the features that make Flagstaff a beautiful place to live, such as steep slopes, pine forests, and floodplains is also a priority. More specifically, these regulations are intended to achieve the following objectives:

1. To accommodate the demand for a variety of housing, including affordable housing, while recognizing the right of all citizens to a safe community without the hazards of flooding, erosion, contamination, and other blight;
2. To insure safe and efficient traffic circulation through coordinated street systems with major thoroughfares, adjoining subdivisions, and public facilities;
3. To provide lots and parcels of sufficient size and appropriate design for the purposes for which they will be used;
4. To secure adequate provisions for water supply, stormwater drainage, sewage disposal, and other utilities and facilities;

Formatted: Border: Bottom: (No border)

5. To provide adequate sites for schools, recreation areas, and other public facilities;
6. To provide logical procedures to facilitate the conveyance of land by accurate legal description, and to establish and assure the rights, duties and responsibilities of subdividers and developers with respect to land development;
7. To assure future buyers of land that the subdivider owns the land proposed to be sold, provides access to each property, and constructs and provides for maintenance of improvements, utilities, and amenities;
8. To apportion the costs of public services and facilities serving subdivision residents through the payment of fees, provision of facilities, and dedication of land and rights-of-way to the City in order to ensure that new development pays its way and does not burden the City's fiscal resources; and
9. To obtain accurate surveying and permanent public record of the separate interests created and conveyed by subdivision.

B. These Subdivision Regulations are intended to provide a common ground of understanding and an equitable working relationship between public and private interests, so that both independent and mutual objectives can be achieved in the subdivision of land.

**11-20.30**  
**Applicability**

Sections:

- 11-20.30.010 General Applicability
- 11-20.30.020 Related Statutes
- 11-20.30.030 Reservation of Public Land

**11-20.30.010 General Applicability**

A. The City shall not approve a final plat of a subdivision or land split unless it conforms to the provisions of this Chapter.

~~B. No person shall sell or commence any development or construction upon any portion of a proposed subdivision until a final plat has been recorded.~~

~~C. No person shall sell or commence any development or construction upon any portion of a proposed land split until a land split map has been recorded.~~

BD. The provisions of this Chapter apply to all subdivisions (including a modified subdivision process), land splits, and boundary adjustments as further described below, except for the following:

1. The sale or exchange of parcels of land to or between adjoining property owners if such sale or exchange does not create additional lots;
2. The partitioning of land in accordance with other statutes regulating the partitioning of land held in common ownership;
3. The leasing of apartments, offices, stores, or similar space within a building or trailer park; or to
4. The leasing of mineral, oil, or gas rights.

CE. As used within this Chapter, subdivision, modified subdivision process, land split, and boundary adjustment are described as follows (specific definitions of these terms are provided in Chapter 11-30, Definitions:

Formatted: Border: Bottom: (No border)

1. Subdivision:

a. A subdivision is the division of improved or unimproved land into either:

- (1) Four or more lots, tracts or parcels of land;
- (2) Two or more lots, tracts or parcels of land, if a new street is involved; or
- (3) Three or more lots, tracts or parcels, the boundaries of which have been fixed by a recorded plat.

b. Subdivision applications are required to adhere to a comprehensive multi-step review process that includes ~~submission of a conceptual plat for review and approval by the Director and City Engineer;~~ submission of a preliminary plat for review and approval by the Director and City Engineer ~~before it is reviewed and recommended for approval by the Planning Commission or;~~ review and approval by the City Council of any preliminary plat utilizing the Planned Residential Development standards or requiring a modification to Engineering Standards; ~~and~~ submission of public improvement plans, and a final plat for review and recommendation approval of the Director and City Engineer ~~prior to approval of a final plat by the City Council for the proposed subdivision.~~

2. Modified Subdivision Process: The modified subdivision process applies to subdivisions with no more than where a maximum of ten four lots is proposed to be created as well as land splits over 2.5 acres.

3. Land Split:

a. A land split is the division of improved or unimproved land whose area is 2.5 acres or less into either:

- (1) No more than two lots, tracts, or parcels, the boundaries of which have been fixed by a recorded plat; or,
- (2) Two or three lots, tracts, or parcels located within unsubdivided lands.

b. A land split application is reviewed and approved by the Director. A concept plan of the proposed land split may be submitted to the Director for review prior to submittal of a final legal description and land split map.

4. Boundary Adjustment: When the lot line between two adjoining parcels requires adjustment, a boundary adjustment following the procedure for a land split application is followed.

**11-20.30.020 Related Statutes**

The subdivision of land in the City of Flagstaff is subject to the requirements and procedures of Arizona and federal law. Specifically related statutes include A.R.S. Title 9; Article 6.2 concerning municipal subdivision regulations; Title 32 concerning the sale of lands; and, Title 33 concerning condominiums.

Formatted: Border: Bottom: (No border)

**11-20.30.030 Reservation of Public Land**

A. Land areas within a subdivision may be reserved for parks, recreational facilities, school sites and other public facilities including fire stations, open space lands and open areas, and flood control facilities, subject to the following conditions:

Formatted: Border: Bottom: (No border)

1. The requirements may only be made upon preliminary plats filed at least 30 days after adoption of a General Plan or Specific Plan affecting the land area to be reserved;

2. The required reservations must be in accordance with the General Plan, ~~the Flagstaff Urban Trails Plan~~, and adopted specific plans and other goals, objectives, and standards adopted by the City Council;

3. The land reserved shall be sized and shaped to permit non-reserved land area of the subdivision to develop in an orderly and efficient manner; and,

4. The land area reserved shall be suitable for the intended use and shall be planned in such a manner to permit an efficient division of the reserved area in case it is not acquired within the prescribed period.

B. The City Council shall have a period of one year after recording the final subdivision plat to enter into an agreement to acquire such reserved land area. The purchase price shall be the fair market value of the land at the time of the filing of the preliminary subdivision plat plus the taxes against such reserved area from the date of the reservation, and any other costs incurred by the subdivider in the

maintenance of such reserved area, including interest costs incurred on any loan covering such reserved area.

C. If the City does not exercise the reservation agreement set forth above within the one-year period or such extended period as may be mutually agreed upon by the City Council and the subdivider, the reservation of such area shall terminate.

**11-20.40**  
**Subdivision Procedures and Requirements**


Sections:

- 11-20.40.010 Overview of Subdivision Procedures and Requirements
- 11-20.40.020 Pre-Application Meeting Conference
- 11-20.40.030 Preliminary Plat
- 11-20.40.040 Final Plat
- 11-20.40.050 Master Block Plats
- 11-20.40.060 Modified Subdivision Process
- 11-20.40.070 Plat Amendments

**11-20.40.010 Overview of Subdivision Procedures and Requirements**

The preparation, submittal, review, and approval of all subdivisions located within the City limits shall proceed through the following progressive stages, except as otherwise provided in this Chapter:

- A. Pre-application meeting Conference (Refer to Section 11-20.40.020);
- ~~B. Conceptual Plats (Refer to Division 11-20.50);~~
- ~~BC. Preliminary pPlats submittal, review, and approval (Refer to Section 11-20.40.030 Division 11-20.70); and,~~



Formatted: Border: Bottom: (No border)

CD. ~~Final plat submittal, review and approvals~~ (Refer to ~~Section 11-20.40.040~~ ~~Division 11-20.80~~).

D. ~~Final plat submittal, review and approvals~~ (Refer to ~~Section 11-20.40.040~~ ~~Division 11-20.80~~).

E. ~~Recordation of approved final plat with the Coconino County Recorder.~~

**11-20.40.020 Pre –Application ~~Meeting~~ ~~Conference~~**

The ~~applicant~~ ~~subdivider~~ and the ~~subdivider's~~ ~~engineer~~ shall ~~initially~~ present their proposal and meet with the Director and City Engineer, ~~or their designee~~, on an informal basis at a pre-application ~~meeting~~ ~~unless waived by the Director~~ ~~conference~~. The ~~applicant~~ ~~subdivider~~ shall present ~~to these individuals~~ a general outline of the subdivision proposal ~~which shall include~~ ~~ing~~ sketch plans; ~~proposed~~ ~~and ideas~~ ~~regarding~~ land use; ~~street~~; and lot arrangement; lot sizes; and conceptual ~~designs for proposals~~ ~~regarding~~ water supply, sewage disposal, grading and drainage, traffic impacts, and street improvements. The Director and the City Engineer, ~~or their designee~~, shall advise the ~~applicant~~ ~~subdivider~~ of specific ~~public objectives~~, ~~standards~~, and regulations related to the subject property, details ~~and suggestions~~ regarding subdivision design and improvement standards, and general platting procedures and requirements, ~~and the determination of a need for a development master plan~~ (~~Division 11-10.80, Development Master Plan~~).

~~11-20.50~~

~~Conceptual Plat~~

**Sections:**

~~—Conceptual Plat Review~~

~~—Conceptual Plat Submittal~~

**11-20.50.010 Conceptual Plat Review** 

~~A.— Before beginning the formal preliminary plat submittal and review process, a conceptual plat review meeting shall be scheduled with the Director. The purpose of this meeting is to provide an opportunity for the applicant to hear any concerns, comments, or requests for additional information from the Director and other City Staff as applicable.~~

~~B.— The subdivider shall submit the required number of copies of the conceptual plat together with a completed application to the Director in accordance with the submittal deadlines established by the Director. Applications are available from the Planning Section.~~

Formatted: Border: Bottom: (No border)

Formatted: p0

Formatted: Border: Bottom: (No border)

~~C.—The Director and City Engineer shall meet with the subdivider and/or the subdivider's representative(s) to review, discuss, and consider the conceptual plat in regards to specific public objectives and adopted standards and regulations. The Director and Chief Engineer shall approve or disapprove the conceptual plat pursuant to the provisions of this Chapter. Following approval by the Director and Chief Engineer, the subdivider shall proceed with the preparation and submittal of the preliminary plat application and/or Development Master Plan in accordance with the procedures and requirements specified in Divisions 11-20.60 and 11-20.80, respectively.~~

~~11-20.50.020 Conceptual Plat Submittal~~

~~A.—The subdivider or an authorized representative shall submit the following materials to the Director in accordance with the review schedule on file with the Planning Section:~~

- ~~1.—The required number of copies of the conceptual plat application as specified in the handout available from the Planning Section;~~
- ~~2.—A completed Conceptual Plat application form. If the subdivider is not the current landowner of all of the subject real property, a signed statement or application shall also be filed attesting that the owner grants to the subdivider authority to represent the owner in this matter. The required number of copies of the preliminary title report as specified in the handout available from the Planning Section shall be filed with the application;~~
- ~~3.—A non-refundable conceptual plat filing fee. (See Title 10, Zoning Code, Appendix 2, Planning Fee Schedule);~~
- ~~4.—The legal description of the subject property;~~
- ~~5.—The names of the developer and the engineering and/or surveying firm;~~
- ~~6.—A topographic map for the subject property and the land within 200 feet of the subject property with a minimum two-foot contour, or such other interval as approved by the Director;~~
- ~~7.—A slope analysis with sufficient data to allow independent verification of the slope analysis. The slope analysis shall indicate by area the following slope categories:
  - ~~a.—0 – less than 17%;~~
  - ~~b.—17 – less than 24.9%;~~~~

Formatted: Border: Bottom: (No border)

~~e.—Greater than 25%—34.9%; and,~~

~~d.—Greater than 35%.~~

~~8.—A preliminary Natural Resources Protection Plan showing floodplains and forest resource locations, as applicable;~~

~~9.—A plan identifying all existing structures (including known heritage resources) on the property to be subdivided and within 200 feet of the subject property, and the conceptual location of proposed structures;~~

~~10.—A map showing generalized land uses in the vicinity of the site;~~

~~11.—A vicinity map, and, if applicable, a map showing the portion to be subdivided in relation to the entire subject property;~~

~~12.—Locations of all existing streets, utilities, rights of way, easements, structures, streams, floodplains, and other significant physical features within the portion to be subdivided and within 200 feet of the subject property;~~

~~13.—A concept plat showing the proposed configuration, size in acres, number of residential units and/or lots, the area in square feet of proposed nonresidential buildings, and the underlying zoning categories for each use. This information should also be included in a summary table on the plat;~~

~~14.—The conceptual plat shall be submitted at a scale of not more than 1 inch = 100 feet. Conceptual plat plan sheets shall not exceed 24 inches by 36 inches in overall dimensions and shall have a left margin of two inches;~~

~~15.—The conceptual plat shall include the following information regarding the proposed subdivision and surrounding land areas:~~

~~a.—Proposed land uses;~~

~~b.—Primary access and interior circulation proposals, including vehicular, bicycle, and pedestrian ways;~~

~~e.—Tentative proposals regarding solid and sewer waste disposal, storm sewer, and electric and gas utility services shall be indicated on the plat or in a companion document;~~

~~d.—Generalized land uses in the vicinity of the site;~~

~~e.—Tentative scoping of traffic impacts;~~

~~f.—Preservation of special scenic locations and view corridors;~~

~~g.—Proposed open space and trails with connectivity to adjoining areas~~

~~16.—Such other information requested by the Director relevant to the factors covered by provisions of this Chapter.~~

#### ~~11-20.60~~

#### ~~Preliminary Plat~~

#### ~~Sections:~~

#### ~~11-20.40.03011-20.60.010 Preliminary Plat Submittal~~

~~This section provides procedures for the review and approval of preliminary plats consistent with applicable law. The procedures established in this section shall apply to all proposals for preliminary plat. Requests for preliminary plat review shall only be made through the procedures described in this section.~~

~~A.—Preliminary Plat 11-20.60.020 —Preliminary Plat Requirements~~

~~B.— Preliminary Plat Approval~~

~~C.— Significance of Preliminary Plat Approval~~

~~D.— 11-20.60.010 Submission Preliminary Submittal.~~

~~E.— A.—The subdivider or an authorized representative applicant shall electronically submit the following materials in support of a preliminary plat application for a new subdivision to the Director in accordance with the submittal deadlines established by the Director and in accordance with the review schedule on file with the Planning & Development Services Section.:~~

~~F.— A. 1.—The required number of copies as specified in the handout available from the Planning Section of the preliminary plat reproduced as blue or black line prints on a white background;~~

Formatted: Indent: First line: 0"

~~12.~~ Completed preliminary plat application forms. If the subdivider is not the current landowner of ~~all of all~~ the subject real property, a signed and notarized statement shall also be filed attesting that the owner grants to the subdivider authority to represent the owner in this matter;

~~23.~~ A non-refundable preliminary plat filing fee. ~~(See Title 10, Zoning Code, Appendix 2, Planning Fee Schedule);~~

~~34.~~ An ALTA survey that delineates all easements and encumbrances in graphic form completed within 6 months of the preliminary plat submittal;-

4. Owner Certification of Notice of Right to Appeal Exactions;

~~5.~~ ~~AThe required number of copies of a~~ Traffic Impact Analysis (TIA) as determined by the City Engineer or designee shall be submitted for review and approval by the City Engineer;

~~65.~~ ~~AThe required number of copies of a preliminary~~ Stormwater Analysis as determined by the Stormwater Manager shall be submitted for review and approval by the Stormwater Manager;

~~76.~~ The results and/or findings of the water and/or sewer impact analysis. A request to the City ~~Utilities Water Services Department Division~~ to complete a water and/or sewer impact analysis shall be submitted prior to the application for a preliminary plat. ~~The results and/or findings of the water and/or Sewer Impact Analysis shall be submitted. The results and/or findings of the water and/or sewer impact analysis shall be submitted with the preliminary plat application; and~~

8. A project narrative that provides project information, an analysis of conformance with the Zoning Code, Subdivision Standards, and Engineering Design Standards and Specifications for New Infrastructure, a description of how utilities will be provided, a description of how stormwater will be managed, information on preliminary traffic impacts and improvements (including bicycles, pedestrian, and transit), phasing plans, requested modifications or variances, a description of how any conflicting land encumbrances will be resolved, and known heritage resources;

9. Prior to the submittal of an application for preliminary plat, the applicant shall submit copies of letters written to the following agencies informing them of the intent to subdivide and to obtain the general requirements for public utilities and public dedications applicable to the subdivision:

a. Appropriate public utilities;

- b. Cable television and communication companies;
- c. School districts;
- d. U.S.D.A. Natural Resource Conservation Service (NRCS);
- e. Coconino County Health Department (only if septic systems and/or wells are proposed);
- f. Arizona Department of Transportation (where land abuts a state right-of-way);
- g. Coconino County Flood Control District;
- h. Coconino County Community Development (if adjacent to an unincorporated area); and
- i. Mountain Line or other public transit operator.

Written recommendations from the review agencies shall be submitted in conjunction with the preliminary plat application. If any of the above review agencies fail to respond within 14 days of applicant's notice of intent to subdivide, the applicant may submit preliminary plat application and supplemental accordingly; and

10. Any request by the Director or City Engineer for additional information that is relevant to assist in the review of a preliminary plat. The Director and City Engineer may waive the requirements for any of the information required in this section if it is determined that such information is not necessary to complete a review of the requested preliminary plat.

~~B. All submittals shall be checked by the Director for completeness and assigned a case number. If a submittal is incomplete according to the requirements set forth in this division, the submittal may be rejected and returned to the subdivider for revision and re-submittal.~~

~~C. Upon a recommendation of approval of the preliminary plat by the Director, the subdivider or an authorized representative shall submit the following materials to the Director in accordance with the submittal deadlines on file with the Planning Section:~~

- ~~1. The required number of copies as specified in the handout available from the Planning Section of the preliminary plat reproduced in the form of blue or black line prints on a white background;~~
- ~~2. A reduction of the preliminary plat onto an 8.5 x 11 inch sheet of paper; and,~~

~~3. A copy of the preliminary plat provided in electronic format in a form determined by the Director.~~

~~D. If preliminary plat approval expires prior to application for final plat approval, the plat shall be resubmitted for preliminary approval as a new case, and the subdivider shall pay the required fee. See Section 11-20-60.040 Significance of Preliminary Plat Approval, for the requirements for extension of a preliminary plat approval.~~

#### 11-20-60.020 Preliminary Plat Requirements

A. Any subdivision shall be designed to comply with the requirements of the specific zoning district within which it is located. Should a change in zoning be necessary due to the proposed use(s), an application for a Zoning Map amendment must be initiated by the property owner or authorized representative, and then reviewed and acted upon by the Planning Commission and City Council prior to their action on the plat. Concurrent applications may be considered, with the requested Zoning Map amendment being resolved first. (See City Code Title 10, Zoning Code, Division 10-20.50, Amendments to Zoning Code Text and the Zoning Map).

B. As a prerequisite of preliminary plat review by the Director and City Engineer, the subdivider shall submit copies of letters written to the following agencies informing them of the intent to subdivide and to learn the general requirements for public utilities and public dedications applicable to the subdivision's needs:

1. Appropriate public utilities;
2. Cable television and communication companies;
3. Flagstaff Unified School District;
4. U.S.D.A. Soil Conservation Service;
5. Coconino County Health Department;
6. Arizona Department of Transportation (if the proposed subdivision abuts a state highway);
7. Coconino County Flood Control District; and,
8. Coconino County Community Development Department if the proposed subdivision is adjacent to an unincorporated area.

Written recommendations from the review agencies shall be transmitted to the Director prior to scheduling of the Planning Commission's public hearing on the preliminary plat.

BC. Preliminary Plat Requirements. —All preliminary plats shall contain the following information shown graphically or by note on plans which may comprise several sheets. Any information required as part of the preliminary plat submittal shall be shown graphically or by note on plans, or by letter, or by combination of these, and may comprise several sheets showing various elements of the required data.

Formatted: Border: Bottom: (No border)

~~All mapped data for the plat shall be drawn at the same engineering scale.~~The preliminary plat shall be drawn to a scale of not more than 1 inch = 100 feet. Preliminary plat sheets shall not exceed 24 inches by 36 inches in overall dimensions and shall have a left margin of two inches. All plats requiring more than one sheet shall have a cover sheet indicating the entire subdivision and the proposed sections to be found on the corresponding individual pages:

~~D. All preliminary plat applications shall contain the following information:~~

~~1. Notation of plat as a preliminary plat;~~

~~12. —A title that includes notation as a preliminary plat, the pProposed subdivision name and location by section, township, range, ~~baseline, meridian~~ and county;~~

~~23. Legal description of property involved and County instrument number, Assessor's Parcel Number(s), and site address;~~

~~34. Name, address, and phone number of subdivider(s), firm preparing the plat, and current landowner(s), including docket/page number by which title was conveyed;~~

~~5. Name, address, and phone number of person or firm preparing the plat;~~

~~6. Name, address, and phone number of landowner(s), and docket/page number or instrument number by which title was conveyed (warranty deed, quit claim deed, purchase agreement, or other legal instrument);~~

~~47. Bar scale, north arrow oriented to top, right or left of sheet, and dates of preparation and any revisions;~~

~~5. Location map with north arrow, scale, site location, and existing points of reference;~~

~~6. Complete and accurate legend;~~

~~7. Certification blocks (Arizona Registered Land Surveyor seal and Arizona Registered Professional Engineer stamp, if applicable);~~

~~8. Basis of bearing and record source;~~

~~9. Detailed description of monuments set and found;~~

10. Subdivision corners tied to two City control points;

11. Site acreage (gross and net);

12. Gross and net densities/intensities by lot or platted area in accordance with the provisions of City Code Title 10, Zoning Code, Chapter 10-40 (Specific to Zones);

13. Existing zoning classification(s) within the subdivision boundaries. Commercial and industrial subdivisions must also identify existing zoning classifications on abutting properties within 200 feet;

14. A topographic map for the subject property and the land within 200 feet of the subject property with a minimum two-foot contour, or such other interval as approved by the Director. Direction of drainage flow shall be indicated;

15. Location of water wells, streams, ditches, washes, lakes, or other water features; direction of flow; 100-year flood plain; location and extent of areas subject to inundation, whether such inundation be frequent, periodic, or occasional, within the subdivision boundaries and 200 feet beyond such boundaries. Also, the proposed location(s) of stormwater detention facilities shall be indicated;

16. Location, widths, and City approved names of all platted streets, bicycle and pedestrian facilities, railroads, utility rights-of-way of public record, and public areas within 200 feet of the proposed development;

17. All existing features, including but not limited to, bridges, buildings, culverts, structures, and driveway entrances within the subdivision boundaries and within 200 feet from such boundaries. Identify those which are to be removed and those to remain, and the date when any removals shall be completed. All proposed conditions shall be graphically differentiated from existing conditions on adjacent properties and on excepted tracts or parcels within the plat;

18. Location and description of proposed and existing utilities within the subdivision and within 200 feet of the proposed development. Location of water and sewer mains with respect to property lines, easements and/or street center lines, with line sizes shown. Reference by note the location and description of such utilities if not located within 200 feet of the proposed development;

19. The location of all existing and proposed fire hydrants within the subdivision;

20. Full dimensioned boundaries of the platted property (to 0.01') and bearings to 1 second, recorded and measured. Boundary survey shall be based upon field work;

21. Lot and tract dimension, bearings, and area (in square feet or acreage), with each lot and tract numbered individually and sequentially;

22. Designation of all land to be dedicated or reserved for public use with the use indicated and those areas that will be deeded to a homeowner's association;

23. 15.—Proposed street layouts shall include street names, widths, alleys, crosswalks, and connections to adjoining tracts or parcels including and street grades/slopes, clear view zones and traffic control devices. Typical cross sections of all all existing and proposed streets/roadways shall be shown.;

Parcels or tracts to be dedicated or reserved for affordable housing, school sites, parks, or other public use are to be indicated as such with intended use;

20.—The location of all proposed fire hydrants within the subdivision; 24. The location of vehicular non-access easements and non-typical building setbacks;

8.—A topographic map for the subject property and the land within 200 feet of the subject property with a minimum two-foot contour, or such other interval as approved by the Director. Direction of drainage flow shall be indicated;

9.—Existing street dedications and lot lines of all adjacent properties. Subdivided properties must be indicated by subdivision name and Coconino County Recorder's Office Case and Map number; if unsubdivided land, property owner and Docket and Page or instrument number shall be noted;

10.—Location, dimensions, and names and types of all existing and proposed rights-of-way and easements within the subdivision boundaries and 200 feet from such boundaries;

~~11.— All existing features, including but not limited to, bridges, buildings, culverts, structures, and driveway entrances within the subdivision boundaries and within a distance of 200 feet from such boundaries. Identify those which are to be removed and those to remain, and the date when any removals shall be completed. All proposed conditions shall be graphically differentiated from existing conditions on adjacent properties and on excepted tracts or parcels within the plat;~~

~~12.— Existing zoning classification(s) within the subdivision boundaries and on abutting properties;~~

~~13.— Note gross acreage of the area being platted and net acreage, if applicable;~~

~~14.— Boundaries of the platted property to be fully dimensioned. The complete boundary survey shall be based upon field work;~~

~~15.— Proposed street layout shall include street names, widths, alleys, crosswalks, and connections to adjoining tracts or parcels and clear view zones. Typical cross sections of all existing and proposed roadways shall be shown;~~

~~16.— Parcels or tracts to be dedicated or reserved for affordable housing, school sites, parks, or other public use are to be indicated as such with intended use;~~

~~17.— Size of each lot, in square feet or acres;~~

~~18.— Location map with north arrow, scale, site location, and existing points of reference;~~

~~19.— Location and description of proposed and existing utilities within the subdivision and within 200 feet of the proposed development. Locations of all above ground utility cabinets and facilities. Location of water and sewer mains with respect to property lines, easements and/or street center lines, with line sizes and valve locations shown. Reference by note the location and description of such utilities if not located within 200 feet of the proposed development;~~

~~20.— The location of all proposed fire hydrants within the subdivision;~~

~~21.— Approximate lot and tract dimensions, bearings, and area, with each lot numbered individually and the total number of lots noted;~~

~~22.— The location of vehicular non-access easements and non-typical building setbacks;~~

~~23.— A typical maximum construction envelope containing minimum building setbacks and maximum lot coverage permitted shall be noted on the plat;~~

~~24.— The preliminary plat shall include a Natural Resources Protection Plan (if applicable) and data sheet meeting the requirements of City Code Title 10, Zoning Code, Division 10-50-80 (Resource Protection Standards). The Natural Resources Protection Plan shall include all areas within the boundaries of the subdivision and access and utility corridors to the site if proposed;~~

Field Code Changed

~~25.— Gross and net densities/intensities by lot or platted area in accordance with the provisions of City Code Title 10, Zoning Code, Chapter 10-40 (Specific to Zones);~~

~~26.— Location of water wells, streams, ditches, washes, lakes, or other water features; direction of flow; 100 year flood plain; location and extent of areas subject to inundation, whether such inundation be frequent, periodic or occasional, within the subdivision boundaries and 200 feet beyond such boundaries. Also, the proposed location(s) of stormwater detention facilities shall be indicated;~~

~~27.— Plans for resource preservation, management, and mitigation of adverse impacts on neighboring properties, in compliance with City Code Title 10, Zoning Code, Division , (Landscaping Standards), if applicable;~~

~~28.— Traffic control devices;~~

~~29.— Approval block for all utilities;~~

~~30.— Certification blocks (Arizona Registered Land Surveyor seal and Arizona Registered Professional Engineer stamp, if applicable);~~

~~32.— Boundary dimensions to 0.01' and bearings to 1 second, recorded and measured;~~

~~33.— Basis of bearing and record source;~~

~~34.— Detailed description of monuments set and found;~~

~~35.— Subdivision corners tied to two City control points;~~

~~36.— Boundary of platted property to have a mathematical closure of not less than 0.01 feet. All non-tangent curves shall include a radial bearing or chord bearing and length;~~25. A typical

maximum building envelope containing minimum building setbacks and maximum lot coverage permitted shall be noted on the plat. For lots with non-typical building envelopes, show and dimension building envelope boundaries and setbacks on each lot;

~~29. Approval block for all utilities;~~

~~30. Certification blocks (Arizona Registered Land Surveyor seal and Arizona Registered Professional Engineer stamp, if applicable);~~

~~37. Approximate embankment and excavation quantities for the project;~~ ~~26. 24. The preliminary plat shall include a Natural Resources Protection Plan (if applicable) and data sheet meeting the requirements of City Code Title 10, Zoning Code, Division 10-50.90 (Resource Protection Standards). The Natural Resources Protection Plan shall include all areas within the boundaries of the subdivision and access and utility corridors to the site if proposed;~~

~~27. The preliminary plat shall include a Landscape Plan in accordance with City Code Title 10, Division 10-50.60 (Landscape Standards). The Landscape Plan shall include all areas within the boundaries of the subdivision and access and utility corridors to the site if proposed; and~~

~~38. Clear view zones;~~

~~2839. -A development phasing map and proposed timing schedule delineating the configuration, size in acres, and general sequence of development and dedication.;~~

~~CE. Proposed Utility Methods—The preliminary plat shall contain the following information with respect to proposed utilities:~~

1. It is the responsibility of the subdivider to furnish the Arizona Department of Environmental Quality (ADEQ) such information as ADEQ may require regarding the design and operation of the proposed sanitary sewage facilities.

a. A statement as to the types of facilities proposed shall appear on the preliminary plat application; and, the subdivider shall show evidence of adequate volume and quality of proposed water supply and facilities to the satisfaction of the Water Services Director.

~~2. The preliminary plat submittal shall include preliminary calculations and a description of proposed stormwater disposal outlets to the satisfaction of the City Engineer.~~

~~3. A plan from private or franchise utility companies showing the location of proposed utility facilities.~~

**DF.** A preliminary plat submittal for a condominium subdivision shall include the following additional information as required by A.R.S. § 33-1219:

1. The location and dimension of the vertical boundaries of each unit and each unit's identifying number;

2. Any horizontal unit boundaries with reference to an established datum and each unit's identifying number;

3. Any units with respect to which the declarant has reserved the right to create additional units or common elements identified appropriately;

4. The location and dimensions of all real estate subject to the development right of withdrawal and identified as such;

5. The location and dimensions of all real estate in which the unit owner will only own an estate for years labeled as a "leasehold condominium";

6. The distance between contiguous parcels of real estate comprising the condominium;

7. The location and dimension of limited common elements ( such as porches, balconies, patios, parking spaces, garage spaces, entryways, etc.);

8. The extent of any encroachments of any portion of the condominium;

9. To the extent feasible, the location and dimensions of all easements serving or burdening any portion of the condominium; and

~~1-10.~~ Any units with respect to which the declarant has reserved the right to create additional units or common elements, identified appropriately.

~~1. The plat shall be clear and legible, and is a part of the declaration; and,~~

2.—The plat shall show the following:

- a.—The name of the condominium;
- b.—The boundaries of the condominium and a legal description of the real estate included in the condominium;
- c.—The extent of any encroachments on any portion of the condominium;
- d.—To the extent feasible, the location and dimensions of all easements serving or burdening any portion of the condominium;
- e.—The location and dimensions of the vertical boundaries of each unit, and each unit's identifying number;
- f.—Any horizontal unit boundaries, with reference to an established datum, and each unit's identifying number;
- g.—Any units with respect to which the declarant has reserved the right to create additional units or common elements, identified appropriately;
- h.—The location and dimensions of all real estate subject to the development right of withdrawal and identified as such;
- i.—The location and dimensions of all real estate in which the unit owner will only own an estate for years, labeled as a "leasehold condominium";
- j.—The distance between noncontiguous parcels of real estate comprising the condominium;
- k.—The location and dimensions of limited common elements, including porches, balconies, patios and entryways; and,

l.—Any other matters the declarant deems appropriate. C.—E. 11-20-60.030 Preliminary Plat Review and

Approval.

-approval of a preliminary

Formatted: Border: Bottom: (No border)

C. Upon a recommendation of approval of the preliminary plat by the Director, the subdivider or an authorized representative shall submit the following materials to the Director in accordance with the submittal deadlines on file with the Planning Section:

Any subdivision shall be designed to comply with the requirements of the specific zoning district within which it is located. Should a change in zoning be necessary due to the proposed use(s), an application for a Zoning Map Amendment must be initiated by the property owner or authorized representative concurrent with the preliminary plat application. (See City Code Title 10, Zoning Code, Division 10-20.50, Amendments to Zoning Code Text and the Zoning Map).

Formatted: Border: Bottom: (No border)

1. Staff Review. All applications shall be reviewed by staff for completeness. If the application is deemed incomplete as to the requirements set forth in this chapter, the submittal will be returned to the applicant for revision and resubmittal. Once the application has been deemed administratively complete, staff will complete substantive review of the preliminary plat. If staff finds the plat requires major revision, the plat shall be returned to the applicant with specific revisions noted. All required revisions shall be called out and noted on the resubmitted plat. Revisions made to a resubmitted plat that are not in response to staff comments shall require the application to be resubmitted as a new application unless the Director determines that a new application is not necessary.

2. Staff Approval. The Director and City Engineer shall approve the application once the preliminary plat has been found in compliance with this chapter; City Code Title 10, Zoning Code; City Code Title 12, Floodplains; and City Code Title 13, Engineering Design Standards and Specifications for New Infrastructure. If the plat is generally acceptable but requires minor revision before proceeding with the preparation of the final plat, a conditional approval may be granted with required revisions noted.

3. Denial of Preliminary Plat. If a preliminary plat application is denied by the Director and City Engineer, the reasons for such denial shall be provided in writing to the subdivider. The preliminary plat application can be re-filed at any time after denial, if required revisions can resolve the reasons for the denial. The re-filing of a preliminary plat application for the same subject property, or any portion of the property, shall follow the procedures and requirements specified in this chapter.

4. Appeal of Preliminary Plat Decision. A decision of the Director and City Engineer may be appealed in compliance with the appeal procedures established in Section 11-20.130 Appeals.

~~1. The required number of copies as specified in the handout available from the Planning Section of the preliminary plat reproduced in the form of blue or black line prints on a white background;~~

~~5. Approval of Preliminary Plat by City Council. Any preliminary plat utilizing the Planned Residential Development standards established in City Code Title 10, Flagstaff Zoning Code Section 10.40.60.280 or modifications to City Code Title 13, Engineering Design Standards and Specifications for New Infrastructure shall be approved by City Council prior to submission of engineering plans.~~

~~2. A reduction of the preliminary plat onto an 8.5 x 11 inch sheet of paper; and,~~

~~3. A copy of the preliminary plat provided in electronic format in a form determined by the Director.~~

~~D. If preliminary plat approval expires prior to application for final plat approval, the plat shall be resubmitted for preliminary approval as a new case, and the subdivider shall pay the required fee. See Section 11-20.60.040 Significance of Preliminary Plat Approval, for the requirements for extension of a preliminary plat approval.~~

~~A. An application for preliminary plat approval shall comply in all respects with the provisions of this Chapter and the City of Flagstaff Flood Plain Regulations.~~

~~B. An applicant shall submit all of the documents, information, data, and other requirements for preliminary plat approval to the Director and City Engineer.~~

~~C. In addition to the requirements of the preceding subsections, the applicant shall provide the Director and City Engineer with any additional information, documents, or other material relevant to the application as required by City codes and regulations that are necessary for the Director, the Planning Commission, and the City Council to evaluate, analyze, or understand the subject matter of the application.~~

~~D. The applicant or the applicant's agent shall be encouraged to either hold a public meeting to inform area residents of the proposed subdivision or notify them by direct mail to provide information on the proposed subdivision. If the applicant or the applicant's agent decides to hold either a public meeting or notify adjoining residents by direct mail of the proposed subdivision, notice of the public meeting and information regarding the proposed subdivision shall be provided to property owners within a minimum~~

~~of 300 feet of the proposed subdivision. Notice of the meeting and information regarding the subdivision should also be provided on the applicant's web site if one exists.~~

~~E.—A preliminary plat application shall not be deemed to have been filed or properly submitted until all fees have been paid and all of the above listed requirements have been satisfied as determined by the Director.~~

~~F.—The procedure for approval, amendment, or denial of preliminary plat applications shall be as follows:~~

~~1.—Pursuant to the provisions of this Chapter, the Director and City Engineer shall review the application for a preliminary plat, including all impact analyses required as part of the submittal with the preliminary plat application.~~

~~2.—The Planning Commission shall recommend the approval or denial of a preliminary plat to the City Council within 45 days of the first consideration of the plat by the Commission.~~

~~3.—After a final recommendation on a preliminary plat by the Planning Commission, the City Council shall approve, conditionally approve, or disapprove the application within 60 days of the first consideration of the plat by the City Council.~~

~~4.—If a preliminary plat application is denied by the City Council, the minutes shall state the reasons for such denial. The preliminary plat application can be re-filed at any time if revision can resolve the reasons for the denial as originally proposed. The new filing of a preliminary plat application for the same subject property, or any portion of the property, shall follow the procedures and requirements specified in this division.~~

~~F. 11-20.60.040 Significance of Preliminary Plat Approval.~~

~~Preliminary plat approval by the Director and City Engineer~~City Council~~ constitutes authorization for the subdivider to proceed with preparation of the final plat and engineering plans and specifications.~~

~~Preliminary plat approval is subject to the following conditions:~~

- ~~1. The preliminary plat is valid for a period of two years from the date of approval; thereafter, such approval shall be deemed to have expired;~~

Formatted: Border: Bottom: (No border)

~~1. A. The conditions under which approval of the preliminary plat is granted will not be changed prior to the expiration date;~~

Formatted: No bullets or numbering

~~2. B. Approval is valid for a period of two years from the date of City Council approval; thereafter, such approval shall be deemed to have expired;~~

Formatted: Indent: Left: 0.25", No bullets or numbering

3. C. Preliminary plat approval may, upon written application to the Director by the subdivider, be extended for an additional one year if, in the opinion of the Director, there is no change in conditions within or adjoining the preliminary plat which could warrant a revision of the original preliminary plat;

2.           

~~3. The conditions under which approval of the preliminary plat is granted will not be changed prior to the expiration date;~~

Formatted: Indent: First line: 0"

~~D. If preliminary plat approval expires prior to application for final approval, the plat shall be resubmitted for preliminary approval as a new case and the subdivider shall be required to pay a new fee;~~

Formatted: Indent: Left: 0.25", Space After: 0 pt, Line spacing: single, No bullets or numbering

Formatted: Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5"

4.           

~~4. E. A preliminary plat may not be recorded; and,~~

Formatted: Indent: Left: 0.25", First line: 0", Numbered + Level: 1 + Numbering Style: 1, 2, 3, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" +

5.           

~~5.6. F. Preliminary plat approval does not constitute approval to clear, grade, remove trees, or perform other land or construction activity. A separate permit as determined by the Engineering Division shall be obtained prior to the initiation of any of the above listed activities.~~

**11-20.70**

**Final Plat**

**Sections:**

~~Plat Submittal and Review by Director~~

~~Final Plat Requirements~~

~~Final Plat Approval~~

**11-20.40.040 Final Plat**~~70.010 Plat Submittal and Review by Director~~ 

This section provides procedures for the review and approval of final plats consistent with applicable law. The procedures established in this section shall apply to all proposals for final plat. Requests for final plat review shall only be made through the procedures described in this section.

A. A. Final Plat Submission. A final plat will only be accepted upon approval of a preliminary plat and approval from the City Engineer that the engineering plans have been reviewed and major substantive comments have been resolved. The applicant shall electronically submit the following materials in support of a final plat application for a new subdivision to the Director in accordance with the submittal deadlines and review schedule on file with the Planning & Development Services Section:engineering. The subdivider shall submit a final plat and application to the Director for review in accordance with the Review Schedule on file with the Planning Section. The final plat shall conform to the approved preliminary plat, and shall contain all information and conform to all requirements for final plat preparation as specified below:

1. CA-completed final plat application form. If the subdivider is not the current landowner of all the subject real property, a signed and notarized statement shall also be filed attesting that the owner grants to the subdivider authority to represent the owner in the final plat submission and approval process;

2. The required number of paper copies of the final plat, as specified in the handout available from the Planning Section, reproduced as blue or black line prints on a white background;

3. A non-refundable final plat filing fee (See Appendix 2, Planning Fee Schedule);

3.4. One complete title report for the property notarized by a state-registered title company, a closure report signed and sealed by a registered surveyor that indicates the boundary of the platted property to have a mathematical closure of not less than 0.01 feet;

4. Legal descriptions and landowner approvals for all dedications required to serve the proposed development outside of the subdivision boundaries in accordance with the approved preliminary plat, civil plans, or as otherwise required through other approvals or agreements;

5. A registered surveyor shall provide a signed and sealed certification that there are no conflicting encumbrances City/Subdivider Agreement executed by the subdivider; and

Formatted: Border: Bottom: (No border)

~~6. The Director may request any other information that is relevant to assist in the review of a final plat. The Director may waive the requirements for any of the information required in this section if it is determined that such information is not necessary to complete a review of the requested final plat.~~

~~6. The required number of copies of landscaping plans for public and private rights-of-ways, if applicable, as specified in the handout available from the Planning Section.~~

~~B. Upon receipt of the final plat application, the Director shall date and initial receipt of the materials and check the plat for conformity to the preliminary plat as approved or modified and for compliance with the requirements for final plats as set forth in Section 11-20.70.020, Final Plat Requirements.~~

Formatted: Indent: Left: 0"

~~BC. Upon approval of the final plat application and final plat by the City Council, the subdivider shall submit to the Director the following, which shall be dated upon receipt:~~

~~1. 1. One opaque linen or Mylar copy of the final plat for recordation including utility companies' signatures and dates, and property owners' signatures and dates;~~

Formatted: Indent: Left: 0.25", First line: 0"

~~1.~~

~~2. 2. One reproducible Mylar copy of the final plat; and,~~

Formatted: Indent: Left: 0.25"

~~2. 3. An eOne-electronic copy of the final plat, provided in a format determined by the City Engineer; and,~~

~~3. Executed Assurance of Performance Agreement.~~

~~C. 11-20.70.020-Final Plat Requirements.~~

Formatted: Border: Bottom: (No border)

~~A. All final subdivision plats shall be designed to comply with the requirements of the specific zoning district (zone) within which they are located.~~

~~B. The subdivider shall submit copies of the final plat to the appropriate public/quasi-public utility agencies prior to seeking City Council action on a final plat. Written comments by the agencies shall be made to the Director as a part of the application. The Director shall submit the final plat application together with the utility agencies' comments to the City Council.~~

~~C.~~—The final plat shall substantially conform, at the discretion of the Director and City Engineer, to the approved preliminary plat, and shall be in compliance with all appropriate City standards, codes, specifications, and requirements. All final plats shall contain the following information shown graphically or by note on plans which may comprise several sheets. The final plat shall be drawn to a scale of not more than 1 inch = 100 feet with a font size no less than 10 points. Final plat sheets shall not exceed 24 inches by 36 inches in overall dimensions and shall have a left margin of two inches. All plats requiring more than one sheet shall have a cover sheet indicating the entire subdivision and the proposed sections to be found on the corresponding individual pages:

Formatted: Border: Bottom: (No border)

~~D.~~—Every subdivision shall conform to the objectives of any comprehensive general plan approved or as amended by the City Council, except where existing development rights supersede the subdivision proposal, such as if the property has vested and/or nonconforming rights.

~~E.~~—Any information required as part of the final plat submittal shall be shown graphically, by note, by letter, or in combination on the plans, and may comprise several sheets showing various elements of the required data.

~~F.~~—The final record plat of a subdivision shall be drawn in waterproof ink on linen or other non-shrinking material on a sheet not to exceed 24 inches by 36 inches in overall dimensions, and shall have a left margin of two inches. All final plats requiring more than one sheet shall have a cover sheet indicating the entire subdivision and the proposed sections to be found on the corresponding individual pages. The final plat shall be drawn to an accurate scale of not more than 1 inch = 100 feet.

~~G.~~—Submittal of documents of dedication does not automatically convey such lands or rights of way into public ownership; such dedications must be accepted by the City Council. Submittal of documents of dedication also does not automatically indicate acceptance of the land dedicated for maintenance by the City. Acceptance for maintenance by the City requires a request by the subdivider or property owner to the City Council and specific action by the Mayor and City Council for such acceptance for maintenance by the City, and the execution of a City/Subdivider Agreement.

~~H.~~—Avigation easement if appropriate.

~~I.~~—All lands to be dedicated to the City that are not considered rights of way require a warranty deed to be recorded with the final plat.

~~J. All final plats shall contain the following information:~~

~~1. A title that includes notation as a final plat, the name of the subdivision, and ~~its~~ location by ~~number of~~ section, township, range, ~~meridian~~ and county;~~

~~2. Legal description of property involved and County instrument number, Assessor's Parcel Number(s), and site address;~~

~~3. Name and address of subdivider (record owner), and name, address, registration number, and seal of the registered land surveyor and civil engineer responsible for preparing the plat;~~

~~3. Name, address, and registration number of the registered civil engineer responsible for the preparation of the engineering drawings that are necessary for the proposed subdivision;~~

~~4. Utility companies' signatures and date;~~

~~4.5. Bar scale, north arrow oriented to top, right or left of sheet, and date of plat preparation;~~

~~5. Location map with north arrow, scale, site location, and existing points of reference;~~

~~6. Complete and accurate legend;~~

~~7. Certification blocks (Arizona Registered Land Surveyor seal and Arizona Register Professional Engineer stamp, if applicable);~~

~~8. Approval block for all utilities;~~

~~9. Basis of bearing and record sources;~~

~~10. Detailed description of monuments set and found;~~

~~11. Subdivision corners tied to two City control points;~~

~~6. Boundaries of the tract to be subdivided shall be mathematically correct and show all record and measured bearings and distances. Boundary dimensions to 0.01' and bearings to 1 second shall be shown, as well as a description of all found monuments;~~

~~127.~~ -Any excepted parcel or parcels within the plat boundaries shall be accurately described by bearings and distances determined by an accurate survey in the field. All dimensions shall be expressed to 0.01' and bearings to 1second;

~~8. — Record basis of bearing and two corners of the subdivision shall be tied by course and distance to separate survey monuments approved by the City Engineer;~~

~~139.~~ -Names, centerlines, right-of-way lines, courses, lengths, and widths of all public streets, alleys, public trails, and easements to be dedicated. Points of tangency of all curvilinear streets and alleys shall be shown. Curve data shall include radius, length, central angle, and radial bearings (or chord bearing and chord length) on non-tangent curves;

~~149.~~ -Location, dimensions, and area (square feet or acres) of all lots and tracts shall be shown. Lot dimensions and appropriate bearings shall be indicated for all lot lines. In areas subject to flooding, minimum finished first floor elevations shall be shown as may be recommended by the appropriate authority;

~~154.~~ -All lots shall be numbered consecutively throughout the plat. Parcels or tracts for affordable housing, school sites, parks, open space areas, or other public uses shall be so designated, lettered, or named, and clearly dimensioned;

~~162.~~ -The accurate outline of all property which is offered for dedication for public use and of all property that may be reserved ~~by deed covenant~~ for the common use of the property owners in the subdivision shall be shown;

~~173.~~ -Subdivision name, case number, and map number of adjacent recorded subdivisions, with location of existing adjacent lots, easements, and rights-of-way shown, or docket and page or instrument number, where appropriate. All proposed conditions shall be graphically differentiated from existing conditions on adjacent properties and on excepted parcels within the plat;

~~184.~~ -The following notation shall be placed upon all final plats for public utility easements: "Except for construction and improvements by governmental entities and certified public utilities, construction and improvements within utility easements shall be limited to the following:

- a. Removable wood, wire, or sectional fencing generally positioned perpendicular to the easement and approved by the City Engineer; and,

- b. Construction, structures, or buildings expressly approved in writing by all public utilities [and the City Engineer](#) which use or shall use the utility easement";

~~1915.~~ -Statement and acknowledgment of the dedication of all streets, alleys, drainageways, utility easements, crosswalks, bike paths, pedestrian ways, including but not limited to sidewalks, crosswalks and trails, and other easements for public use by the persons holding title of record, by persons holding title as vendees under land contract, and by spouses of said parties, if jointly owned. If lands dedicated are mortgaged, the mortgagee shall also sign the plat. Dedications shall include a written location by section, township, and range of the tract. If the plat contains private streets, provisions should be made so that the public utilities reserve the right to install and maintain utilities above, on, and below such private streets or ways;

~~2016.~~ -The following certifications must be included on the final plat in the form as determined by the Director:

- a. Certification by a registered land surveyor that the plat is correct and accurate, and that the monuments described in it have been located as described;
- b. Certification of plat approval by the City Engineer;
- c. Certification of plat approval by the Director;

~~d. Certification of plat approval by the City Council;~~

~~2147.~~ -The location of appropriate vehicular non-access restrictions as well as intersection clear view zones if located on a lot(s) shall be included on the plat;

~~22. H. Avigation easement if appropriate;~~

~~23~~

~~18.~~ -A typical maximum construction envelope containing minimum building setbacks and maximum permitted lot coverage shall be shown on the plat. Dimensioned non-typical construction envelopes shall be shown on the individual lots which are affected;

~~2449.~~ –Floodplain limits and the following text when applicable: "Lots \_\_\_\_\_ have been identified as being partially or wholly within a flood hazard area per F.I.R.M. Map \_\_\_\_\_, revision date \_\_\_\_\_. Because flood hazard boundaries may be revised periodically, the most recent flood hazard map for this area should be reviewed to determine the exact limits and severity of potential flooding on these lots. Flood hazard maps and requirements for construction within flood hazard areas can be obtained from the City of Flagstaff";

~~259.~~ –Subdivisions that are associated with a rezoning ordinance shall identify the ordinance number and the instrument number of the recorded ordinance on the plat; and

~~23.—A complete and accurate legend;~~

~~24.—A location map with north arrow; and,~~

~~25.—All information on the plat must be legible.~~

~~26K.~~ –A final plat submittal for a condominium subdivision shall also include the additional information as required by Section 11-20.60.020, Preliminary Plat Requirements.

D. Dedications. A statement of dedication of all streets, alleys, drainageways, pedestrian ways, and other easements for public use by the subdivider shall be provided with the final plat submittal. Standard dedication language is kept on file with the Planning & Development Services Section. This language shall be utilized on all final plats unless alternative language is approved by the Director and City Engineer. If lands to be dedicated are mortgaged, the mortgagee shall sign the plat and required dedications.

1. City Council Acceptance of Dedications. All public land dedications and all lands dedicated for maintenance by the City must be accepted by the City Council prior to recordation of the final plat. All lands to be dedicated to the City that are not included in the plat boundaries require a separate instrument (warranty deed) to be recorded with the final plat. If the plat contains private streets, public access and utility easements shall be provided.

2. Abandonment of Dedications. Where there are temporary easements, landscaped easements and/or utility easements that are to be vacated (removing any City interest in the easement) they can be shown on the plat and described as such. A roadway right-of-way or easement can be shown

for abandonment on the plat or replat only if the requirements of State law are met concurrently with City Council approval.

3. Acknowledgement of Dedication. Execution of dedication shall be acknowledged and certified by a notary public.

E. ~~11-20-70-030~~ Final Plat Review and Approval. Any subdivision shall be designed to comply with the requirements of the specific zoning district within which it is located. Should a change in zoning be necessary due to the proposed use(s), an application for a Zoning Map Amendment must be initiated by the property owner or authorized representative, and then reviewed and acted upon by the Planning Commission and City Council prior to submittal of a final plat. (See City Code Title 10, Zoning Code, Division 10-20.50, Amendments to Zoning Code Text and the Zoning Map).

Formatted: Border: Bottom: (No border)

~~A.—An application for approval of a final plat shall not be filed unless there is an approved preliminary plat for the proposed subdivision as provided for in Division , Preliminary Plat.~~

~~B.—An applicant for final plat approval shall comply in all respects with the provisions of this Chapter.~~

~~C.—An applicant shall submit all of the documents, information, data, and other requirements for final plat approval to the Director and shall furnish all information and materials needed by the Director and City Engineer to satisfy the requirements of Division , Final Plat.~~

~~D.—In addition to the requirements of the preceding subsections, the applicant shall provide to the Director and City Engineer any additional information, documents, or other material relevant to the application that the Director and City Engineer reasonably believe are necessary in order for the City Council to evaluate, analyze, or understand the subject matter of the application.~~

~~E.—An application for final plat approval shall not be deemed to have been filed or properly submitted until all fees have been paid and assurances provided and all of the above listed requirements have been complied with as determined by the Director.~~

~~F.—The procedures for approval, amendment, or denial of final plat applications shall be as follows:~~

1. Staff Review. All applications shall be reviewed by staff for completeness. If the application is deemed incomplete as to the requirements set forth in this chapter, the submittal will be returned to the applicant for revision and resubmittal. Once the application has been deemed administratively complete, staff will complete substantive review of the final plat. If staff finds that

~~the plat requires revision, the plat shall be returned to the applicant with specific revisions noted. During the substantive review period, the subdivider may only respond to comments provided by staff. All required revisions shall be called out and noted on the plat. Revisions made to the plat, not in response to staff comments, shall require the application to be resubmitted as a new application unless determined that a new application is not necessary by the Director and City Engineer. The Director and City Engineer shall approve or disapprove an application for a final plat pursuant to the provisions of this Chapter.~~

Formatted: Not Highlight

Formatted: Not Highlight

2. Staff Approval. ~~The Director and City Engineer shall approve the application once the final plat has been found in compliance with this chapter; City Code Title 10, Zoning Code; City Code Title 12 Floodplains; and City Code Title 13, Engineering Design Standards and Specifications for New Infrastructure.~~ ;

~~a. Upon receipt of a final recommendation on an application for a final plat from the Director and City Engineer, the application and an executed City/Subdivider Agreement shall be transmitted to the City Council for final approval. After approval of the final plat by the City Council and certification by the City Engineer, the City Manager shall request that the City Clerk and the Mayor transcribe a certificate of approval upon the plat and that the Mayor and City Clerk execute the City/Subdivider Agreement, first making sure that the other required certifications and dedications have been duly signed and acknowledged.~~

~~b. The subdivider shall then pay to the City the fee charged by the Coconino County Recorder for the recordation of the plat and the City/Subdivider Agreement. The City shall then promptly record the plat with the Coconino County Recorder, pursuant to A.R.S. § 9-463.01.~~

~~3. Amendment:~~

~~a. When the final plat has been approved by the City Council and recorded with the Coconino County Recorder all development regulations and conditions of approval applicable to the final plat are final and may not be amended except upon application to the Director following the procedures for subdivision approval established in Division 11-20-40, Subdivision Procedures and Requirements.~~

Field Code Changed

~~b. If the City Council finds that the plat requires further amendment, the case shall not be approved until the amendments can be satisfactorily accomplished.~~

~~3.4. Denial of Final Plat. If a final plat application is denied by the Director and City Engineer, the reasons for such denial shall be provided in writing to the subdivider. The final plat application can be re-filed at any time if revision can resolve the reason for the denial as originally proposed. The new filing of a final plat application for the same subject property, or any portion of the property, shall follow the procedures and requirements specified in this chapter; and:~~

~~4. Appeal of Final Plat Decision. A decision of the Director and City Engineer may be appealed in compliance with the appeal procedures established in Section 11-20.130 Appeals. If the City Council disapproves the final plat, the minutes shall state the reasons for such denial. The final plat application may be re-filed at any time if revision can resolve the reasons for the denial as originally proposed. The new filing of a final plat application for the same tract, or any portion of the plat, shall follow the procedures and requirements specified in this section.~~

~~G. The final plat shall not be recorded until both of the following requirements have been satisfied:~~

~~1. Engineering plans for water, public sanitary sewer facilities, grading, and all other improvements have been approved by the City Engineer, and~~

~~2. The subdivider has posted an assurance of performance as set forth in City Code Title 10, Zoning Code, Division , Assurance of Performance for Construction, to guarantee the installation of required improvements.~~

~~G. Submittal of documents of dedication does not automatically convey such lands or rights of way into public ownership; such dedications must be accepted by the City Council. Submittal of documents of dedication also does not automatically indicate acceptance of the land dedicated for maintenance by the City. Acceptance for maintenance by the City requires a request by the subdivider or property owner to the City Council and specific action by the Mayor and City Council for such acceptance for maintenance by the City, and the execution of a City/Subdivider Agreement.~~

~~I. All lands to be dedicated to the City that are not considered rights of way require a warranty deed to be recorded with the final plat.~~

F. Recordation. Final plats shall not be recorded until the following requirements have been satisfied:

**Commented [DLM1]:** Do we need to clarify that the City Clerk records the final plat?

**Commented [TAZR1]:** Yes I talked to Stacy and she is good with this. Have language and will add.

**Formatted:** Indent: Left: 0", First line: 0", Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 6 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5", Tab stops: 0.25", Left

1. Engineering plans for water, public sanitary sewer facilities, grading, and all other improvements have been approved by the City Engineer;

2. All public dedications have been accepted by the City Council;

3. The subdivider has posted the required assurance of performance and/or third party trust and the City Engineer has fully executed the Subdivider Performance Agreement and/or third party trust agreement as set forth in City Code Title 10, Zoning Code, Division 10-20.100, Assurance of Performance for Construction, to guarantee the installation of required improvements. If applicable, the third party trust agreement shall be recorded by the City Clerk along with the final plat; and-

4. The City Clerk shall be responsible for recording all plats with the Coconino County Recorder's office.

Formatted: p2, Indent: Left: 0.25", Space After: 12 pt

Formatted: Font: Not Bold

**11-20.40.050~~80~~**

**Development Master Block Plats**

Sections:

—In General

**11-20.80.010 In General**

A ~~Development master block plat~~ **Master Plan** is a comprehensive ~~preliminary~~ master subdivision to assist with plan for the development of a large or complicated land area, which may be developed in progressive steps ~~or as a planned development~~.

Formatted: Border: Bottom: (No border)

A. A ~~development master block plat plan~~ is required ~~as a condition precedent to the review and approval of a preliminary plat or for a Zoning Map amendment request (See Division 10-20.50, Amendments to the Zoning Code Text and the Zoning Map)~~ when:

1. The subject property ~~(ies)~~ is proposed to be ~~subdivided~~ developed in stages, phases, or units; or,

2. ~~The subject property(ies) proposed for development is part of a larger land area that has unusual topographic, utility, land use, or other conditions. The larger land area may or may not be under the subdivider's control; or,~~

~~3.— A Planned Residential Development (Refer to City Code Title 10, Zoning Code, Section 10-40.60.250 (Planned Residential Development) is proposed; or, 2. The subdivider is intending to manage required resource preservation or open space requirements throughout a larger land holding with individual subdivisions or developments; or~~

~~3.4. The subject property(ies) initially proposed for platting is is only a portion of a larger land holding of the subdivider that is intended to be subdivided or developed separately; or,~~

~~4.55. The subject property(ies) is located within two or more zoning districts with different land uses.~~

B. The ~~master block plat Development Master Plan~~ shall be prepared in accordance with the provisions of this chapter for preliminary and final plat. The master block plat may also include the following as determined by the Director and City Engineer: to scale and accuracy commensurate with its purpose, and shall include the following items:

1. —A development phasing map and proposed timing schedule delineating the configuration, size in acres, and general sequence of development and dedication;

~~2. —Drawings of the final plat, digital and hard copy, in accordance with the provisions of the Engineering Standards;~~

2. General street pattern with particular attention to collector streets and future circulation throughout the larger land area, and proposed traffic impacts and access plan;

3. General location and size of school sites, parks, or other public areas;

4. Location of proposed land uses;

5. Methods proposed for sewage disposal, water supply, and storm drainage, and their general layout;

6. Identification of the proposed phases of development, and the anticipated time frame for such development;

**Commented [TA3]:** Each phase shall be have its own engineering plans and final plat.

- 7. General location of all natural resources and environmental constraints including but not limited to forests, floodplains, and steep slopes which will be affected by the proposed subdivision;
- 8. General location of natural resources to be protected; and,
- 9. Pedestrian/bicycle circulation infrastructure system concept.

~~C.—If the Director determines that a development master plan is required, then the development master plan shall be submitted in accordance with the submittal deadlines established by the Director. The Director shall approve or disapprove the Development Master Plan pursuant to the provisions of this chapter. If the development master plan is denied by the Director, the subdivider/applicant may appeal to the Planning Commission in accordance with the appeal provisions established in Division 11-20.180, Appeals. Following action by the Director, the development master plan shall be submitted to the Planning Commission for their review and approval. If the development master plan is not approved by the Planning Commission, the subdivider may appeal to the City Council.~~

~~D.—The development master plan shall be submitted as part of the preliminary plat application to the Planning Commission and City Council. If development will take place in several phases, the development master plan shall be submitted as supporting data for each phase. The development master plan shall be kept up to date by the subdivider as modifications take place.~~

**11-20.90**

**11-20.40.060 Modified Subdivision Process**

Sections:

- Applicability
- Modified Subdivision

**11-20.90.010** ~~Applicability~~ 

A modified subdivision process applies to subdivisions where a maximum of tenfour lots are proposed.

Formatted: Border: Bottom: (No border)

~~A. 11-20.90.020 Modified Subdivision Review and Approval Process.~~

~~B.A. The requirement for Planning Commission review of a preliminary plat may be waived at the request of the subdivider when the proposed subdivision contains four or fewer lots. The review and approval of these modified subdivisions includes the following progressive stages:~~

~~1. A. Pre application conference (Refer to Section )~~

~~B. Conceptual Plats (Refer to Division )~~

~~C. Final Plats (Refer to Division )~~

~~Pre-application meeting (Refer to Section 11-20.40.020);~~

~~2. Submittal and approval of engineering plans for the required subdivision improvements;~~

~~3. Final plat submittal, review, and approval (Refer to Section 11-20.40.040); and~~

~~4. Recordation of approved Final Plat with the Coconino County Recorder.~~

#### 11-20.40.070 Plat Amendments

~~A. Certificate of Correction. The Director and City Engineer may approve minor amendments to a recorded subdivision plat without re-platting the subdivision, through a Certificate of Correction.~~

~~1. Allowable minor change items include the following:~~

~~a. Engineering Errors. Change is due to an obvious error or omission in the preparation of the final plat. This does not include design errors; changes to or relocations of any parcel or easement boundary or line; or changes to the legal description or the land area which is included in the subdivision.~~

~~b. Name changes, including but not limited to change in the names of subdivisions, streets, or places.~~

~~2. The Certificate of Correction shall include the following information:~~

~~a. The corrections and/or changes requested;~~

~~b. The date the plat was recorded;~~

~~c. The instrument number of the plat which is to be modified;~~

**Formatted:** Indent: Left: 0", Numbered + Level: 1 + Numbering Style: A, B, C, ... + Start at: 1 + Alignment: Left + Aligned at: 0.25" + Indent at: 0.5", Border: Bottom: (No border)

**Formatted:** Font: (Default) +Body (Calibri), 11 pt, Font color: Text 1

d. Signature lines for approval by the Director and City Engineer.

3. The Certificate of Correction shall be recorded prior to any act on the changes.

B. Replat. Any request to vacate, alter, or amend some or all of a recorded subdivision plat that does not include a certificate of correction, boundary adjustments, abandonment or vacation of public rights-of-way, or a reversion to acreage.

1. Petition for Replat. The City on its own initiative may consider the vacation, alternation, or amendment of a subdivision plat. Any fee owner of property lying within a recorded subdivision plat may petition the City to vacate, alter, or amend some or all of the subdivision plat. The petition shall include the following:

a. The name and address of all owners of record of the land contained in the entire plat or on that portion of the plat described in the petition;

b. The signature of each of the owners identified in the petition; and

c. If the land described in the petition is owned in common for the benefit of all other fee owners within the subdivision boundaries, the signatures of each owner within the subdivision plat shall be provided unless individual representatives are elected through covenants, conditions, and restrictions.

2. Notice. Notice of any subdivision replat shall be provided as specified in City Code Title 10, Zoning Code, Subsection 10-20.30.080 Notice of Public Hearing to all fee owners within the subdivision plat boundaries. The notice must include provisions for any fee owners to object in writing to the City within 15 days of the mailed notice.

3. Replat Review and Approval. The replat shall be reviewed and approved in accordance with the provision for final plat review and approval except as modified below:

a. If the City receives written objections within the required timeframes from any fee owner within the boundaries of the subdivision plat to be re-platted the matter shall be referred to the City Council for review and approval.

4. Grounds for Approving a Replat. The Director and City Engineer or City Council may approve a re-plat if they find that there is good cause for the replat, and no public street or municipal utility easement has been vacated or amended.

**3. Amendment:**

1. ~~a.~~ and City Engineer (written consent) and City Engineer due to an or omission in the preparation of the final plat. When the final plat has been approved by the City Council and recorded with the Coconino County Recorder all development regulations and conditions of approval applicable to the final plat are final and may not be amended except upon application to the Director following the procedures for subdivision approval established in Division Subdivision Procedures and Requirements.

Formatted: Font: (Default) +Body (Calibri), 11 pt

5 and: b. If the City Council finds that the plat requires further amendment, the case shall not be approved until the amendments can be satisfactorily accomplished.

**11-20.50**

**Land Splits and Combinations**

Sections:

11-20.50.010 Purpose and Intent

11-20.50.020 Land Split Procedures and Requirements

11-20.50.030 Pre-Application Conference

11-20.50.040 Land Split or Combination Applications

~~—Lot Splits for Secondary Single-Family Dwellings~~

**11-20.50.010 Purpose and Intent** 

The purpose of these regulations is:

- A. To provide for the partitioning of land into two or three lots, tracts or parcels of land or the combination of lots, tracts or parcels through a process that is more expeditious than the subdivision process;
- B. To assure that the proposed parcels are in conformance with the City’s development standards;
- C. To obtain accurate surveying and permanent public record of the separate interests created and conveyed by the division of lands; and,
- D. To assure adequate access and to provide a coordinated street system.

**11-20.50.020 Land Split or Combination Procedures and Requirements**

The preparation, submittal, review, and approval of all land splits or combinations located within the City limits shall proceed through the following progressive stages, except as otherwise provided in this chapter:

- A. Optional pre-application ~~meeting~~ conference with the Director;
- B. Submittal by the subdivider, and review and approval of the land split or combination application and map by the Director; and
- C. Recordation of the approved land split or combination map and associated legal description with the Coconino County Recorder’s office.

**11-20.50.030 Pre-Application Meeting ~~Conference~~**

- A. The pre-application ~~meeting~~ conference stage of land split or combination review is an optional investigatory period preceding the preparation and submittal of the land split or combination application by the subdivider. The subdivider shall initially present the land split or combination

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

proposal to the Director who shall advise the subdivider of specific public objectives, standards, and regulations related to the property and the procedure for land split or combination review.

B. An application for land split or combination approval shall include a sketch plan of the proposed land split or combination so that the Director can determine whether the approval process authorized by this Division can and should be utilized. The Director may require the applicant to submit whatever information is necessary to make this determination, including, but not limited to, a copy of the Coconino County Assessor's Map showing the land being divided and all lots or parcels previously divided from that tract of land and all contiguous land under the same ownership 15 years prior to December 16, 2010, the effective date of these regulations.

#### **11-20.50.040 Land Split and Combination Applications**

A. Application Submittal:

1. All land split or combination applications shall include the following materials:
  - a. The required number of copies of the land split or combination map reproduced in the form of blue or black line prints on a white background, or suitable copies showing the proposed Land split or combination, existing conditions including the location of all structures, and anticipated setbacks from existing and proposed property lines;
  - b. Any information required as part of the land split or combination submittal shall be shown graphically, or by note, or by letter, or in combination on the plans, and may if necessary comprise several sheets showing various elements of the required data. All mapped data for the same map shall be drawn at the same engineering scale; said scale not to be greater than 100 feet to an inch;
  - c. A completed land split or combination application form;
  - d. Legal description in a form approved by the Coconino County Recorder's office;
  - e. A non-refundable land split or combination application fee ~~(See City Code, Title 10, Zoning Code, Appendix 2, Planning Fee Schedule), available as a separate document from the Planning Section;~~ and
  - f. Complete contact information for the subdivider.

Formatted: Border: Bottom: (No border)

2. All submittals shall be checked by the Director for completeness. If the application is determined to be incomplete, the submittal may be rejected and returned to the applicant for revision and resubmittal.

B. Application Approval Standards:

1. All land split or combination applications shall be designed to comply with the requirements of the specific zoning district within which it is located, including minimum lot area, lot depth, lot width and minimum access requirements.

2. No lot or parcel shall be divided in such a way that any division contains more dwelling units than are permitted by the zoning regulations in the district in which the lot or parcel is situated.

3. Water and sewer services shall be provided to the frontage of each lot in areas served by the City of Flagstaff. Water or sewer services and/or yard lines shall not cross any other parcel.

C. Process for Approval.

1. The subdivider shall submit ~~all of~~ the documents, information, data, and other requirements for approval of a land split or combination to the Director. The subdivider shall also furnish to the Director any additional information and materials relevant to the application that are reasonably believed to be necessary ~~in order~~ for the Director to evaluate, analyze, or understand the subject matter of the application, and to ensure compliance with the requirements of this division. Compliance shall be determined by the Director.

2. The procedures for approval, modification, or denial of land split or combination applications shall be as follows:

a. The Director shall approve or disapprove applications for land splits or combinations pursuant to the provisions of this Division and shall ensure compliance with any applicable conditions of approval.

b. A subdivider may appeal a final action of the Director to the Planning Commission in accordance with Division 11-20.180, Appeals, of this Chapter.

11-20-100.050 Lot Splits for Secondary Single Family Dwellings

A.— Applicability. This section applies to existing detached residential units (except for accessory dwelling units) established prior to November 5, 2002 on lots located in the MR and HR Zones not subject to the Resource Protection Overlay. Where two existing detached residences are located on a lot, following the procedures established in Division 11-20-90, Modified Subdivision Process, or Division 11-20-100, Land Splits and Combinations, two new lots may be created subject to the standards provided below.

B.— Standards. If the lot with two existing detached residential units is proposed to be divided pursuant to this section, each resulting lot shall have frontage on, and/or legal access to, a public street or alley. The following standards in Table 11-20-100.050.A, Secondary Single Family Dwelling, shall also be met.

1.— Existing residential units shall maintain building separation requirements of applicable Sections for the R1N, MR and HR Zones, to the maximum extent feasible.

2.— Lots proposed to be divided: the new property line shall be drawn in such a manner as to divide this distance approximately equally between the two new lots, but in no case shall a new property line be drawn between existing structures that would be inconsistent with applicable City Building Code separation requirements.

Table 11-20-100.050.A: Secondary Single Family Dwelling

Building Placement Requirements	
-	Existing residential units shall maintain building separation requirements of applicable sections for the MR and HR Zones.
	Lots proposed to be divided: the new property line shall be drawn in such a manner as to divide this distance approximately equally between the two new lots, but in no case shall a new property line be drawn between existing structures that would be inconsistent with applicable City Building Code separation requirements.
Lot Requirements	
	5,000 sf in MR and HR Zones

Formatted: Border: Bottom: (No border)

Lot Size (min.)	If the lot is proposed to be divided, the smaller of the two remaining lots shall be at least 40% of the original lot or 2,000 sf, whichever is larger.
Lot Width (min.)	50' If the lot is proposed to be divided, the smaller of the two remaining lots shall have a lot width of at least 40'.
Lot Depth (min.)	75' If the lot is proposed to be divided, the smaller of the two remaining lots shall have a lot depth of at least 40'.
<b>Building Form Requirements</b>	
Lot Coverage (max.)	40% If the lot is proposed to be divided, each remaining lot shall have maximum coverage of 40%.
<b>Utilities</b>	
-	If the lot is proposed to be divided, each residential unit shall be provided with separate utility services in approved locations, subject to the provision of utility easements as necessary.

**11-20.60**  
**Boundary Adjustments**

Sections:

11-20.60.010 Boundary Adjustments

**11-20.60.010 Boundary Adjustments**

A. When a common lot line between two adjoining parcels requires adjustment, the submittal requirements and procedures for a land split provided in Division 11-20.100, Land Splits or Combinations, shall be followed for review and approval by the Director.

B. In addition to the submittal requirements for a land split or combinations established in Section 11-20.100.040, Land Split and Combination Applications, the written consent of all owners of the real property associated with the proposed boundary adjustment shall be submitted.

Formatted: Border: Bottom: (No border)

## 11-20.70

### Subdivision Design Standards and Requirements

#### Sections:

- 11-20.70.010 In General
- 11-20.70.020 Lot Design
- 11-20.70.030 Street Design
- 11-20.70.040 Alley and Easement Design
- 11-20.70.050 Block Design

#### **11-20.70.010 In General**

Except where expressly modified by the City Council, each subdivision plat shall be in conformity with the standards set forth or referred to in this chapter and the Engineering Standards.

A. All lots or parcels created by the subdivision of land shall have their own frontage to a public or private street. Public and private streets shall be designed and improved to public street standards in

accordance with the street design standards provided in Section 11-20.120.030, Street Design, and the Engineering Standards.

B. Driveways shall be designed in accordance with the standards established in the Engineering Standards and City Code, Title 4, Section 4-01-001-0005, Amendments.

C. The site planning standards provided in City Code, Title 10, Zoning Code, Division 10-30.60, Site Planning Design Standards, shall also be applied to the maximum extent feasible to the design of all new subdivisions.

**11-20.70.020 Lot Design**

A. The size, shape, and orientation of lots in the subdivision shall be appropriate to the location of the proposed subdivision and to the type of development contemplated. Lot width, depth, frontage, area and building setbacks shall comply with the minimum requirements of the Zoning Code (Title 10 of the City Code) and shall be appropriate for the location and character of development proposed and for the type and extent of street and utility improvements being installed. Where steep topography, unusual soil conditions or drainage problems exist or prevail, special lot width, depth and area standards may be considered. Innovative development approaches, such as clustered or planned development, should be explored in the interest of producing unique, environmentally-sensitive projects. Refer to City Code Title 10, Zoning Code, Section 10-40.60.250, Planned Residential Development.

B. No remnants of property shall be left in the subdivision that does not conform to lot requirements, unless required for a private utility or public purpose.

C. All subdivisions shall result in the creation of lots which are capable of being lawfully built upon. Except for parcels or tracts to be maintained as open space, no subdivision shall create lots which are physically unsuitable for improvement due to size or shape, steepness of terrain, location of water courses, problems of sewage or driveway grades, or other natural physical conditions.

D. Lots having double frontage shall be avoided except where necessary to provide separation of residential development from traffic arterials, to provide ingress and egress in commercial or industrial subdivisions, or to overcome specific disadvantages of topography and orientation.

E. Corner lots may be required to be wider than interior lots to provide for setback requirements.

Formatted: Border: Bottom: (No border)

F. Lot lines shall be located on or near the crest of ridges to preclude prominent line of sight building construction. Where feasible, the buildable area of a lot (i.e. the area within the setbacks) shall not be located on or near the crest of ridge lines.

G. The construction envelope on a lot shall be determined by the setback requirements for the lot and the location of natural topographic features such as watercourses, rock outcrops, native vegetation and trees. The Director may, upon application by the property owner, modify the construction envelope for an individual lot as shown on the final plat, provided that:

1. The revised construction envelope is equally as sensitive to the natural conditions as the original construction envelope;
2. The area of the construction envelope is not enlarged; and,
3. Setback requirements are not amended.

#### **11-20.70.030 Street Design**

A. The minimum requirements for street design are established in the Engineering Standards.

B. Standard utility locations shall comply with the Engineering Standards.

C. Local streets shall be designed to promote connectivity by creating a comprehensive grid-like network of vehicular and pedestrian connections to provide diversity of route choices between the proposed subdivision and existing streets and pedestrian routes, unless topographic conditions preclude such connectivity.

D. Names of streets should be consistent with the natural alignments and extensions of existing streets and the City's Address Policy. New street names should not duplicate, in whole or in part, or be confused with existing names.

E. Local circulation systems and land development patterns shall be designed so that multiple modes of transportation shall be considered and that the efficiency of bordering arterial routes is maintained.

F. Proposed streets, as designated by the City, shall be extended to the tract boundary to provide future connection with adjoining unplatted lands. The street pattern in the subdivision shall not land lock adjacent property nor prevent access to public land.

Formatted: Border: Bottom: (No border)

- G. The functional classification of streets shall be assigned by the City.
- H. Whenever a tract to be subdivided includes any part of a street designated in an adopted General Plan, the street shall be platted in conformance with the General Plan.
- I. Whenever a tract to be subdivided is located within an area for which a development master plan has been approved by the Planning Commission, the street arrangement shall conform substantially to this plan.
- J. Streets shall be designed in relation to existing topography to produce streets of reasonable gradient to facilitate adequate drainage and to produce desirable lots of maximum utility. Where feasible, streets shall be placed along the top of ridges to minimize the extent of grading and reduce the visual impact of development.
- K. Boundary streets (half streets) shall be discouraged except where necessary to provide right-of-way required by the General Plan, to complete a street pattern already begun or to insure reasonable development of a number of adjoining parcels. Where a platted half street abuts the tract to be subdivided, the remaining half shall usually be platted within the tract.

**11-20.70.040 Alley, Lane, and Easement Design**

- A. Alleys and lanes shall be designed and constructed in accordance with City regulations and standards.
- B. Easements shall be provided and dedicated where deemed necessary for specific purposes for use by the general public, corporations, or the City of Flagstaff. Easements necessary to assure non-motorized access to adjacent public lands shall be provided to the satisfaction of the Director. Such easement shall not prevent the reasonable improvement of any development. Pedestrian, bicycle and equestrian ways may be required where essential for circulation or access to schools, playgrounds, shopping centers, transportation and other community facilities. Pedestrian ways may be used for utility purposes.
- C. A non-vehicular access restriction prohibiting vehicular access from the collector or arterial street side of a double frontage or corner residential lot is required, except in Traditional Neighborhood developments approved as part of a Traditional Neighborhood Community Plan (See City Code Title 10, Zoning Code, Division 10-30.80, Traditional Neighborhood Community Plans.

Formatted: Border: Bottom: (No border)

D. The subdivider shall dedicate a right-of-way or easement for storm drainage conforming substantially to the line of any watercourse that traverses the land; or at the option of the City, the subdivider shall provide by dedication further and sufficient easements or construction, or both, to dispose of such surface and stormwater, upon the direction of the City Engineer.

**11-20.70.050 Block Design**

A. Blocks in non-transect zones shall not normally exceed 1,200 feet in length measured from the property lines, except in hillside developments or where a subdivision of one-half acre lots or larger justify or require a variation from this requirement, or where there are unusual conditions of the property being subdivided.

B. Blocks shall normally have sufficient width for an ultimate layout of two tiers of sized in accordance with the minimum requirements of the zoning district in which the subdivision is proposed. See City Code Title 10, Zoning Code, Chapter 10-40, Specific to Zones.

C. Blocks shall not normally be less than 400 feet in length (measured from the property lines), except where it is necessary due to unusual conditions of the property being subdivided and not merely convenience.

D. The standards provided in Sections 11-20.120.050A through C shall not apply in new traditional neighborhood developments approved under the provisions of City Code Title 10, Zoning Code, Division 10-30.80, Traditional Neighborhood Community Plans.

Formatted: Border: Bottom: (No border)

**11-20.80**  
**Minimum Required Subdivision Improvements**

Sections:

11-20.80.010 In General

11-20.80.020 Minimum Improvements Required

**11-20.80.010 In General**

A. It shall be the responsibility of the subdivider to improve all streets, pedestrian ways, alleys and easements in the subdivision and adjacent to it as required to serve the subdivision. No permanent improvement work shall be commenced until improvement plans have been approved by the City Engineer. Improvements shall be installed to the permanent line and grade and to the satisfaction of the City Engineer, and in accordance with the standard subdivision specifications of the City of Flagstaff. The cost of the inspection shall be paid by the subdivider.

B. For subdivisions that will be platted and developed in more than a single phase, the final plat and assurance of performance for improvements shall represent only the limits of each individual phase proposed for development. Each phase of a subdivision shall have improvements designed to be fully

Formatted: Border: Bottom: (No border)

operational and functional in perpetuity without reliance on the development of future phases. Construction plans submitted for approval shall not represent multiple phases and shall depict only the design of improvements necessary to make an individual phase operational and functional.

**11-20.80.020 Minimum Improvements Required**

A. The minimum requirements for public improvements for new subdivisions are provided in City Code Title 10, Zoning Code, Division 10-30.50 (Public Improvements).

Formatted: Border: Bottom: (No border)

**11-20.90  
Modifications**

Sections:

11-20.90.010 Modifications

**11-20.90.010 Modifications**

A. Where, in the opinion of the City Council, there exists extraordinary conditions of topography, land ownership, or adjacent development, or other circumstances not provided for in these regulations, the City Council may modify the provisions of this Title in such a manner and to such extent as it may deem appropriate to the public interest. The burden of proof for City Council determination of a modification rests with the subdivider. The written request for modification shall be made to the Director and shall be submitted to the City Council after review and recommendation by the Planning Commission.

B. In modifying the standards or requirements of these provisions, as outlined above, the City Council may make such additional requirements as appear necessary in its judgment to secure substantially the objectives of the standards or requirements so modified.

Formatted: Border: Bottom: (No border)

**11-20.100**  
**Reversion to Acreage**

Sections:

- 11-20.100.010 Purpose
- 11-20.100.020 Reversion Application Required
- 11-20.100.030 Action by the Planning Commission
- 11-20.100.040 Action by the City Council
- 11-20.100.050 Recording of Survey

**11-20.100.010 Purpose**

This division establishes the procedures for the reversion to acreage of any subdivided lands upon approval by the City Council.

**11-20.100.020 Reversion Application Required**

To initiate a reversion to acreage, an application for reversion must be filed with the Director. All applications for reversion to acreage shall be submitted to the Director in writing on a form prescribed by the City. The application shall include the information and materials specified in the checklist for

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

reversion to acreage, together with the required fee established in City Code Title 10, Zoning Code, Appendix 2, Planning Fee Schedule. Upon receipt of an application for reversion to acreage, the Director shall conduct an investigation and prepare a report for presentation to the Planning Commission at a public meeting.

**11-20.100.030 Action by the Planning Commission**

The Planning Commission shall conduct a public meeting on an application for reversion to acreage in accordance with the Review Schedule on file with the Planning Section. Upon completion of the hearing, the Planning Commission shall recommend that the City Council approve, approve in modified form, or deny the application. Any action to recommend approval shall be based on all of the following findings:

- A. That the subdivided lands to revert to acreage are under one ownership entity;
- B. That no immediate use of such subdivided lands as they were intended appears imminent;
- C. That such reversion to acreage will not be detrimental to the general welfare of the public.

**11-20.100.040 Action by the City Council**

Upon receipt of a recommendation from the Planning Commission, the City Council shall conduct a public meeting on an application for reversion to acreage. The City Council shall approve, approve in modified form, or deny the application. Any action to approve shall be based on all of the findings set forth in Section 11-20.150.030, Action by Planning Commission.

**11-20.100.050 Recording of Survey**

The applicant shall record with the County Recorder a survey of all lands approved for reversion to acreage prepared by a surveyor or engineer licensed by the State of Arizona and a copy of the abandonment of subdivision filed with the Arizona Department of Real Estate.

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

**11-20.110**

**Abandonment or Vacation of Public Right-of-Way**

Sections:

- 11-20.110.010 Purpose
- 11-20.110.020 Procedures
- 11-20.110.030 Submittal Requirements
- 11-20.110.040 Effective Date
- 11-20.110.050 Appeals

**11-20.110.010 Purpose**

The purpose of this division is to provide procedures for the abandonment or vacation of public rights-of-way or portions thereof (including streets, alleys, or public access easements).

**11-20.110.020 Procedures**

A. Initiation. The abandonment or vacation of public right-of-way may be initiated by the City Council, the City Manager or the City Engineer, as well as any property owner who owns land adjoining the public right-of-way contemplated for abandonment or vacation.

B. Process.

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

1. The processing procedure for a written request for abandonment or vacation by the City Engineer shall include:

- a. The written request for abandonment or vacation shall be checked for compliance with required submittal information;
- b. A location map of the area proposed to be abandoned or vacated showing abutting properties and a vicinity map, if necessary; and,
- c. A memorandum stating the reasons for requested abandonment or vacation.

2. The memorandum and map of the requested abandonment or vacation of public right-of-way shall be forwarded to all public utility companies, City divisions and agencies serving the proposed area to be abandoned or vacated to request their review and comments.

3. For public rights-of-way, including roadways as defined in A.R.S. § 28-7201, notice shall be provided in the manner specified in A.R.S. § 28-20, Article 8, Disposition of Public Roadways.

C. Staff Report. The City Engineer in consultation with the ~~Water Services~~~~Utilities~~ Director and Public Works Director shall prepare and transmit a staff report to the City Council. The report shall include an evaluation of the consistency of the proposed vacation or abandonment with the General Plan, Zoning Code, any applicable Specific Plan, and all applicable ~~Water Services~~~~Utilities~~ and Public Works Division standards. The staff report shall also provide an analysis and recommendation. A copy of the staff report shall be made available to the public and affected parties prior to the public hearing.

D. Action by the City Council. Upon receipt of a recommendation from the Planning Commission, the City Council shall conduct a public hearing. Upon completion of this hearing, the City Council shall approve, approve in modified form, or deny the application. Approval shall be by resolution.

E. Recordation. The City ~~Clerk~~~~Engineer~~ shall record the final vacation resolution with the office of the Coconino County Recorder.

#### **11-20.110.030 Submittal Requirements**

All applications for the vacation of public streets or easements shall be submitted to the City Engineer in writing on a form prescribed by the City. The application shall include the information and materials

Formatted: Border: Bottom: (No border)

specified in the checklist for the Abandonment of Public Rights-of-Way, together with the required fee established in City Code Title 10, Zoning Code, Appendix 2, Planning Fee Schedule.

**11-20.110.040 Effective Date**

The effective date of vacation of streets and easements is the date of City Council approval.

**11-20.110.050 Appeals**

Decisions of the City Council on the vacation of streets and easements are final.

Formatted: Border: Bottom: (No border)

Formatted: Border: Bottom: (No border)

**11-20.120  
Violations**

Sections:

11-20.120.010 Violations

**11-20.120.010 Violations**

A. It shall be a Class 1 misdemeanor to achieve or attempt to achieve a land split or combination or to establish or attempt to establish a subdivision of any land within the City of Flagstaff without first having obtained the approval of the City Council or Director as required by this Chapter.

B. It shall be a Class 1 misdemeanor to record or attempt to record a subdivision plat or land spit or combination map with the Coconino County Recorder if such plat or map includes any land within the City and such plat or map has not been given approval by the City Council or Director, or the necessary certifications and signatures of approval have not been obtained as required by this Chapter.

Formatted: Border: Bottom: (No border)

**11-20.130**  
**Appeals**

Sections:

11-20.130.010 Appeals

**11-20.130.010 Appeals**

The following appeal procedures shall be utilized by all parties.

A. Appeal of a decision by the Director.

1. During the course of boundary adjustment land split/combination, preliminary plat, final plat and Master Block Plat preparation and review, a decision of the Director may be appealed to the Planning Commission within ten days of such decision.

a. The appeal shall be filed with the Director on a form prescribed for this purpose provided by the City describing the reason(s) for, and details of, the appeal.

b. The appeal shall be acted upon by the Planning Commission within 45 days of the date upon which the appeal is filed, unless circumstances beyond the control of the Planning Commission require a longer review period.

Formatted: Border: Bottom: (No border)

(1) In this case, the Director shall notify the appellant when the appeal will be heard by the Planning Commission, but in no case shall the review period be longer than 60 days from the date the appeal is filed with the City.

2. If the issues are not reconciled by the Planning Commission, the City Council shall hear, review, and decide upon the appeal as outlined in Subsection "B" below.

3. The findings of the City Council shall be incorporated into the plat or map and, if found necessary by the City Council, the plat or map shall be resubmitted for review by the Director, to assure conformity to the City Council's decisions and other requirements.

B. Appeal of Planning Commission

1. Decisions reached by the Planning Commission during the course of preliminary plat ~~review, and review and~~ appeals of a decision of the Director as described in Section 11-20.180.010A, may be appealed to the City Council. An appeal shall be filed within ten days of such decision with the Director. The City Council shall act upon the appeal within 45 days of the date upon which the appeal was filed with the Director, unless circumstances beyond the control of the City Council require a longer review period. In this case, the Director shall notify the appellant when the appeal will be heard by the City Council, but in no case shall the review period be longer than 60 days from the date the appeal is filed with the City.

~~C.—Parcel Division. If two residential units exist on a lot in conformance with subsection (A) of this section, such lot may be divided, upon application through the modified subdivision process set forth in Division 11-20.10, Title and Authority, or land split procedure outlined in Division 11-20.100, Land Splits and Combinations, into two separate lots, one for each residential unit, if the following requirements are met:~~

~~1.—The lot line created between the two residential units shall be substantially perpendicular to the side lot lines if the buildings are located in the front and rear portions of the original lot, or to the front and rear lot lines if the buildings are located side by side;~~

~~2.—The division complies with the Land Split requirements of Chapter 11-20, Subdivision and Land Split Regulations, except as modified by this Section for development standards in the MR and HR Zones not subject to the resource protection overlay;~~

~~3.—If the proposed property division is a land split and the lot boundaries are set by a recorded plat and all public improvements exist along the entire frontage of the property prior to splitting, then the division may be processed as a land split in compliance with Division 11.20.10, Title and Authority; and~~

~~4.—If the City Engineer determines that as a result of the proposed property division public improvements are required in compliance with Section 10-30.50.060, Minimum Requirements, then the property division shall follow the modified subdivision process as defined in Division 11-20.90, Modified Subdivision Process. (Ord. 2016-07, Amended, 02/16/2007. Formerly 10-40.60.300)~~