SHENANDOAH CONSTRUCTION

1888 N.W. 22nd Street • Pompano Beach, FL 33069
(772) 467-8861 Fax: (772) 467-8863

PROPOSAL #P5007

DATE: November 09, 2016
SUBMITTED TO: City of Fort Pierce
STREET: 100 N. US 1
CITY, STATE & ZIP: Ft. Pierce, Fl 34954
PHONE: (772) 467-3783
FAX: 7724606847
EMAIL: dhermoso@city-ftpierce.com
JOB NAME: 1705 Sunset Isles RD
ATTENTION: Dina Hermoso

We propose to furnish a crew and all necessary equipment to dewater, clean and install 18" cured in place pipe liner in storm drainage pipe from inlet to sea wall and restore surface with fill dirt, sod and cement at the above mentioned job location. This work will be performed at our following hourly and/or unit prices:

18" CIPP	(at $118.00 Per L.F.)	150 L.F.	$17,700.00
surface restoration (*)	(at $3,200.00 Fixed Cost)	1 Fixed	$3,200.00
Estimated Total:			**$20,900.00**

NOTE: Due to the fragile condition of the existing pipe(s), the possibility of the pipe collapsing exists during the construction phase. If this unlikely event occurs, we will provide you with an additional estimate for a necessary point repair to complete the lining process. Due to the poor condition of the original host pipe, residual settling may appear at the surface grade, post lining. This condition is not covered under warrantee.

This proposal may be withdrawn if not accepted within 30 days. Payment terms net 30 days. (If we encounter an Insurance compliance fee requirement, this fee will be invoiced in addition to the above rates.)

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Price above is only an estimate of foreseen conditions. Unforeseen conditions can affect the amount of time to complete the work, therefore increasing or decreasing estimate. All agreements are contingent upon strikes, accidents or delays beyond our control. Unless noted above engineering, permits, testing and bonds are not included in the pricing. Owner is to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance. Parties to this proposal/contract expressly waive all tort claims against each other and limit their remedies to breach of contract.

SIGNATURE:

SHENANDOAH GENERAL CONSTRUCTION CO.	TITLE	DATE
Mindy Cotrupi	Estimator	11/09/2016

ACCEPTANCE OF PROPOSAL / SIGN & RETURN

The above prices, specification and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified.

SIGNATURE: _____

COMPANY NAME: TRACY TELLE DATE: 11/10/16
REPRESENTATIVE: CITY OF FORT PIERCE TITLE: ASST. CITY ENG.

(*) see email attached

APPROVED
11/10/16