

BID NO. 2022-004
NORTH 8TH STREET
(AVENUE D TO AVENUE E)
29-Nov-21

ITEM NO.	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	AMOUNT
101-1A	MOBILIZATION/PERMITS/ GENERAL CONDITIONS/BONDS	LS	1	\$ 49,812.00	\$ 49,812.00
101-2A	MATERIAL TESTING	LS	1	\$ 8,625.00	\$ 8,625.00
101-1B	PRE-CONSTRUCTION VIDEO	LS	1	\$ 600.00	\$ 600.00
101-1C	RECORD DRAWINGS / CONSTRUCTION LAYOUT / AS-BUILTS	LS	1	\$ 18,700.00	\$ 18,700.00
102-1	MAINTENANCE OF TRAFFIC	LS	1	\$ 14,500.00	\$ 14,500.00
104-10-3	SEDIMENT BARRIER	LF	1,020	\$ 3.00	\$ 3,060.00
104-15	SOIL TRACKING PREVENTION DEVICE	EA	1	\$ 3,500.00	\$ 3,500.00
104-18	INLET PROTECTION SYSTEM	EA	6	\$ 100.00	\$ 600.00
110-1	CLEARING/GRUBBING/DEMOLITION	AC	0.56	\$ 83,500.00	\$ 46,760.00
120-1	REGULAR EXCAVATION	CY	536	\$ 6.00	\$ 3,216.00
120-6	EMBANKMENT	CY	10	\$ 20.00	\$ 200.00
160-4	TYPE B STABILIZATION (12" THICK)	SY	1,860	\$ 4.50	\$ 8,370.00
285-709	OPTIONAL BASE, BASE GROUP 09 (LBR 100)	SY	1,590	\$ 21.00	\$ 33,390.00
327-70-5	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	62	\$ 20.00	\$ 1,240.00
334-1-13A	SUPERPAVE ASPHALTIC CONCRETE TRAFFIC C (SP-9.5) (1" THICK)	TON	88	\$ 175.00	\$ 15,400.00
334-1-13B	SUPERPAVE ASPHALTIC CONCRETE TRAFFIC C (SP-12.5) (2" THICK)	TON	175	\$ 145.00	\$ 25,375.00
425-1-209	INLETS, CURB, MODIFY, TOP	EA	2	\$ 4,000.00	\$ 8,000.00
425-1-211	INLETS, CURB, TYPE P-10, < 10'	EA	2	\$ 7,700.00	\$ 15,400.00
425-1-521	INLETS, DITCH BOTTOM, TYPE C, < 10'	EA	2	\$ 4,900.00	\$ 9,800.00
425-2-41	MANHOLE, P-7, < 10'	EA	2	\$ 8,250.00	\$ 16,500.00
430-174-115	PIPE CULVERT, REINFORCED CONCRETE PIPE, ROUND, 15"SD	LF	262	\$ 55.00	\$ 14,410.00
520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	1,040	\$ 23.00	\$ 23,920.00
520-3	CONCRETE HEADER CURB	LF	65	\$ 25.00	\$ 1,625.00
522-1	CONCRETE W/ FIBERMESS (4" THICK) (SIDEWALK)	SY	537	\$ 45.00	\$ 24,165.00
522-2	CONCRETE W/ FIBERMESS (6" THICK) (SIDEWALK)	SY	60	\$ 47.00	\$ 2,820.00
523-1	CONCRETE BRICK PAVER CROSSWALKS	SY	20	\$ 361.00	\$ 7,220.00
527-2	ADA CURB RAMP W/ DETECTABLE WARNING (COMPLETE)	SF	136	\$ 100.00	\$ 13,600.00
550-10-110	FENCING RELOCATION	LF	70	\$ 20.00	\$ 1,400.00
570-1-2	PERFORMANCE TURF, SOD	SY	400	\$ 4.00	\$ 1,600.00
700-1-11	SINGLE POST SIGN, F&I GM, < 12 SF (R1-1 STOP)	EA	3	\$ 270.00	\$ 810.00
706-1-1	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	15	\$ 8.00	\$ 120.00
711-11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	160	\$ 5.00	\$ 800.00
711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	33	\$ 16.50	\$ 544.50
711-11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID 6"	LF	740	\$ 2.00	\$ 1,480.00
711-11-241	THERMOPLASTIC, STANDARD, YELLOW, 6" 6-10 SKIP	GM	0.01	\$ 60,500.00	\$ 605.00
1080-21106	UTILITY ADJUSTMENTS	EA	6	\$ 2,750.00	\$ 16,500.00
1080-5	FPUA 2" ROADWAY CROSSING CONDUITS INSTALLATION ONLY	LF	40	\$ 27.50	\$ 1,100.00
1080-5	FPUA 4" ROADWAY CROSSING CONDUITS INSTALLATION ONLY	LF	120	\$ 27.50	\$ 3,300.00
C1	4" PVC CONDUIT INSTALLATION (FURNISH & INSTALL)	LF	4,000	\$ 21.50	\$ 86,000.00
Subtotal					\$ 485,067.50
Add 10% Construction Contingency for potential field change orders					\$ 48,506.75
TOTAL FINAL BID					\$ 533,574.25

OPTION FOR SUBMITTING THIS FORM

The Bid Response Form is available in Excel Format. To access the form, open Excel Attachment from the website, perform "file save as" and save spreadsheet to your computer. Fill in pricing, preferably electronically. Include the Bid Response Form, in excel format (not pdf), on a USB drive with the rest of your submittal documents.