

NOTICE OF MEETING CITY OF GARLAND, TEXAS

PLAN COMMISSION City Hall, Council Chambers William E. Dollar Municipal Building 200 N. Fifth Street Garland, Texas May 12, 2025 at 6:30 p.m.

A meeting of the Plan Commission of the City of Garland, Texas will be held at the aforementioned location, date, and time to discuss and consider the following agenda items.

INVOCATION AND PLEDGE OF ALLEGIANCE: It is the custom and tradition of the members of the Plan Commission to have an invocation and recital of the Pledge of Allegiance prior to the beginning of the meeting. Members of the audience are invited to participate. However, members of the audience are not required to participate. The decision to participate is strictly a matter of personal choice and has no bearing on matters to be considered by the Plan Commission and will not affect the decisions to be made during the meeting.

The meeting will be broadcast on City of Garland Government Access Television (CGTV). CGTV is available via GarlandTX.gov, channel 16 (Spectrum), Channel 44 (Frontier), and channel 99 (AT&T U-verse). Meetings are broadcast online via live-streaming, on-demand, and air on CGTV with several rebroadcasts during the week of the meeting.

Public Comments

Your comments must relate to an item on this agenda - non-germane comments are not in order. Time limits will be imposed by the Chairman as appropriate to the nature of the agenda item. Generally, public speakers are given three minutes.

IN-PERSON COMMENTS: Registration will be required for any citizen wishing to speak. Anyone wishing to speak must fill out a speaker card (located at the entrance to the Council Chambers).

Garland City Hall and Council Chambers are wheelchair accessible. Special parking is available on the east side of City Hall and on Austin & State Street west of City Hall. Persons with disabilities who plan to attend this meeting and who may need auxiliary aids or services must contact the City Secretary's Office at (972) 205-2404 at least two working days prior to the meeting so that appropriate arrangements can be made. BRAILLE IS NOT AVAILABLE.

If the Plan Commission adjourns into executive session during this meeting, the executive session will be conducted between and among the members of the Plan Commission and relevant City staff. Public access to that meeting is prohibited by State law.

CONSENT AGENDA

All items under this section are recommended for approval by a single motion of the Plan Commission, without discussion. The Chairman will announce the agenda and provide an opportunity for members of the audience and the Plan Commission to request that an item be removed and considered separately.

1. MINUTES

Consider approval of the Plan Commission Minutes for the April 14, 2025 meeting.

ITEMS FOR INDIVIDUAL CONSIDERATION

Speaker Regulations:

Anyone wishing to speak for, against, or on agenda items must fill out a speaker card and give it to the Plan Commission Secretary before speaking (cards are located at the entrance to the Council Chambers). The Chairman will recognize speakers; he may impose a time limit and may provide for rebuttal. All comments and testimony are to be presented from the podium.

ZONING

a. Hold a public hearing and consider the application of **Urban Strategy**, requesting a "Major Waiver" from the Downtown Development Code for the at-grade and above-grade window percentage of the facade, architectural articulatio, Build-To-Zone, streetscaping, and a monument sign standards. The site is located at 801 West Avenue D. (District 2) (File DD 24-04)

- b. Hold a public hearing and consider the application of **Trak Group Inc.**, requesting a Specific Use Provision (SUP) for Fuel Pumps, Retail use on property zoned Community Retail (CR). The property is addressed as 3420 W Walnut Road. (District 6) (File Z 24-02)
- c. Hold a public hearing and consider the application of The Kroger Co., requesting approval of a Specific Use Provision for Fuel Pumps, Retail use. The site is located at 6850 North Shiloh Road. (District 1) (File Z 25-03)
- d. Hold a public hearing and consider the application of **Dynamic Engineering Consultants**, P.C., requesting an amendment to Planned Development District (PD 85-55) to allow a Self-Storage Facility (miniwarehouse). The site is located at 1788 Firewheel Parkway. (District 1) (File Z 25-13)
- e. Hold a public hearing and consider the application of **CCM Engineering**, proposing an amendment to Planned Development (PD) District 20-44 to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces. The site is located at 2126 Rowlett Road. (District 3) (File Z 25-16)
- f. Hold a public hearing to consider amendments to Chapter 2 Zoning Regulations, Attachment 1 Land use chart and Article 4, Division 4 Mixed-Use Districts as it relates to the permitted land uses and development regulations for the Urban Residential (UR) and Urban Business (UB) districts.
- g. Hold a public hearing and consider the application of the City of Garland, requesting approval of a change in zoning from multiple zoning districts including but not limited to Industrial (IN), Community Retail (CR), and Planned Developments with IN and CR base zoning to Urban Residential (UR) and Urban Business (UB) Districts. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5) (File Z 25-08)

3. ADJOURN

NOTICE: The Plan Commission may recess from the open session and convene in a closed session if the discussion of any of the listed agenda items concerns matters regarding priviledged and unpriviledged client information deemed confidential by Rule 1.05 of the Texas Disciplinary Rules of Professional Conduct. Sec. 551.071, Tex. Gov't Code.

NOTE: A quorum of the City Council may be in attendance and may or may not participate in the discussions of the Committee or board



Plan Commission 1. a.

Meeting Date: 05/12/2025

Item Title: Plan Commission Minutes for April 14, 2025

Summary:

Consider approval of the Plan Commission Minutes for the April 14, 2025 meeting.

Attachments

April 14, 2025 Plan Commission Minutes



The Plan Commission of the City of Garland convened in regular session at 6:30 p.m. on Monday, April 14, 2025, in the Council Chambers at the William E. Dollar Municipal Building, 200 N. Fifth Street, Garland, Texas, with the following members present:

Present: Scott Roberts, Chairman

Wayne Dalton, 2nd Vice Chair Georgie Cornelius, Commissioner

Jaric Jones, Commissioner
Patrick Abell, Commissioner
Michael Rose, Commissioner
Bob Duckworth, Commissioner

Absent: Julius Jenkins, 1st Vice Chair

Stephanie Paris, Commissioner

Staff Present: Nabila Nur, Planning Director

Kurt Banowsky, Sr. Assistant City Attorney II

Emma Chetuya, Planning Administrator - Development

Matthew Wolverton, Planner II Elisa Morales, Recording Secretary

CONSENT AGENDA

All items under this section are recommended for approval by a single motion of the Plan Commission, without discussion. The Chairman will announce the agenda and provide an opportunity for members of the audience and the Plan Commission to request that an item be removed and considered separately.

Motion was made by Commissioner Dalton to approve the Consent Agenda as presented. Seconded by Commissioner Abell. Motion carried: 7 Ayes, 0 Nays.

1. MINUTES

a. Consider approval of the Plan Commission Minutes for the March 10, 2025 meeting.

APPROVED

ITEMS FOR INDIVIDUAL CONSIDERATION

Speaker Regulations:

Anyone wishing to speak for, against, or on agenda items must fill out a speaker card and give it to the Plan Commission Secretary before speaking (cards are located at the entrance to the Council Chambers). The Chairman will recognize speakers; he may impose a time limit and may provide for rebuttal. All comments and testimony are to be presented from the podium.

2. ZONING

a. Hold a public hearing and consider the application of Leslie Montena, requesting approval of APPROVED a Major Waiver to Chapter 7, Table 7-7 of the Garland Development Code to install a 30-square-foot wall sign positioned lower on the façade, where only 10-square-foot signs are permitted below 12 feet above grade on a property zoned Downtown (DT) District, Downtown Historic (DH) sub-district. The site is located at 622 West State Street. (District 2) (File DD 25-01)

Planner II, Matthew Wolverton, presented the request to the Commission and remained available for questions.

The applicant, Leslie Montena, 622 West State Street, Garland, TX 75040, provided an overview of the request and remained available for questions.

Motion was made by Commissioner Abell to close the public hearing and **approve** the application as presented. Seconded by Commissioner Rose. **Motion carried**: 7 Ayes, 0 Nays.

- b. Hold a public hearing to consider amendments to Chapter 2 Zoning Regulations, Attachment 1 POSTPONED

 Land use chart and Division 4 Mixed-Use Districts as it relates to the permitted land uses
 and development regulations for the Urban Residential (UR) and Urban Business (UB)
 districts. (This item has been postponed to the April 28, 2025 Plan Commission Meeting)
- c. Hold a public hearing and consider the application of the City of Garland, requesting approval of a change in zoning from multiple zoning districts including but not limited to Industrial (IN), Community Retail (CR), and Planned Developments with IN and CR base zoning to Urban Residential (UR) and Urban Business (UB) Districts. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5) (File Z 25-08) (This item has been postponed to the April 28, 2025 Plan Commission Meeting)

ADJOURN

There being no further business to come forward before the Plan Commission, the meeting adjourned at 6:44 p.m.

CITY OF GARLAND, TEXAS

/s/ Scott Roberts, Chairman

/s/ Elisa Morales, Secretary

POSTPONED



Plan Commission 2. a.

Meeting Date: 05/12/2025

Item Title: DD 24-04 Urban Strategy (District 2)

Summary:

Hold a public hearing and consider the application of **Urban Strategy**, requesting a "Major Waiver" from the Downtown Development Code for the at-grade and above-grade window percentage of the facade, architectural articulatio, Build-To-Zone, streetscaping, and a monument sign standards. The site is located at 801 West Avenue D. (District 2) (File DD 24-04)

Attachments

DD 24-04 Urban Strategy Report & Attachments DD 24-04 Urban Strategy Responses

Planning Report

File No: DD 24-04/District 2

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2024



REQUEST

Hold a public hearing and consider approval of 1) a Major Waiver to Chapter 7, Table 7-7 of the Garland Development Code for the at-grade and above-grade window percentage of the façade, architectural articulation, Build-To-Zone, streetscaping, and a monument sign standards and 2) a Downtown Development Plan to allow for a church expansion and addition, including a major waiver for the at-grade and above-grade window percentage of the façade, architectural articulation, Build-To-Zone, streetscaping, and a monument sign standards on a property zoned Downtown (DT) District, Uptown (U) sub-district.

LOCATION

801 West Avenue D

APPLICANT

Urban Strategy

OWNER

First Baptist Church Garland

BACKGROUND

The building on the subject property is currently occupied by the First Baptist Church of Garland. The Church is looking to demolish about two thirds of their existing building and rebuild it slightly larger. The remodeling of the church will be a large project and has triggered the need for the Downtown Development process. The form-based code that applies to the Downtown (DT) District in Garland has the categories of townhouses, mixed residential, loft, live/work, linear buildings, mixed use, and commercial for buildings and their standards. The Church is categorized as a commercial structure despite not having a business there. Due to the nature of a church being considered a commercial structure under the Downtown form-based code, major waivers are being triggered. In addition to this, engineering and logistical challenges have triggered the need for others.

SITE DATA

The subject site contains approximately 1.861 acres. The site has approximately 290 lineal feet of frontage along West Avenue D, South Glenbrook Drive, South 9th Street, and West Avenue C as it occupies an entire grid in the Downtown of the city. The Southern two thirds of the site will be redeveloped while the Northern one third along West Avenue C will remain the same.

USE OF PROPERTY UNDER CURRENT ZONING

The property is zoned within the Uptown (U) Sub-district of the overall Downtown (DT) District. The Uptown (U) Sub-district allows a variety of mixed uses. The current use of the property [church] is allowed by right. The public hearing Major Waiver process is triggered due to the design of the church within the Downtown (DT) District's form-based code, requiring deviations for the at-grade and above-grade window percentage of the façade, architectural articulation, Build-To-Zone, streetscaping, and monument sign standards.

CONSIDERATIONS

- 1. Monument Sign: The applicant proposes a 43 square-feet monument sign. Per section 7.26 of the GDC, the Uptown Subdistrict of the Downtown District does not permit for new monument signs. In other areas of the city where monument sings are permitted, the maximum allowed size is 50 square feet.
- 2. At-grade window percentage of the façade: The applicant proposes a window percentage of 56% on the South elevation, 27% on the East, and 33% on the West. Section 7.11 (G) (1) of the GDC states that windows shall be highly transparent and comprise a minimum of 60 and 80 percent. The church is considered a commercial structure, but a church typically isn't designed to have the appearance of a retail building.
- 3. Above-grade window percentage of the façade: The applicant proposes a window percentage of 21% on the East elevation and 25% on the West elevation of the second level of the building. Section 7.11 (G) (2) of the GDC states that windows shall represent a minimum of 30% and a maximum of 60% of each building elevation above the ground floor. The church is considered a commercial structure, but a church typically isn't designed to have the appearance of a retail building.
- 4. Streetscaping: The applicant proposes to install three (3) street trees along South 9th Street that are 25-feet apart and seven (7) small ornamental trees that are 15-feet apart along South Glenbrook Drive. Section 7.17 (A) (2) of the GDC requires that Seven (7) trees are required to be planted along South 9th Street and eight (8) trees are required to be installed along South Glenbrook Drive. The 25-feet spacing requirements are not met along South Glenbrook Drive. This is due to the limited amount of spacing on this side of Glenbrook and underground utilities. The trees meet the code on the South elevation.
- 5. *Build-To-Zone*: The Build-To-Zone in this area requires buildings to begin 26-36 feet from the curb. The Church building complies with this on all elevations but a canopy and roof overhang into the Build-To-Zone on the North, East, and South elevations.
- 6. Architectural Articulation: Proposed is a church which does not follow mixed use nor commercial building design. The code requires all buildings shall be designed and constructed in tri-partite architecture, with a distinct base, middle and top. An expression line, setback or other architectural element shall delineate the base and top.

The following table summarizes the request:

Development Standard	Required	Proposed
Monument Sign	Not allowed in the Uptown sub-district of the Downtown (DT) District.	A 43-square foot monument sign.
At-grade window percentage of the façade.	Shall comprise a minimum of 60% and a maximum of 80% of the ground floor façade.	Approximately 56% on the South elevation, 27% for East elevation, and 33% on West elevation.

Development Standard	Required	Proposed
Above-grade window percentage of the façade	Shall comprise a minimum of 30% and a maximum of 60% of each building elevation above the ground floor.	Approximately 21% on the East elevation and 25% on the West elevation.
Streetscaping	Trees must meet spacing and count requirements.	Underground utilities and limited spacing have triggered this reduction. For the west side, the applicant did not want trees in front of the main entrance.
Build-To-Zone	Building must begin within 26-36 feet of the curb.	Overhangs from canopies and roof on the North, East, and South sides.
Architectural Articulation	All buildings shall be designed and constructed in tripartite architecture, with a distinct base, middle and top. An expression line, setback or other architectural element shall delineate the base and top.	The building will not follow commercial design as it is a church.

- 7. The applicant states, "Our Plan has taken into consideration the current zoning requirements and the city's future growth and development plans ensuring that it supports and compliments the surrounding community."
- 8. The intent of the Downtown (DT) District is to create a pedestrian-oriented area in context with the current Downtown. The Downtown (DT) District combines minimum and maximum specifications and standards for site layout, building design, and streetscape. One of the flexibility mechanisms in the Downtown (DT) District is the option of Major Waivers, which allow relief from the standards of the district, where applicable.

Section 7.30(C) of the GDC states that Major Waivers are material and substantial changes to the design standards in the DT District, or changes which may initially appear to be in conflict with the goals and intent of this district, including possible standards changes to land uses in the Downtown sub-districts. Major Waivers may be approved by the City Council, following a recommendation by the Planning Director and the Plan Commission. In order to approve a Major Waiver, the City Council findings are listed as follows:

Meets the general intent of this district; and

 Will result in an improved project which will be an attractive contribution to the Downtown District.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends Community Centers for the subject property. Community centers are areas with compact development, primarily non-residential, serving a collection of neighborhoods. This type of development consists of a mix of uses, including retail, services, office use, multi-family residential, and entertainment. Community centers may be developed at the intersections of major arterial streets and along major arterials, highways, and turnpike corridors. This type of area is served by numerous roads and transit routes, providing a variety of connections to adjacent residential neighborhoods, retail centers, and employment centers.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

The surrounding properties are zoned Uptown (U) sub-district within the Downtown (DT) District. The First Baptist Church owns the properties to the West, East, and south containing parking lots and an activity center. The property to the North is another church. A church is considered a service to the community and the proposed remodeling will enhance the exterior appearance of the building.

STAFF RECOMMENDATION

Staff recommends approval of 1) a Major Waiver to Chapter 7, Table 7-7 of the Garland Development Code for the at-grade and above-grade window percentage of the façade, architectural articulation, Build-To-Zone, streetscaping, and a monument sign standards and 2) a Downtown Development Plan to allow for a church expansion and addition, including a major waiver for the at-grade and above-grade window percentage of the façade, architectural articulation, Build-To-Zone, streetscaping, and a monument sign standards on a property zoned Downtown (DT) District, Uptown (U) sub-district.

The proposal meets the general intent of the district and will result in an improved project which will be an attractive contribution to the Downtown District.

ADDITIONAL INFORMATION

- i. Location Map
- ii. Downtown Development Plan Exhibits
- iii. Site Photos


CITY COUNCIL DATE: June 03, 2025

PREPARED BY:


Matthew Wolverton Planner II Planning & Development 972-205-2454 mwolverton@garlandtx.gov


REVIEWED BY:


Emma Chetuya Ph.D., AICP Planning Administrator Planning and Development 972-205-2453 echetuya@garlandtx.gov



801 W. Avenue D








A SITE PLAN

garthoffdesign
landscape architecture

landscape architecture 5646 milton, suite 606 dallas, texas 75206 214.750.4727 www.garthoffdesign.com



FIRST BAPTIST CHURCH GARLA
BUILDING EXPANSION
SOLWEST AVENUE D. SO

ISSUE:

DEVELOPMENT
10/14/2024 PLAN

REVISIONS:

1 01.24.25 CITY COMMENTS
 2 03.14.25 CITY COMMENTS


② 03.14.25 CITY COMMEN

HARDSCAPE PLAN

OWNER
FIRST BAPTIST CHURCH
801 WEST AVENUE D
GARLAND, TEXAS 75040
PHONE: 972.276.7184

SCALE: 1/16" = 1'-0"

CASE 240702-2



landscape architecture 5646 milton, suite 606 dallas, texas 75206 214.750.4727 www.garthoffdesign.com

BUILDII Δ **FIRS**

DEVELOPMENT 10/14/2024 PLAN

REVISIONS:

01.24.25 CITY COMMENTS


03.14.25 CITY COMMENTS

LANDSCAPE

PLAN OWNER FIRST BAPTIST CHURCH 801 WEST AVENUE D
GARLAND, TEXAS 75040
PHONE: 972.276.7184

CASE 240702-2

L2.1



landscape architecture 5646 milton, suite 606 dallas, texas 75206 214.750.4727 www.garthoffdesign.com

BUILDII Δ FIRS

DEVELOPMENT 10/14/2024 PLAN

REVISIONS:


01.24.25 CITY COMMENTS

03.14.25 CITY COMMENTS

LANDSCAPE PLAN


CASE 240702-2

L2.1



BEC

BECK ARCHITECTURE 1601 ELM STREET SUITE 2800 DALLAS, TX 75201 PH: 214-303-6200 FAX: 214-303-6300 WWW.BECKARCHITECTURE.COM



ARCHITECT NAME STATE REGISTRATION #

INCOMPLETE DOCUMENTS
FOR INTERIM REVIEW
ONLY. NOT FOR
REGULATORY APPROVAL,
PERMIT, OR CONSTRUCTION.

ARCHITECT SEAL


1/24/2025 2:26:56 PM



FIRST BAPTIST CHURCH GARLAND BUILDING EXPANSION

EXTERIOR ELEVATIONS - DDP

175594 JOB NO. SHEET






FAX: 214-303-6300


WWW.BECKARCHITECTURE.COM



1 ELEVATION- COURTYARD NORTH SCALE: 3/32" = 1'-0"




ARCHITECT NAME STATE REGISTRATION # INCOMPLETE DOCUMENTS FOR INTERIM REVIEW ONLY. NOT FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION 1/24/2025 2:27:12 PM ARCHITECT SEAL




FIRST BAPTIST CHURCH GARLAND **BUILDING EXPANSION**

EXTERIOR ELEVATIONS - DDP

175594 SHEET JOB NO.






5 SCALE: 1/8" = 1'-0"


SOUTH LARGE CURTAIN WALL

SCALE: 1/8" = 1'-0"




3 ELEVATION- COURTYARD NORTH

SCALE: 1/8" = 1'-0"



7 ELEVATION- EAST BY GLENBROOK AVENUE

SCALE: 1/8" = 1'-0"



2 ELEVATION- SOUTH ALONG AVENUE D

SCALE: 1/8" = 1'-0"



BECK ARCHITECTURE 1601 ELM STREET SUITE 2800 DALLAS, TX 75201 PH: 214-303-6200 FAX: 214-303-6300 WWW.BECKARCHITECTURE.COM

	T	SUBMISSION:	
#	DATE	SUBMISSION	

FIRST BAPTIST CHURCH GARLAND BUILDING EXPANSION

WALL SECTIONS -DIAGRAM

175594	A8.
JOB NO.	SHEET



















DD 24-04



View of the subject site looking North on Glenbrook Avenue.




View of the subject site looking North from West Avenue D.



View of the subject site looking North up 9th Avenue.



View from the subject site looking South across West Avenue D.



801 W. Avenue D

To date we have not received any responses for this case.



Plan Commission 2. b.

Meeting Date: 05/12/2025

Item Title: Z 24-02 Trak Group Inc. (District 6)

Summary:

Hold a public hearing and consider the application of **Trak Group Inc.**, requesting a Specific Use Provision (SUP) for Fuel Pumps, Retail use on property zoned Community Retail (CR). The property is addressed as 3420 W Walnut Road. (District 6) (File Z 24-02)

Attachments

Z 24-02 Trak Group Inc. Report & Attachments

Z 24-02 Trak Group Inc. Responses

Planning Report



File No: Z 24-02/District 6

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025

REQUEST

Hold a public hearing and consider approval of 1) a Specific Use Provision (SUP) for Fuel Pumps, Retail use on property zoned Community Retail (CR) District and 2) a Concept Plan for the existing Fuel Pumps, Retail use.

LOCATION

3420 W Walnut

APPLICANT

Trak Group Inc.

OWNER

Trak Group Inc.

BACKGROUND

The subject property is currently zoned Community Retail (CR). An SUP was granted for the property to have a Fuel Pumps, Retail use in 1998. The SUP was effective for 20 years and has expired since 2018. The site is currently developed with a convenience store and six (6) fuel pumps.

SITE DATA

The subject site is approximately 21,060 square feet and is accessed from West Walnut Street on the north and South Jupiter Road on the west. The convenience store is approximately 2,160 square feet in size.

USE OF PROPERTY UNDER CURRENT ZONING

The site is zoned Community Retail (CR). The Community Retail (CR) district is intended to accommodate a variety of retail, service, and business establishments that may or may not be designed in a shopping center configuration. The district may be used as a transition district between lower intensity retail or office uses and more intense uses. A CR district is generally appropriate along major transportation corridors but is generally not appropriate in proximity to low-density residential districts without significant buffering and screening features. An example of allowed use in a CR district is a retail shopping area that may be large in scale with very limited or no outside storage. Traffic generated by uses in a CR district must be focused onto the major thoroughfare network. Development in a CR district may not be designed in a manner that increases traffic through residential areas.

CONSIDERATIONS

- The applicant is requesting the SUP to be permitted for an unlimited number of years. The SUP time period guide recommends a period of 20-25 years. However, it is worthy to note that this business has operated for several years after the SUP expired.
- 2. The convenience store and fuel pumps were constructed 27 years ago and is currently in operation. The establishment has been serving the community with relatively minimal code violations throughout the years.

3. The applicant will increase landscaping on the site by adding a continuous row of shrubs on the south side of the site in the existing landscape median and a screening row of shrubs along at least 50% of each street frontage of South Jupiter Road and West Walnut Street.

Section 2.21 of the Garland Development Code (GDC) allows for the Plan Commission and City Council to attach conditions to the Specific Use Provision to mitigate adverse effects of the proposed use and to carry out the intent of this Section. Conditions may include any, or a combination, of the following:

- (1) Limitation of building size or height;
- (2) Increased open space;
- (3) Limitations on impervious surfaces;
- (4) Enhanced loading and parking requirements;
- (5) Additional landscaping, sidewalk, screening, vehicular access and parking improvements;
- (6) Placement or orientation of buildings and entryways;
- (7) Buffer yards, landscaping and screening;
- (8) Signage restrictions and design;
- (9) Limitation on operation or function of proposed use (for example, hours of operation);
- (10) Limitation on the effective time period for an SUP; or
- (11 Any other criteria to safeguard and protect public health, safety, and welfare.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends Vital Neighborhoods with an Urban Neighborhoods subcategory for the subject site. Urban neighborhoods are higher density residential developments. This residential option may utilize vertical mixed-use integrated into the surrounding area, reflecting the area's dominant character or, when desired, promoting a new character. This type of development should encourage access to a range of mobility options and is generally located in the vicinity of major intersections and/or secondary arterial streets, with proximity to significant bus or rail amenities.

Urban neighborhoods are characterized by moderate to high density single-family attached and multifamily residential units, greater than 12 dwelling units per acre. Developments within this category generally are predominantly residential but may include compatible non-residential uses.

The existing convenience store is compatible with the comprehensive plan as it is a non-residential use which serves the routine needs of the surrounding community.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

The properties to the north, east, and west are zoned Community Retail (CR) and has an auto minor repair use on the north, check cashing business on the east, and a variety of retail, restaurant and personal care uses on the west. The property to the south is zoned Community Retail (CR) with an SUP for a Reception Facility and has several retail uses, a grocery/supermarket, and office uses to the south.

Although the fuel pumps are autocentric in nature and there is another fuel pump use across the street from this establishment, this gas station has served the community for over two (2) decades with minimal code violations. The applicant will improve the site by adding landscaping within and along the edges of the site.

STAFF RECOMMENDATION

Staff recommends the Plan Commission consider approval of a Specific Use Provision (SUP) for the Fuel Pumps, Retail use to continue on the property zoned Community Retail (CR) District and 2) a Concept Plan for the Fuel Pumps, Retail Use.

Saff recommends a five-year time period for this SUP. The shorter time frame is recommended to ensure that the enhancements proposed are maintained on the site and also, to encourage the business to stay vigilant so that the present situation of operating without a valid SUP does not occur in the future.

ADDITIONAL INFORMATION

- i. Location Map
- ii. Site Photos
- iii. Concept Plan
- iv. Applicant's Written Request
- v. SUP Conditions


CITY COUNCIL DATE: June 3, 2025

PREPARED BY:

Emma Chetuya Ph.D., AICP Planning Administrator Planning & Development 972-205-2453 echetuya@garlandtx.gov

REVIEWED BY:

Nabila Nur, AICP Planning Director Planning and Development 972-205-2449 echetuya@garlandtx.gov



3420 West Walnut Street

Z 24-02




Photo of existing convenience store facing east


Photo of fuel pumps facing south



Photo of fuel pumps and Refuse container facing west







SITE DATA TABLE			
LAND AREA	0.483 ACRES (21060 SQ.FT)		
EXITING ZONING	COMMERCIAL		
EXISTING LAND USE	COMMERCIAL		

		Name of the	- FE		
	a subline		Quends Bupt at Charles		Q terms
Confidence Dr.	atuntu i i	Fresbyterian Church UBC A	coderny Q	Lar Hou	/
Y	P teres	. 181	MAIN S DOM	nt/	15
	STOPPING STOP			Direct And Justice	Contemps D.
	/-	3100		Food Store 🖓 🕠	Sar
in a	Fré soni (P	Walnut 3 NS ♥ of 2 ♥ Wo	other pro- levet - N - ES		N Sames Or
CON HAA	Tagas no.	Walnut (b. Jupius W. PS	Page Patien West Work Syreet Talean Terrer		Lak
9	N. HAMMAN A		Www. St. Aprile W. Wanaray	P	SP III
W. William				8	4
	Febr Ché 0: Gió Chú & To	SITE	0	U Catilo Dather Shopl y Salon Garland-Salon	2-
and a	Classic Or		Sariand Sazza B Rancho Supermorcedo		7
		ubirbet .	D RANGO SAPO HISTORY		4/1
Et of	O Plany Park Dr				
Plaz s Park Di	Dalles Drywell & Restoration		Spanish Plaza Apartmetts	Walnut Crock south Library	
	Edgyweod Dr		WoodDz Edgento	odor	E
	To libut	APPOLITE STATE	(D. J. J. St. 120		G. C. Saller
F	cheitjhill Lts		C Apartmets	206	The same of the sa

VICINITY MAP NOT TO SCALE

NOTE:

SITE DESIGN AND CONSTRUCTION PLANS SHALL CONFORM TO ALL REQUIREMENTS OF THE GARLAND DEVELOPMENT CODE (GDC), TECHNICAL STANDARD MANUAL (TSM), AND CITY CODES UNLESS AN APPROVED PD NARRATIVE CONDITION EXPRESSLY PROVIDES OTHERWISE. THE CONCEPT PLAN SHALL BE USED TO REPRESENT THE GENERAL IDEA OF THE PROPOSED LAND USE AND SITE ELEMENTS. THE CONCEPT PLAN SHALL NOT SUPERSEDE, AND SHALL BE SUBORDINATE TO, THE STANDARDS, REQUIREMENTS, AND CONDITIONS OF THE GDC, TSM, CITY CODE, OR THE APPROVED PD.

LEGEND

PROPERTY LINE

CONVENIENT STORE

3 NOS. FUEL DISPENSER

EXISTING SIDEWALK

EXISTING DUMPSTER

EXISTING PAVEMENT

ADDITIONAL LANDSCAPE TO BE

ADDED

EXISTING OFFSITE LANDSCAPE

OFFSITE PAVEMENT

OFFSITE SIDEWALK

OFFSITE CHANNEL (KEEN

CREEK)



OWNER: TRAK GROUP INC.

NAME OF APPLICANT: KHALID REZWAN PLAN PREPARER: KHALID REZWAN

COMPANY NAME: TRAK GROUP INC.

SITE PLAN

PROJECT NAME- TRANK TEN 3420 W. WALNUT ST., GARLAND TX. 75042 DEVELOPMENT SERVICES

To,

City Of Garland, Planning Division

Dear Sir/Madam,

I am applying for the SUP permit renewal for Trak Group Inc, physically addressed at 3420 W Walnut Street, Garland, TX 75042 for next 20years or the highest applicable time frame.

It is a gas station with a convenience store. We sell all the products which are gas station normally sells.

Should there be an questions for this application, please feel free to contact me at 214.674.6745.

Kind Regards,

Khalid Rezwan. (President)

Trak Group Inc.

SPECIFIC USE PROVISION CONDITIONS

ZONING FILE Z 24-02

3420 W. Walnut Street

[Requested by the Applicant]

- I. Statement of Purpose: The purpose of this Specific Use Provision is to allow a Fuel Pumps, Retail use.
- II. Statement of Effect: This Specific Use Provision shall not affect any regulation found in the Garland Development Code, Ordinance No. 6773, as amended prior to adoption of this ordinance, except as specifically provided herein.
- III. General Regulations: All regulations of the Community Retail (CR) District and Site Development Standards as set forth in Chapter 2 and 4 of the Garland Development Code, Ordinance 6773, are included by reference and shall apply, except as otherwise specified by this ordinance.

IV. Concept Plan:

Concept Plan: The site shall be in general conformance with the approved Concept Plan. The concept plan shall be used to represent the general idea of the proposed land use and site elements. The concept plan shall not supersede, and shall be subordinate to, the standards, requirements, and conditions of the GDC, Technical Standard Manual (TSM), a, City code, or the approved SUP.

I. Abandonment: In the event the land use for which this Specific Use Provision was granted ("Land Use") is abandoned, the SUP and all rights to the Land Use are automatically terminated, and the premises must be used in conformance with the PD, GDC, federal, and state law.

For the purposes of this Specific Use Provision, Abandonment is any of the following acts:

A. A failure to apply for a site or building permit on the premises, where applicable, within 180 days of the effective date of this SUP;

- B. A failure to obtain a certificate of occupancy for the Land use within 730 days of the effective date of this SUP;
- C. A failure to commence operating the Land Use on the premises within 90 days of receiving a final certificate of occupancy for the Land Use;
- D. Discontinuance of the Land Use for a period of 180 days;
- E. Applying for, and receiving, a new Certificate of Occupancy for a use other than the Land Use; or
- F. Operating a use on the premises, whether as a primary or secondary use, that is not allowed within the PD District, by the GDC, or by state or federal law.

The termination of utilities on the premises for a period of 180 calendar days is prima facie evidence of abandonment and the owner shall have the burden to prove that the Land Use has not been abandoned.

V. Specific Regulations:

A. <u>SUP Time Period:</u> The Specific Use Provision for a Fuel Pumps, Retail Use shall be in effect indefinitely.

[Condition recommended by staff]


A. <u>SUP Time Period:</u> The Specific Use Provision for a Fuel Pumps, Retail Use shall be in effect for a period of five (5) years.

B. Additional Landscaping:

- (1) There shall be a continuous row of shrubs planted on the south side of the site in the existing landscape median. The plants shall originate from the City's Approved Plant List.
- (2) A screening row of shrubs is required along at least 50% of each street frontage along South Jupiter Road and West Walnut Street.
- (3) Shrubs that are of a "dwarf" or "miniature" variety must be a minimum of one foot in planted height at time of installation unless that particular variety and size of shrub is typically less than one foot in planted height in North Central Texas.

SUP Requirements Zoning File 24-09 Page 2

(4) All landscaping shall be maintained in accordance with Section 4.33 of the Garland Development Code.



Comment Form Case Z 24-02

Z 24-02 Trak Group Inc. The applicant is requesting a Specific Use Provision (SUP) for Fuel Pumps, Retail on property zoned Community Retail (CR). The property is addressed as 3420 W Walnut

Z 24-02 Trak Group Inc. El solicitante solicita una Disposición de Uso Específico (SUP) para

Minorista Comunitario (CR). La propiedad está ubicada en 3420 W Walnut Road (Distrito 6) (véase el mapa adjunto).
Z 24-02 Trak Group Inc. Người nộp đơn đang yêu cầu Quy định sử dụng cụ thế (SUP) cho Máy bơm nhiên liệu, Bán lẻ trên bắt động sản được phân vùng là Bán lẻ cộng đồng (CR). Bắt động sản được định địa chỉ là 3420 W Walnut Road. (Quận 6) (xem bán đồ kèm theo)
Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envie el formulario por correo electrór a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o env por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Yui long dièn dày thông tin sau và giới biểu mấu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main St Garland, TX; hoặc gửi thư đến Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad. Dueño de la empresa, Inquilino, etc.) / (Chú số hữu bắt động sắn, Chủ doanh
3501 Classic Drive Mille William
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
_ Garland TX
City, State / Estado de la Ciudad / Thành bang
75042
Zip Code / Código postal / Mã B u Ohính
andre Dulleger 5/2/2025
Signature / Firma / Ch



Plan Commission 2. c.

Meeting Date: 05/12/2025

Item Title: Z 25-03 The Kroger Co. (District 1)

Summary:

Hold a public hearing and consider the application of **The Kroger Co.**, requesting approval of a Specific Use Provision for Fuel Pumps, Retail use. The site is located at 6850 North Shiloh Road. (District 1) (File Z 25-03)

Attachments

Z 25-03 The Kroger Co. Report & Attachments

Z 25-03 The Kroger Co. Responses

Planning Report



File No: Z 25-03/District 1

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025

REQUEST

Hold a public hearing and consider approval of 1) a Specific Use Provision (SUP) for Fuel Pumps, Retail Use and 2) a Concept Plan for a Fuel Pumps, Retail Use.

LOCATION

6850 North Shiloh Road

APPLICANT

The Kroger Co.

OWNER

US Regency Shiloh Springs, LLC

BACKGROUND

The subject property is currently a shopping center containing a Kroger and many individual suites on both sides of the Kroger containing various uses such as retail, restaurant, personal services, and more. The Kroger wishes to replace 63 parking spots with a 10-fuel pump gas station. This gas station would be associated with the Kroger grocery stores and similar concept can be found at many other locations within the metroplex.

The applicant also wishes to have the ability to add more fuel pumps than currently proposed in the future. They will need to submit an SUP amendment request if they wish to expand in the future.

SITE DATA

The subject site is a 6.183-acre tract of land developed with a shopping center containing a Kroger and has approximately 895 linear feet along North Shiloh Road while the fuel area will have approximately 260 linear feet of frontage along North Shiloh Road. The site can be accessed from North Shiloh Road where a traffic signal will be added per the request of the Transportation department. Even though this development will replace 63 parking spaces, there will still be a parking surplus on site.

USE OF PROPERTY UNDER CURRENT ZONING

The site is zoned Planned Development (PD) District 98-28. This site's base zoning is Community Retail (CR). The Community Retail (CR) District is intended to accommodate a variety of retail, service, and business establishments that may or may not be designed in a shopping center configuration. The district may be used as a transition district between lower intensity retail or office uses and more intense uses. A Community Retail (CR) District is generally appropriate along major transportation corridors but is generally not appropriate in proximity to low-density residential districts without significant buffering and screening features. An example of allowed use in a CR district is a retail shopping area that may be large in scale with very limited or no outside storage. Traffic generated by uses in a Community Retail (CR) District must be focused onto the major thoroughfare network. Development in a Community Retail (CR) District may not be designed in a manner that increases traffic through residential areas.

CONSIDERATIONS

Specific Use Provision

- 1. The applicant is requesting a Specific Use Provision (SUP) for Fuel Pumps, Retail with an indefinite time period.
- 2. The SUP Time period guide recommends 20-25 years for Fuel Pumps, Retail.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends Community Centers for the subject site. Community centers are areas with compact development, primarily nonresidential, which serves nearby neighborhoods with a mix of uses that include retail, office, multi-family, and entertainment.

It is envisioned that retail centers such as these promote high quality retail and service uses which promote placemaking and desirable destinations. While gas stations are not always a desired use in Garland due to the existing number of stations in the city and its autocentric nature, especially on vacant land, this would be attached to the existing Kroger and replace a parking lot.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

The properties to the North are zoned Planned Development (PD) District 00-69, Planned Development (PD) District 97-54, Specific Use provision (SUP) 00-18, and Planned Development (PD) District 00-72 all with a base zoning of Community Retail (CR) District. These sites contain a fast-food restaurant with drive-through, animal clinic, urgent care, doctor's office, and a gas station with convenience store. The property to the East is zoned Planned Development (PD) district 97-04 with a base zoning of Multi-Family-1 and contains an apartment development. The properties to the West are zoned Planned development (PD) District 92-30 for Single-Family-7 uses and contains a single-family detached neighborhood. The properties to the south are zoned Planned Development (PD) District 03-49 and Planned Development (PD) District 15-35 both with a Community Retail (CR) District base zoning. The sites contain a bank with drive-through ATM lanes and a minor automobile repair (oil and lube change establishment).

Although the proposed gas station will increase the amount of traffic in this area, the proposed use may be considered a neighborhood service use in this context as there is an existing grocery store that will be associated with the fuel pumps if approved. Additionally, the proposed traffic signal will help alleviate the traffic generated by this new use, as well as improve the existing traffic situation.

The applicant requests they be allowed more fuel pumps in the future than currently proposed to permit for a potential expansion in the future. In staff's opinion, the proposed 10 fuel pumps (that are included within this request) would fit within the scale and size of the existing development, and the maximum allowed number of pumps should be restricted to 10. However, that request would need to be separately evaluated as an SUP amendment.

STAFF RECOMMENDATION

Staff recommends approval of 1) a Specific Use Provision (SUP) for Fuel Pumps, Retail Use and 2) a Concept Plan for a Fuel Pumps, Retail Use.

ADDITIONAL INFORMATION

- i. Location Map
- ii. SUP Conditions

iii. Concept Planiv. Site Photos

v. Applicant Written Request


CITY COUNCIL DATE: June 3, 2025

PREPARED BY:

Matthew Wolverton Planner II Planning & Development 972-205-2454 mwolverton@garlandtx.gov

REVIEWED BY:

Emma Chetuya Ph.D., AICP Planning Administrator Planning and Development 972-205-2453 echetuya@garlandtx.gov



6850 North Shiloh Road

SPECIFIC USE PROVISION

ZONING FILE Z 25-03

6850 North Shiloh Road

[Requested by the Applicant]

- I. Statement of Purpose: The purpose of this Specific Use Provision is to allow a Fuel Pumps, Retail Use.
- II. Statement of Effect: This Specific Use Provision shall not affect any regulation found in the Garland Development Code, Ordinance No. 6773, as amended prior to adoption of this ordinance, except as specifically provided herein.
- III. General Regulations: All regulations of the Community Retail (CR) District as set forth in Chapter 2 of the Garland Development Code Ordinance 6773, are included by reference and shall apply, except as otherwise specified by this ordinance.
- IV. Abandonment: In the event the land use for which this Specific Use Provision was granted ("Land Use") is abandoned, the SUP and all rights to the Land Use are automatically terminated, and the premises must be used in conformance with the PD, GDC, federal, and state law.

For the purposes of this Specific Use Provision, Abandonment is any of the following acts:

- A. A failure to apply for a site or building permit on the premises, where applicable, within 180 days of the effective date of this SUP;
- B. A failure to obtain a certificate of occupancy for the Land use within 730 days of the effective date of this SUP;
- C. A failure to commence operating the Land Use on the premises within 90 days of receiving a final certificate of occupancy for the Land Use;
- D. Discontinuance of the Land Use for a period of 180 days;
- E. Applying for, and receiving, a new Certificate of Occupancy for a use other than the Land Use; or

F. Operating a use on the premises, whether as a primary or secondary use, that is not allowed within the PD District, by the GDC, or by state or federal law.


The termination of utilities on the premises for a period of 180 calendar days is prima facie evidence of abandonment and the owner shall have the burden to prove that the Land Use has not been abandoned.

V. Specific Regulations:


<u>Time Period:</u> The Specific Use Provision shall have an indefinite time period.

[Condition recommended by staff]

Number of Pumps: The maximum number of Fuel Pumps allowed per this Specific Use Provision is ten (10).




E: THIS DRAWING IS FOR CONCEPTUAL PURPOSES ONLY. SITE INFORMATION WAS OBTAINED FROM CLIENT'S DOCUMENTS; DESIGN MAY VARY, DEPENDING ON ACTUAL TOPOGRAPHY, DRAINAGE, SOILS, SURVEY, ETC. THIS ADDITIONAL DATA AND SITE CONDITIONS COULD CAUSE CHANGES IN PARKING RATIOS AND SPACE AVAILABLE FOR DEVELOPMENT, AND MAY INCREASE ESTIMATED DEVELOPMENT COSTS.





SITE ZONING: PD CR 98-28

SITE DATA		SETBACKS	
65,350± SF	FRONT BUILDING SETBACK 30 FEET		
262 (1/250 GFA)	SIDE BUILDING SETBACK	20 FEET	
355 STALLS	REAR BUILDING SETBACK	30 FEET	
184 SF	FRONT YARD (N SHILOH RD)	20 FEET	
N/A	SIDE YARD (N/A)	(TBD) FEET	
63 STALLS	REAR YARD	(TBD) FEET	
292 STALLS	PUMP ISLAND (IF APPLICABLE)	20 FEET	
248,147 SF	SITE ARE POST PLAT	269,327 SF	
	65,350± SF 262 (1/250 GFA) 355 STALLS 184 SF N/A 63 STALLS 292 STALLS	65,350± SF FRONT BUILDING SETBACK 262 (1/250 GFA) SIDE BUILDING SETBACK 355 STALLS REAR BUILDING SETBACK 184 SF FRONT YARD (N SHILOH RD) N/A SIDE YARD (N/A) 63 STALLS REAR YARD 292 STALLS PUMP ISLAND (IF APPLICABLE)	



FIT CONSULTATION NUMBER: 240425-2

NOTE: SITE DESIGN AND CONSTRUCTION PLANS SHALL CONFORM TO ALL REQUIREMENTS OF THE GARLAND DEVELOPMENT CODE (GDC), TECHNICAL STANDARD MANUAL (TSM), AND CITY CODES UNLESS AN APPROVED PD NARRATIVE CONDITION EXPRESSLY PROVIDES OTHERWISE. THE CONCEPT PLAN SHALL BE USED TO REPRESENT THE GENERAL IDEA OF THE PROPOSED LAND USE AND SITE ELEMENTS. THE CONCEPT PLAN SHALL NOT SUPERSEDE, AND SHALL BE SUBORDINATE TO, THE STANDARDS, REQUIREMENTS, AND CONDITIONS OF THE GDC, TSM, CITY CODE, OR THE APPROVED PD.

LEGEND	
	EXISTING KROGER SUPERMARKET
	RETAIL PARKING - ASPHALT AND CONCRETE PAVEMENT
	EXISTING ACCESS DRIVES
	EXISTING LANDSCAPING
	EXISTING RETAIL BUILDINGS
	PROPOSED ASPHALT PAVEMENT
	PROPOSED CONCRETE / SIDEWALK
	PROPOSED FUEL STATION CANOPY
	PROPOSED FUEL STATION KIOSK
	PROPOSED LANDSCAPING

OWNER: US REGENCY SHILOH SPRINGS, LLC 8080 N. CENTRAL EXPY, SUITE 1650 DALLAS, TX 75206			
APPLICANT: THE KROGER CO. 751 FREEPORT PARKWAY COPPELL, TX 75019 CONTACT NAME: RICHARD BINKLEY 817-675-8428			
PLAN PREPARER: CEI ENGINEERING ASSOCIATES, INC. 2600 NE 11TH ST BENTONVILLE, AR 72712 CONTACT NAME: MICHAEL SERRATO 479-715-4425			
LEGAL DESCRIPTION LOT 5R2 AND LOT 5R3 BLOCK 1 SHILOH SPRINGS RETAIL ADDITION			
CITY: STATE: TEXAS			
COUNTY: DALLAS			<u>FIT NO.</u> 240425-2



CEI ENGINEERING ASSOCIATES, INC. 710 W PINEDALE AVE FRESNO, CA 93711 PHONE: (559) 447-3119 FAX: (559) 447-3129


> 52 KROGER FUEL - 6850 N. SHILOH ROAD GARLAND, TX

> > PRELIMINARY NOT FOR CONSTRUCTION

PROFESSIONAL OF RECORD	POR
PROJECT MANAGER	MS
DESIGNER	EN
CEI PROJECT NUMBER	96000
DATE	4/23/2025


CONCEPTUAL SITE PLAN

SHEET NUMBER



© 2025 CEI ENGINEERING ASSOCIATES, INC.








Know what's below.
Call before you dig.

SITE ZONING: PD CR 98-28

SITE DATA		SETBACKS	
EXISTING KROGER AREA	65,350± SF	FRONT BUILDING SETBACK	30 FEET
REQUIRED PARKING	262 (1/250 GFA)	SIDE BUILDING SETBACK	20 FEET
EXISTING PARKING	355 STALLS	REAR BUILDING SETBACK	30 FEET
PROPOSED FUEL AREA	184 SF	FRONT YARD (N SHILOH RD)	20 FEET
REQUIRED PARKING	N/A	SIDE YARD (N/A)	(TBD) FEET
STALLS REMOVED FOR FUEL	63 STALLS	REAR YARD	(TBD) FEET
POST FUEL PARKING	292 STALLS	PUMP ISLAND (IF APPLICABLE)	20 FEET
SITE AREA PRE PLAT	248,147 SF	SITE ARE POST PLAT	269,327 SF



FIT CONSULTATION NUMBER: 240425-2

NOTE: SITE DESIGN AND CONSTRUCTION PLANS SHALL CONFORM TO ALL REQUIREMENTS OF THE GARLAND DEVELOPMENT CODE (GDC), TECHNICAL STANDARD MANUAL (TSM), AND CITY CODES UNLESS AN APPROVED PD NARRATIVE CONDITION EXPRESSLY PROVIDES OTHERWISE. THE CONCEPT PLAN SHALL BE USED TO REPRESENT THE GENERAL IDEA OF THE PROPOSED LAND USE AND SITE ELEMENTS. THE CONCEPT PLAN SHALL NOT SUPERSEDE, AND SHALL BE SUBORDINATE TO, THE STANDARDS, REQUIREMENTS, AND CONDITIONS OF THE GDC, TSM, CITY CODE, OR THE APPROVED PD.

LEGEND	
	EXISTING KROGER SUPERMARKET
	RETAIL PARKING - ASPHALT AND CONCRETE PAVEN
	EXISTING ACCESS DRIVES
	EXISTING LANDSCAPING
	EXISTING RETAIL BUILDINGS
	PROPOSED ASPHALT PAVEMENT
	PROPOSED CONCRETE / SIDEWALK
	PROPOSED FUEL STATION CANOPY
	PROPOSED FUEL STATION KIOSK
	PROPOSED LANDSCAPING
	PROPOSED LAINDSCAPING

OWNER: S REGENCY SHILOH SPRINGS, LLC 080 N. CENTRAL EXPY, SUITE 1650 ALLAS, TX 75206 ONTACT NAME: LAUREN HAWKINS 214-706-2514			
APPLICANT: HE KROGER CO. 51 FREEPORT PARKWAY OPPELL, TX 75019 ONTACT NAME: RICHARD BINKLEY 817-675-8428			
PLAN PREPARER: EI ENGINEERING ASSOCIATES, INC. 600 NE 11TH ST ENTONVILLE, AR 72712 ONTACT NAME: MICHAEL SERRATO 479-715-4425			
LEGAL DESCRIPTION LOT 5R2 AND LOT 5R3 BLOCK 1 SHILOH SPRINGS RETAIL ADDITION			
CITY: STATE: TEXAS			
COUNTY: DALLAS	<u>SURVEY</u> NORTH TE SURVEYING	XAS	<u>FIT NO.</u> 240425-2



CEI ENGINEERING ASSOCIATES, INC. 710 W PINEDALE AVE FRESNO, CA 93711 PHONE: (559) 447-3119 FAX: (559) 447-3129

> 57 2


> > PRELIMINARY NOT FOR CONSTRUCTION

PROFESSIONAL OF RECORD	POR
PROJECT MANAGER	MS
DESIGNER	EN
CEI PROJECT NUMBER	96000
DATE	4/23/2025


CONCEPTUAL SITE PLAN

SHEET TITLE
SHEET NUMBER

CSP-1A



INFORMATION WAS OBTAINED FROM CLIENT'S DOCUMENTS; DESIGN MAY VARY, DEPENDING ON ACTUAL TOPOGRAPHY, DRAINAGE, SOILS, SURVEY, ETC. THIS ADDITIONAL DATA AND SITE CONDITIONS COULD CAUSE CHANGES IN PARKING RATIOS AND SPACE AVAILABLE FOR DEVELOPMENT, AND MAY INCREASE ESTIMATED DEVELOPMENT COSTS.






Know what's below.
Call before you dig.

SITE ZONING: PD CR 98-28

SITE DATA		SETBACKS		
EXISTING KROGER AREA	65,350± SF	FRONT BUILDING SETBACK	30 FEET	
REQUIRED PARKING	262 (1/250 GFA)	SIDE BUILDING SETBACK	20 FEET	
EXISTING PARKING	355 STALLS	REAR BUILDING SETBACK	30 FEET	
PROPOSED FUEL AREA	184 SF	FRONT YARD (N SHILOH RD)	20 FEET	
REQUIRED PARKING	N/A	SIDE YARD (N/A)	(TBD) FEET	
STALLS REMOVED FOR FUEL	63 STALLS	REAR YARD	(TBD) FEET	
POST FUEL PARKING	292 STALLS	PUMP ISLAND (IF APPLICABLE)	20 FEET	
SITE AREA PRE PLAT	248,147 SF	SITE ARE POST PLAT	269,327 SF	
		-		



FIT CONSULTATION NUMBER: 240425-2

NOTE: SITE DESIGN AND CONSTRUCTION PLANS SHALL CONFORM TO ALL REQUIREMENTS OF THE GARLAND DEVELOPMENT CODE (GDC), TECHNICAL STANDARD MANUAL (TSM), AND CITY CODES UNLESS AN APPROVED PD NARRATIVE CONDITION EXPRESSLY PROVIDES OTHERWISE. THE CONCEPT PLAN SHALL BE USED TO REPRESENT THE GENERAL IDEA OF THE PROPOSED LAND USE AND SITE ELEMENTS. THE CONCEPT PLAN SHALL NOT SUPERSEDE, AND SHALL BE SUBORDINATE TO, THE STANDARDS, REQUIREMENTS, AND CONDITIONS OF THE GDC, TSM, CITY CODE, OR THE

EXISTING KROGER SUPERMARKET
RETAIL PARKING - ASPHALT AND CONCRETE PAVEMENT
EXISTING ACCESS DRIVES
EXISTING LANDSCAPING
EXISTING RETAIL BUILDINGS
PROPOSED ASPHALT PAVEMENT
PROPOSED CONCRETE / SIDEWALK
PROPOSED FUEL STATION CANOPY
PROPOSED FUEL STATION KIOSK
PROPOSED LANDSCAPING
EXISTING PROPERTY LINE
ADJUSTED PROPERTY LINE

OWNER: S REGENCY SHILOH SPRINGS, LLC 080 N. CENTRAL EXPY, SUITE 1650 ALLAS, TX 75206 ONTACT NAME: LAUREN HAWKINS 214-706-2514			
APPLICANT: HE KROGER CO. 51 FREEPORT PARKWAY OPPELL, TX 75019 ONTACT NAME: RICHARD BINKLEY 817-675-8428			
PLAN PREPARER: EI ENGINEERING ASSOCIATES, INC. 600 NE 11TH ST ENTONVILLE, AR 72712 ONTACT NAME: MICHAEL SERRATO 479-715-4425			
LEGAL DESCRIPTION LOT 5R2 AND LOT 5R3 BLOCK 1 SHILOH SPRINGS RETAIL ADDITION			
CITY: GARLAND STATE: TEXAS			
COUNTY:SURVEY:FIT NO.DALLASNORTH TEXAS SURVEYING LLC240425-2		<u>FIT NO.</u> 240425-2	

Solutions for Land and Life

CEI ENGINEERING ASSOCIATES, INC. 710 W PINEDALE AVE FRESNO, CA 93711 PHONE: (559) 447-3119 FAX: (559) 447-3129


> 52 KROGER FUEL - 6850 N. SHILOH ROAD GARLAND, TX

> > PRELIMINARY NOT FOR CONSTRUCTION


PROFESSIONAL OF RECORD	POR
PROJECT MANAGER	MS
DESIGNER	EN
CEI PROJECT NUMBER	96000
DATE	4/23/2025

CONCEPTUAL SITE PLAN PROPERTY **EXHIBIT**

SHEET NUMBER












SITE ZONING: PD CR 98-28


SITE [DATA	SETB	ACKS
EXISTING KROGER AREA	65,350± SF	FRONT BUILDING SETBACK	30 FEET
REQUIRED PARKING	262 (1/250 GFA)	SIDE BUILDING SETBACK	20 FEET
EXISTING PARKING	355 STALLS	REAR BUILDING SETBACK	30 FEET
PROPOSED FUEL AREA	184 SF	FRONT YARD (N SHILOH RD)	20 FEET
REQUIRED PARKING	N/A	SIDE YARD (N/A)	(TBD) FEET
STALLS REMOVED FOR FUEL	63 STALLS	REAR YARD	(TBD) FEET
POST FUEL PARKING	292 STALLS	PUMP ISLAND (IF APPLICABLE)	20 FEET
SITE AREA PRE PLAT	248,147 SF	SITE ARE POST PLAT	269,327 SF



FIT CONSULTATION NUMBER: 240425-2

NOTE: SITE DESIGN AND CONSTRUCTION PLANS SHALL CONFORM TO ALL REQUIREMENTS OF THE GARLAND DEVELOPMENT CODE (GDC), TECHNICAL STANDARD MANUAL (TSM), AND CITY CODES UNLESS AN APPROVED PD NARRATIVE CONDITION EXPRESSLY PROVIDES OTHERWISE. THE CONCEPT PLAN SHALL BE USED TO REPRESENT THE GENERAL IDEA OF THE PROPOSED LAND USE AND SITE ELEMENTS. THE CONCEPT PLAN SHALL NOT SUPERSEDE, AND SHALL BE SUBORDINATE TO, THE STANDARDS, REQUIREMENTS, AND CONDITIONS OF THE GDC, TSM, CITY CODE, OR THE APPROVED PD.

LEGEND



	ADJUSTED PROPERTY LINE
OWI US REGENCY SHILOH SPRING 8080 N. CENTRAL EXPY, SUIT DALLAS, TX 75206 CONTACT NAME: LAUREN HA	E 1650
APPLI THE KROGER CO. 751 FREEPORT PARKWAY COPPELL, TX 75019 CONTACT NAME: RICHARD B	CANT: SINKLEY 817-675-8428
PLAN PR CEI ENGINEERING ASSOCIAT 2600 NE 11TH ST BENTONVILLE, AR 72712 CONTACT NAME: MICHAEL S	,
LOT 5R2 AND LO	SCRIPTION DT 5R3 BLOCK 1 RETAIL ADDITION
<u>CITY:</u> GARLAND	STATE: TEXAS

SURVEY: NORTH TEXAS SURVEYING LLC

DALLAS

FIT NO. 240425-2

EXISTING PROPERTY LINE

Solutions for Land and Life

CEI ENGINEERING ASSOCIATES, INC. 710 W PINEDALE AVE FRESNO, CA 93711 PHONE: (559) 447-3119 FAX: (559) 447-3129

> 2 2 KROGER FUEL - 6850 N. SHILOH ROAD GARLAND, TX

> > PRELIMINARY NOT FOR CONSTRUCTION

PROFESSIONAL OF RECORD	POR
PROJECT MANAGER	MS
DESIGNER	EN
CEI PROJECT NUMBER	96000
DATE	4/23/2025

CSP-3AE CONCEPTUAL SITE PLAN PROPERTY **EXHIBIT**

SHEET NUMBER

CSP-1AE

Z 25-03







View from the subject site North up North Shiloh Road.



View from the subject site looking South down North Shiloh Road.



View of the subject site looking across North Shiloh Road.



Civil Engineering, Landscape Architecture, Survey, Planning & Program Management

> 710 W. Pinedale Avenue Fresno, CA 93711 Office: 559.447.3119 Toll-free: 1.800.473.1887

> > ceieng.com

April 23, 2025

City of Garland Planning Department 200 N. Fifth St. Garland, TX 75046

Re: SUP Request - Kroger - 6850 N. Shiloh Road

Planning Department:

Please let this letter serve as a request for a Specific Use permit for the proposed Kroger Fuel Center to accompany the Existing Kroger Grocery Store located at 6850 N. Shiloh Road.

Summary of Project:

We are requesting the approval to develop a portion of an existing Kroger Fuel store to add an accessory use of a Fuel Station to the property. The Existing Kroger Grocery Store is currently 65,350 SF. The Fuel Kiosk would add an additional 179 SF with a Kiosk building height of 11ft and a canopy height of 19ft. The proposed fuel station would include a dual product fuel price sign and a monument sign. The proposed fuel station would have a total of 5 inline fuel pumps with each pump having 2 fueling positions (a fueling position at each side) totaling 10 fueling positions for the site. Kroger would consider a maximum fuel pump limit being set in the SUP ordinance, but requests that we be allowed more fuel pumps than currently proposed to allow for potential expansion in the future. If Kroger does expand its fuel station in the future, the expansion would be limited to the currently proposed fuel station area.

The proposed development is comprised of a total of 0.75 acres and is known as Lot 5R2 Block 1 of the Shiloh Springs Retail Addition. This SUP will only apply to Lot 5R2. The SUP will address allowing the use of a Fuel Facility as a supplemental use. The site will have 3 points of access to N. Shiloh Road (public roadway) and 2 points of access to W. Campbell Road (public roadway). These access points will remain as existing with the proposed development onsite.

The proposed fuel center will be operational 24 hours via pay at the pump and will have an attendant from 7AM – 10PM. The proposed development will be harmonious with the surrounding areas as the property and will provide service to the surrounding residential homes. The activities associated with the addition of the fuel center will fall in line with the current developed site and is appropriate within the area shown. This should not create a negative impact to the surrounding area.

The proposed Fuel Center will offer access to the current customers visiting the Grocery store. We are not proposing any retention or detention ponds with this expansion. This site is not located within a floodplain.


SUP Criteria

- 1. The use is harmonious and compatible with surrounding existing uses or proposed uses; The proposed use of the Kroger Fuel Center will fit into the surrounding settings. The proposed site is located within a community retail zone and will provide a service that is compatible within the area.
- 2. The activities requested by the applicant are normally associated with the permitted uses in the base district; The activities/uses are in line as a complementary use to the Community Retail zoning district. The proposed use is commonly located within a commercial development such as the Shiloh Springs retail center.
- 3. The nature of the use is reasonable and appropriate in the immediate area; The proposed site offers a great opportunity to offer the surrounding area with a service to complement their grocery shopping. The service/use of the proposed development is appropriate for a commercial development such as the Shiloh Springs retail center.
- 4. The City traffic engineer identified the need for a traffic impact analysis for the intersection of N. Shiloh Rd and Clear Springs Pkwy due to historical issues. CEI and Kroger have hired Lee Engineering to conduct a traffic impact analysis based on items requested during the initial meeting with the City traffic engineer. Based on the traffic impact analysis, Kroger and the City of Garland have worked together to propose the addition of traffic signals to the intersection of N Shiloh Road and Clear Springs Parkway. This will ensure that access to both the residential community and commercial development are safer and experience a little impact as possible.
- 5. The development of the fuel station will remove approximately 63 stalls.
- 6. That any additional conditions specified ensure that the intent of the district purposes are being upheld. There are not any additional special conditions requested at this time.

Kroger is very excited to bring their development into the Town of Garland. Please let us know if you need additional information for this request. Should you have any questions or concerns, please contact me at 479-715-4425.

Sincerely,

Michael Serrato, P.M.



6850 North Shiloh Road

Comment Form Case Z 25-03

Z 25-03 The Kroger Co. The applicant requests a Specific Use Provision for Fuel Pumps. The site is located at 6850 North Shiloh Road. (District 1)

Z 25-03 The Kroger Co. El solicitante solicita una Disposición de Uso Específico para Surtidores de Combustible. El sitio está ubicado en 6850 North Shiloh Road. (Distrito 1)

Z 25-03 The Kroger Co. Người nộp đơn đang yêu cầu Quy định sử dụng cụ thể cho Máy bơm nhiên liệu. Địa điểm nằm tại 6850 North Shiloh Road. (Quận 1)

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
RAT GOPAL / Franchise Owner Pizza HUT
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuế, v.v.)
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Garland
City, State / Estado de la Ciudad / Thành bang
7,044
Zip Code / Código postal / Mã B u O hính
05/04/25
Signature / Firma / Ch
(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)

Comment Form

Case Z 25-03


Z 25-03 The Kroger Co. The applicant requests a Specific Use Provision for Fuel Pumps. The site is located at 6850 North Shiloh Road. (District 1)

Z 25-03 The Kroger Co. El solicitante solicita una Disposición de Uso Específico para Surtidores de Combustible. El sitio está ubicado en 6850 North Shiloh Road. (Distrito 1)

Z 25-03 The Kroger Co. Người nộp đơn đang yêu cầu Quy định sử dụng cụ thể cho Máy bơm nhiên liệu. Địa điểm nằm tại 6850 North Shiloh Road. (Quận 1)

Please Check One Below / Marque uno a continuación	/ Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng	I SHOW THE PARTY OF THE PARTY O
Against / En Contra	
Please complete the following information and email the form to be Department at 800 Main Street Garland, TX; or mail to City of Garland, TX 75406-9002. Por favor Complete la siguiente informa a Planning@garlandbc.gov; entregar al Departamento de Planificor correo a City of Garland, Planning Department, P.O. Box 4690 hong tin sau và girì biểu mẫu qua email tới Planning@garlandbc.gorland, TX; hoặc girì thư đến Thành phố Garland, Sở Kế hoạch,	Sarland, Planning Department, P.O. Box ción y envie el formulario por correo elec ación en 800 Main Street Garland, TX; o 02 Garland, TX 75406-9002./ Vui lòng dièr gov; giao cho Phòng Kế hoạch tại 800 Mai
Kim Phyona Vu Pham	who man this sen !
Printed Name & Title /Nombre Impreso y Titulo / Tên in và Tiêu d	iè i de la companya d
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la engliée, Nouro thue, v.v.)	mpresa, Inquillino, etc.) / (Chủ sở hữu bắt động sản, Chủ
6902 Woodsprings Drive	THE WALL BEING
our Property Address / La dirección de su propiedad / địa chỉ tài	isản
awland Karaman	MAKEN ANTENDE
y, State / Estado de la Ciudad / Thành bang	MADE INDEANS AND
75044	A PART OF THE PART
Code / Código postal / Mã B u Chính	A STATE OF THE STA
Kimphwigterpham nature / Firma / Ch ürký	may 04,2025
nature / Firma / Ch ũ kỷ	Date / Fecha / Ngày
	e electrónico y el número de teléfono son opci

oviding email address and phone number is optional. / La dirección de correo el all và só diện thoại là tùy chọn.)



The statements below reflect my (our) opinion regarding the proposed request(s). Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

Our home is estudied at the entrance to the Spring Park subdivision,
directly facing the Krogers chapping Plaza, and only a few yards
from the Campbell / Shilph interection. It's a migh traffic area
during run hour and motor vehicle accidents are regular
pear of cee in fact care have collided directly into the residence
at (90) Clear Sirings Plany (the other Single family dwelling
lanking the Spring Park Antrance) more than a Con times in
MILE LANGE DE LANGE TOWN THE UNIVERSE THE THE THE THE
Will Dien De the me Ve me in wearen that the formers in
(Notice and) invoduction of a knowled station of this order certific
A - I A SILL OUR TO MAKEURE CON THE MILL MENNE
her is already he full station at 1235 PG BT serving two
all (Myany n full Statute of another full chance
eightorhoudy news, therefore the shallow y works from
I be some shooping Plate would not provide much, gang,
ler is already in first station at 1235 PGBT serving two eightorhoods needs, therefore the addition is an their first states in the sum shopping plate would not provide much, if any, nefit.
ancimplan . my on 12025

Comment Form Case Z 25-03

Z 25-03 The Kroger Co. The applicant requests a Specific Use Provision for Fuel Pumps. The site is located at 6850 North Shiloh Road. (District 1)

Z 25-03 The Kroger Co. El solicitante solicita una Disposición de Uso Específico para Surtidores de Combustible. El sitio está ubicado en 6850 North Shiloh Road. (Distrito 1)

Z 25-03 The Kroger Co. Người nộp đơn đang yêu cầu Quy định sử dụng cụ thể cho Máy bơm nhiên liệu. Địa điểm nằm tại 6850 North Shiloh Road. (Quận 1)

liệu. Địa điểm nằm tại 6850 North Shiloh Road. (Quận 1)
Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điện đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Thomas V MurtaII (Property Owner)
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề (Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuế, v.v.)
7010 Woodsprings Dr.
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Garland, Tx 75044
City, State / Estado de la Ciudad / Thành bang
75044
Zip Code / Código postal / Mã B u Chính
5/7/25
Signature / Firma / Ch ữ ký Date / Fecha / Ngày

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)



Plan Commission 2. d.

Meeting Date: 05/12/2025

Item Title: Z 25-13 Dynamic Engineering Consultants, P.C. (District 1)

Summary:

Hold a public hearing and consider the application of **Dynamic Engineering Consultants**, P.C., requesting an amendment to Planned Development District (PD 85-55) to allow a Self-Storage Facility (mini-warehouse). The site is located at 1788 Firewheel Parkway. (District 1) (File Z 25-13)

Attachments

Z 25-13 Dynamic Engineering Consultants, P.C. Report & Attachments

Z 25-13 Dynamic Engineering Consultants, P.C. Responses

Planning Report



File No: Z 25-13/District 1

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025

REQUEST

Hold a public hearing and consider approval of 1) an Amendment to Planned Development (PD) District 85-55 for a Self-Storage Facility (mini-warehouse) and 2) a Concept Plan for a Self-Storage Facility (mini-warehouse).

LOCATION

1788 Firewheel Parkway

APPLICANT

Dynamic Engineering Consultants, P.C.

OWNER

Springfield JV

BACKGROUND

The subject property is currently an undeveloped tract of land within Planned Development (PD) District 85-55. The Planned Development allows for a variety of other uses that are permitted in the Community Retail (CR) District. It does not currently allow a Self-Storage Facility (mini-warehouse) by right as a primary use, but only as a secondary use.

SITE DATA

The subject site is approximately four acres of undeveloped tract of land and has approximately 680 linear feet of frontage along Firewheel Parkway. The site can be accessed from two points along Firewheel Parkway.

USE OF PROPERTY UNDER CURRENT ZONING

The site is zoned Planned Development (PD) District 85-55. This site's base zoning is Community Retail (CR). The Community Retail (CR) District is intended to accommodate a variety of retail, service, and business establishments that may or may not be designed in a shopping center configuration. The district may be used as a transition district between lower intensity retail or office uses and more intense uses. A Community Retail (CR) District is generally appropriate along major transportation corridors but is generally not appropriate in proximity to low-density residential districts without significant buffering and screening features. An example of allowed use in a CR district is a retail shopping area that may be large in scale with very limited or no outside storage. Traffic generated by uses in a Community Retail (CR) District must be focused onto the major thoroughfare network. Development in a Community Retail (CR) District may not be designed in a manner that increases traffic through residential areas.

CONSIDERATIONS

Planned Development:

1. The applicant is requesting the Self-Storage Facility (mini-warehouse) use to be permitted by right as the use is not currently allowed in Planned Development (PD)

District 00-39 as a primary use.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends Compact Neighborhoods for the subject site. Compact neighborhoods provide areas for moderate increases in residential density, including single-family attached and small detached housing. It expands housing options through infill and redevelopment, while continuing valuable development patterns.

These areas provide transitions between traditional residential neighborhoods and higher density residential neighborhoods and non-residential developments. These areas support mixed-use small commercial centers (goods and services), office space, and public services. Building heights and development intensities in these areas are compatible with adjacent residential development.

A self-storage use is not compatible with the Future Land Use Map as it is considered more of an intense commercial use with 106,680 square feet of proposed building area. Although the vision supports commercial centers, it is in the context of mixed-use and neighborhood service developments. This is an important area that can serve as a gateway to the City of Garland, and a self-storage use does not contribute positively toward creating a vibrant place to provide that sense of arrival.

Under the Garland Development Code self-storage facility uses are only permitted by right in the Industrial and Heavy Commercial Districts. The PD of this site permits it only as a secondary use as part of a larger commercial/retail development. A self-storage in this context would not be compatible with the vision of the comprehensive plan.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

The properties to the North are zoned Agricultural (AG) District (including s 77-17) and contain vacant wooded floodplain land. Further North within S 77-17 is the landfill. The property to the East is zoned Planned Development (PD) District 21-62 for a horizontal multi-family development which is nearly complete. The property to the West is also zoned Agricultural (AG) District and contains vacant and wooded land that is entirely flood plain. Finally, the property to the South is zoned Planned Development (PD) District 09-06 with a base zoning of Community Retail and is vacant.

The proposed Self-Storage Facility (mini-warehouse) use is not compatible with the surrounding areas as there is prospect for other retail, service, residential, and mixed uses here.

STAFF RECOMMENDATION

Staff recommends denial of the applicant's proposal. The proposed Self-Storage (miniwarehouse) is not compatible with the Future Land Use Map's designation of Compact Neighborhoods for the property nor with the surrounding areas.

ADDITIONAL INFORMATION

i. Location Map

ii. PD Conditions

iii. Concept Plan


iv. Site Photos

CITY COUNCIL DATE: June 3, 2025

PREPARED BY:

Matthew Wolverton Planner II Planning & Development 972-205-2454 mwolverton@garlandtx.gov

REVIEWED BY: Emma Chetuya Ph.D., AICP Planning Administrator Planning and Development 972-205-2453 echetuya@garlandtx.gov



PLANNED DEVELOPMENT CONDITIONS

ZONING FILE Z 25-13

1788 Firewheel Parkway

[Requested by the Applicant]


- I. Statement of Purpose: The purpose of this Planned Development (PD) amendment is to allow and regulate the development of a Self-Storage (mini-warehouse) Use.
- II. Statement of Effect: This Planned Development amendment shall not affect any regulation found in the Garland Development Code, Ordinance No. 6773, as amended prior to adoption of this ordinance, except as specifically provided herein.
- III. General Regulations: All regulations of the Community Retail (CR) District and Planned Development (PD) District 85-55 as set forth in Chapter 2 of the Garland Development Code, Ordinance 6773, are included by reference and shall apply, except as otherwise specified by this ordinance.

IV. Development Plans:

Concept Plan: Development shall be in general conformance with the Concept Plan labeled Exhibit C. In the event there is conflict between the approved Concept Plan and the Specific Regulations below, the Specific Regulations shall apply.

V. Specific Conditions:

- A. Permitted Use: In addition to the uses permitted within Planned Development (PD) District 85-55, Self-Storage Facility (mini-warehouse) Use shall be permitted by right.
- B. Concept Plan: The site layout, building placement, parking, walking paths, and other development proposed shall be in general conformance with the approved Concept Plan labeled Exhibit C.



Z 25-13





View of the subject site from Firewheel Parkway.


View from the subject site looking East down Firewheel Parkway





View from the subject site looking Southeast.

View from the subject site looking Southwest down Firewheel Parkway



1788 Firewheel Pkwy

Comment Form Case Z 25-13

Z 25-13 Dynamic Engineering Consultants, P.C. The applicant requests an amendment to Planned Development District (PD 85-55) to allow a Self-Storage Facility (mini-warehouse). The site is located at 1788 Firewheel parkway. (District 1)

Z 25-13 Dynamic Engineering Consultants, P.C. El solicitante solicita una enmienda al Distrito de Desarrollo Planificado (PD 85-55) para permitir una instalación de autoalmacenamiento (mini-almacén). El terreno está ubicado en 1788 Firewheel Parkway. (Distrito 1)

Z 25-13 Dynamic Engineering Consultants, P.C. Người nộp đơn yêu cầu sửa đổi Khu phát triển theo quy hoạch (PD 85-55) để cho phép xây dựng Cơ sở lưu trữ tự phục vụ (kho mini). Địa điểm này nằm tại 1788 Firewheel parkway. (Quận 1)

Flease Check One Below / Marque uno a continuación / Vui long kiệm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không Please complete the following information and email the form to Please complete the following information and email the form to Pleanning@garlandtx.gov; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ hông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Glenn Lanier, Director
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bắt động sản, Chủ doanh nghiệp, Người thuế, v.v.)
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Garland, Tx
City, State / Estado de la Ciudad / Thành bang
Zip Code / Código postal / Mã B u Ohính
Signlature Firma / Çh ü ký Date / Fecha / Ngày
Date / Food / Hgay
Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)


Comment Form Continued – Case Z 25-13

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

we are in favor of the proposed use conditioned on the 6ft masonry perimeter wall, and light fixtures that do not cast onto our property as reflected in the appended exhibits.
conditioned on the GFF masonry perimeter
wall, and light fixtures that do not cast
onto our property as reflected in the
appended exhibits.







JDA ESS Firewheel Carland, TX te Photometri



0





ARC2 LED


& 7°


Simplimit

0 2 2 2

(Access ----









Plan Commission 2. e.

Meeting Date: 05/12/2025

Item Title: Z 25-16 CCM Engineering (District 3)

Summary:

Hold a public hearing and consider the application of **CCM Engineering**, proposing an amendment to Planned Development (PD) District 20-44 to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces. The site is located at 2126 Rowlett Road. (District 3) (File Z 25-16)

Attachments

Z 25-16 CCM Engineering Report & Attachments Z 25-16 CCM Engineering Responses

Planning Report



File No: Z 25-16/District 3

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025

REQUEST

Hold a public hearing and consider approval of 1) an Amendment to Planned Development (PD) District 20-44 to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces.

LOCATION

2126 Rowlett Road

APPLICANT

CCM Engineering

OWNER

CHP Development LLC

BACKGROUND

The subject property is currently zoned PD20-44 for the development of 43 townhomes and associated easements and open space lots. It is currently developed with internal streets, landscaping and masonry screening wall as was approved per the PD. During the site plan review process, staff found that Lots 17-25 of Block 2 do not meet the minimum lot depth and/or size requirements due to the 10 feet pedestrian and utility easement and 8 feet landscape buffer located at the rear of the lots. The applicant will also be providing 11 guest parking spaces per the GDC. The PD states that 13 guest parking spaces will be provided.

SITE DATA

The subject site is 4.67 acres in size. The site can be accessed from Crescent Heights Road on the west and east.

USE OF PROPERTY UNDER CURRENT ZONING

The site is zoned Planned Development (PD) District 20-44 for single-family attached uses. There is an approved detail plan with landscaping, elevation, and site plans. The Single-Family Attached district is intended to promote stable, quality, attached-occupancy residential development on individual lots in logical, livable, and sustainable neighborhoods. This district may be included within certain areas of neighborhoods or, when in accordance with the intent of the *Comprehensive Plan*, may provide a transition district between lower density residential areas, multifamily or nonresidential areas, or major thoroughfares.

CONSIDERATIONS

Planned Development:

1. The subject zoning requires for the lots to be a minimum of 1,925 square feet and have a minimum lot depth of 75 feet. In order to accommodate for the 10 feet pedestrian and utility easement and 8 feet landscape buffer, Lots 17-25 of Block 2 are proposed to have a reduced size ranging from 1,713 square feet to 1,913 square feet. The depths will also range from 66 feet to 77 feet.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends Compact Neighborhoods for the subject site. Compact neighborhoods provide areas for moderate increases in residential density, including single-family attached and single-family detached housing. It expands housing options through infill and redevelopment, while continuing walkable development patterns.

These areas provide transitions between traditional residential neighborhoods and higher density residential neighborhoods and non-residential developments. These areas accommodate uses such as convenience retail (goods and services), office space, and public services. The architectural character and scale of these areas are compatible with adjacent residential development.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

The subject site is surrounded by properties that are primarily zoned residential districts. The property to the north, across Roan Road, is zoned Agricultural (AG) District and has a single-family dwelling. The property to the south is zoned Agricultural (AG) District and is vacant. Further to the southwest is zoned Community Retail (CR) District and developed with a skating rink. To the south of that tract is zoned Single-Family (SF-7) and developed with single-family detached homes. The property to the east, across Roan Road, is zoned Planned Development (PD) District 72-14 and developed with single-family detached homes. The property to west is zoned Agricultural District (AG) and is developed with a church. Across Rowlett Road, is zoned Single-Family-10 (SF-10) District and Planned Development (PD) District 06-05. The Single-Family-10 (SF-10) area is developed with an event center and the Planned Development (PD) District 06-05 is for Neighborhood Service Uses and developed with a single-family home.

STAFF RECOMMENDATION

Staff recommends approval of an amendment to Planned Development (PD) District 20-44 to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces.

ADDITIONAL INFORMATION

i. Location Map

ii. PD Conditions

iii. Concept Plan

iv. Site Photos

v. Applicant's Written Request


CITY COUNCIL DATE: June 3, 2025

PREPARED BY:

Emma Chetuya, Ph.D., AICP Planning Administrator Planning & Development 972-205-2453 echetuya@garlandtx.gov

REVIEWED BY:

Nabila Nur, AICP Planning Director Planning and Development 972-205-2454 nnur@garlandtx.gov



PLANNED DEVELOPMENT CONDITIONS

ZONING FILE Z 25-16

2126 Rowlett Road

[Requested by the Applicant]

- I. Statement of Purpose: The purpose of this Planned Development (PD) amendment is to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces.
- II. Statement of Effect: This Planned Development amendment shall not affect any regulation found in the Garland Development Code, Ordinance No. 6773, as amended prior to adoption of this ordinance, except as specifically provided herein.
- III. General Regulations: All regulations of Planned Development (PD) District PD 20-44 as set forth in Chapter 2 of the Garland Development Code, Ordinance 6773, are included by reference and shall apply, except as otherwise specified by this ordinance.

V. Specific Conditions:

- A. Lot Size: Lots 17-25 of Block 2 shall be allowed a minimum lot size of 1,713 square feet.
- B. Lot Depth: Lots 17-25 of Block 2 shall be allowed a minimum lot depth of 66 feet.
- C. Parking: 11 quest parking spaces shall be provided.

Z 25-16



Photo on Roan Road facing north



Photo from within the development facing east



Photo from within the development facing east on the intersection of Rowlett Rd. and Crescent Heights Road


April 21, 2025

Crescent Heights Luxury Townhomes

PD Zoning

The site will conform to all items as stated in the ordinance PD-20-40 (SFA) except for the following:

- (A) Minimum Lot Depth = 66'
- (B) Minimum Lot Size = 1,713 SF
- (C) Parking Spaces Provided = 11 spaces



Comment Form Case Z 25-16

Z 25-16 CCM Engineering. The applicant proposes an amendment to Planned Development (PD) District 20-44 to reduce the minimum lot size and depth requirements on specific lots and number of provided parking spaces and amend the fencing material requirement. The site is located near 2126 Rowlett Road. (District 3) (District 3)

Z 25-16 CCM Engineering. El solicitante propone una enmienda al Distrito de Desarrollo Planificado (PD) 20-44 para reducir los requisitos mínimos de tamaño y profundidad de los lotes en lotes específicos, así como el número de plazas de aparcamiento, y modificar el requisito de material para cercas. El terreno se encuentra cerca de 2126 Rowlett Road (Distrito3)

Z 25-16 CCM Engineering. Người nộp đơn đề xuất sửa đổi Quy hoạch Phát triển (PD) Quận 20-44 để giảm yêu cầu về kích thước lô đất tối thiểu và độ sâu đối với các lô đất cụ thể và số lượng chỗ đậu xe được cung cấp, và sửa đổi yêu cầu về vật liệu rào chắn. Khu đất nằm gần 2126 Rowlett Road. (Quận 3)

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới	
For / A Favor / Đúng	
Against / En Contra / Không Please complete the following information and email the form to Please complete the following information and email the form to Pleaning@garlandtx.gov; deliver to the Plaaning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electa Planning@garlandtx.gov; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o exportante de Planning@garlandtx.gov; garland, TX 75406-9002./ Vui lòng điển och correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điển och chong tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.	rónico nvielo đầy đủ
Enriselda Torres	
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề	
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bắt động sản, Chủ doi nghiệp, Người thuế, v.v.)	anh
2310 Hillyten Dr.	
Your Property Address / La dirección de su propiedad / địa chỉ tài sản	
City, State / Estado de la Ciudad / Thành bang	
75043	
Zip Code / Código postal Mã Bu Othinh 05 - 01 - 2025	
Signature / Firma / Ch r ký Date / Fecha / Ngày	

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)



Plan Commission 2. f.

Meeting Date: 05/12/2025

Item Title: GDC Amendment ORD 25-05

Summary:

Hold a public hearing to consider amendments to Chapter 2 Zoning Regulations, Attachment 1 - Land use chart and Article 4, Division 4 Mixed-Use Districts as it relates to the permitted land uses and development regulations for the Urban Residential (UR) and Urban Business (UB) districts.

Attachments

GDC Amendment ORD 25-05 Report & Attachments

Planning Report

GDC Amendment ORD 25-05

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025



REQUEST

A public hearing to consider amendments to Chapter 2 Zoning Regulations, Attachment 1 - Land use chart and Article 4, Division 4 Mixed-Use Districts as it relates to the permitted land uses and development regulations for the Urban Residential (UR) and Urban Business (UB) districts.

BACKGROUND

The City of Garland has initiated a rezoning process for an approximately 317 acres of property generally located on the north side of I-635, on both sides of S Garland Avenue. The overall area currently has several zoning designations; however, the predominant ones are Community Retail (CR) and Industrial (I).

The current zoning districts allow a variety of uses that resulted in some less than preferred developments in the past. The goal of this city-initiated rezoning is to set the stage for revitalization of the area. The proposed zoning districts are Urban Residential (UR) and Urban Business (UB). These districts are intended to allow cohesive, orderly, creative, and predominantly vertically oriented mixed-use and mixed-density developments.

The rezoning case (Z 25-08) is scheduled for a public hearing within the same agenda. This proposed GDC amendment acts as a supplement to that request as it intends to update the use chart for UR and UB district to allow only compatible and desirable uses in these districts. Additionally, staff reviewed the development regulations within the mixed-use districts and proposes some revisions to allow maximum focus on creating vibrant pedestrian-oriented places and increased density for urban setting.

STAFF RECOMMENDATION

Staff recommends approval of the GDC amendment.

ADDITIONAL INFORMATION

- i. Proposed Mixed-Use Districts Regulations
- ii. Proposed Land Use Chart

CITY COUNCIL DATE: June 3, 2025

PREPARED BY:

Nabila Nur, AICP Director Planning & Development 972-205-2449 nnur@garlandtx.qov

DIVISION 4 Mixed-Use Districts

§ 2.49. U, Urban Districts (UR and UB).

(A) <u>Purpose.</u> The Urban (U) districts are intended to allow cohesive, orderly, creative, and predominantly vertically-oriented mixed-use and mixed-density developments. There are two types of Urban districts: Urban Residential (UR) and Urban Business (UB). UR districts are predominantly residentially-oriented districts that may also include a limited number of integrated nonresidential uses that are compatible with, harmonious with, and supportive of, a high-density, urban-style residential neighborhood. UB districts are predominantly business- and shopping-oriented districts that may also include a limited-amount of integrated residential uses that are compatible with, and supportive of, a high-density, urban-style business district.

The Urban districts are also intended to establish a distinctive community character in specially selected areas through innovative and mutually-sustaining land uses, urban-style and pedestrian-oriented site design, efficient traffic and pedestrian circulation, innovative and high-quality architectural elements and landscaping concepts, and other similar enhanced design features that will in turn elicit a strong sense of community, civic pride, and of satisfaction with quality of life among those who choose to enjoy the lifestyle created by these districts.

Appropriate flexibility in final design should be given to developers and designers of Urban districts to allow creativity for the opportunities associated with individual sites. The Urban districts can include a mixture of architectural styles ranging from contemporary to traditional. The general intent of these districts is to maximize utilization of land for a mixture of mutually sustainable uses, while also utilizing open spaces to the greatest extent possible in an urban setting for public recreation and leisure purposes. Urban districts are intended to include a diverse mixture of residential housing choices and business/employment opportunities (for example, live-work units) in a symbiotic and urban-style environment that not only accommodates residents' needs to live, work, learn, and play within a neighborhood setting, but that also builds long-term stability, civic pride and fiscal value for the community in general.

- (B) <u>Allowed Uses.</u> All allowed uses (whether by right or by SUP) in the UR or UB district (as applicable) are indicated within the Land Use Matrix, Article 5 of this Chapter 2. Single- family attached residences are only allowed in the Urban districts to the extent they are in compliance with the SFA district requirements.
- (C) <u>Use Integration</u>. Developments within the Urban districts must be comprised of a mixture of residential and nonresidential uses that are conducive to a live-work environment.
 - (1) For URIn all Urban districts, compatible, complementary nonresidential land uses on the first (ground) floor level are allowed but not required. However, all first (ground) floor levels must be constructed to retail building standards, including a minimum floor-to-ceiling height of twelve feet. These ground floor areas may be occupied by any allowed use, but shall be constructed to accommodate retail and restaurant uses in response to market demand.

(2) For UB districts, a minimum of seventy percent of the total building square footage within each development must be devoted to nonresidential uses (such as, retail, office, personal services). The remaining building square footage (maximum 30%) must be devoted to residential land uses, predominantly on levels above the first floor.

- (3)(2) Other combinations (in terms of percentages) of land use mixtures may be achieved by establishment of a Planned Development (PD) district that is based upon the applicable Urban district.
- (D) <u>Parking.</u> Off-street parking and loading for Urban districts must be in compliance with provisions of the Land Use Matrix, Article 5 of this Chapter 2 and with Chapter 4, Article 2 of this GDC unless otherwise provided below.
 - (1) Number of Parking Spaces. For all nonresidential uses in an Urban district, the number of required off-street parking spaces may be reduced as provided in Section 7.11(D) 7.12(D) in Chapter 7 of this GDC (the DT district) for each type of use as shown on the Land Use Matrix, Article 5 of this Chapter 2.
 - (2) <u>Location.</u> Surface off-street parking areas in an Urban district is prohibited in front of any structure within a designated front yard unless specifically approved during the plan review process. Surface off-street parking areas must be located generally to the side or rear of the main buildings in designated side or rear yards.
 - (3) <u>Orientation.</u> Surface off-street parking areas in an Urban district must be subdivided so as to avoid large expanses of pavement.
 - (4) On-Street Head-In or Angled Parking. Unless a street segment is restricted by City ordinance as a "No Parking" zone, a single bay of angled or parallel parking in an Urban district may be provided along the street in front of main buildings (see Illustration 2-7).

Illustration 2-7 Example of Angled and Parallel Parking in Urban Districts



- (5) <u>Shared and Off-Site Parking.</u> Shared or off-site parking arrangements in an Urban district may be approved during the review and approval of the initial development application. The requirements and procedures for a shared or off-site parking arrangement are provided in Article 2, Division 3 in Chapter 4 of this GDC.
- (6) <u>Structured (Garage) Parking.</u> To enhance the overall visual character of an Urban district, and to mitigate overall bulk appearance of parking structures, the following design standards apply to parking structures in an Urban district:
 - (a) All above-grade parking structures must be designed to be consistent with and complementary to the architectural style of the main building(s), and must

incorporate at least two of the following design elements:

- i. Distinctive architectural elements (cornices, piers, columns, friezes, quoins, mullions, fenestration, pilasters, rustication, or accentuating belt courses see Illustration 2-8);
- ii. Variation in wall planes (wall openings, canopies, articulations, wall convexities and/or concavities, balconies, or awnings see Illustration 2-8);
- iii. Change in materials (defined as a minimum of two separate, compatible materials excluding glazing each separate material must be at least twenty percent of each facade's surface area, excluding glazing);
- iv. Change in colors (defined as a minimum of two separate, compatible colors excluding glazing each separate color must be at least twenty percent of each facade's surface area, excluding glazing).
- (b) All above-grade parking structures must be designed with a distinguishable first floor, upper facades, and roofs. Parking garage first floors must be designed at human scale with pedestrian-scale elements such as awnings, canopies, window breaks, and door openings.
- (c) Above-grade parking garages may be designed using decorative metal elements such as ornate meshes, screens and the like, but non-decorative steel guard cables that are visible to the public or to adjacent properties are prohibited.

(7) Individual Residential Garages and Driveways.

- (a) Individual residential garages and driveways in an Urban district must be designed, constructed, and operated to allow access only from a rear (or side) alley or an interior common access service drive aisle, a dedicated fire lane, or a dedicated shared parking court (and may not be facing or accessed from a public street).
- (b) Garages in an Urban district must be set back from any street or alley right-of-way a minimum of twenty feet;
- (c) Driveways for residential dwelling units must be no wider than twelve feet until the driveway is beyond the adjacent front building face.

Illustration 2-8 Examples of Acceptable Facade Articulation for Parking Structures











(E) <u>Screening and Buffering.</u>

- (1) Screening and Buffering Between Uses. Screening walls or other buffering elements in an Urban district, which are typically required between varying types of uses (see Chapter 4, Article 3 in this GDC), are only required when establishing a new nonresidential use adjacent to a pre-existing residential use or residential zoning district. This requirement may be waived by the Planning Director during the review and approval of the initial development application if the Director determines the screening is not necessary to protect the adjacent property from the new use. Required screening devices in an Urban district must be designed in such a way that allows pedestrian access to the development from public sidewalks along streets, as well as from adjacent properties where cross-access would be beneficial to both properties.
- (2) Screening of parking areas, loading areas, solid waste containers, ground-mounted and roof-mounted mechanical equipment, and other site features must be in compliance with the standards provided in Chapter 4, Article 3 of this GDC.
- (F) <u>Signage</u>. All signage within an Urban district must be in compliance with Chapter 4, Article 5 unless otherwise provided below:

(1) <u>Unity in Design.</u> Signs within an Urban district must conform to a unified design, such that size, materials, and colors of each sign are similar and complementary.

- (2) <u>Freestanding Signs.</u> All freestanding signs within an Urban district must be monument style (that is, not pole or pylon style), unless otherwise varied and approved during the sign permitting process.
- (3) <u>Pedestrian-Scale Signs.</u> Signs in a pedestrian-scale setting (such as along storefront pedestrian walkways) within an Urban district must be pedestrian-oriented and may include under-awning, hanging signs, or perpendicular signs attached to a building.
- (G) <u>Pedestrian Access Sidewalks.</u> Sidewalks must be provided between the street and the building, and shall be a minimum of eight feet in width except in pre-developed areas where the sidewalk system is already established prior to the effective date of this GDC. In those areas, redevelopment of lots or tracts must include repairs or replacement of the adjacent portion of the existing sidewalk, as determined by the Director of Transportation and in compliance with the City's standards in effect at the time. Barrier-free ramps must be added (or replaced) at all street corners and at any designated mid-block pedestrian crossings in accordance with local, state, and federal law.

(H) <u>Building/Architectural Design.</u>

- (1) <u>Purpose.</u> The intent of architectural design controls in Urban districts is to promote distinctive, high-quality architectural design in a pedestrian-scale setting that sets a particular Urban development apart visually (and thematically) from other developments in the vicinity. The development standards provided in this Section are intended to promote continuity among redevelopment projects and new structures within a particular Urban district.
- (2) <u>Compatibility.</u> Exterior construction in an Urban district must be compatible and complementary as to design and colors throughout each development.
- (3) <u>Uniformity.</u> All buildings must employ "four-sided architecture" in an Urban district, meaning that comparable design elements must be used on all exposed sides of a building. No lesser quality design elements may be used in an Urban district for the rear or any side of a building unless the <u>rear or</u> side is screened from ground level view.
- (4) <u>Articulation.</u> Architectural features of buildings in an Urban district must provide diversity and articulation of wall surfaces through use of one or more of the following architectural elements: pilasters, quoins, projected awnings, solid canopies, bay windows, or towers. Additional horizontal and vertical building articulation requirements of an Urban district are as follows:

(a) <u>Horizontal Building Articulation</u>.

i. Building facades that are visible to a public street and that are between forty feet and one hundred feet in length require at least one horizontal articulation break that is a minimum of two feet in depth for at least twenty percent of the total length of the building facade. Curved facades may be used to meet the articulation requirement if at least one-half of the curved facade meets the

minimum two-foot depth.

ii. Building facades that are visible to a public street and that are over one hundred feet in length require at least one horizontal articulation break per fifty linear feet that is a minimum of two feet in depth, so that the cumulative articulation breaks total at least twenty percent of the building facade's total length. Curved facades may be used to meet the articulation requirement if at least one-half of the curved facade meets the minimum two-foot depth.

(b) <u>Vertical (Roofline) and Building Articulation.</u>

- i. Building facades that are visible to a public street and that are between forty feet and one hundred feet in length require at least one vertical articulation break that is a minimum of twenty percent higher or lower than the building facade's average unarticulated height for at least twenty percent of the building facade's total length.
- ii. Building facades that are visible to a public street and that are over one hundred feet in length require at least one vertical articulation break that is a minimum of twenty percent higher or lower than the building facade's average unarticulated height for every fifty linear feet, so that the cumulative vertical articulation breaks total at least twenty percent of the building facade's total length.
- (c) Each sequential block of new development within an Urban district must contain a unique, but visually compatible, building facade to encourage architectural variety within larger projects by using a combination of architectural elements.
- (5) <u>Facades and Building Forms.</u> An identifiable first floor, upper facade, and rooflines. First floor facades must be designed Building facades that are visible to a public street in an Urban district must be designed with at human scale with elements such as window bays, recessed entries, awnings, canopies, and other human-scale architectural features. Additional building facade and form requirements for Urban districts are as follows:
 - (a) First floor facades may not exceed twenty feet in height, but interior spaces may be taller than upper level building floor-to-ceiling heights;
 - (b) First floor facade heights must be consistent for individual buildings, so as to form a distinctive horizontal "base floor" visual element;
 - (c) Buildings must reflect a small-scale visual pattern along the street frontage with building bay widths of approximately twenty-five to fifty feet;
 - (d) Upper facades must be designed using architectural elements such as window spacing, facade sections, projections/concavities, awnings, window covers, window hoods, and balconies:
 - (e) Individual floors must be identifiable with elements such as material changes, trim, color changes, moldings, cornices, belt courses, awnings, balconies, or other

similar architectural features; and

- (f) To emphasize the pedestrian scale, building facades must incorporate at least one element from at least two of the following groupings:
 - i. Architectural elements such as cornices, piers, columns, friezes, quoins, mullions, fenestration, pilasters, rustication, or belt courses.
 - ii. Variations in wall planes with canopies, balconies, or awnings.
 - iii. Changes in materials or color each facade must incorporate at least two separate materials or color changes, excluding glazing. Each separate material or color change must comprise at least twenty percent of each facade's appearance, excluding glazing.
- (6) <u>Highly Reflective Exterior Construction Materials.</u> Highly reflective materials and surfaces, including reflective metal siding and mirrored glass glazing, must be installed in such a manner as to diffuse reflective light and prevent the focused redirection of sunlight or other luminants beyond the boundary line of the premises on which the facility is located.

(7) Exterior Colors.

- (a) The use of florescent paint and florescent colors are prohibited in an Urban district.
- (b) Exterior colors must complement one another, and must promote the architectural style of the Urban district.

(8) Building Entries.

- (a) Main building entrances in an Urban district must be from public sidewalks or plazas and comply with the following:
 - i. In order to create a pedestrian-oriented and access-friendly environment, a building must have its main entrance from a public sidewalk or plaza or from a private sidewalk or plaza that is publicly accessible through a public easement.
 - ii. Secondary entrances to a building from a parking lot are permitted.
 - iii. Main entrances to a building must be easily identifiable and must utilize pedestrian-scale design elements.
- (b) Building entrances in an Urban district must be accented by architectural elements such as recessed facades, columns, overhanging roofs, awnings, or balconies.
- (c) Spaces in an Urban district that are along pedestrian walkways and parking lots must provide rear entrances to buildings that are identifiable with elements such as signage, plantings, awnings above rear windows, or other human-scale elements.
- (d) <u>Residential Entries.</u> Street-level dwelling units within multi-unit structures in an Urban district must have individual street-oriented or common corridor entries.

The fronts of all townhouse, row home or other single-family attached dwelling units shall face an adjacent open space, park or street.

- (9) Residential Entries. Street-level dwelling units within multi-unit structures in an Urban district must have individual street-oriented entries. The fronts of all townhouse, row home or other single-family attached dwelling units shall face an adjacent open space, park or street.
- (9)(10) Active Depth. The street-facing ground level of any building must have at least nine feet of active uses. Active uses do not include storage, parking or other uses with no or very little activity. Active depth refers to the interior depth of the building from the front façade,

(11) Roofs.

- (a) Roof lines in an Urban district must be consistent with the coordinated architectural theme and variable in terms of shape, pitch, and height, in order to avoid long expanses of flat similar roof lines.
- (b) Roofs in an Urban district must be designed as individual design elements, and must be utilized to screen roof-mounted mechanical equipment and satellite dishes.
- (c) The use of mansard or gambrel roofs is prohibited in an Urban district.

(I) Site Design.

(1) <u>Purpose.</u> The intent of site design controls in Urban districts is to optimize pedestrian scale, building utilization, efficient traffic circulation, and visual quality. The arrangement of building masses, parking areas, open spaces, landscaping, pedestrian walkways, and site furnishings must encourage pedestrian activity, create unique views, and create an attractive, safe, and sustainable development site.

(2) <u>Site Design.</u>

- (a) <u>Building Orientation.</u> Building orientation in an Urban district must consider uses both within structures and outside; plazas, open spaces, and other pedestrian spaces must be integrated into the site.
- (b) <u>Block Lengths.</u> Block lengths in Urban districts must be characterized by smaller, walkable blocks that are connected to each other; cul-de-sacs or other single- entrance streets are prohibited unless, due to topography or existing development patterns, there is no other reasonable alternative to serve the Urban development. Single-entrance streets may be approved by the Planning Director during the development review process based on the foregoing criteria. Small block lengths and connected street patterns provide opportunities for traffic efficiency and pedestrian connectivity.
 - i. The minimum length of a street block is two hundred feet in an Urban district.
 - ii. The maximum length of a street block is five hundred feet in an Urban district.
- (c) <u>View Corridors.</u> The arrangement of streets, open spaces, and buildings in an Urban district must create view corridors where practicable.
- (d) <u>Scale.</u> The massing of new buildings in an Urban district must be articulated in a variety of ways, including the use of projecting and recessed elements such as porches, cantilevers,

balconies, bay windows, and roof dormers, to reduce their apparent overall bulk and volume, to enhance visual quality, and to contribute to human-scale development. Larger-scale residential buildings with a box-like appearance are prohibited in an Urban district unless approved by the Planning Director during the development approval process to the extent that the Planning Director determines that the buildings meet the spirit and intent of the Urban district.

- (3) <u>Height, Density and Area Requirements.</u> The following are the height, density, and area requirements required for lots and structures in an Urban district, unless otherwise provided in this Section:
 - (a) Minimum size of an Urban district rezoning request is three acres unless the area to be rezoned is immediately adjacent to an existing Urban district.
 - (b) Minimum lot width is thirty feet.
 - (c) Minimum lot width for multifamily tracts is seventy-five feet.
 - (d) Minimum lot depth is one hundred feet.
 - (e) Maximum lot coverage may not exceed eighty percent of the site unless a higher amount is granted as part of a Planned Development.
 - (f) Minimum building height is 24thirty feet if residential or vertical mixed use, fifteen feet if nonresidential.
 - (g) Maximum building height is only applicable where the subject property abuts an existing single-family residential zoned property as regulated by Section 2.49(I) (4)(d)(ii)seventy-five feet, excluding roof-mounted mechanical equipment or architectural design features.
 - (h) Minimum density of multifamily residential is thirty dwelling units per net developable acre of land for Urban Residential (UR) and forty dwelling units Urban Business (UB).
 - (i) Maximum density of multifamily residential is eighty dwelling units per net developable acre of land.
 - (j) The minimum dwelling unit sizes in the Urban district must follow the MF district standards.

(4) Yard and Build-To Lines.

- (a) Yards in an Urban district must be free from any encroachments, unless otherwise provided for in this GDC, including primary buildings, accessory buildings, detached garages, and ground-mounted mechanical equipment.
- (b) Buildings and structures in an Urban district must be in compliance with the following provisions (all setbacks are measured from the property line):
 - i. Front maximum build-to line is twenty feet; all areas adjacent to a street are front yards; no parking is allowed in the front yard unless otherwise approved during the site permitting process.
 - ii. Front minimum build-to line is ten feet from a public street right-of-way line, and zero feet from a private street or access easement provided that utilities

and pedestrian circulation (sidewalks) are accommodated.

- iii. The maximum front porch setback is fifteen feet.
- iv. All rear and side yards must be a minimum of ten feet.
- iv.v. All side yards must be a minimum of five feet for residential structure and a minimum of ten feet for all other structures.
- <u>v.vi.</u> Dwelling units may be attached to each other with appropriate fire walls (in accordance with the City Code).
- (c) At least seventy-five percent of the front facade of any structure facing a street in an Urban district must be located between the minimum and the maximum build-to lines. Up to twenty-five percent of the facade may be located further from the back-of-curb than the front yard maximum build-to line but may not be located greater than fifty feet beyond the front street maximum build-to line front facade in an Urban district may be located between the back-of-curb and the minimum build-to line (see Illustration 2-10).
- (d) The following provisions apply to side-yard and rear-yard setbacks in an Urban district, where adjacent to traditional single- or two-family residential districts:
 - i. Urban developments must provide a solid masonry screening wall that is in compliance with the design standards provided in Chapter 4, Article 3 of this GDC), and the minimum side and rear setbacks must be 1.25 times the maximum height of the building or a maximum of fifty feet.
 - ii. Where adjacent to a single-family district, all portions of the building above thirty-five feet in height must be set back to fit within a forty-five degree slope measured from the residential property line to maintain privacy for adjacent traditional single- or two-family residential zoning (see Illustration 2-9).

Illustration 2-9 Example of Setback for Shallow Parcels Adjacent to Traditional Single- and Two-Family Zoned Residential Areas





Illustration 2-10 Front Setback and Build-To Lines for Mixed-Use Buildings



- (5) <u>Amenities.</u> The residential components of an Urban district must incorporate and provide communal and personal convenience amenities on-site (that is, within the development), in accordance with the minimum number requirements provided in Subsection (6) below, unless provision of the amenities is approved in an off-site location in accordance with Subsection (7) below. Communal and personal amenities may include the following:
 - (a) Swimming pool;
 - (b) Fitness center;
 - (c) Business center;
 - (d) Dining establishment;
 - (e) Game and leisure room;
 - (f) Personal services (such as, hair salon, therapeutic massage);
 - (g) Multi-purpose gymnasium;
 - (h) Meeting/conference rooms;
 - (i) Convenience/sundries shop; or
 - (i) Child care center.
- (6) Amenities Required by Size of Development. The minimum number of amenities that

must be provided on-site (or as may be approved off-site pursuant to Subsection (7) below) for the residential components of an Urban district are as follows:

- (a) A development having up to, and including two hundred dwelling units must provide at least two of the amenities listed in Subsection (5) above;
- (b) A development having two hundred and one dwelling units to five hundred units must provide at least four of the amenities listed in Subsection (5) above; and
- (c) A development having five hundred and one or more dwelling units must provide at least six of the amenities listed in Subsection (5) above.
- (7) <u>Shared Amenities.</u> The Planning Director may, using the procedure for alternative compliance (as set forth in Chapter 4, Article 1, Division 2 of this GDC), approve shared use of amenities among two or more developments provided that use of the amenities by residents of all applicable developments is ensured in perpetuity in a form that is acceptable to the City.
- (8) <u>Site Furnishings.</u> Site furnishings in an Urban district development must comply with the following:
 - (a) Site furnishings, including (but not limited to) benches, litter receptacles, planters, bollards, lighting, bicycle racks, public art, and fountains in an Urban district must emphasize the architectural character of each individual Urban development.
 - (b) Individual Urban developments must maintain continuity in the style, forms, materials, and colors of site furnishings. Site furnishings must be of the same architectural character as the buildings in the development.
 - (c) Site furnishings must be durable, low-maintenance, and resistant to vandalism.
 - (d) Site furnishings must be placed so as to maintain an unencumbered walkway of at least four feet in width for pedestrians.
 - (e) Lighting for off-street parking facilities and pedestrian corridors must be of the same height, style, and color. Lighting must complement the architectural style and character of the buildings in the development.

(Ordinance 6773 adopted 5/19/15; Ordinance 7079, sec. 27, adopted 8/20/19; Ordinance 7107, sec. 25, adopted 12/3/19; Ordinance 7344 adopted 7/5/22)

2 Attachment 1

LAND USE MATRIX

N/A – Not applicable (i.e., no parking requirement) * – See Chapter 2, Section 2.52 for special standards	Р	The land use is allowed by right in the zoning district indicated.
gfa – Gross floor area		The land use is prohibited in the zoning district indicated.
	S	The land use is allowed only upon approval of a Specific Use Provision (SUP) in the zoning district indicated.

ZONING REGULATIONS

		1	1	1	1			1		GCL		~				_	•			1
	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
AGRICULTURAL USES																				
Farm, Ranch, Orchard	P																	-	2/dwelling unit	-
Feed Store	S												S	S				-	1/250 gfa	-
Stable, Commercial	P																	-	.5/stall	-
Stable, Private	P	S																-	N/A	Sec. 22.09, Art.1, Ch. 22, City Code
Stockyards, Livestock Auction, Livestock Hauling																		-	-	-
RESIDENTIAL USES																				
Accessory Dwellings:		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Guard/Manager/ Caretaker	S												S	S	S			-	2/dwelling unit	Sec. 2.58
Guest House	S	S	S	S														-	1/dwelling unit	Sec. 2.58
Rental Unit	S	S																-	Efficiency and 1 bedroom: 1 space 2+ bedrooms: 2 spaces	Sec. 2.58
Congregate Adult Living Facilities:	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Rehabilitation Facility, In Home/Residential	S	S	S				S	S									S	-	.2/resident	-
Rehabilitation Facility, Institutionalized								S										-	.3/resident	-
Elder Care Facilities:	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Assisted Living								P		S1						S	S	-	1/3 dwelling units	Sec. 2.52(A) (12)
Continuing Care (combination)								P		S1						\$	Ş	-	as determined by components, and best/current practices	Sec. 2.52(A) (12)
Independent Living								P								P	P	-	1/dwelling unit	Sec. 2.52(A) (12)
Nursing/Convalescent Care								P		S1						S	S	-	.5/bed	Sec. 2.52(A) (12)

2 Attachment 1:3

GARLAND DEVELOPMENT CODE

2 Attachment 1:4 Supp 5, Mar 2024

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Dwelling, Two-Family (duplex)							P	P										-	2 enclosed/ dwelling unit	Sec. 2.38
Dwelling, Industrialized Housing Unit	P	P	P	P	P	P	P											1	2 enclosed/ dwelling unit	Sec. 2.52(A) (5)(d)
Dwelling, Manufactured/HUD- Code Home	S																	-	2 enclosed/ dwelling unit	-
Dwelling, Mobile Home	S																	-	2 enclosed/ dwelling unit	-
Dwelling, Multifamily								Р								P	P	1	Efficiency: 1 space 1 bedroom: 1.5 spaces 2+ bedrooms: 2 spaces	Sec. 2.39
Dwelling, Live/Work																P	P	-	2 spaces, plus nonresidential requirement	Sec. 2.52(A) (5)(e)
Dwelling, Zero-Lot- Line Home					P			P										-	2 enclosed/dwelli ng unit	Sec. 2.36(C)
Dwelling, Single- Family Detached	P	P	P	P	P	P	P	P										-	2 enclosed/ dwelling unit	Sec. 2.36
Dwelling, Single- Family Attached (Townhouse)						P		Р								P	Р	-	2.25 enclosed/dwelli ng unit	Sec. 2.37
Dwelling, Apartment																P	P	,	Efficiency: 1 space 1 bedroom: 1.5 spaces 2+ bedrooms: 2 spaces	-
Manufactured/Mobile Home Park or Subdivision	DARY	Hara																-	-	-
ACCESSORY & TEMPOR	RARY P	USES P	P	P	P	P	P	P										_	N/A	Sec. 2.58
Convenience Facilities:	-	-	-	-	-	-	-	-	-	-	-	_	_	_	_	-	_	_	-	-

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	НС	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Drive-In Service												S	S	S	S			-	1/order station + 1 space per employee at maximum shift	-
Drive-Through Service										S		S	S	S	S			-	N/A	Sec. 4.20
Walk-Up Service											P	P	Р	P	Р	P	P	ı	1/walk-up window or order station + 1 space per employee at maximum shift	-
Fuel Pumps, Retail												S	P	P	P			1	N/A	Sec. 2.52(A) (3)
Itinerant Retail Vendor												*	*	*	*	*	*	1	N/A	Art. IX, Ch. 26, City Code
Kiosks, Self-Service:	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Automated Teller Machine (ATM) – Drive-Up										P		P	P	P	P	S	₽ <u>S</u>	1	1/ATM station (at the ATM)	Sec. 2.52(A) (7), Sec. 4.20
Automated Teller Machine (ATM) – Walk-Up									P	P	P	P	P	P	P	P	P	ı	1/walk-up ATM	Sec. 2.52(A) (7)
Retail (ice, water, etc.)												S	S	S				i	1 space	Sec. 2.52(A) (7), Sec. 4.20
Recycled Materials Collection											S	S	S	P	P			1	1 space	Sec. 2.52(A) (8), Sec. 4.20
Outside Display, New Materials											P	P	P	P	P		S	-	N/A	Sec. 2.52(A) (14)
Outside Display, Used Materials												S	S	P	P			1	N/A	Sec. 2.52(A) (14)
Outside Storage, New Materials											_	S	S	P	P			-	N/A	Sec. 2.52(A) (14)
Outside Storage, Used Materials													S	S	P			-	N/A	Sec. 2.52(A) (14)

2 Attachment 1:6 Supp 5, Mar 2024

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Outside Storage Unit, Portable (POD)		*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	-	N/A	Sec. 2.52(A) (14)
Seasonal Sales									*	*	*	*	*	*	*	*	*	-	N/A	Art.VIII, Ch. 30, City Code
Shelter Tent																		-	N/A	-
Shipping Container												*	*	*	*			-	N/A	Sec. 2.52(A) (15), Art. XII, Ch. 30, City Code
Temporary Building/Office (field office, construction office, subdivision sales office, etc.)	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	1	1/1,000sf site area	Sec. 2.52(A) (19), and 30.03, 30.06, 30.194, City Code
INSTITUTIONAL AND E	DUCA	TIONA	L USES																	
Church or Place of Worship	P	P	P	P	P	Р	P	Р	Р	Р	P	P	Р	P	Р	Р	P	Р	1/4 seats for buildings designed or constructed to accommodate assemblies of 100 persons or greater; 1/100 sq. feet for buildings designed or constructed to accommodate small assemblies under 100 persons.	Sec. 2.52(A) (29)
College or University									S	Р		P	P	P		S	<u>PS</u>	-	.5/student (site- specific study required)	-
Convention Facility										S		S	P	P	P		P	-	1/100 gfa	-
Day Care Facilities:	-	-	-	-	-	-	-	-	-	-	-		ı	-	-	-	-	-	-	-

2 Attachment 1:7

GARLAND DEVELOPMENT CODE

								MF (MF-												
		SF-						0, MF-1 and								U		DT (see Ch.	Parking	Cross- Reference(s) for Special
	AG	E	SF-10	SF-7	SF-5	SFA	2F	MF-2)	NO	CO	NS	CR	LC	НС	IN	R	UB	7)	Requirements	Standards
Day Care Center, Adult	S	S	S	S	S	S	S	S	P	P	P	P	P		S	S	d <mark>o</mark>	-	1/3 clients + 1 per employee at maximum shift	Sec. 2.52(A) (13)
Day Care, Youth – Licensed Child-Care Center	S	S	S	S	S	S	S	S	P	P	P	P	P		S	S	S	1	1/10 children + 1 per employee at maximum shift	Sec. 2.52(A) (2)
Day Care, Youth – Registered Child-Care Home	2	2	2	2	2	2	2	2								2	2 2	-	N/A	Sec. 2.61
Learning Center, Specialized									S	P	S	P	P	P	S	S	S	1	1/10 students	-
Makerspace (Hackerspace)															P		S		1/3 students + 1/500 sq. ft gross floor area workshop + 1/1000 sq. ft. gross floor area of warehouse	Sec. 2.52(A) (36)
School, Business									S	P	S	P	P	P	P		P		1/3 students	-
School, Retail/Personal Services Training									S	S	S	P	P	P	P	S	P	-	1/3 students	-
School, Trade													S	P	P			-	1/3 students	-
School, Private, Religious or Charter	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	-	Elementary: 1/17 students Middle: 1/17 students High: 1/3 students	2.52(A)(2)
School, Public	P	P	P	Р	Р	P	P	Р	Р	P	Р	Р	Р	P	Р	P	P	1	Elementary: 1/17 students Middle: 1/17 students High: 1/3 students	•
GOVERNMENT & HUMA	AN SE	RVICE	S USES																	
Charitable Boarding								S	S	S		S	S	S				-	.5/bed	-
Garden, Charitable	P	S	S	S	S	S	S	S	S	S	S	S	P	P	P	S	S	-	2 spaces	-

2 Attachment 1:8

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Garden, Civic	P	P	P	P	P	P	P	P								P	P	-	2 spaces	-
Post Office									P	P		P	P	P	P	P	P	-	1/300 gfa	-
Social Service									S	S	S	P	P	P				-	1/300 gfa	-
Facility/Agency																				
MEDICAL & HEALTH S	ERVI	CES USI	ES																	
Care of Alcoholic, Drug Dependent or Psychiatric Patients, Institutional										S		S	S	S	S				1 space per 4 beds	
Cemetery	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S			1	Determined by SUP	-
Hospital										P		S	P	P	S			-	1.5/bed	-
Medical and Dental Office/Clinic									P	P	P	P	P	P	P	P	P	1	1/250 gfa	-
Mortuary/Funeral Home	S											S	S	P	S			1	1/200 gfa, or 1/4 seats in sanctuary and chapel(s) (whichever is greater)	
RECREATIONAL, SOCI	AL AN	D ENTI	ERTAIN.	MENT	USES															
Athletic Events Facility, Indoor										S		P	P	P	P		<u>PS</u>	1	1/125 gfa or 1/3 bleacher and spectator seats (whichever is greater)	•
Athletic Events Facility, Outdoor	S												S	S	S		<u>S</u>	-	1/125 gfa or 1/3 bleacher and spectator seats (whichever is greater)	-
Athletic Field, Stadium, Arena	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	-	1/125 gfa or 1/3 bleacher and spectator seats (whichever is greater)	-
Civic Club/Fraternal Lodge										P		P	P	P	P		P	-	1/200 gfa	-

2 Attachment 1:9

Supp 5, Mar 2024

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Commercial Amusement, Indoor												P	P	P	P	S	P	-	1/150 gfa	-
Commercial Amusement, Outdoor												S	P	P	S		S	-	1/1,000 sf of amusement area and accessory uses	-
Cultural Facility										P	S	P	P	P	S		P	-	1/300 gfa	-
Day Camp, Private	S																	-	Determined by SUP	-
Dry Boat Storage	S												S	S	P				1/2000 gfa	1
Equestrian Camp, Private	P	S																-	.5/stall	ı
Golf Course/Country Club	S	S	S	S														-	5/green + 1/150 gfa for clubhouse/ dining areas	-
Health & Fitness Gym (indoor)										S		P	P	P	S	P	P	-	1/150 gfa	-
Marina	S											S	S	S			<mark>cp</mark>	1	1/5 slips + 1/2000 gfa for dry boat storage + 1/150 gfa for retail/dining areas	-
Public Amusement, Temporary												*	*	*	*		<u>*</u>	-	N/A	Art. VIII, Ch. 30, City Code.
Racing Track																		-	-	-
Reception Facility, Large Scale												S	S	S	S			1	1/100 gfa or 1 space for each 3 occupants (whichever is greater)	Sec. 2.52(A) (20)
Reception Facility, Small Scale												P	P	P	P				1/100 gfa or 1 space for each 3 occupants (whichever is greater)	Sec. 2.52(A) (20)

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	НС	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Recreational Vehicle Park													P (PD req.)					-	1/RV pad + 1/8 RV pads for guest/customer/ employee parking	Sec. 2.52(A) (34)
Shooting Range, Indoor													S	P	P			-	1/500 gfa + 1/target alley	-
Shooting Range, Outdoor	S																	-	1/500 gfa + 1/target alley	-
Theater, Large Scale												S	P	P				-	1/3 seats	-
Theater, Small Scale												P	P	P			S	-	1/3 seats	-
Zoo	S																	-	1/600 square feet of exhibit area	-
OFFICE, RETAIL & SER	VICE	USES																		
Alternative Financial Establishment													S					-	1/250 gfa	-
Antique Shop (indoors only)												P	P	P			<u>S</u>	-	1/250 gfa	-
Bait Sales, Live												S	S	P				-	1/250 gfa	-
Bakery, Retail									S	P	P	P	P	P	P	P	P	-	1/250 gfa	-
Bed and Breakfast	P	S	S													S	S	-	1/guest room + residential use requirement (according to that use)	Sec. 2.52(A) (11)
Business & Media Service									P	P	P	P	P	P	P	P	P	-	1/300 gfa	-
Call Center										P		P	P	P	P		S	-	1/150 gfa	-
Commercial Blood, Plasma, Tissue and Cell Collection Center												P	P	P					1/250 gfa	Sec. 2.52(A) (28)
Convenience Store (1,000–5,000sf)										S	S	P	P	P	P	<mark>₽</mark>	<u>PS</u>	-	1/250 gfa	Sec. 2.52(A) (1)
Financial Institution									P	P	P	P	P	P		P	P	-	1/300 gfa	Sec. 4.20
Flea Market, Indoor													S	S				-	1/200 gfa	Sec. 2.52(A) (32)
Flea Market, Outdoor														S				-	1/500 sf site area	Sec. 2.52(A) (32)

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Furniture, Household Furnishings and Appliance Sales/Rental												P	P	P				-	1/400 gfa	-
Grocery/Supermarket (>5,000sf)												P	P	P		S	S	-	1/250 gfa	-
Home Improvement Center (>50,000sf)												Р	P	P				1	1/250 gfa	-
Hotel/Motel, Extended Stay										S		S	S		S		<mark>vp.</mark>	1	1.25/room + 1/200sf restaurant, retail, conference and office area	Sec. 2.52(A) (11)
Hotel/Motel, Full Service										P		Р	P		S		<u>₽S</u>	1	1/room + 1/200sf restaurant, retail, conference and office area	Sec. 2.52(A) (11)
Hotel/Motel, Limited Service										S		S	S		S		<mark>do.</mark>	1	1/room + 1/200sf restaurant, retail, conference and office area	Sec. 2.52(A) (11)
Indoor Shopping Mall												Р	P	Р				-	0–400,000 gfa: 1/250 gfa 401,000+ gfa: 1/300 gfa	Sec. 2.52(A) (33)
Kiosk, Trailer or Mini- Structure (attended):		-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-
Retail/Service											S	P	P	P	P		S	-	1/employee	Sec. 2.52(A) (7), Sec. 4.20
Recycled Materials Collection												S	P	P	P			-	1/employee	Sec. 2.52(A) (8), Sec. 4.20

2 Attachment 1:12

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Landscape Nursery (retail)												P	P	P	S			-	1/250 gfa + 1/2,000sf outdoor area	-
Landscape Nursery/Tree Farm (wholesale)	S												S	P	P			-	1/2,000sf outdoor area	Sec. 2.52(A) (17)
Laundry, Drop-Off (with drive-through or window)											P	P	P	P		S	S	1	1/250 gfa	Sec. 4.20
Laundry, Drop-Off (without drive-through or window)											P	P	P	P		<u>PS</u>	<u>PS</u>	1	1/250 gfa	-
Laundry, Self-Serve (Laundromat)											S	P	P	P		\$	\$	1	1/250 gfa	-
Mobile Food Truck Park												S	S	S	S		S		Set by SUP	Sec. 2.52(A) (37)
Office, General									P	P	P	P	P	P	P	P	P	-	1/300 gfa	-
Pawn Shop														P				-	1/250 gfa	-
Personal Services										S	P	P	P	P	S	P	P	-	1/250 gfa	-
Pet Store (indoors only)											S	P	P	P		P	P	-	1/250 gfa	-
Pharmacy (with drive- through or window)										Р	S	P	P	P		S	S	-	1/250 gfa	Sec. 4.20
Pharmacy (without drive- through or window)										P	S	P	P	P		P	P	-	1/250 gfa	-
Produce Stand/Outdoor Farmers Market	S										S	S	P	P			S	-	4+1/600sf of site area	-
Restaurant										P	S	P	P	P	P	P	P	-	1/100 gfa	-
Restaurant, Drive-Through												S	S	S	S			-	1/100 gfa	Sec. 4.20
Retail Store											P	P	P	P		P	P	-	1/333 gfa	-
Sexually Oriented Business															P			-	1/250 gfa	Art. VIII, Ch. 26, City Code
Smoke Shop															S			-	1/250 gfa	-
Studio, Arts/Crafts											P	P	P	P		P	P	-	1/250 gfa	-
Studio, Fitness or Performing Arts											P	P	P	P		P	P	-	1/150 gfa	-
Tattooing/Body Piercing Establishment												S	S	S				-	1/250 gfa	Sec. 2.52(A) (6)
Used Goods, Retail Sales (Indoors)												S	P	P				-	1/250 gfa	-

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
COMMERCIAL USES																				
Bakery, Commercial													S	P	P			-	1/1,000 gfa	-
Building/Garden Materials Sales & Storage (wholesale)														P	P			1	1/400 gfa + 1/1,000 gfa storage area	Sec. 2.52(A) (23)
Bulk Material Sales & Storage (retail or wholesale)														S	S			1	1/1,000 gfa or 1/1,000 outdoor area (whichever is greater)	Sec. 2.52(A) (18)
Contractor's Office/Storage Yard (outside storage)													S	S	P			1	1/500 gfa for office + 1/1,000sf for warehouse	Sec. 2.52(A) (24)
Contractor's Office/Warehouse (indoors only)													P	P	P			1	1/500 gfa for office + 1/1,000sf for warehouse	Sec. 2.52(A) (25)
Custom Products Manufacturing													S	P	P			-	1/1,000 gfa	-
Equipment Leasing/Rental, Indoor												P	P	P	P			1	1/250 gfa	-
Equipment Leasing/Rental, Outdoor														S	P			-	1/600 gfa	Sec. 2.52(A) (27)
Feed/Grain Mill																		-	-	-
Furniture and Appliance Cleaning/Repair												S	P	P	P			ı	1/1,000 gfa	-
Garden, Commercial	P																	1	1/5,000sf of site area-	-
Laundry Plant, Commercial													S	P	P			1	1/300 office gfa + 1/1,000 remainder gfa	-
Meat and Game Processing													S	P	P			-	1/500 gfa	-
Pet Care/Play Facility (indoor)								_				S	P	P	P	<u>PS</u>	<u>PS</u>	ı	1/300 gfa	Sec. 2.52(A) (9)
Pet Care/Play Facility (outdoor)	S												S	P	P			-	1/300 gfa	Sec. 2.52(A) (9)

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	НС	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Portable Building Sales/Leasing														P	P			1	1/300 office gfa + 1/1,000sf for indoor sales/storage area	-
Printing/Publishing House										S		S	S	P	P			-	1/300 office gfa + 1/1,000 remainder gfa	-
Recording Studio/Media Production										S		P	P	P	P		S	-	1/300 gfa	-
Recycling Collection Center (no outside storage)														S	S			-	1/300 gfa for office + 1/1,000sf warehouse and storage area	Sec. 2.52(A) (8)
Recycling Salvage Yard (unlimited outside storage)															S			-	1/300 gfa for office + 1/1,000sf warehouse and storage area	Sec. 2.52(A) (8)
Self-Storage Facility (mini-warehouse)												S	S	Р	P				1/20 units (1/25 units if over 100 units in development) + 1/300 office gfa	Sec. 2.52(A) (16)
Small Engine/Lawn Equipment Rental & Repair (indoors)												S	P	P	P			1	1/300 gfa	-
Taxidermist													S	P	P			-	1/400 gfa	-
Vehicle Dispatch & Storage													S	S	P			-	1/300 office gfa + 1/1,000 remainder gfa	-
Veterinary Clinic, Large Animal (outdoor pens)	S			_														-	1/400 gfa	-
Veterinary Clinic, Small Animal (indoors only)									S	P	S	P	P	Р	P	P	P	-	1/300 gfa	-

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Veterinary Clinic, Small Animal (outdoor kennels, runs)	S							í					S	P	P			1	1/300 gfa	-
MOTOR VEHICLE & RE	LATE	D USES																		
Automobile Leasing/Rental										S		P	P	P	P			-	1/400 gfa	Sec. 2.52(A) (3)
Automobile Repair, Major													S	P	P			-	1/400 gfa + 2/repair bay	Sec. 2.52(A) (3), Sec. 4.20
Automobile Repair, Minor												S	P	P	P			ı	1/400 gfa + 2/repair bay	Sec. 2.52(A) (3), Sec. 4.20
Automobile Sales, New or Used													S	P	S			1	customer parking: 1/400 gfa (minimum 2 spaces), plus 1 space per employee on- site at any time	-
Boat Sales, Leasing & Repair (outside storage)												S	S	P	S			-	1/600 gfa	Sec. 2.52(A) (14)
Car Wash, Automated/Rollover												S	P	P	P			-	1/200 gfa	Sec. 2.52(A) (3), Sec. 4.20
Car Wash, Full-Service/Detail												S	P	P	P			1	1/200 gfa	Sec. 2.52(A) (3), Sec. 4.20
Car Wash, Self-Service/Wand													S	P	P			-	1/bay	Sec. 2.52(A) (3), Sec. 4.20
Impoundment Lot (commercial/private)															S			-	1/300 office gfa	-
Motorcycle/ATV Sales, Leasing & Repair (new and used – indoors only)													P	P	S			-	1/400 gfa	ı
Parking Lot or Garage, Commercial										P		P	P	P	P	P	P	-	1/300 office gfa	-

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Personal Watercraft Sales, Leasing & Repair (new and used)								,				S	P	P	S			-	1/400 gfa	-
Recreational Vehicle/Trailer Sales, Leasing & Repair													S	P	S			-	1/600 gfa	-
Salvage Yard, Automotive Travel Center																		-	-	-
															C			-	- 1/600 C	-
Truck/Bus Repair														S	S			-	1/600 gfa	-
Truck/Bus Sales & Leasing/Rental														S	S			-	1/600 gfa	-
Truck/Bus Storage														S	S			-	1/300 office gfa	-
Truck/Bus Wash														P	P			1	1/250 gfa + 1/bay	Sec. 2.52(A) (3), Sec. 4.20
Wrecker/Towing Service														P	P			1	1/300 office gfa + 1/wrecker	-
TRANSPORTATION USE	ES																			
Airport/Heliport														S	S			-	1/4 seating accommodation + .5/employee at maximum shift	-
Bus Stop	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	-	NA	-
Helipad										S		S	S	S	S		S	1	5/helipad	-
Motor Freight Terminal/Railroad Switching Yard															P			1	1/1,000 gfa	-
Transit Station, Public									P	P	P	P	P	P	P	P	P	1	Determined by operating agency	-
Transportation Depot, Passenger (commercial)													S	S	S			1	Determined by SUP	Sec. 2.52(A) (10)
Transportation Terminal, Passenger (commercial)																		1	-	-
INDUSTRIAL USES																				

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	НС	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Animal Feed Processing & Storage															S			1	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-
Batching Plant															S			-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	Sec. 2.52(A) (26)
Batching Plant, Temporary	Р	Р	P	Р	P	Р	P	P	Р	Р	P	Р	P	Р	Р	Р	P	-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	Sec. 2.52(A) (26)
Breweries/Wineries/ Distilleries												S	S	S	Р	S	S		1/1,000 gfa or 5 visitors + 1/employee at max. shift, whichever is greater 1/100 gfa for dining and tasting areas	Sec. 2.52(A) (35)
Data Center Distribution Center, Large (indoors only)										S				P S	P P		S	-	1/5,000 gfa 1/300 office gfa + 1/1,000 remainder gfa	Sec. 2.52(A) (30)
Distribution Center, Small (indoors only)													S	Р	Р			-	1/300 office gfa + 1/1,000 remainder gfa	Sec. 2.52(A) (30)

ZONING REGULATIONS

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Food Processing & Storage														S	S			1	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-
Gas or Petroleum Drilling or Pipeline	S														S				N/A	Sec. 2.52(A) (21)
Heavy Machinery Sales, Rental, Storage & Repair														S	S			1	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-
High Risk Use															S			,	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-
Industrial or Manufacturing, Heavy															S			-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	Sec. 2.52(A) (31)
Industrial or Manufacturing, Light													S	P/S3	P/S3			-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	Sec. 2.52(A) (31)
Laboratory, Analytical or Research (indoor)										S		S	P	P	P			-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-

GARLAND DEVELOPMENT CODE

	AG	SF- E	SF-10	SF-7	SF-5	SFA	2F	MF (MF- 0, MF-1 and MF-2)	NO	СО	NS	CR	LC	нс	IN	U R	UB	DT (see Ch. 7)	Parking Requirements	Cross- Reference(s) for Special Standards
Leather & Allied Products Manufacturing															S			-	1/1,000 gfa or 5 visitors + 1/employee at maximum shift, whichever is greater	-
Mining/Mineral Extraction																		-	-	-
Warehouse, Office/Showroom (indoors only)												S	P	P	P			-	1/300 office gfa + 1/1,000 remainder gfa	-
UTILITY & SERVICE US	ES																			
Antenna, Commercial	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	1	N/A	Div. 5, Art. 5, Ch. 2
Antenna, Private	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	-	N/A	Div. 6, Art. 5, Ch. 2
Electric Generating Plant	S														S			-	1/employee at maximum shift	-
Electric Substation	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S			-	1/employee at maximum shift	-
Gas Regulating Station	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S			-	1/employee at maximum shift	-
Telecommunications Switching Station	S	S	S	S	S	S	S	S	P/S4	P/ S4	P/S4	P/S4	P/ S4	P/S4	P/S4			-	1/employee at maximum shift	-
Wind Energy Conversion System	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	-	N/A	Div. 7, Art. 5, Ch.2

ZONING REGULATIONS

2 Attachment 1:21

ZONING REGULATIONS

- ¹ These Elder Care uses are permitted by right in this district if located within 1,000 feet of a Hospital, measured property line to property line.
- ² Day Care, Youth Registered Child-Care Home: Allowed by right in the designated zoning districts, subject to the regulations for Home Occupations (see Section 2.61 of Chapter 2)
- ³ Light Industrial/Manufacturing uses require issuance of an SUP where contiguous or where within 100' of a residential zoning district or a residential use.
- ⁴ Telecommunications Switching Station uses require issuance of an SUP when located within 1,000 feet of a residential zoning district.

(Ordinance 6773 adopted 5/19/15; Ordinance 6876 adopted 12/13/16; Ordinance 6925 adopted 7/18/17; Ordinance 6979, sec. 1, adopted 4/17/18; Ordinance 7001, sec. 1, adopted 8/7/18; Ordinance 7104, sec. 2, adopted 11/5/19; Ordinance 7107, sec. 26, adopted 12/3/19; Ordinance 7138, sec. 2, adopted 4/7/20; Ordinance 7142, sec. 1, adopted 5/5/20; Ordinance 7323 adopted 5/3/22; Ordinance 7344 adopted 7/5/22; Ordinance 7352 adopted 8/16/22; Ordinance 7370 adopted 10/11/2022; Ordinance 7371 adopted 10/11/2022; Ordinance 7483 adopted 11/14/2023; Ordinance 7497 adopted 1/9/2023)



Plan Commission 2. g.

Meeting Date: 05/12/2025

Item Title: Z 25-08 City of Garland (District 5)

Summary:

Hold a public hearing and consider the application of the **City of Garland**, requesting approval of a change in zoning from multiple zoning districts including but not limited to Industrial (IN), Community Retail (CR), and Planned Developments with IN and CR base zoning to Urban Residential (UR) and Urban Business (UB) Districts. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5) (File Z 25-08)

Attachments

Z 25-08 City of Garland Report & Attachments Z 25-08 City of Garland Responses

Planning Report



File No: Z 25-08/District 5

Agenda Item:

Meeting: Plan Commission

Date: May 12, 2025

REQUEST

Hold a public hearing and consider approval of a change in zoning from multiple zoning districts including but not limited to Industrial (IN), Community Retail (CR), and Planned Developments with IN and CR base zoning to Urban Residential (UR) and Urban Business (UB) Districts.

LOCATION

The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue.

APPLICANT

City of Garland

OWNER

This site contains over one-hundred parcels having many owners.

BACKGROUND

The area of request is mostly developed with many uses. The variety of uses include apartments, retail store, restaurants, and offices. In addition, there are several auto-oriented uses, self-storage facilities, and warehouses as well. This general area is a major gateway to the City of Garland that is ripe for redevelopment and revitalization. The existing zoning on this area and the applicable regulations do not lend themselves into bringing the vision of revitalization into fruition. The purpose of this city-initiated rezoning is to set the stage for future substantial developments to take place with urban mixed-use regulations in mind.

Staff would like to note that this rezoning proposal does not take into account any specific development. It is possible and envisioned that future development would come in with possible Planned Development options. However, those would then be considered with the merits of the base zoning of Urban Residential (UR) and Urban Business (UB), if this rezoning proposal is approved.

SITE DATA

The area of request is approximately 317 acres undeveloped tract of land. The area is bisected by S Garland Avenue. The portion to the west is bound by W Kingsley Avenue and S Shiloh Road and S Garland Avenue. The larger portion of the area of request is located on the east side of S Garland Avenue, west of Saturn Road and north I-635.

USE OF PROPERTY UNDER CURRENT ZONING

Currently the area of request is governed by Industrial (IN), Community Retail (CR), or planned developments with base zoning of those districts. There are some parcels that are governed by other zoning districts such as Light Commercial (LC) and Multifamily (MF).

CONSIDERATIONS

Proposed Zoning (UR and UB):

The Urban (U) districts are intended to allow cohesive, orderly, creative, and predominantly vertically oriented mixed-use and mixed-density developments. There are two types of Urban districts: Urban Residential (UR) and Urban Business (UB). UR districts are predominantly residentially oriented districts that may also include a limited number of integrated nonresidential uses that are compatible with, harmonious with, and supportive of, a high-density, urban-style residential neighborhood. UB districts are predominantly business- and shopping-oriented districts that may also include a limited amount of integrated residential uses that are compatible with, and supportive of, a high-density, urban-style business district.

The Urban districts are also intended to establish a distinctive community character in specially selected areas through innovative and mutually-sustaining land uses, urban-style and pedestrian-oriented site design, efficient traffic and pedestrian circulation, innovative and high-quality architectural elements and landscaping concepts, and other similar enhanced design features that will in turn elicit a strong sense of community, civic pride, and of satisfaction with quality of life among those who choose to enjoy the lifestyle created by these districts.

Appropriate flexibility in final design should be given to developers and designers of Urban districts to allow creativity for the opportunities associated with individual sites. The Urban districts can include a mixture of architectural styles ranging from contemporary to traditional. The general intent of these districts is to maximize utilization of land for a mixture of mutually sustainable uses, while also utilizing open spaces to the greatest extent possible in an urban setting for public recreation and leisure purposes. Urban districts are intended to include a diverse mixture of residential housing choices and business/employment opportunities (for example, live-work units) in a symbiotic and urban-style environment that not only accommodates residents' needs to live, work, learn, and play within a neighborhood setting, but that also builds long-term stability, civic pride and fiscal value for the community in general.

COMPREHENSIVE PLAN

The Future Land Use Map of the Envision Garland Plan recommends a combination of Community Centers, Neighborhood Centers, Urban Neighborhoods, and Business Centers. The proposed zoning Urban Residential (UR) and Urban Business (UB) are the most eligible zoning districts to cohesively implement the visions of these land use designations.

COMPATIBILITY OF REQUEST WITH SURROUNDING ZONING AND LAND USES

This entire area of request is a gateway to the City of Garland. Being adjacent on I-635 and bounded by key thoroughfares, this area is ideal for revitalization and redevelopment.

STAFF RECOMMENDATION


Staff recommends approval of this rezoning proposal. In addition, staff is bringing forward a GDC amendment as it relates to the permitted land uses and development regulations within the proposed UR and UB zoning districts. The GDC amendment is scheduled for public hearing on the same agenda.


ADDITIONAL INFORMATION


- i. Location Map
- ii. Proposed zoning designations

CITY COUNCIL DATE: June 3, 2025

PREPARED BY: Nabila Nur, AICP Director Planning and Development 972-205-2449 nnur@garlandtx.gov







Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Monte Brown Owner
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuê, v.v.)
2005 Town Count
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
CARLAND, TX
City, State / Estado de la Ciudad / Thành bang
75041
Zip Code / Código postal / Mã B u Ohính

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

Date / Fecha / Ngày

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envie el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o envielo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Marvin Bolds
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuê, v.v.)
2021 Town Place
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
City, State / Estado de la Ciudad / Thành bang
75041-4818
Zip Code / Çódigo postal / Mã B u Ohính
04-08-25
Signature / Firma / Ch

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / M	arque uno a continuación / Vui lòng kiểm tra một bên dưới
	For / A Favor / Đúng
	Against / En Contra / Không
Garland, TX 75406-9002./ Por favor C a Planning@garlandtx.gov; entregar por correo a City of Garland, Planning thông tin sau và gửi biểu mẫu qua em Garland, TX; hoặc gửi thư đến Thành	nation and email the form to Planning@garlandtx.gov; deliver to the Planning and, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 complete la siguiente información y envíe el formulario por correo electrónico al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo pepartment, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ ail tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
KEITH TRAYWILL, PR	
Printed Name & Title / Nombre Impre (Property Owner, Business Owner, Tenant, etc.) / nghiệp, Người thuế, v.v.)	eso y Título / Tên in và Tiêu đề (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
2028 TOWNGATE O	>RUE
Your Property Address / La dirección	de su propiedad / địa chỉ tài sản
2078 POWN CATE D	PLIVE GARLAND, TX
City, State / Estado de la Ciudad / Tha	anh bang
6 ATLAND, TX 7504	
Zip Code / Código postal / Mã B u O	ıính
75041 Pelluayi	t 3.31-2025
Signature / Firma / Ch ữ ký	Date / Fecha / Ngày

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

	For / A Favor / Đúng
X	Against / En Contra / Không
Department at 800 Main Street Garla Garland, TX 75406-9002./ Por favor Coa Planning@garlandtx.gov; entregar por correo a City of Garland, Planning thông tin sau và gửi biểu mẫu qua em	ation and email the form to Planning@garlandtx.gov ; deliver to the Planning and, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 complete la siguiente información y envíe el formulario por correo electrónico al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo popartment, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ ail tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Betty Berry	/ PINC Bank
Printed Name & Title / Nombre Impre	
(Property Owner, Business Owner, Tenant, etc.) / nghiệp, Người thuê, v.v.)	(Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
3004 Browne	DR
Your Property Address / La dirección	de su propiedad / địa chỉ tài sản
Garland TX	
City, State / Estado de la Ciudad / Tha	ành bang
75041	
Zip Code / Código postal / Mã B u O	nính
Satter Buy	4-4-25
Signature / Firma / Ch ữ ký	Date / Fecha / Ngày

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

	For / A Favor / Đúng
	Against / En Contra / Không
Department at 800 Main Street Garland, TX 75406-9002./ Por favor Ca Planning@garlandtx.gov; entregal por correo a City of Garland, Plannin thông tin sau và gửi biểu mẫu qua er	mation and email the form to Planning@garlandtx.gov ; deliver to the Planning land, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Complete la siguiente información y envíe el formulario por correo electrónico al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo go Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ nail tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street h phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Baccy Blothe	Bysiness awner
Printed Name & Title / Nombre Imp	reso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.)	/ (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
nghiệp, Người thuế, v.v.) 3209 5. Shìlph #	
Your Property Address / La direcció	n de su propiedad / địa chỉ tài sản
Garland TK	
City, State / Estado de la Ciudad / Ti	nành bang
75041	
Zip Code / Código postal / Mã B u 6	Dhính
Zm 7/1/1	
1 0.71	

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Đia chỉ

Date / Fecha / Ngày

Signature / Firma / Ch ũ ký

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

I Don't Want poorle Livin across 14	Strain	T
There already too much Traffice Why like in a Industrial part of Town		
why like in a industrial part of Town	· #	
	<u>.</u>	
	.ó.r	<u></u>
		<u> </u>
		·
	<u></u>	
	•	
	<u></u>	
		
	<u>.</u> .	··
		<u> </u>

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marc	que uno a continuación / Vui lòng kiểm tra một bên dưới
F	or / A Favor / Đúng
A	gainst / En Contra / Không
Garland, TX 75406-9002./ Por favor Com a Planning@garlandtx.gov; entregar al l por correo a City of Garland, Planning D thông tin sau và gửi biểu mẫu qua email	on and email the form to Planning@garlandtx.gov; deliver to the Planning, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 plete la siguiente información y envíe el formulario por correo electrónico Departamento de Planificación en 800 Main Street Garland, TX; o envíelo epartment, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street ố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Linda Canol Talbe	rt
Printed Name & Title / Nombre Impreso	y Título / Tên in và Tiêu đề
ngnięp, Người thúe, v.v.)	eño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
1502 Mayfield au Your Property Address / La dirección de	enae
Your Property Address / La dirección de	su propiedad / địa chỉ tài sản
Garland, Texas	
City, State / Estado de la Ciudad / Thành	bang
75041	
Zip Code / Código postal / Mã B u Q hínl	ו
Luida C. Jarbent	Gonil 14, 2025

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

Date / Fecha / Ngày

Signature / Firma / Ch ữ ký

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

No more Dollar on 99 & Stores 1
Plan for more businesses like refunants etc.
Central Market or a closer Home Depot would
be very nice. Sudac. Dolbert

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a co	ntinuación / Vui lòng kiểm tra một bên dưới
For / A Favo	or / Đúng
Against / E	n Contra / Không
Department at 800 Main Street Garland, TX; or mail Garland, TX 75406-9002./ Por favor Complete la siguie Planning@garlandtx.gov; entregar al Departamento por correo a City of Garland, Planning Department, P.C hông tin sau và gửi biểu mẫu qua email tới Planning@Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở	
Printed Name & Title / Nombre Impreso y Título / Tên	in và Tiệu đề
	Dueño de la empresa, Inquillino, etc.) / (Chủ sở hữu bắt động sản, Chủ doanh
2016 lowngate DR'	
Your Property Address / La dirección de su propiedad	địa chỉ tài sản
Garland TX 7	
City, State / Estado de la Ciudad / Thành bang	
7504	
Zip Code / Código postal / Mã B u Ohính	
La Clarce	4/21/25
Signature / Firma / Ch	Date / Fecha / Ngày

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

After having my questions answered by the Planning Overter, Nabila New, I think I understand why the
for the future by being consected. If it is to protect the are.
To maintain the quality of life we have in our quiet, safe weighborhood, Town sale.

Morales, Elisa

From: Nur, Nabila

Sent: Monday, April 14, 2025 2:13 PM

To: Morales, Elisa

Subject: FW: CarMax #7109 (RI #3327) - Potential zoning change 12715 Lyndon B Johnson Fwy,

Garland TX 75041

Attachments: 3327 - Public Hearing Notice.pdf

Importance: High

Please file.

Nabila Nur, AICP

Director of Planning and Development

800 Main Street | Garland, Texas 75040

phone: 972.205.2449

nnur@garlandtx.gov | GarlandTx.gov



From: Jessica Lopes <jlopes@realtyincome.com>

Sent: Wednesday, April 9, 2025 12:08 PM **To:** Nur, Nabila <NNur@garlandtx.gov>

Subject: CarMax #7109 (RI #3327) - Potential zoning change 12715 Lyndon B Johnson Fwy, Garland TX 75041

Importance: High

You don't often get email from jlopes@realtyincome.com. Learn why this is important

Dear Nabila Nur:

Our office is in receipt of the attached public hearing notices regarding the proposed rezoning of the above referenced property that we own and is leased to CarMax. Please consider this email an objection to the rezoning of our property. The rezoning of the property detrimentally affects us and results in us becoming a non-conforming use.

Please let us know what our next steps are as a remote property owner to voice our concerns as we do not wish for our property to be rezoned.

Thank you,

Jessica Lopes

Associate Director, Right of Way, Condemnations, & Real Estate West Team Lead
Realty Income Corporation (NYSE "O")
The Monthly Dividend Company®
11995 El Camino Real, San Diego, CA 92130
www.realtyincome.com
(O) 858-284-5000



This email may contain material that is confidential, privileged and/or attorney work product for the sole use of the intended recipient. Any review, reliance or distribution by others or forwarding without express permission is strictly prohibited. If you are not the intended recipient, please contact the sender and delete all copies.

CAUTION: This email is from an external source. DO NOT click links or open attachments without verifying the sender. Never enter **USERNAME**, **PASSWORD** or **SENSITIVE INFORMATION** on linked pages from this email. If you are unsure about the message, please contact the **Help Desk at x7240** for assistance.

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S

Please Check One Belo	ow / Marque uno a continuación / Vui	lòng kiểm tra một bên dưới
a specific supplies	For / A Favor / Đúng	
	Against / En Contra / Kh	ông
Department at 800 Main Stree Garland, TX 75406-9002./ Por fa a Planning@garlandtx.gov; en por correo a City of Garland, Pl thông tin sau và gửi biểu mẫu c	information and email the form to <u>Plannin</u> t Garland, TX; or mail to City of Garland, avor Complete la siguiente información y e tregar al Departamento de Planificación e anning Department, P.O. Box 469002 Garla qua email tó Planning@garlandtx.gov; gia Thành phố Garland, Sở Kế hoạch, P.O. Hộ	Planning Department, P.O. Box 469002 envíe el formulario por correo electrónico n 800 Main Street Garland, TX; o envíelo and, TX 75406-9002./ Vui lòng điền đầy đủ o cho Phòng Kế hoạch tại 800 Main Street
Judy F	ord, Propert	y Owner
	e Impreso y Ťítulo / Tên in và Tieu đề	age of the normal
(Property Owner, Business Owner, Tenai nghiệp, Người thuê, v.v.)	nt, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inc	uilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
2027 7	own Court	च निर्मा निर्मा
Your Property Address / La dir	ección de su propiedad / địa chỉ tài sản	225
Garland	.TX	n i negati e e e e e e e e e e e e e e e e e e e
City, State / Estado de la Ciuda	nd / Thành bang	and the large transfer of
75041	The state of the s	
Zip Code / Código postal / Mã	B u Ohinh	4/4/2025
Signature / Firma / Ch	mber is optional. / La dirección de correo electrónico	Pate / Fecha / Ngày
email và số điện thoại là từy chọn	imber la optional. / La dirección de correo electronico	y el fiumero de telefono son opcionales. / Địa chi

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

I live (40+ years) in the Towngate Homeowners Association immediately east of the proposed rezoning (Case Z 25-08). The proposed rezoning will have impact on the residents living in this area.

First, there's the pollution.

- The construction on Northwest Highway and LBJ has created great pollution, dirt, noise and heavyequipment traffic. There seems to be no end in sight for the completion of this project. When completed, my neighborhood will continue to endure endless traffic, smog, noise and pollution. Being outside will continue to be dreadful.
- The cement plant the City has placed on Garland Road is a nasty, dirty mess with enough dust in the air to make me think I'm driving through fog. I've heard this is being replaced with a soccer stadium? More traffic, smog, noise, pollution and crime.
- North of the townhomes is the Logistics plant. Twenty-four hours a day 18 wheelers are driving in and out
 of the plant, backing into the bay with a loud warning alarm or worst yet, getting lost and "trapped" on the
 neighborhood streets. Behind the Logistic plant are other businesses with 18 wheelers creating traffic,
 noise, and pollution.
- High rise apartments, restaurants, drive-thru fast food, et al. How much dirty, noisy construction can the City inflict on this area?
- I've heard this is to be a "walking" community with amenities and restaurants with residents using Dart for transportation. Is the City expecting these new residents to walk to restaurants and movies in July and August heat or sub-zero temps in December and January? These people are going to have multiple cars which continue to make the environment worse.

Then there's City services.

- How does the City plan to provide water when current residents have restrictions on water usage in the summer now. How does the City plan to provide electricity when there's not sufficient electricity during emergency weather conditions? Will the City continue to send out notices in the utility bills letting us know if we need electrical power in the winter during an outage, it's our personal responsibility to provide it? Will the City notify new residents of the lead in our drinking water?
- The high-rise apartments, condos, and single family homes are going to add substantially to the population and to the City's responsibility to provide utilities and services. Who's going to pay for more police, firefighters, EMTS, roads, and road maintenance? Is the City expecting the good old residents of Garland to make this project possible with higher and/or more taxes?

No. th	nis rezor	ing '	will a	affect the	neighborho	od. And not in a good way.	Vote	"NO"	on this zoning project	
•	ir year.			ř,		3	u		and manning project	
	<u>. "</u>			4#£	- ·-	Age active		ঞ	The state of the s	
		e#.	•		••	展費 ・セ	*		the trade to the time of the	

Morales, Elisa

From:

Nur, Nabila

Sent:

Wednesday, April 16, 2025 6:16 PM

To:

Morales, Elisa

Subject:

FW: Rezoning

Follow Up Flag:

Follow up

Flag Status:

Flagged

Outside the Notification Area

Please file.

Nabila Nur, AICP

Director of Planning and Development

800 Main Street | Garland, Texas 75040

phone: 972.205.2449

nnur@garlandtx.gov | GarlandTx.gov



From: greg skinner < wgskinner@hotmail.com> Sent: Wednesday, April 16, 2025 10:50 AM To: Nur, Nabila < NNur@garlandtx.gov>

Subject: Rezoning

You don't often get email from wgskinner@hotmail.com. Learn why this is important

For Chairman Roberts

City staff seems poised to rezone more than 300 acres along LBJ Freeway. The proposal calls for a mixed use oasis of sorts that I do not see happening anytime soon.

I have no problem with the vision other than it negatively impacts the businesses already there.

I am now retired and have lived in Garland since 1979. My children went to Garland schools and I've seen many changes to the community and they have usually come with robust debate. In this case I only heard about it from someone in real estate, a field I worked in throughout my career.

Cities gain reputation over time with the real estate community. Dallas, for instance, has a terrible but well deserved reputation for taking away the zoning rights of businesses and being extremely difficult to deal with. The result has been the market has punished them. In a period when most cities have grown dramatically, Dallas continues to shrink in population and get older. It's a city that's fallen behind the rest of the region.

When a city takes away the rights of a large national company, you start to run the same risk. A drive through the area showed me many of Americas largest operators may be negatively impacted. Did the city staff meet with them? Are they in favor?

Walmart, Braums, McDonalds, RaceTrac, and many others create sizable sales tax and as a retiree I worry about Garland's ability to keep services up. The tax rate in Garland is already higher than most would like.

I worked in the development community for decades and I don't believe anyone from the city ask the business owners for their input. The planning and zoning commission and city council would never allow a developer to just waltz in and not have meetings with the community and neighboring property owners.

This seems rushed, possibly because of politics, and it shouldn't be. There are no big developments ready to come to this industrial area. Take the time to do this right and not hurt the people already doing business in our city.

Greg Skinner 1201 Wedgecrest Ln

Get Outlook for iOS

CAUTION: This email is from an external source. DO NOT click links or open attachments without verifying the sender. Never enter **USERNAME**, **PASSWORD** or **SENSITIVE INFORMATION** on linked pages from this email. If you are unsure about the message, please contact the **Help Desk at x7240** for assistance.

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
James Leon
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad. Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bắt động sản, Chủ doanh nghiệp, Người thuế, v.v.)
2321 Lee St.
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Garland, Texas
City, State / Estado de la Ciudad / Thành bang
75041
Zip Code / Código postal / Mã B u Ohính
4,21.25
Signature / Pirma / Ch r ký (Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación multiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la l-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khôảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Ganana Avenue. (etakii o).	1. 外国内的政策 (1. 10 A) 2. 11 A)			
Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên đười				
	For / A Favor / Đúng			
×	Against / En Contra / Không			

Please complete the following information and email the form to Planning@garlandtx.gov; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Department of Planning@garlandtx.gov; entregar al Departmento de Planlificación en 800 Main Street Garland, TX; o envielo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lòng dièn đầy đủ thông tin sau và gửi biểu mấu qua email tới Planning@garlandtx.gov; giao cho Phòng Kê hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.

Guillermo Rivera Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề (Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquillino, etc.) / (Chú sở hữu bắt động sản, Chủ doanh nghiệp, Người thuộ, v.v.) 3209 S. Shiloh Rd. STE. C. Your Property Address / La dirección de su propiedad / dja chỉ tài sản Garland, TX. City, State / Estado de la Ciudad / Thành bang 75041 Zip Code / Código postal / Mã B u Ohinh

Signature/Firma / Ch ür ký

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Dis email và số điện thoại là tùy chọn.)

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một hên dưới

the same the same to be same to b
For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ hông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất đồng sản, Chủ doanh
nghiệp, Người thuế, v.v.) 2005 TOWN Count
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Canlano, TX
City, State / Estado de la Ciudad / Thành bang
75041
Zip Code / Código postal / Mã B u Qhính

Signature / Firma / Ch ữ ký

Date / Fecha / Ngày

(Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

	For / A Favor / Đung
	Against / En Contra / Không
Department at 800 Main Street Ga Garland, TX 75406-9002./ Por favor a Planning@garlandtx.gov; entreg por correo a City of Garland, Plann thông tin sau và gửi biểu mẫu qua	ormation and email the form to Planning@garlandtx.gov ; deliver to the Planning arland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 or Complete la siguiente información y envíe el formulario por correo electrónico ar al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo hing Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street anh phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
José Fighte	1 Moneta
Printed Name & Title / Nombre Im	preso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc nghiệp, Người thuê, v.v.)	c.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
1501 Mayfield A	we garaba
Your Property Address / La direcci	ión de su propiedad / địa chỉ tài sản
X	
City, State / Estado de la Ciudad /	Thành bang
75041	
Zip Code / Código postal / Mã B u	O hính
Signature / Firma / Ch	Date / Fecha / Ngày er is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ
(Froviding citial address and priorie fulfibe	a is optional, a La dirección de correo electronico y el numero de telefono son opcionales. A Dia chi

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất agree that manges should be made in the area.

Morales, Elisa

From: Nur, Nabila

Sent: Monday, April 28, 2025 12:57 PM

To: Morales, Elisa

Subject: FW: Letter Opposing Zoning Change

Please file.

Nabila Nur, AICP

Director of Planning and Development

800 Main Street | Garland, Texas 75040

phone: 972.205.2449

nnur@garlandtx.gov | GarlandTx.gov



From: Morgera, Katrina < Katrina _ Morgera@pepboys.com >

Sent: Monday, April 28, 2025 12:54 PM To: Nur, Nabila <NNur@garlandtx.gov>

Cc: Dallas Cothrum, Ph. D. <dallas@masterplantexas.com>; lgunn@masterplantexas.com

Subject: Letter Opposing Zoning Change

You don't often get email from katrina morgera@pepboys.com. Learn why this is important

Dear Director Nur,

I am writing to oppose the zoning change for the Pep Boys store located at 2002 Northwest Highway. We have operated this store for 39 years and this is a high performing location for our company.

Any change to our zoning that would make us non-conforming is not acceptable. It creates a risk for our business that is unfair and jeopardizes the investment we have made. We would not have selected this site to do business if it was non-conforming.

We also would expect that the city would have held in person and electronic meetings to address our concerns and explain their actions.

We look forward to you holding these meetings and believe this meeting of the plan commission is being rushed. This is a serious decision that impacts numerous businesses. More time is needed to assess the potential impact of this change.

Please do not hesitate to contact me or our representative, Masterplan, on this matter.

Respectfully,



Katrina Morgera Director, Licensing

Office: 215-430-9403 Cell: 302-373-3031 Katrina_Morgera@pepboys.com One Presidential Blvd Bala Cynwyd, PA 19004

Disclaimer: It is the policy of Icahn Automotive Group LLC and its affiliates not to enter into contracts or binding commitments by email. Nothing in this email shall constitute a contract or legally binding commitment by Icahn Automotive Group LLC and its affiliates. This email is intended only for the person or entity to which it is addressed and may contain confidential, proprietary and/or privileged material. Any review, distribution, reliance on, or other use of this information by persons or entities other than the intended recipient is prohibited. If you receive this message in error, please immediately notify the sender and delete it and all copies of it from your system. Thank You.

Pep Boys Email Disclaimer: It is the policy of The Pep Boys – Manny, Moe & Jack LLC and its affiliates not to enter into contracts or binding commitments by email. Nothing in this email shall constitute a contract or legally binding commitment by The Pep Boys – Manny, Moe & Jack LLC and its affiliates. This email is intended only for the person or entity to which it is addressed and may contain confidential, proprietary and/or privileged material. Any review, distribution, reliance on, or other use of this information by persons or entities other than the intended recipient is prohibited. If you receive this message in error, please immediately notify the sender and delete it and all copies of it from your system. Thank You.

CAUTION: This email is from an external source. DO NOT click links or open attachments without verifying the sender. Never enter **USERNAME**, **PASSWORD** or **SENSITIVE INFORMATION** on linked pages from this email. If you are unsure about the message, please contact the **Help Desk at x7240** for assistance.

Comment Form Case Z 25-08

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

	For / A Favor / Đúng	
\bowtie	Against / En Contra / K	hông
Gepartment at 800 Main Street Gar Garland, TX 75406-9002./ Por favor (n Planning@garlandtx.gov; entrega por correo a City of Garland, Plannir hông tin sau và gửi biểu mẫu qua ei	land, TX; or mail to City of Garlar Complete la siguiente información r al Departamento de Planificación ng Department, P.O. Box 469002 Ga nail tói Planning@garlandtx.gov; q	ing@garlandtx.gov; deliver to the Planning nd, Planning Department, P.O. Box 469002 y envíe el formulario por correo electrónico en 800 Main Street Garland, TX; o envíelo rland, TX 75406-9002./ Vui lòng điền đầy đủ iao cho Phòng Kế hoạch tại 800 Main Street Hộp 469002 Garland, TX 75406-9002.
Amber Ray De	Brown Inc - Rep)
Printed Name & Title / Nombre Imp	reso y Título / Tên in và Tiêu đề	
(Property Owner, Business Owner, Tenant, etc.) nghiệp, Người thuê, v.v.)	/ (Dueño de la propiedad, Dueño de la empresa,	Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh
4/01 S. Shilob	Rd-	. 1
Your Property Address / La direcció	n de su propiedad / địa chỉ tài sản	
Garland TX		
City, State / Estado de la Ciudad / Ti	nành bang	
7504		
Zip Code / Código postal / Mã B u ()hính	
Miskan		April 29, 2025
Signature / Firma / Ch ữ ký /		Date / Fecha / Ngày
roviding email address and phone number is	s optional / La dirección de correo electróni	co v al número de teléfene con enciencies / Die al-?

email và số điện thoại là tùy chọn.)

Comment Form Case Z 25-08

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ thông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Forced Eggle Ex 2 Owner
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuê, v.v.)
7221 1 EE ST
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Car Cond TX
City, State / Estado de la Ciudad / Thành bang
Zip Code / Código postal / Mã B u Q hính
750 W
Signature / Firma / Ch v ký Date / Fecha / Ngày (Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ

email và số điện thoại là tùy chọn.)

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

This will affect unfavor crowd in the over	
infavor cowd in the over	
<u> </u>	
· · · · · · · · · · · · · · · · · · ·	
	-
-	
	•
	_
	<u>-</u>

From: ö

Azeb Debebe

Date: Subject:

Planning Group Comment Form Case Z 25-08 Saturday, May 3, 2025 6:12:45 PM

You don't often get email from azebdebebe@ymail.com. Learn why this is important

	Comment Form
	Case Z 25-08
	Garland. The applicant proposes a zoning change from multiple zoning districts to (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 is, generally located on the north side of I-635, on both sides of S Garland Avenue.
consta de aproxí	rrland. El solicitante propone un cambio de zonificación de distritos de zonificación o de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno madamente 317 acres de propietades, generalmente ubicadas en el lado norte de lados de la Avenida S. Garland, (Distrito 5).
mann knu vực do	arland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch ry hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu àng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Quận 5).
Please Check One	Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới
	For / A Favor / Đúng
Department at 800 Main S Garland, TX 75406-9002./ F a Planning@garlandtx.gov por correo a City of Garlan	Against / En Contra / Không wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Breet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900; Por favor Complete la siguilente información y envie el formulario por correo electrónic; critregar al Departamento de Planificación en 800 Main Street Garland, TX; o enviel d, Planning Department, P.O. Box 469002 Garland, TX, 75406-9002./ Vui lòng dién dày d aluqua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoach ta is 800 Main Street
Department at 800 Main & Garland, TX 75406-9002./ F a Planning@garlandtx.gov por correo a City of Garlan thông tin sau và gửi biểu n Garland, TX; hoặc gửi thư	wing information and email the form to <u>Planning@garlandtx.gov</u> ; deliver to the Planninstreet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 45900 or favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o enviet de Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lóng dièn dày d'aiu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main & Garland, TX 75406-9002./ F a Planning@garlandtx.gov por correo a City of Garlan thông tin sau và gửi biểu m Garland, TX; hoặc gửi thư	ving information and email the form to <u>Planning@garlandtx.gov</u> ; deliver to the Planning. Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900 or favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o enviet de Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lóng dièn dày d'aiu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main & Garland, TX 75406-9002./ F a Planning@garlandtx.gov por correo a City of Garlan thông tin sau và gửi biểu m Garland, TX; hoặc gửi thư Azel Debel Printed Name & Title / Nor	wing information and email the form to <u>Planning@garlandtx.gov</u> ; deliver to the Planning treet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900: Por favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o enviet de Janning Department, P.O. Box 469002 Garland, TX 75406-9002. Vul ibon diàu d'au qua email toi Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street đến Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main & Garland, TX 75406-9002./ F a Planning@garlandtx.gov por correo a City of Garlan thông tin sau và gửi biểu m Garland, TX; hoặc gửi thư Azel Debel Printed Name & Title / Nor	ving information and email the form to <u>Planning@garlandtx.gov</u> ; deliver to the Planning. Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900 or favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o enviet de Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lóng dièn dày d'aiu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main S Garland, TX 75406-9002. F a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giời biểu m Garland, TX; hoặc gửi thư Az L De bo Printed Name & Title / Nor (Property Owner, Business Owner, I oghielp, Người thưế, YX)	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900? For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o enviel d, Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui long dièn day d nâu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phó Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main S Garland, TX 75406-9002. F a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giời biểu m Garland, TX; hoặc gửi thư Az L De toc Printed Name & Title / Nor (Praperty Owner, Business Owner, oghiệp, Người thưế, VX) 2007 Town	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900? For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o enviel d, Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui long dièn day d nâu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phó Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Department at 800 Main S Garland, TX 75406-9002. F a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và gừi biểu m Garland, TX; hoặc gửi thu Printed Name & Title / Nor (Property Owner, Business Owner, I aghiep, Người thuế, VV.) Your Property Address / La	wing information and email the form to Planning@garlandtx.gov; deliver to the Planninstreet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 45900 Por favor Complete la siguiente información y envíe el formulario por correo electrónic; entregar al Departmento de Planificación en 800 Main Street Garland, TX; o enviel de Planning Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lòng dièn dày d'aiu qua email toi Planning@garlandtx.gov; giao cho Phòng Kè hoạch tại 800 Main Street đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. Department of the Planning@garlandtx.gov; giao cho Phòng Kè hoạch tại 800 Main Street đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. Department of the Planning Wall of t
Department at 800 Main S Garland, TX 75406-9002 / P a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giờ biểu m Garland, TX; hoặc gửi thư Az ch De bo Printed Name & Title / Nor (Property Owner, Business Owner, oghiệp, Người thưế VV) Your Property Address / La Gay Land	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900: For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department de Planlificación en 800 Main Street Garland, TX; o enviel de Albaning Department, P.O. Box 469002 Garland, TX 75406-9002/ Vul iong dièn day d'nau qua email toi Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phó Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. De mbre Impreso y Titulo / Tên in và Tiêu đề Tanant. etc.) / (Dunilo de la propieded. Dueño de la empresa, Inquilino, etc.) / (Chù sở hữu bắt động sản. Chù doanh
Department at 800 Main S Garland, TX 75406-9002. F a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và gừi biểu m Garland, TX; hoặc gửi thu Printed Name & Title / Nor (Property Owner, Business Owner, I aghiep, Người thuế, VV.) Your Property Address / La	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900: For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department de Planlificación en 800 Main Street Garland, TX; o enviel de Albaning Department, P.O. Box 469002 Garland, TX 75406-9002/ Vul iong dièn day d'nau qua email toi Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phó Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. De mbre Impreso y Titulo / Tên in và Tiêu đề Tanant. etc.) / (Dunilo de la propieded. Dueño de la empresa, Inquilino, etc.) / (Chù sở hữu bắt động sản. Chù doanh
Department at 800 Main S Garland, TX 75406-9002 / a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giời biểu m Garland, TX; hoặc giời thư Az L De bo Printed Name & Title / Nor (Property Owner, Business Owner, oghiệp, Người thuế v v) Your Property Address / La City, State / Estado de la C	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900: For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department de Planlificación en 800 Main Street Garland, TX; o enviel de Albaning Department, P.O. Box 469002 Garland, TX 75406-9002/ Vul iong dièn day d'nau qua email toi Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dén Thành phó Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. De mbre Impreso y Titulo / Tên in và Tiêu đề Tanant. etc.) / (Dunilo de la propieded. Dueño de la empresa, Inquilino, etc.) / (Chù sở hữu bắt động sản. Chù doanh
Department at 800 Main S Garland, TX 75406-9002 / a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giời biểu m Garland, TX; hoặc giời thư Az L De bo Printed Name & Title / Nor (Property Owner, Business Owner, oghiệp, Người thưề v v) Your Property Address / La City, State / Estado de la C	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900? For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department de Planlificación en 800 Main Street Garland, TX; o enviel de Albaning Department, P.O. Box 469002 Garland, TX 75406-9002/ Vul iòng dièn dây d'aiu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street dên Thành phó Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. Decembre Impreso y Título / Tên in và Tiêu đề Tenant: etc.) / (Dunilo de la propieded, Dueño de la empresa, Inquiline, etc.) / (Chù số hữu bắt động sản, Chủ doanh COUNT adirección de su propiedad / địa chỉ tài sản
Department at 800 Main S Garland, TX 75406-9002 / a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và giời biểu m Garland, TX; hoặc giời thư Az L De bo Printed Name & Title / Nor (Property Owner, Business Owner, oghiệp, Người thuế v v) Your Property Address / La City, State / Estado de la C	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900 Por favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department de Planificación en 800 Main Street Garland, TX; o enviel de Planificación de 80002 Garland, TX 75406-9002. Value email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street den Thành phó Garland, Sò Ké hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. De mbre Impreso y Título / Tên in và Tiêu đề Tanant etc.) / (Dunito de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chù só hữu bắt động sản, Chù doanh COUNT dirección de su propiedad / địa chỉ tài sản Mà B u Ohinh
Department at 800 Main S Garland, TX 75406-9002. F a Planning@garlandtx.gov por correo a City of Garlan thöng tin sau và girì biểu m Garland, TX; hoặc gửi thu Azeb Debo Printed Name & Title / Nor (Property Owner, Business Owner, J orghele, Người thựế, VV) Your Property Address / La City, State / Estado de la C TSOUI Zip Code / Código postal /	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Breet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900 For favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department, P.O. Box 469002 Garland, TX 75406-9002. Vui lóng dièn dây diáu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street gián Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. De mbre Impreso y Titulo / Tên in và Tiêu đề renant, etc.) / (Dunho de la propiedad, Dueho de la empresa, Inquilino, etc.) / (Chù số hữu bắt động sân, Chủ doanh dirección de su propiedad / địa chỉ tài sân
Department at 800 Main Sarland, TX 75406-9002. Fa a Planning@garlandtx.gov por correo a City of Garlant thöng tin sau và giời biểu m Garland, TX; hoặc gửi thư Azel Debo Printed Name & Title / Nor (Property Owner, Business Owner, Toghiele, Niguroi thuế VV.) Your Property Address / La City, State / Estado de la C	wing information and email the form to Planning@garlandtx.gov; deliver to the Planning Breet Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 46900 Por favor Complete la siguiente información y envie el formulario por correo electrónic; entregar al Department, P.O. Box 469002 Garland, TX 75406-9002. Vul ióng dièn dây diáu qua email tói Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Street đến Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002. Do mbre Impreso y Titulo / Tên in và Tiêu đề renant, etc.) / (Chủ số hữu bắt động sân, Chủ doanh COUNT) dirección de su propiedad, Dueho de la empresa, Inquilino, etc.) / (Chủ số hữu bắt động sân, Chủ doanh COUNT) dirección de su propiedad / địa chỉ tài sân

Yahoo Mail: Search, Organize, Conquer

CAUTION: This email is from an external source. DO NOT click links or open attachments without verifying the sender. Never enter **USERNAME**, **PASSWORD or SENSITIVE INFORMATION** on linked pages from this email. If you are unsure about the message, please contact the **Help Desk at x7240** for assistance.

Comment Form Case Z 25-08

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / Marque uno a continuación / Vui lòng kiểm tra một bên dưới

For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov ; deliver to the Planning Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Por favor Complete la siguiente información y envíe el formulario por correo electrónico a Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o envíelo por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002./ Vui lòng điền đầy đủ hông tin sau và gửi biểu mẫu qua email tới Planning@garlandtx.gov; giao cho Phòng Kế hoạch tại 800 Main Street Garland, TX; hoặc gửi thư đến Thành phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
Angel Sanchez and Mayra Sanchez
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad, Dueño de la empresa, Inquilino, etc.) / (Chủ sở hữu bất động sản, Chủ doanh nghiệp, Người thuế, v v.)
1529 Clear Point Dr Gartand
Your Property Address / La dirección de su propiedad / địa chỉ tài sản
Garland, Texas
City, State / Estado de la Ciudad / Thành bang
75041
Zip Code / Código postal / Mã B u O hính
Ang Survey Survey 05/05/2025 Signature / Firma / Ch ü ký Date / Fecha / Ngày
Signature / Firma / Ch ữ ký Date / Fecha / Ngày
Providing email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chỉ email và số điện thoại là tùy chọn.)

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s).

Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas.

Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất

We oppose to the zoni	ng change	that will
affect our property we	believe this	change
(ald damage our property		
	¥	

Comment Form Case Z 25-08

Z 25-08 City of Garland. El solicitante propo

consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el tado norte de 1-635, a ambos tados de ta Avenida S. Garland. (Distrito 5).
Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doạnh (US). Khi đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).
Please Check One Below / Marque uno a continuación / Vui lóng kiếm tra một bén đượi
For / A Favor / Đúng
Against / En Contra / Không
Please complete the following information and email the form to Planning@garlandtx.gov; deliver to the Plan Department at 800 Main Street Garland, TX; or mail to City of Garland, Planning Department, P.O. Box 48 Garland, TX 75406-9002 / Por favor Complete la siguiente información y envie el formulario por correo electrica Planning@garlandtx.gov; entregar al Departamento de Planificación en 800 Main Street Garland, TX; o er por correo a City of Garland, Planning Department, P.O. Box 469002 Garland, TX 75406-9002 / Vul long dien di thông tin sau và giữi biểu mẫu qua email tôi Planning@garlandtx.gov; giao cho Phòng Ké hoạch tại 800 Main Garland, TX; hoặc gửi thư đến Thành phố Garland, Số Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
EMILY BAKER - OWNER
Printed Name & Title / Nombre Impreso y Título / Tên in và Tiêu đề
(Property Owner, Business Owner, Tenant, etc.) / (Dueño de la propiedad. Dueño de la empresa, Inquieno, etc.) / (Chá só hou bát dong são, Chá só nghiệp, Người thuế, v.v.)
1805 CLEAR POINT DR.
Your Property Address / La dirección de su propiedad / dia chỉ tài sản
GARLAND TX
City, State / Estado de la Ciudad / Thành bang
7504)
In Code / Código postal / Má B u Ohinh Inily Baker 5/6/25
C. L. Contraction of the Contrac
Signature / Firma / Qh ū ký roviding email address and phone number is optional. / La dirección de correo electrónico y el número de teléfono son opcionale
nail và số điện thoại là tùy chọn.)

City

Comment Form Case Z 25-08

Z 25-08 City of Gartand. The applicant proposes a zoning change from multiple zoning districts to acres of properties, generally located on the north side of I-635, on both sides of 5 Gartand Avenue.

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la 1-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland, Người nóp đơn để xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Đấn cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đại, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quân 5).

Please Check One Below /	Marque uno a continuación / Vui long kiểm tra một bên dưới
	For / A Favor / Đúng
	Against / En Contra / Không
partment at 800 Main Street Garland, TX 75406-9002./ Por favor lanning@garlandtx.gov; entreg correo a City of Garland, Plann	rmation and email the form to Planning riand , TX; or mail to City of Garland, Planning Department, P.O. Box 469902. Complete la siguiente información y envie el formulario por correo electrónico ar al Departamento de Planificación en 800 Main Street Garland, TX; o envieio ing Department, P.O. Box 469902 Garland, TX 75406-9002. Vui long dién day du email toi Planning@garlandtx.gov; glao cho Phong Ké hoạch tại 800 Main Street inh phố Garland, Sở Kế hoạch, P.O. Hộp 469002 Garland, TX 75406-9002.
wanty Owner, Business Owner, Tenant, et	SO O Livera spreso y Titulo / Tên in và Tiêu dê c) / (Duelo de la propiedat Duelo de la expresa, inquiero, el: 1/50% ab hou bât dong sân. Chủ duelo.)
20 9 Holm dr G ur Property Address / La direct	Garland Tx 450 (1) sion de su propiedad / dia chil tal sion
orland Texa y, State / Estado de la Ciudad	5
25041 p Code / Código postal / Ma B	A Property of the second
N Ocac	
	Date / Fecha / Ngây Det la optional / La dirección de currec electrónico y el número de teléfono son opcionales. / D

Pi Di a pth Gi

Comment Form Case Z 25-08

Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning district. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5).

Z 25-08 City of Garland. El solicitante propone un cambio de zonificación de distritos de zonificación múltiple a distrito de zonificación Urbana Residencial (UR) y Urbana Comercial (UB). El terreno consta de aproximadamente 317 acres de propiedades, generalmente ubicadas en el lado norte de la I-635, a ambos lados de la Avenida S. Garland. (Distrito 5).

Z 25-08 City of Garland. Người nộp đơn đề xuất thay đổi quy hoạch từ nhiều khu vực quy hoạch thành khu vực quy hoạch Đô thị Dân cư (UR) và Khu vực quy hoạch Đô thị Kinh doanh (UB). Khu đất bao gồm khoảng 317 mẫu Anh đất đai, thường nằm ở phía bắc của I-635, ở cả hai bên của S Garland Avenue. (Quận 5).

Please Check One Below / M	arque uno a continuación / Vui lòng	kiểm tra một bên dưới
	For / A Favor / Đúng	
	Against / En Contra / Không	ta y
Garland, TX 75406-9002./ Por favor Co a Planning@garlandtx.gov; entregar por correo a City of Garland, Planning thông tin sau và gửi biểu mẫu qua em	ation and email the form to Planning@gaind, TX; or mail to City of Garland, Plantomplete la siguiente información y envie e al Departamento de Planificación en 800 pepartment, P.O. Box 469002 Garland, Tail to Planning@garlandtx.gov; giao cho phó Garland, Sò Ké hoạch, P.O. Hộp 4690	ning Department, P.O. Box 469002 el formulario por correo electrónico Main Street Garland, TX; o envielo X 75406-9002./ Vui lòng điền đầy đủ Phòng Kế boach tại 800 Main Street
Kristin Wolfkill	Property Owner	
Printed Name & Title / Nombre Impre		
(Property Owner, Business Owner, Tenant, etc.) / (nghiệp, Người thuế, v.v.)	Dueño de la propiedad. Dueño de la empresa, Inquilino, el	c.) / (Chủ sở hữu bắt động sắn, Chú doanh
1710 marfield A	<i>x</i> € .	
Your Property Address / La dirección	de su propiedad / địa chỉ tài sản	1
Corland TX		
City, State / Estado de la Ciudad / Tha	anh bang	
75041		
Zip Code / Código postal / Mā B u Of	nính	
Must will	S-2	-2025
Signature / Firma / Ch ür ký	Date / F	echa / Ngày

(Providing email address and phone number is optional / La dirección de correo electrónico y el número de teléfono son opcionales. / Địa chí

email và số điện thoại là tùy chọn.)

Comment Form Continued – Case Z 25-08

The statements below reflect my (our) opinion regarding the proposed request(s). Las declaraciones a continuación reflejan mi (nuestra) opinión con respecto a las solicitudes propuestas. Các tuyên bố dưới đây phản ánh quan điểm của tôi (chúng tôi) về (các) yêu cầu được đề xuất I strongly oppose the proposed rezoning to UR+UB, as it poses signaficant risks to our community's charac making it more difficult for reside Additionally, the change in zoning con bushesses. If the commenty perceives this change as negative, it can led to live propos

Morales, Elisa

From:

Nur, Nabila

Sent:

Thursday, May 8, 2025 9:38 AM

To:

Morales, Elisa

Subject:

FW: Rezoning Case Z25-08

Please file.

Nabila Nur, AICP

Director of Planning and Development

800 Main Street | Garland, Texas 75040

phone: 972.205.2449

nnur@garlandtx.gov | GarlandTx.gov



From: David Minnigan <dwm@thegwydirpartnership.com>

Sent: Wednesday, May 7, 2025 3:13 PM **To:** Nur, Nabila <NNur@garlandtx.gov>

Subject: Rezoning Case Z25-08

4771 SATURN

You don't often get email from dwm@thegwydirpartnership.com. Learn why this is important

I represent HG Lipscomb Realty, and we own the Wells Fargo Bank Property in the area of rezoning for case Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning districts. The site consists of approximately 317 acres of properties.

WE ARE AGAINST THIS REZONING!

Please call me if you have questions.

Thanks, David

The Gwydir Partnership David W. Minnigan, AIA, IIDA LEED* Accredited Professional

6500 Arrowhead Springs Court Brentwood, TN 37027

615-477-3051

dwm@thegwydirpartnership.com

Morales, Elisa

From:

Nur, Nabila

Sent:

Thursday, May 8, 2025 9:45 AM

To:

Morales, Elisa

Subject:

FW: 1720 Northwest Hwy

Please file.

Nabila Nur, AICP

Director of Planning and Development

800 Main Street | Garland, Texas 75040

phone: 972.205.2449

nnur@garlandtx.gov | GarlandTx.gov



From: Ben Siegel <ben.siegel@bleeckerpartners.com>

Sent: Thursday, May 8, 2025 8:01 AM
To: Nur, Nabila <NNur@garlandtx.gov>

Cc: Ethan Silverman <ethan.silverman@bleeckerpartners.com>

Subject: 1720 Northwest Hwy

You don't often get email from ben.siegel@bleeckerpartners.com. Learn why this is important

Good morning Nabila,

We are supportive of your proposed zoning change for pro business and pro development zoning in Garland. The nearing of I-635's construction gives this location and unique opportunity to flourish and we support Garland's initiative to enhance this area!

Ben

Ben Siegel

ben.siegel@bleeckerpartners.com

T: (972) 534-3106 | M: (214) 460-7833

4245 North Central Expressway, Ste. 225, Dallas, TX 75205

CONFIDENTIALITY NOTICE: This e-mail communication is intended only for the addressee(s) named above and any others who have been specifically authorized to receive it and may contain information that is privileged, confidential or otherwise protected from disclosure. If you are not the intended recipient of prohibited. Please notify us immediately by returning it to the sender and permanently delete this message and any attachments from your system. This email or any part to any other person.

CAUTION: This email is from an external source. DO NOT click links or open attachments without verifying the sender. Never enter **USERNAME**, **PASSWORD** or **SENSITIVE INFORMATION** on linked pages from this email. If you are unsure about the message, please contact the **Help Desk at x7240** for assistance.

Zoning Response Case Comments

ase Number	PC Hearing Date	CC Hearing Date	Planner Name		
25-08	April 28, 2025	May 20, 2025	Nabila Nur		
	Z 25-08 City of Garland. The applicant proposes a zoning change from multiple zoning districts to Urban Residential (UR) and Urban Business (UB) zoning districts. The site consists of approximately 317 acres of properties, generally located on the north side of I-635, on both sides of S Garland Avenue. (District 5) >d>>b> >dre information about this case can be found in this document.				
CarMax Auto Superstores, Inc.	Against				
4/28/2025	12800 Tuckahoe Cre	ek			
1:14:52 PM	Pkwy				
	Richmond				
	VA	Outside the Notifi	cation Area		
	United States				
	23238				
Carllian	Ansinat	٠			
CarMax	Against				
4/28/2025	12715 Lyndon B John	nson			
1:12:42 PM	Fwy				
	Garland				
	Texas				
	United States				
	75041				
RaceTrac	Against				
4/27/2025	2018 Northwest High	way trutigliano@racet	rac.com		
11:11:24 PM	0.1.1				
	Garland				
	Texas				
	United States				
	75041				
	RaceTrac has operat	ed in Garland since 2012, and	d currently have seven		

Case Number	PC Hearing Date	CC Hearing Date	Planner Name		
Z 25-08	April 28, 2025	May 20, 2025	Nabila Nur		
	business-friendly en change would preve preferences and ind event, would prever disappointed that we that we were not giv	ange. We located in Garland be avironment and strong citizen be ant us from reinvesting in these lustry trends change over time, at us from rebuilding altogether. It was the were only recently made awaren an opportunity collaborate was property owner rights and meet this case.	ase. The proposed zoning stores as customer and in a catastrophic. We are very re of this proposal and with the City on a solution		
RaceTrac	Against				
4/27/2025 11:09:44 PM	3401 S. Garland	trutigliano@racetr	ac.com		
	Garland				
	Texas				
	United States				
	75041	75041			
	stores in the city; two proposed zoning cha business-friendly en change would preve preferences and ind event, would preven disappointed that we that we were not give	ated in Garland since 2012, and of which would be detrimental ange. We located in Garland by vironment and strong citizen bant us from reinvesting in these ustry trends change over time, to us from rebuilding altogether. It was to an opportunity collaborate was property owner rights and methis case.	ally impacted by this recause of its recause of its rese. The proposed zoning stores as customer and in a catastrophic research we are very refer this proposal and with the City on a solution		
RaceTrac	Against				
4/27/2025 11:09:41 PM	3401 S. Garland	trutigliano@racetra	ac.com		
	Garland				
	Texas				
	United States				
	75041				
	stores in the city; two proposed zoning cha business-friendly env change would prever preferences and indu event, would prevent	ted in Garland since 2012, and of which would be detrimental ange. We located in Garland be vironment and strong citizen bant us from reinvesting in these sustry trends change over time, as us from rebuilding altogether, were only recently made aware.	lly impacted by this ecause of its ise. The proposed zoning stores as customer and in a catastrophic We are very		

Case Number	PC Hearing Date	CC Hearing Date	Planner Name
25-08	April 28, 2025	May 20, 2025	Nabila Nur
	that we were not given ar that respects existing pro We strongly oppose this	opportunity collaborate with perty owner rights and meet case.	n the City on a solution s your goals for area.
CarMax	Against		
4/24/2025 6:03:21 PM	12715 Lyndon B Johnson Fwy		
	Garland		
	Texas		
	United States		
	75041		
Realty Income	Against		
Corporation 4/23/2025	10715 Lyndon D. Johnson	ilonoo@rooltuinga	
8:54:19 PM	12715 Lyndon B Johnson Fwy	jlopes@realtyincome	e.com
	Garland	8582845369	
	Texas		
	United States		
	75041		
Realty Income Corporation	Against		
4/23/2025 8:53:43 PM	12715 Lyndon B Johnson Fwy	jlopes@realtyincome	e.com
	Garland	8582845369	
	Texas		
	United States		
	75041		
Realty Income	Against		
Corporation			
4/23/2025	12715 Lyndon B Johnson	jlopes@realtyincome	.com
8:51:55 PM	Fwy Garland	8582845369	
		0002040008	
	Texas		

Case Number	PC Hearing Date	CC Hearing Date	Planner Name
25-08	April 28, 2025	May 20, 2025	Nabila Nur
	United States		
	75041		
	73041		
Realty Income Corporation	Against		
4/23/2025	12715 Lyndon B Johnson	jlopes@realtyincome.	com
8:50:59 PM	Fwy	jiopoo@roakyiiloome.com	
	Garland	8582845369	
	Texas		
	United States		
	75041		
Realty Income Corporation	Against		
4/23/2025	12715 Lyndon B Johnson	jlopes@realtyincome.d	com
8:50:21 PM	Fwy	0500045000	
	Garland	8582845369	
	Texas		
	United States		
	75041		
Realty Income Corporation	Against		
4/23/2025 8:49:33 PM	12715 Lyndon B Johnson	jlopes@realtyincome.c	com
0.49.33 PIVI	Fwy Garland	8582845260	
	Texas	8582845369	
	United States		
	75041		
Realty Income	Against		
Corporation 4/23/2025	12715 Lyndon B Johnson	jlopes@realtyincome.c	om
8:48:23 PM	Fwy	Jiopes@realtyllicome.c	OIII
	Garland	8582845369	

Case Number	PC Hearing Date	CC Hearing Date	Planner Name
25-08	April 28, 2025	May 20, 2025	Nabila Nur
	Texas		
	United States		
	75041		
	75041		
	The proposed zoning changes would render our tenant non-conforming and they have made clear to us that this is not tenable. The proposed change wiresult in us losing the right to continue using our property for the current use We are being forced into a non-conforming status. This is not acceptable and we do not support the proposed zoning change.		
Khoa Nguyen	For		
4/19/2025 1:33:10 AM	2406 Mapleridge Dr	soohuynk@gmail.d	com
	Garland	a	
	Texas		
	United States	Outside the N	lotification Area
	75044		
	For		
Khoa Nguyen	For		
4/19/2025 1:32:43 AM	2406 Mapleridge Dr	sooh <mark>uynk@gmail.</mark> c	com
	Garland		
	Texas		
	United States	Outside the N	lotification Area
	75044		ouncation Area
	For		
Khoa Nguyen	For		
4/19/2025 1:32:38 AM	2406 Mapleridge Dr		
	Garland		
	Texas	Outoids the North	
	United States	Outside the Notifica	tion Area

	PC Hearing Date	CC Hearing Date	Planner Name
25-08	April 28, 2025	May 20, 2025	Nabila Nur
Khoa Nguyen	For		
4/19/2025 1:32:22 AM	2406 Mapleridge Dr		
	Garland	Outside the Notification Area	
	Texas		
	United States		
	75044		
Khoa Nguyen	For		
4/19/2025 1:32:18 AM	2406 Mapleridge Dr		
	Garland		
	Texas	Outside the Notific	ation Area
	United States		
	75044		
Thomas Martines	For		
Martinez 4/15/2025	3910 Roanoke		
12:15:16 AM			
12:15:16 AM	Garland		
12:15:16 AM	Garland Texas	Outside the Notific	cation Area
12:15:16 AM		Outside the Notific	cation Area
12:15:16 AM	Texas	Outside the Notific	cation Area
12:15:16 AM	Texas United States	Outside the Notific	cation Area
	Texas United States <null></null>	Outside the Notific	cation Area
Thomas Martinez	Texas United States <null> For</null>	Outside the Notific	cation Area
Thomas Martinez	Texas United States <null> For</null>		
Thomas Martinez 1/15:15 AM	Texas United States <null> For For 3910 Roanoke</null>	Outside the Notifica	
Fhomas Martinez 1/15/2025	Texas United States <null> For For 3910 Roanoke Garland</null>		

Case Number	PC Hearing Date	CC Hearing Date	Planner Name
Z 25-08	April 28, 2025	May 20, 2025	Nabila Nur
			The state of the s
Sissy Coco	For		
4/8/2025 2:45:06 PM	11708 Lanewood Cir		
	Garland		
	Texas	Outolds the Nett	
	United States	Outside the Notification Area	
	<null></null>	6	
	Stulle		
Sissy Coco	For		
4/8/2025	11708 Lanewood Cir		
2:45:04 PM			
	Garland		
	Texas		
	United States	Outside the No	tincation Area
	<null></null>		
Dilan Patel	Against		
4/7/2025	1901 Pendleton Dr	mioratale ade ad	
1:58:14 PM	13011 endleton Di	microtelgarland@ya	ahoo.com
	Garland	2147141065	
	Texas		
	United States		
	United States 75041		
Gayle Owens	75041		
4/5/2025	75041	Gayle.Owens@iclou	ud.com
4/5/2025	For 4018 Keele Drive		ud.com
4/5/2025	For 4018 Keele Drive Garland	Gayle.Owens@iclou 214-729-1861	ud.com
4/5/2025	For 4018 Keele Drive Garland Texas	214-729-1861	
Gayle Owens 4/5/2025 12:29:05 PM	For 4018 Keele Drive Garland	214-729-1861	ud.com otification Area

Case Number	PC Hearing Date	CC Hearing Date	Planner Name	
Z 25-08	April 28, 2025	May 20, 2025	Nabila Nur	
	This area needs urba	n residences and businesses.		
Gayle Owens	For			
4/5/2025 12:29:03 PM	4018 Keele Drive	Gayle.Owens@icloud.com		
	Garland	214-729-1861		
	Texas	Outside the Notification Area		
	United States			
	75041			
	This area needs urban	residences and businesses.		
Brad Parker	Against			
4/4/2025 1:37:11 PM	3710 S Shiloh Rd	brad.parker@parkerplumbing.com		
	Garland	2145352128		
	Texas			
	United States			
	75041			
	This zoning change will if we are forced to reloc	negatively impact our busines	ss and how we operate ange.	
Khoa Nguyen	For			
4/4/2025 5:07:14 AM	2406 Mapleridge Dr			
	Garland			
	Texas	Outside the Notifical	tion Area	
	United States	Outside the Hothica		
	75044			