


FINAL PLAT
OF
"STONEHAVEN PHASE 3, PARCEL 11"
A PLANNED AREA DEVELOPMENT
A PORTION OF THE NORTHEAST QUARTER OF SECTION 15, TOWNSHIP 2
NORTH, RANGE 1 EAST OF THE GILA AND SALT RIVER BASE AND MERIDIAN,
MARICOPA COUNTY, ARIZONA



VICINITY MAP
N.T.S.

DEDICATION

STATE OF ARIZONA)
) SS.
COUNTY OF MARICOPA)

KNOW ALL MEN BY THESE PRESENTS:

THAT TAYLOR MORRISON/ARIZONA, INC., AN ARIZONA CORPORATION, AS OWNER, DOES HEREBY PUBLISH THIS FINAL PLAT OF "STONEHAVEN PHASE 3, PARCEL 11", SITUATED IN A PORTION OF THE NORTHEAST QUARTER OF SECTION 15, TOWNSHIP 2 NORTH, RANGE 1 EAST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, AS SHOWN AND PLATTED HEREON AND DOES HEREBY PUBLISH THIS PLAT AS AND FOR THE PLAT OF SAID "STONEHAVEN PHASE 3, PARCEL 11" AND HEREBY DECLARES THAT SAID PLAT SETS FORTH THE LOCATION AND GIVES THE DIMENSIONS OF THE LOTS, TRACTS, EASEMENTS, AND STREETS CONSTITUTING SAME, AND THAT EACH LOT, TRACT, AND STREET SHALL BE KNOWN BY THE NUMBER, LETTER OR NAME GIVEN TO EACH RESPECTIVELY ON SAID PLAT AND HEREBY DEDICATES TO THE CITY OF GLENDALE FOR USE, AS SUCH, THE EASEMENTS AS SHOWN ON SAID PLAT AND INCLUDED IN THE ABOVE DESCRIBED PREMISES. EASEMENTS ARE DEDICATED FOR THE PURPOSES SHOWN HEREON.

TRACT 11G SHALL BE A PRIVATE STREET. OWNER HEREBY DEDICATES, GRANTS AND CONVEYS TO THE PUBLIC AN EASEMENT FOR INGRESS AND EGRESS, FOR REFUSE COLLECTION, FOR EMERGENCY VEHICLES AND/OR SERVICE TYPE VEHICLES OVER AND ACROSS TRACT 11G.

WATER AND SEWER EASEMENTS ARE HEREBY CONVEYED TO THE CITY OF GLENDALE IN, OVER, AND UNDER TRACT 11G FOR THE INSTALLATION, OPERATION, REPAIR AND MAINTENANCE, REMOVAL AND REPLACEMENT OF WATER AND SEWER LINES AND ASSOCIATED APPURTENANCES.

TRACTS ARE HEREBY DEDICATED TO A FUTURE HOMEOWNER'S ASSOCIATION AND ARE DECLARED FOR THE SPECIFIC USES IDENTIFIED ON THE TRACT SUMMARY TABLE PROVIDED HEREON ON PAGE 2 OF THIS FINAL PLAT AND SUBJECT TO THE EASEMENTS DEDICATED TO THE CITY OF GLENDALE.

OWNER HEREBY GRANTS TO THE PUBLIC A PERPETUAL NON-EXCLUSIVE EASEMENT IN, UPON, OVER, UNDER, THROUGH, AND ACROSS THE AREAS DESIGNATED AS PUBLIC UTILITY EASEMENTS AS SHOWN ON THE PLAT FOR THE PURPOSE OF ACCESSING, INSTALLING, CONSTRUCTING, MAINTAINING, REPAIRING, REPLACING AND UTILIZING PUBLIC UTILITIES.

IN WITNESS WHEREOF, TAYLOR MORRISON/ARIZONA, INC. AN ARIZONA CORPORATION, AS OWNER, HAS HEREUNTO CAUSED ITS CORPORATE NAME TO BE AFFIXED AND THE SAME TO BE ATTESTED BY THE SIGNATURE OF THE UNDERSIGNED, DULY AUTHORIZED OFFICER THIS _____ DAY OF _____, 20__.

TAYLOR MORRISON/ARIZONA, INC., AN ARIZONA CORPORATION

ACKNOWLEDGEMENT

STATE OF ARIZONA)
) SS.
COUNTY OF MARICOPA)

ON THIS _____ DAY OF _____, 20__ BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, STEVE HAHN PERSONALLY APPEARED, WHO ACKNOWLEDGE HERSELF TO BE THE VICE PRESIDENT OF TAYLOR MORRISON/ARIZONA, INC. AN ARIZONA CORPORATION AND BEING AUTHORIZED TO DO SO ON BEHALF OF SAID ENTITY, EXECUTED THIS INSTRUMENT FOR THE PURPOSES HEREIN CONTAINED.

IN WITNESS WHEREOF:

I HEREUNTO SET MY HAND AND OFFICIAL SEAL

NOTARY PUBLIC
MY COMMISSION EXPIRES _____

PRELIMINARY PLAT CONFORMANCE

I HEREBY CERTIFY THAT THIS PLAT HAS BEEN PREPARED IN GENERAL CONFORMANCE TO THE PRELIMINARY PLAT OF THIS SUBDIVISION APPROVED BY THE CITY OF GLENDALE PLANNING AND ZONING COMMISSION.

BY: _____ DATE _____
PLANNING MANAGER
CITY OF GLENDALE

IMPROVEMENT ASSURANCES

I HEREBY ACKNOWLEDGE THAT ENGINEERING PLANS FOR PUBLIC IMPROVEMENTS ASSOCIATED WITH THIS SUBDIVISION HAVE BEEN APPROVED AND THAT ALL NECESSARY ASSURANCES FOR THESE IMPROVEMENTS HAVE BEEN RECEIVED IN A FORM ACCEPTABLE TO THE CITY.

BY: _____ DATE _____
CITY ENGINEER OR DESIGNATE

APPROVALS

APPROVED BY THE CITY COUNCIL OF THE CITY OF GLENDALE, ARIZONA.

THIS _____ DAY OF _____, 20__

MAYOR DATE _____

ATTEST CITY CLERK DATE _____

STONEHAVEN COMMUNITY ASSOCIATION RATIFICATION AND CONSENT

THE UNDERSIGNED HEREBY RATIFIES AND CONSENTS TO THIS PLAT, INCLUDING ITS MAINTENANCE OBLIGATIONS AS SET FORTH HEREIN.

STONEHAVEN COMMUNITY ASSOCIATION, AN ARIZONA NON-PROFIT CORPORATION

BY: _____

BY: LAUREN VAN TUSSENBROEK

ITS: PRESIDENT

STONEHAVEN COMMUNITY ASSOCIATION RATIFICATION ACKNOWLEDGEMENT

STATE OF ARIZONA)
) SS.
COUNTY OF MARICOPA)

ON THIS _____ DAY OF _____, 20__ BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, LAUREN VAN TUSSENBROEK PERSONALLY APPEARED, WHO ACKNOWLEDGED HERSELF TO BE PRESIDENT OF THE STONEHAVEN COMMUNITY ASSOCIATION, AN ARIZONA NON-PROFIT CORPORATION AND BEING AUTHORIZED TO DO SO ON BEHALF OF SAID ENTITY, EXECUTED THIS INSTRUMENT FOR THE PURPOSES HEREIN CONTAINED.

IN WITNESS WHEREOF:
I HEREUNTO SET MY HAND AND OFFICIAL SEAL

NOTARY PUBLIC
MY COMMISSION EXPIRES _____

BASIS OF BEARINGS

N 00°00'41" W ALONG THE MONUMENT LINE OF 91ST AVENUE AS MEASURED BETWEEN MONUMENTS NUMBERED 1 AND 2 SHOWN HEREON AND DESCRIBED UNDER MONUMENT NOTES.

NOTES

- THIS SUBDIVISION IS LOCATED WITHIN THE CITY OF GLENDALE WATER SERVICE AREA WHICH HAS BEEN DESIGNATED AS HAVING AN ASSURED WATER SUPPLY UNDER A.R.S. SECTION 45-576.
- ALL NEW UTILITIES AND ALL EXISTING UTILITIES, EXCEPT ELECTRICAL TRANSMISSION LINES CARRYING 69 KV OR MORE, WITHIN OR CONTIGUOUS TO THIS SITE, SHALL BE PLACED UNDERGROUND.
- EXCEPT FOR CONSTRUCTION AND IMPROVEMENTS BY GOVERNMENTAL ENTITIES AND CERTIFIED PUBLIC UTILITIES, CONSTRUCTION AND IMPROVEMENTS WITHIN EASEMENTS SHALL BE LIMITED TO ONLY THE FOLLOWING:
 - WOOD, WIRE, OR REMOVABLE SECTION TYPE FENCING.
 - CONSTRUCTION, STRUCTURES OR BUILDINGS EXPRESSLY APPROVED IN WRITING BY ALL PUBLIC UTILITIES AND THE CITY OF GLENDALE WHICH USE OR SHALL USE THE UTILITY EASEMENT.
- ALL LANDSCAPE TRACTS DEDICATED BY THIS PLAT SHALL BE MAINTAINED BY THE DEVELOPMENT HOMEOWNER'S ASSOCIATION.
- FIRE DEPARTMENT ACCESS AND WATER SUPPLY REQUIREMENTS SHALL BE IN PLACE PRIOR TO THE START OF VERTICAL CONSTRUCTION.
- ALL DRAINAGE STRUCTURES LOCATED IN TRACTS AND OUTSIDE OF CITY RIGHT-OF-WAY SHALL BE MAINTAINED BY THE DEVELOPMENT HOMEOWNER'S ASSOCIATION.


SURVEYOR'S STATEMENT

I, LANCE C. DICKSON, HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR IN THE STATE OF ARIZONA, THAT THIS MAP CORRECTLY REPRESENTS A BOUNDARY SURVEY MADE UNDER MY SUPERVISION AND THE SURVEY IS TRUE AND COMPLETE AS SHOWN, MEETS THE MINIMUM STANDARDS FOR ARIZONA LAND BOUNDARY SURVEYS, ALL MONUMENTS SHOWN ACTUALLY EXIST AS SHOWN, THEIR POSITIONS ARE CORRECTLY SHOWN AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.



BY: LANCE C. DICKSON, R.L.S. #46643
ARIZONA SURVEYING AND MAPPING
2440 W. MISSION LANE, SUITE 4
PHOENIX, ARIZONA 85021
(602) 246-9919

I, JOHN N. ROGERS, HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR IN THE STATE OF ARIZONA, DO HEREBY DECLARE THAT THE INTERNAL LOT AND TRACT LINES, EASEMENTS, RIGHTS-OF-WAY, AND OTHER CALCULATIONS OTHER THAN PROPERTY BOUNDARY, WERE PROPERLY PREPARED UNDER MY PERSONAL SUPERVISION IN ACCORDANCE WITH THE PLATTING RULES AND REGULATIONS OF THE STATE OF ARIZONA.



BY: JOHN N. ROGERS, R.L.S. #54332
GOODWIN AND MARSHALL, INC.
2705 S. ALMA SCHOOL RD., STE. 2
CHANDLER, ARIZONA 85286
(602) 218-7285

NOTE:
A.R.S. 32-151 STATES THAT THE USE OF THE WORD "CERTIFY" OR "CERTIFICATE" IS AN EXPRESSION OF PROFESSIONAL OPINION REGARDING THE FACTS OF THE SURVEY AND DOES NOT CONSTITUTE A GUARANTEE, EXPRESS OR IMPLIED.

SHEET INDEX

SHEET 1	COVER
SHEET 2	LOT AND TRACT SUMMARY TABLES, TYPICAL LOT DETAIL, KEY MAP, MONUMENT NOTES, AND LEGEND
SHEET 3	TYPICAL PLAN SHEET, LINE AND CURVE TABLES

OWNER/DEVELOPER:

taylor morrison
Homes Inspired by You
4900 North Scottsdale Road #2200
Scottsdale, AZ 85251
(480) 508-7118
Contract: Jonathan Bastianelli

PREPARED BY:

GOODWIN AND MARSHALL
CIVIL ENGINEERS ~ PLANNERS ~ SURVEYORS

2705 S. Alma School Road, Suite 2
Chandler, Arizona 85044
(602) 218-7285

SURVEYED BY:

ASAM
Arizona Surveying & Mapping

Arizona Surveying and Mapping
2440 W. Mission Lane, Suite 4, Phoenix, Arizona 85021
TEL (602) 246-9919 FAX (602) 246-9944 info@asam1.com

SITE SUMMARY TABLE															
PARCEL NO	NUMBER OF LOTS	ACREAGE (GROSS)	APPROXIMATE OPEN SPACE PROVIDED (AC) [9]	PERCENTAGE OF OPEN SPACE PROVIDED (AC)	DENSITY DU/AC (GROSS) [10]	ARTERIAL / COLLECTOR ACREAGE	ACREAGE (NET) [6]	UNBUILDABLE AREA ROADWAY TRACTS EXCLUDING PERIMETER STREETS	ZONING	MINIMUM LOT AREA (SQ. FT.) [1]	TYPICAL LOT SIZE (WIDTH X DEPTH) (FT) [7] [8]	MINIMUM YARD SETBACKS			
												FRONT [2] (FT)	REAR [3] (FT)	SIDE (FT)	MAX ALLOWABLE LOT COVERAGE
11	24	9.270	1.847	19.92%	2.59	0.000	9.270	2.441	SHD-7 PAD	7,000	70 X 120	15	15	5	55%

TRACT SUMMARY TABLE LEGEND

L.S. LANDSCAPE
O.S. OPEN SPACE
D.E. DRAINAGE EASEMENT
PED. ACCESS PEDESTRIAN ACCESS
PUE PUBLIC UTILITY EASEMENT

TRACT SUMMARY TABLE				
TRACT	AREA (SQ. FT.)	AREA (ACRES)	USAGE	MAINTENANCE RESPONSIBILITY
TRACT 11A	12,753	0.293	L.S., D.E., O.S., PED. ACCESS, PUE	H.O.A.
TRACT 11B	1,100	0.025	L.S., O.S., PUE	H.O.A.
TRACT 11C	2,200	0.051	L.S., O.S., PUE	H.O.A.
TRACT 11D	1,100	0.025	L.S., O.S., PUE	H.O.A.
TRACT 11E	6,961	0.160	L.S., O.S., PUE	H.O.A.
TRACT 11F	56,322	1.293	L.S., D.E., O.S., PED. ACCESS, PUE	H.O.A.
TRACT 11G	106,347	2.441	PRIVATE ACCESSWAY, PUBLIC WATER AND SEWER EASEMENTS, D.E., REFUSE COLLECTION EASEMENT, EMERGENCY EQUIPMENT ACCESS EASEMENT FOR SERVICE VEHICLES, PUE	H.O.A.

PAD NOTES:



- [1] THE MINIMUM LOT AREA PERMITTED WITHIN DISTRICT. LOT DEPTH IS A FUNCTION OF MINIMUM AREA AND MINIMUM WIDTH.
- [2] THE MINIMUM SETBACK TO ANY FRONT FACING GARAGE DOOR SHALL BE 18 FEET FROM FACE OF THE GARAGE DOOR TO THE BACK OF PUBLIC SIDEWALK.
- [3] REAR COVERED PATIOS MAY ENCROACH TO WITHIN 15 FEET FROM THE REAR PROPERTY LINE.
- [4] FOR ADDITIONAL INFORMATION REGARDING YARD ENCROACHMENTS, REFER TO THE PROVISIONS OF SECTION 5.4.3. (OF APPROVED PAD)
- [5A] THE MINIMUM SIDE YARD SETBACKS MAY BE REDUCED TO 0' ALONG ONE OF THE TWO SIDE YARD PROPERTY LINES, (SHD-4 ZONING DISTRICT ONLY)
- [5B] THE COMBINED SIDE YARD SETBACKS MAY BE REDUCED TO 5' WHEN THE HOME IS PLACED ON THE OPPOSITE SIDE YARD LOT LINE. (SHD-4 ZONING DISTRICT ONLY)

ADDITIONAL NOTES:


- [6] NET ACREAGE IS THE DIFFERENCE OF GROSS ACREAGE AND COLLECTOR/ARTERIAL ROADWAY ACREAGE.
- [7] LOT WIDTH IS MEASURED AT THE "FRONT GARAGE" FRONT YARD BUILDING SETBACK.
- [8] LOT DEPTH IS TYPICAL AND NOT A MINIMUM. LOT DEPTH MAY BE REDUCED BY UP TO 10 FEET AT KNUCKLES AND CUL-DE-SACS.
- [9] AS ESTIMATED BY THE PRELIMINARY PLAT, HOWEVER THE PERCENTAGES OF OPEN SPACE MAY VARY IN THE FINAL PLAT.
- [10] NUMBER OF RESIDENTIAL UNITS DIVIDED BY THE GROSS AREA.

AREAS

TRACTS 11A - 11E	=	80,435 SQ. FT.	1.847 ACRES
TRACT 11G	=	106,347 SQ. FT.	2.441 ACRES
LOTS	=	217,006 SQ. FT.	4.982 ACRES
GROSS	=	403,788 SQ. FT.	9.270 ACRES



LEGEND	
●	FOUND MONUMENT AS NOTED
•	SET CORNER OF THIS PLAT PER MAG. STD. DTL. 120-1 TYPE "C"
•	SET BRASS CAP FLUSH PER MAG. STD. DTL. 120-1 TYPE "B"
SQ. FT.	SQUARE FEET
R/W	RIGHT-OF-WAY
PUE	PUBLIC UTILITY EASEMENT
S/W	SIDEWALK
LS	LANDSCAPE
OS	OPEN SPACE
DE	DRAINAGE EASEMENT
PED. ACCESS	PEDESTRIAN ACCESS EASEMENT
BSL	BUILDING SETBACK LINE
SHD	STONEHAVEN DISTRICT
B/C	BACK OF CRUB
VNAE	VEHICLE NON-ACCESS EASEMENT
BK	BOOK
PG	PAGE
MCR	MARICOPA COUNTY RECORDS
APN	ASSESSOR PARCEL NUMBER
①	LOCAL & COLLECTOR UNOBSTRUCTED VIEW EASEMENT (30' X 30')
—	PLAT BOUNDARY LINE
—	LOT/TRACT LINE
—	ADJONER LINE
—	SECTION LINE
—	EASEMENT LINE
—	CENTER LINE



UNOBSTRUCTED VIEW EASEMENT (TYP)
N.T.S.

NOTES:

- 1. NO SIGNS, FENCES, WALLS, UTILITY BOXES, STRUCTURES, SHRUBS, HEDGES OR OTHER PLANTS (EXCLUDING TREES OVER 30 INCHES IN HEIGHT) SHALL BE PERMITTED WITHIN THE RESTRICTED AREAS, EXCEPT AS APPROVED BY THE CITY TRANSPORTATION DIRECTOR.
- 2. TREES ARE PERMITTED WITH THE RESTRICTED AREAS, PROVIDED:
 - A. NO LIMBS, LEAVES, NEEDLES OR OTHER FOLIAGE ABOVE 30 INCHES OR BELOW 84 INCHES ARE PERMITTED.
 - B. TREES ARE PLANTED SO AS NOT TO OBSTRUCT 20% OF THE VISIBILITY WHEN COMBINED WITH OTHER OBSTRUCTIONS PRESENT.

LOT AREA TABLE

LOT	AREA (SQ. FT.)	AREA (ACRES)
1	8,400	0.193
2	8,400	0.193
3	8,400	0.193
4	8,388	0.193
5	12,950	0.297
6	10,241	0.235
7	9,174	0.211
8	8,449	0.194
9	8,400	0.193
10	8,400	0.193
11	8,388	0.193
12	8,388	0.193


LOT AREA TABLE

LOT	AREA (SQ. FT.)	AREA (ACRES)
13	8,400	0.193
14	8,400	0.193
15	8,449	0.194
16	9,503	0.218
17	10,591	0.243
18	13,300	0.305
19	8,388	0.193
20	8,400	0.193
21	8,400	0.193
22	8,400	0.193
23	8,400	0.193
24	8,400	0.193

ALL LOTS TO BE RESIDENTIAL USE.

TYPICAL LOT DETAIL NOTES

- 1. FRONT YARD SETBACK IS 15' WITH 18' FROM FACE OF GARAGE DOOR TO BACK OF SIDEWALK SHALL BE PROVIDED FOR FORWARD FACING GARAGES.
- 2. MINIMUM LOT DEPTHS MAY BE DECREASED BY UP TO 10' AT CUL-DE-SACS AND KNUCKLES AS LONG AS MINIMUM LOT AREAS AND SETBACKS ARE ADHERED TO.
- 3. REAR LOT LINE IS DEFINED AS THE LOT LINE MOST NEARLY OPPOSITE TO THE FRONT PROPERTY LINE. IN THE EVENT THAT THE FRONT PROPERTY LINE IS A CURVED LINE, THEN THE REAR PROPERTY LINE SHALL BE THE LOT LINE THAT IS CONSISTENT WITH REAR LOT LINES ON ADJACENT OR NEARBY LOTS.
- 4. A MAXIMUM OF ONE LOCATION WITHIN ANY BLOCK LENGTH MAY HAVE A MINIMUM 10' DISTANCE BETWEEN BUILDINGS. THE SPECIFIC LOCATION OF THE 10' BUILDING SEPARATION WILL BE DETERMINED AT THE TIME OF BUILDING PERMIT APPROVAL, SUBJECT TO THE ADMINISTRATIVE APPROVAL BY THE PLANNING DIRECTOR OR THEIR DESIGNEE.
- 5. MAXIMUM ALLOWABLE LOT COVERAGE 55%
- 6. REAR COVERED PATIOS MAY ENCROACH TO WITHIN 15 FEET FROM THE REAR PROPERTY LINE.





70' x 120' TYPICAL LOT DETAIL
N.T.S.

MONUMENT NOTES


ALL MONUMENTATION SHOWN HEREON WAS ACCEPTED UNLESS OTHERWISE NOTED.

- 1 MARICOPA COUNTY HIGHWAY DEPARTMENT BRASS CAP IN HANDHOLE FOR THE SOUTHWEST CORNER OF SECTION 15, T2N, R1E
- 2 MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION BRASS CAP IN HANDHOLE FOR THE WEST QUARTER CORNER OF SECTION 15, T2N, R1E
- 3 PK NAIL WITH STADDLERS FOR THE NORTHWEST CORNER OF SECTION 15, T2N, R1E
- 4 CALCULATED POSITION OF NORTH QUARTER CORNER OF SECTION 15, T2N, R1E
- 5 CITY OF GLENDALE BRASS CAP FLUSH FOR THE NORTHEAST CORNER OF SECTION 15, T2N, R1E
- 6 BRASS CAP IN HANDHOLE FOR THE EAST QUARTER CORNER OF SECTION 15, T2N, R1E
- 7 MARICOPA COUNTY HIGHWAY DEPARTMENT BRASS CAP IN HANDHOLE FOR THE SOUTHEAST CORNER OF SECTION 15, T2N, R1E
- 8 MARICOPA COUNTY HIGHWAY DEPARTMENT BRASS CAP IN HANDHOLE FOR THE SOUTH QUARTER CORNER OF SECTION 15, T2N, R1E
- 9 FOUND 1" IRON BAR CENTER CORNER OF SECTION 15, T2N, R1E



PREPARED BY: **GOODWIN AND MARSHALL** CIVIL ENGINEERS ~ PLANNERS ~ SURVEYORS
2705 S. Alma School Road, Suite 2
Chandler, Arizona 85044
(602) 218-7285

SURVEYED BY: **AS&M** Arizona Surveying & Mapping
2440 W. Mission Lane, Suite 4, Phoenix, Arizona 85021
TEL (602) 246-9919 FAX (602) 246-9944 info@asam1.com




CURVE TABLE					
CURVE #	RADIUS	ARC LENGTH	DELTA ANGLE	CHORD BEARING	CHORD LENGTH
C1	250.00'	5.60'	1°16'58"	S89°06'35"W	5.60'
C2	55.00'	86.39'	90°00'00"	N44°45'04"E	77.78'
C3	25.00'	20.32'	46°34'03"	S23°02'06"W	19.76'
C4	55.00'	89.40'	93°08'06"	N00°14'56"W	79.88'
C5	25.00'	20.32'	46°34'03"	S23°31'57"E	19.76'
C6	25.00'	34.55'	79°11'35"	S39°20'52"W	31.87'
C7	55.00'	248.81'	259°11'35"	N50°39'08"W	84.76'
C8	55.00'	248.81'	259°11'35"	S50°09'17"W	84.76'
C9	25.00'	34.55'	79°11'35"	N39°50'43"W	31.87'

LINE TABLE		
LINE #	BEARING	DISTANCE
L1	N34°02'00"W	24.00'
L2	S75°27'18"E	12.99'
L3	S41°50'26"E	15.15'
L4	N44°51'28"E	21.17'
L5	S45°02'07"E	21.21'
L6	S89°45'04"W	32.50'
L7	N89°45'04"E	32.50'
L8	N44°45'04"E	21.21'
L9	S45°14'56"E	21.21'
L10	N44°45'04"E	21.21'
L11	S45°14'56"E	21.21'
L12	N44°45'04"E	21.21'
L13	S29°40'40"W	20.00'
L14	N30°10'31"W	20.00'

APN: 102-12-040D
TAYLOR MORRISON/ARIZONA, INC.
(UNSUBDIVIDED)

APN: 102-12-040D
TAYLOR MORRISON/ARIZONA, INC.
(UNSUBDIVIDED)

MISSOURI RANCH
BK. 582 OF MAPS, PG. 33, MCR



SHEET 3 OF 3

PREPARED BY:
GOODWIN AND MARSHALL INC.
CIVIL ENGINEERS ~ PLANNERS ~ SURVEYORS

2705 S. Alma School Road, Suite 2
Chandler, Arizona 85044
(602) 218-7285

SURVEYED BY:

Arizona Surveying and Mapping
2440 W. Mission Lane, Suite 4, Phoenix, Arizona 85021
TEL (602) 246-9919 FAX (602) 246-9944 info@asam1.com

"FINAL PLAT OF STONEHAVEN PHASE 3, PARCEL II"
W:\10883A - TM Stonehaven\Cogo\FPLAT\PHASE 3\PHASE 3-1\10883A-FPLAT 3-11-SHEETS.dwg