

LEGAL DESCRIPTION


PARCEL NO. 1:
A PARCEL OF LAND LOCATED IN THE NORTHWEST QUARTER OF SECTION 16, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, DESCRIBED AS FOLLOWS:
COMMENCING AT THE NORTHWEST CORNER OF SAID SECTION 16;
THENCE SOUTH 01° 53' 13" EAST, 577.50 FEET ALONG THE WEST LINE OF SAID SECTION 16 TO THE POINT OF BEGINNING;
THENCE SOUTH 01° 53' 13" EAST, 1631.76 FEET ALONG SAID WEST LINE;
THENCE NORTH 38° 07' 25" EAST, 2748.05 FEET TO A POINT ON THE SOUTHERLY RIGHT OF WAY OF WESTERN AVENUE;
THENCE NORTH 89° 34' 19" WEST, 1126.54 FEET ALONG SAID SOUTHERLY RIGHT OF WAY OF WESTERN AVENUE;
THENCE SOUTH 01° 53' 13" EAST, 544.47 FEET;
THENCE NORTH 89° 34' 19" WEST, 641.71 FEET TO THE POINT OF BEGINNING;
EXCEPT ALL COAL AND OTHER MINERALS RESERVED IN PATENT FROM STATE OF ARIZONA; AND
EXCEPT ALL MINES, MINERALS, OIL, GAS AND COAL AS RESERVED IN DEED RECORDED IN BOOK 581 OF DEEDS, PAGE 375, RECORDS OF MARICOPA COUNTY, ARIZONA.

PARCEL NO. 2:
THAT PART OF THE NORTHWEST QUARTER OF SECTION 16, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, DESCRIBED AS FOLLOWS:
BEGINNING 241.71 FEET EAST AND 33 FEET SOUTH OF THE NORTHWEST CORNER OF SAID SECTION 16;
THENCE SOUTH AND PARALLEL WITH THE WEST LINE OF SAID SECTION 16, A DISTANCE OF 544.5 FEET;
THENCE EAST AND PARALLEL WITH THE NORTH LINE OF SAID SECTION 16, A DISTANCE OF 400 FEET;
THENCE NORTH 544.5 FEET; THENCE WEST 400 FEET TO THE POINT OF BEGINNING;
EXCEPT ALL COAL AND OTHER MINERALS RESERVED IN PATENT FROM STATE OF ARIZONA.


PARCEL NO. 3:
THAT PORTION OF SECTION 16, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, DESCRIBED AS FOLLOWS:
BEGINNING AT THE NORTHWEST CORNER OF SAID SECTION 16;
THENCE SOUTH 02° 07' EAST, ALONG THE WEST LINE OF SAID SECTION 16, A DISTANCE OF 577.50 FEET;
THENCE SOUTH 89° 48' EAST, PARALLEL WITH THE NORTH LINE OF SAID SECTION 16, A DISTANCE OF 400 FEET;
THENCE NORTH 02° 07' WEST, PARALLEL WITH THE WEST LINE OF SAID SECTION 16, A DISTANCE OF 577.50 FEET TO THE NORTH LINE OF SAID SECTION 16;
THENCE NORTH 89° 48' WEST ALONG SAID NORTH LINE, A DISTANCE OF 241.71 FEET TO THE POINT OF BEGINNING;
EXCEPT THEREFROM THE NORTH 33.00 FEET THEREOF; AND
EXCEPT ANY PORTION LYING WITHIN THE RAILROAD RIGHTS OF WAY; AND
EXCEPT ALL COAL AND OTHER MINERALS RESERVED IN PATENT FROM STATE OF ARIZONA; AND
EXCEPT ALL MINES, MINERALS, OIL, GAS AND COAL AS RESERVED IN DEED RECORDED IN BOOK 581 OF DEEDS, PAGE 375, RECORDS OF MARICOPA COUNTY, ARIZONA; AND
EXCEPT ANY PORTION DEDICATED TO THE CITY OF GOODYEAR, AN ARIZONA MUNICIPAL CORPORATION, BY RIGHT OF WAY DEDICATION RECORDED IN DOCUMENT NO. 2009-0118617, AND REFORMATION AGREEMENT RECORDED IN DOCUMENT NO. 2014-0541673, AND RERECORDED IN DOCUMENT NO. 2014-0550110, RECORDS OF MARICOPA COUNTY, ARIZONA.

PARCEL NO. 4:
THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 17, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA;
EXCEPT THAT PART THEREOF DESCRIBED AS FOLLOWS:
COMMENCING AT THE NORTHEAST CORNER OF SAID SECTION 17;
THENCE SOUTH 01°22' 44" WEST, 58.99 FEET TO THE BEGINNING OF A TANGENT CURVE OF 1045.80 FOOT RADIUS, CONCAVE NORTHWESTERLY;
THENCE SOUTHWESTERLY ALONG SAID CURVE, THROUGH A CENTRAL ANGLE OF 26° 23' 20", A DISTANCE OF 481. 82 FEET;
THENCE SOUTH 62° 13' 26" EAST, 55.00 FEET TO THE POINT OF BEGINNING;
THENCE CONTINUING SOUTH 62° 13' 26" EAST, 39.79 FEET TO A POINT ON A LINE WHICH IS PARALLEL TO AND 51.10 FEET WESTERLY, AS MEASURED AT RIGHT ANGLES, FROM THE EAST LINE OF SAID SECTION 17;
THENCE SOUTH 01° 21' 13" EAST, ALONG SAID PARALLEL LINE, 40.00 FEET;
THENCE SOUTH 88° 38' 47" WEST, 70.33 FEET TO A POINT ON A 1100.80 FOOT RADIUS NON-TANGENT CURVE, WHOSE CENTER BEARS NORTH 58° 37' 15" WEST;
THENCE NORTHEASTERLY, ALONG SAID CURVE, THROUGH A CENTRAL ANGLE OF 03° 36' 11", A DISTANCE OF 69.22 FEET TO THE POINT OF BEGINNING, AS CONVEYED BY INSTRUMENT RECORDED IN DOCUMENT NO. 2002-0026623, RECORDS OF MARICOPA COUNTY, ARIZONA; AND
EXCEPT ANY PORTION LYING NORTH OF THE SOUTH LINE OF ESTRELLA VISTA TANK SITE AND WELL SITE ACCESS ROAD DESCRIBED IN SPECIAL WARRANTY DEED RECORDED IN DOCUMENT NO. 2002-0026625, RECORDS OF MARICOPA COUNTY, ARIZONA; AND
EXCEPT ANY PORTION LYING NORTH OF THE SOUTH LINE OF "GOODYEAR RIGHT OF WAY" MAP OF DEDICATION OF RECORDED AS BOOK 963 OF MAPS, PAGE 22, RECORDS OF MARICOPA COUNTY, ARIZONA; AND
EXCEPT ANY PORTION DEDICATED TO THE CITY OF GOODYEAR, AN ARIZONA MUNICIPAL CORPORATION, BY RIGHT OF WAY DEDICATION RECORDED IN DOCUMENT NO. 2009-0118617, AND REFORMATION AGREEMENT RECORDED IN DOCUMENT NO. 2014-0541673, AND RERECORDED IN DOCUMENT NO. 2014-0550110, RECORDS OF MARICOPA COUNTY, ARIZONA.

PARCEL NO. 5:
THE EAST HALF OF SECTION 17, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA;
EXCEPT THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF SAID SECTION 17; AND
EXCEPT THAT PART OF THE SOUTHEAST QUARTER OF SAID SECTION 17 DESCRIBED AS FOLLOWS:
BEGINNING AT THE SOUTHEAST CORNER OF SAID SOUTHEAST QUARTER OF SAID SECTION 17;
THENCE NORTH 00° 16' WEST (ASSUMED BEARING), ALONG THE EAST LINE OF SAID SOUTHEAST QUARTER OF SECTION 17, A DISTANCE OF 2078.19 FEET TO A POINT FROM WHICH THE NORTHEAST CORNER OF SAID SOUTHEAST QUARTER OF SECTION 17 BEARS NORTH 00° 16' WEST, A DISTANCE OF 545.11 FEET;
THENCE SOUTH 39° 45' 30" WEST, A DISTANCE OF 2649.45 FEET TO A POINT FROM WHICH THE SOUTHWEST CORNER OF SAID SOUTHEAST QUARTER OF SECTION 17 BEARS NORTH 88° 36' WEST, A DISTANCE OF 915.31 FEET;
THENCE SOUTH 88° 36' EAST, A DISTANCE OF 1704.79 FEET TO THE POINT OF BEGINNING; AND
EXCEPT THAT PART OF THE EAST HALF OF SAID SECTION 17, CONVEYED TO THE CITY OF PHOENIX IN DOCUMENT NO. 88-360358, RECORDS OF MARICOPA COUNTY, ARIZONA DESCRIBED AS FOLLOWS:
COMMENCING AT THE NORTHEAST CORNER OF SAID SECTION 17;
THENCE SOUTH 01° 53' 13" EAST 2391.07 FEET ALONG THE EAST LINE OF SAID SECTION 17 TO THE POINT OF BEGINNING;
THENCE SOUTH 01° 53' 13" EAST, 232.64 FEET ALONG SAID EAST LINE TO THE EAST QUARTER CORNER OF SAID SECTION 17;
THENCE SOUTH 01° 52' 56" EAST, 545.11 FEET ALONG THE EAST LINE OF SAID SECTION 17;
THENCE SOUTH 38° 07' 25" WEST, 2650.80 FEET TO A POINT ON THE SOUTH LINE OF THE SOUTHEAST QUARTER OF SAID SECTION 17;
THENCE SOUTH 89° 44' 00" WEST 637.92 FEET ALONG SAID SOUTH LINE OF SAID SECTION 17;
THENCE NORTH 38° 07' 25" EAST, 3642.68 FEET TO THE POINT OF BEGINNING;
EXCEPT ANY PORTION LYING NORTH AND WEST OF THE SOUTH AND EAST LINE OF "GOODYEAR RIGHT OF WAY" MAP OF DEDICATION OF RECORDED IN BOOK 963 OF MAPS, PAGE 22, RECORDS OF MARICOPA COUNTY, ARIZONA; AND
EXCEPT THAT PORTION CONVEYED TO CITY OF GOODYEAR, ARIZONA, AN ARIZONA MUNICIPAL CORPORATION BY SPECIAL WARRANTY DEED RECORDED AUGUST 27, 2014 IN DOCUMENT NO. 2014-567661, RECORDS OF MARICOPA COUNTY, ARIZONA;
EXCEPT THAT PORTION CONVEYED TO CITY OF GOODYEAR, ARIZONA, AN ARIZONA MUNICIPAL CORPORATION BY SPECIAL WARRANTY DEED RECORDED AUGUST 27, 2014 IN DOCUMENT NO. 2014-567663, RECORDS OF MARICOPA COUNTY, ARIZONA.



PRELIMINARY PLAT
FOR
AIRPARK LOGISTICS CENTER
SEC OF YUMA RD & BULLARD AVE
GOODYEAR, ARIZONA



KEY MAP

SHEET INDEX

PRELIMINARY PLAT COVER SHEET	.P1
PRELIMINARY PLAT	.P2-P4

ABBREVIATIONS

ABC	AGGREGATE BASE COURSE	ESMT	EASEMENT	R/W	RIGHT OF WAY
AC	ASPHALTIC CEMENT	EX	EXISTING	SD	STORM DRAIN
BC	BACK OF CURB	F/C	FACE OF CURB	SS	SANITARY SEWER
BFP	BACKFLOW PREVENTOR	FF	FINISH FLOOR	SSMH	SANITARY SEWER MANHOLE
BOT	BOTTOM	FG	FINISH GRADE	S/W	SIDEWALK
CB	CATCH BASIN	FH	FIRE HYDRANT	TC	TOP OF CURB
CF	CUBIC FEET	FL	FLOW LINE	UGRT	UNDERGROUND RETENTION PIPE
CL	CENTERLINE	G	GUTTER	UGE	UNDERGROUND ELECTRICAL
CO	CURB OPENING	HDWL	HEADWALL	VCP	VITRIFIED CLAY PIPE
DNL	DAY-NIGHT SOUND LEVEL (LUKE AFB)	HW	HIGH WATER	VP	VOLUME PROVIDED
DW	DRYWELL	NTS	NOT TO SCALE	VR	VOLUME REQUIRED
		P	PAVEMENT	W	WATER
		PUE	PUBLIC UTILITY EASEMENT		

PHASING PLAN



THE PHASING PLAN IS CONCEPTUAL IN NATURE AND IS SUBJECT TO CHANGE AS THE PROPERTY DEVELOPS. THE PROJECT WILL BE COMPLETED IN TWO (2) PHASES.

OFFSITE IMPROVEMENT PHASING:

- PHASE 1: ALL OFFSITE HALF STREET IMPROVEMENTS ALONG YUMA ROAD AND THE DECELERATION LANES AND MEDIAN BREAKS ALONG BULLARD AVENUE FOR LOTS 1-3. INCLUDING THE ACCESS BETWEEN LOTS 3&4.
- PHASE 2: THE DECELERATION LANES AND MEDIAN BREAKS FOR LOTS 4&5.

UTILITY PHASING:

- PHASE 1: SEWER AND WATER TAPS FOR LOTS 1-3.
- PHASE 2: SEWER AND WATER TAPS FOR LOTS 4&5.



PHASING STATEMENT

PHASE 1 INCLUDES LOTS 1-3 AND THE RENOVATED INFRASTRUCTURE. PHASE 2 INCLUDES LOTS 4 AND 5. FULL DRIVE IMPROVEMENTS BETWEEN LOTS 3 AND 4 WILL BE INCLUDED WITH PHASE 1. TEMPORARY RETENTION WILL BE PROVIDED IF NECESSARY.

VICINITY MAP

OWNER

SUN MP INVESTMENT
PROPERTIES, LLC
5665 N. SCOTTSDALE ROAD, SUITE 135
SCOTTSDALE, ARIZONA 85258
CONTACT: PHILIP J. HANDLEY

DEVELOPER

LGE DESIGN GROUP
1200 N. 52ND STREET
PHOENIX, ARIZONA 85008
PHONE: (480) 966-4001
CONTACT: BLAKE WELLS
EMAIL: BLAKEW@LGEDESIGNBUILD.COM

ARCHITECT

LGE DESIGN GROUP
1200 N. 52ND STREET
PHOENIX, ARIZONA 85008
PHONE: (480) 966-4001
CONTACT: JOHN MOCARSKI
EMAIL: JOHNML@LGEDESIGNGROUP.COM

ZONING: PAD W/UNDERLYING I-1 & I-2

BENCHMARK

3" BRASS CAP IN HANDHOLE STAMPED "MARICOPA COUNTY HIGHWAY DEPT." LOCATED AT THE INTERSECTION OF LITCHFIELD ROAD & VAN BUREN ST. CITY OF GOODYEAR BENCHMARK POINT NO. G332.
ELEVATION = 981.64 (NAVD 88 DATUM).

3" BRASS CAP IN HANDHOLE STAMPED "MARICOPA COUNTY HIGHWAY DEPT." LOCATED ON LITCHFIELD ROAD 1/2 MILE NORTH OF YUMA ROAD. CITY OF GOODYEAR BENCHMARK POINT NO. G328.
ELEVATION = 977.78 (NAVD 88 DATUM).

BASIS OF BEARING

BASIS OF BEARING FOR THIS SURVEY IS A BEARING OF SOUTH 89°21'01" EAST, ALONG THE NORTH LINE OF THE NORTHWEST QUARTER OF SECTION 16, TOWNSHIP 1 NORTH, RANGE 1 WEST OF THE GILA AND SALT RIVER BASE AND MERIDIAN, MARICOPA COUNTY, ARIZONA, PER THE RECORD OF SURVEY OF LEASE PARCELS FOR LUX FBO AT PHOENIX-GOODYEAR AIRPORT AS RECORDED IN BK. 1192, PG. 18, M.C.R.

FEMA CLASSIFICATION

THE CURRENT FEMA FLOOD INSURANCE RATE MAP (FIRM) FOR THIS AREA, MAP NUMBER 04013C2145 & 04013C2165N (EFFECTIVE REVISED DATE SEPTEMBER 18, 2020), DESIGNATES THE PROPERTY WITHIN FLOOD HAZARD ZONE X & AE.

ZONE: X IS DEFINED AS AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT, OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

ZONE:AE ARE DEFINED AS BASE FLOOD ELEVATIONS DETERMINED.

AREA TABLE

DESCRIPTION	AREA (NET)	AREA (NET)	USE	OWNERSHIP	MAINTENANCE
LOT 1	21.81 AC	878,973.63 SF	PROPOSED BUILDING A	LGE	LGE
LOT 2	29.79 AC	1,297,707.57 SF	PROPOSED BUILDING B	LGE	LGE
LOT 3	34.51 AC	1,503,393.40 SF	PROPOSED BUILDING C	LGE	LGE
LOT 4	37.03 AC	1,613,192.99 SF	PROPOSED BUILDING D	LGE	LGE
LOT 5	47.11 AC	2,052,250.75 SF	PROPOSED BUILDING E	LGE	LGE

UTILITY SERVICE PROVIDERS

SEWER	CITY OF GOODYEAR
WATER	CITY OF GOODYEAR
GAS	SOUTHWEST GAS
ELECTRIC	ARIZONA PUBLIC SERVICE (APS)
TELEPHONE	CENTURY LINK
CATV	COX COMMUNICATION
IRRIGATION	ROOSEVELT IRRIGATION DISTRICT

EXISTING LEGEND


CENTERLINE	---
RIGHT OF WAY	---
PROPERTY LINE	---
EASEMENT	---
MAJOR CONTOUR	---1035---
MINOR CONTOUR	---1032---
SANITARY SEWERLINE	---SS---
WATERLINE	---W---
CHAIN LINK FENCE	---X---
DOWN GUY/ANCHOR	---
POWER POLE	---
STREET LIGHT	---
SANITARY SEWER MANHOLE	---
WATER VALVE	---
FIRE HYDRANT	---

NO.	DATE	REVISION	BY

DESIGN BY: LT
DRAWN BY: DFK
CHECKED BY: LT

PURPOSE:
PRELIMINARY PLAT SUBMITTAL

HUNTER ENGINEERING	CIVIL AND SURVEY
10450 NORTH 74TH STREET, SUITE 200 SCOTTSDALE, AZ 85258 T 480 961 3366 F 480 961 3366	



PRELIMINARY PLAT COVER SHEET
FOR
AIRPARK LOGISTICS CENTER
SEC OF YUMA RD & BULLARD AVE
GOODYEAR, ARIZONA



CONTACT ARIZONA AT AT LEAST 2 FULL WORKING DAYS BEFORE YOU BEGIN CONSTRUCTION
AR ZONAB11
CALL 811 OR CLICK ARZONAB11.COM

THESE PLANS ARE NOT APPROVED FOR CONSTRUCTION WITHOUT AN APPROVED SIGNATURE FROM THE GOVERNING MUNICIPALITY.

PROJECT NAME:
AIRPARK LOGISTICS CENTER

HE NO.: LGEC282
SCALE: N.T.S.

SHEET:
P1



MATCH LINE SEE SHEET P3

NO.	DATE	REVISION	BY

PURPOSE:
PRELIMINARY PLAT SUBMITTAL

DESIGN BY: LT
DRAWN BY: DFK
CHECKED BY: LT

HUNTER
ENGINEERING
10450 NORTH 74TH STREET,
SUITE 200
SCOTTSDALE, AZ 85260
T 480 981 3386
F 480 981 3386

CIVIL AND SURVEY



PRELIMINARY PLAT
FOR
AIRPARK LOGISTICS CENTER
SEC OF YUMA RD & BULLARD AVE
GOODYEAR, ARIZONA




THESE PLANS ARE
NOT APPROVED FOR
CONSTRUCTION
WITHOUT AN
APPROVED SIGNATURE
FROM THE GOVERNING
MUNICIPALITY.

PROJECT NAME:
AIRPARK
LOGISTICS
CENTER

HE NO.: LGEC282
SCALE: 1"=100'

SHEET:
P2

APN 500-07-009B
DEED NO. 1988-0360358, M.C.R.
CITY OF GOODYEAR



NO.	DATE	REVISION	BY


PURPOSE:
PRELIMINARY PLAT SUBMITTAL

DESIGN BY: LT
DRAWN BY: DFK
CHECKED BY: LT

HUNTER
ENGINEERING

10450 NORTH 74TH STREET,
SUITE 200
SCOTTSDALE, AZ 85258
T 480 991 3985
F 480 991 3986

CIVIL AND SURVEY



**PRELIMINARY PLAT
FOR
AIRPARK LOGISTICS CENTER
SEC OF YUMA RD & BULLARD AVE
GOODYEAR, ARIZONA**

CONTACT ARIZONA 811 AT LEAST 2 FULL
WORKING DAYS BEFORE YOU BEGIN EXCAVATION

ARIZONA811
BLUE STAKE, INC.
CALL 811 OR CLICK ARIZONA811.COM


THESE PLANS ARE
NOT APPROVED FOR
CONSTRUCTION
WITHOUT AN
APPROVED SIGNATURE
FROM THE GOVERNING
MUNICIPALITY.

**PROJECT NAME:
AIRPARK
LOGISTICS
CENTER**

HE NO.: LGEC282
SCALE: 1"=100'


SHEET:
P3

MATCH LINE SEE SHEET P3



CURVE TABLE			
CURVE	DELTA	RADIUS	LENGTH
C1	$\Delta = 67^{\circ}59'41''$	1045.80'	1241.08'
C2	$\Delta = 30^{\circ}32'20''$	1092.05'	582.07'
C3	$\Delta = 26^{\circ}31'56''$	2450.00'	1134.53'
C4	$\Delta = 12^{\circ}46'54''$	2450.00'	546.55'
C5	$\Delta = 23^{\circ}51'48''$	1110.80'	462.64'
C6	$\Delta = 3^{\circ}36'11''$	1100.80'	69.22'
C7	$\Delta = 38^{\circ}18'45''$	1110.80'	742.77'
C8	$\Delta = 65^{\circ}07'14''$	980.80'	1114.75'
C9	$\Delta = 13^{\circ}11'48''$	1027.05'	236.55'
C10	$\Delta = 38^{\circ}20'02''$	1110.80'	743.19'
C11	$\Delta = 9^{\circ}09'11''$	1110.80'	177.45'
C12	$\Delta = 7^{\circ}51'45''$	2385.00'	327.28'
C13	$\Delta = 17^{\circ}20'32''$	1027.05'	310.87'

LINE TABLE		
LINE	BEARING	DISTANCE
L1	S00°33'31"W	58.78'
L2	S38°00'35"W	1119.62'
L3	S00°39'16"W	42.00'
L4	S46°52'50"W	47.66'
L5	N63°02'29"E	9.89'
L6	N87°49'44"E	11.72'
L7	S68°33'29"W	299.73'
L8	N21°26'31"W	119.76'
L9	S21°27'08"E	0.15'
L10	S02°10'32"E	40.00'
L11	S63°02'45"E	29.91'
L12	S87°49'28"W	58.60'
L13	S1°40'17"E	189.31'
L14	S89°56'58"E	26.71'



NO.	DATE	REVISION	BY	PURPOSE:
				PRELIMINARY PLAT SUBMITTAL

DESIGN BY: LT
DRAWN BY: DFK
CHECKED BY: LT

HUNTER
ENGINEERING
CIVIL AND SURVEY
10450 NORTH 74TH STREET, SUITE 200
SCOTTSDALE, ARIZONA 85258
T 480.981.3986
F 480.981.3986



PRELIMINARY PLAT FOR
AIRPARK LOGISTICS CENTER
SEC OF YUMA RD & BULLARD AVE
GOODYEAR, ARIZONA

CONTACT AIRPARK AT AT LEAST 2 FULL WORKING DAYS BEFORE YOU BEGIN EXCAVATION.
AR ZONAB11
CALL 811 OR CLICK ARZONAB11.COM

THESE PLANS ARE NOT APPROVED FOR CONSTRUCTION WITHOUT AN APPROVED SIGNATURE FROM THE GOVERNING MUNICIPALITY.

PROJECT NAME:
AIRPARK LOGISTICS CENTER

HE NO.: LGEC282
SCALE: 1"=100'

SHEET:
P4