

NW SEC 9 1N, 1W
33.445886, -
112.369832
500-10-731C WE014836,
WE015826 CDJ/DMS

AERIAL UTILITY LINE EASEMENT

THE CITY OF GOODYEAR, an Arizona municipal corporation, (hereinafter called "Grantor"), is the owner of the following described real property located in Maricopa County, Arizona described in Exhibit "A," attached hereto and incorporated herein (hereinafter called "Grantor's Property").

Grantor, for and in consideration of One Dollar (\$1.00) and other valuable consideration, receipt of which is hereby acknowledged, does hereby grant and convey to **ARIZONA PUBLIC SERVICE COMPANY**, an Arizona corporation, (hereinafter called "Grantee") a non-exclusive Aerial Utility Line Easement over the real property described in Exhibit "B," attached hereto and incorporated herein, (the "Easement Premises") for the purposes described herein and subject to the terms and conditions set forth herein.

This Aerial Utility Line Easement shall be a permanent easement for use solely by Grantee for the installation, operation, maintenance, and repair of overhead high voltage electrical transmission lines owned and operated by Grantee as needed to transmit 69kV of electricity or greater by Grantee over the Easement Premises (the "Electrical Transmission Lines"). The Electrical Transmission Lines shall be installed above the southern boundary of Grantor's Property or to the closest extent possible if the Electrical Transmission Lines cannot be located directly above the southern boundary of Grantor's Property. Electrical Transmission Lines transmitting 69kV of electricity shall be located a minimum of 40 feet above ground level, measured at its highest point, and Electrical Transmission Lines transmitting electricity in excess of 69kV shall be located a minimum of 80 feet above ground level, measured at its highest point. No equipment, poles, or appurtenances shall be located within the Easement Premises.

Grantee understands that Grantor's Property is a secure facility and agrees that the installation, operation, maintenance, and repair of the Electrical Transmission Lines located over the Easement Premises shall be done from the property adjacent to the southern boundary of Grantor's Property. Except as follows, the easement granted herein does not provide Grantee any right to access the Easement Premises. Subject to Grantee obtaining permission from Grantor, Grantee shall be entitled to access the Easement Premises only if work required for the installation, maintenance, repair, or replacement of the electrical transmission lines authorized to be installed over the Easement Premises cannot be done from the property adjacent to the

southern boundary of Grantor's Property. Grantee is expressly prohibited from permitting others to use the Easement Premises for any facilities jointly with or separately from the Grantee for their purposes.

This Aerial Utility Line Easement is subject to Grantor's right to install, construct, operate, use, maintain, repair, and replace within the Easement Premises all improvements identified and depicted in the Landscape Plan prepared by Architekton for the Goodyear Police Department attached hereto as Exhibit C or comparable improvements thereto. Subject to all other provisions of this Aerial Utility Line Easement, and in addition to the foregoing, Grantor reserves the right to use and occupy the Easement Premises for any purpose consistent with the rights and privileges herein granted, and which do not interfere with or endanger any of Grantee's electrical transmission lines.

By accepting and utilizing this easement, Grantee agrees that following any installation, maintenance, repair, or other work by Grantee within the Easement Premises, the affected area will be restored by Grantee, to as close to original condition as is reasonably practicable and as approved by Grantor, at the expense of Grantee; and that Grantee shall indemnify Grantor, to the fullest extent allowed by law, for any loss, cost or damage incurred by Grantor as a result of any negligent installation, operation, maintenance, repair or other work performed by Grantee within the Easement Premises.

The easement granted herein shall not be deemed abandoned except upon Grantee's execution and recording of a formal instrument abandoning the easement.

The covenants and provisions herein set forth shall extend and inure in favor and to the benefit of, and shall be binding on the heirs, administrators, executors, successors in ownership and estate, assigns, and lessees of Grantor and Grantee.

[THE REST OF THIS PAGE IS INTENTIONALLY LEFT BLANK]

IN WITNESS WHEREOF, **THE CITY OF GOODYEAR, an Arizona municipal corporation** has caused this Aerial Utility Line Easement to be executed by its duly authorized representative, this ____ day of _____, 2024.

**THE CITY OF GOODYEAR,
an Arizona municipal corporation**

BY: _____

Name: Wynette Reed
Its: City Manager

STATE OF ARIZONA }
 } ss.
COUNTY OF MARICOPA }

This instrument was acknowledged before me this ____ day of _____, 2024 by Wynette Reed, the City Manager for **THE CITY OF GOODYEAR, an Arizona municipal corporation**.

IN WITNESS WHEREOF I hereunto set my hand and official seal.

Notary Seal:

Notary Public

Exhibits on the Following Pages

EXHIBIT 'A'

Grantor's Property Legal Description

[On the Following Pages]

EXHIBIT "A"

LEGAL DESCRIPTION OF GRANTOR'S PROPERTY as recorded at Recording No. 2015-0072235 at Maricopa County Recorder's Office, Maricopa, County, Arizona

A parcel of land situated in the Northwest quarter of Section 9, Township 1 North, Range 1 West of the Gila and Salt River Base and Meridian, Maricopa County, Arizona, and being a portion of that certain property described in Instrument No. 2011-1070323, Official Records of Maricopa County, Arizona, and being more particularly described as follows:

Commencing at the North quarter corner of said Section 9 from which the Northwest corner thereof bears South 89 degrees 53 minutes 47 seconds West, 2626.72 feet;

Thence South 89 degrees 53 minutes 47 seconds West, along and with the North line of said Northwest quarter, 660.00 feet;

Thence departing said North line, South 00 degrees 07 minutes 55 seconds East, along and with the West line of the East 660.00 feet of said Northwest quarter, 903.04 feet to the Southeast corner of that certain parcel recorded in Book 1079 of Maps, Page 17, Official Records of Maricopa County, Arizona and the Point of Beginning of the herein described parcel;

Thence continuing South 00 degrees 07 minutes 55 seconds East, 579.18 feet;

Thence departing said West line, South 89 degrees 52 minutes 05 seconds West, 526.47 feet;

Thence North 00 degrees 07 minutes 55 seconds West, 536.55 feet to the beginning of a curve to the left, having a radius of 750.00 feet;

Thence along and with the arc of said curve through a central angle of 03 degrees 16 minutes 10 seconds, an arc length of 42.80 feet to the Southwest corner of the aforesaid parcel recorded in Book 1079 of Maps, Page 17;

Thence North 89 degrees 53 minutes 00 seconds East, along and with the South line of said parcel, 527.69 feet to the Point of Beginning.

EXHIBIT 'B'

Easement Premises Legal Description

[On the Following Pages]

Exhibit 'B'

July 19, 2023

LEGAL DESCRIPTION FOR
ARIZONA PUBLIC SERVICE
RIGHT OF WAY EASEMENT

That part of the Northwest Quarter of Section 9, Township 1 North, Range 1 West, of the Gila and Salt River Meridian, Maricopa County, Arizona, more particularly described as follows:

Commencing at the Brass Cap flush marking the North Quarter Corner of said Section 9, from which the Brass Cap in a handhole marking the Northwest Corner of said Section 9 bears South 89°53'47" West (Basis of Bearing), a distance of 2,626.72 feet;

Thence South 89°53'47" West, along the North line of the Northwest Quarter of said Section 9, a distance of 660.00 feet;

Thence South 00°07'55" East, departing said North line, a distance of 903.04 feet to a point being the Northeast Corner of that certain parcel of land described in Document No. 2015-0072235, Records of Maricopa County, Arizona;

Thence continuing South 00°07'55" East, along the Easterly line of said certain parcel, a distance of 534.18 feet to the True Point of Beginning;

Thence continuing South 00°07'55" East, along said Easterly line, a distance of 45.00 feet to the Southeast corner of said certain parcel;

Thence South 89°52'05" West, along the South line of said certain parcel, a distance of 496.36 feet to the Southwest corner of said certain parcel and the Easterly Right-of-Way line of 145th Avenue;

Thence North 00°07'55" West, along the Westerly line of said certain parcel, a distance of 45.00 feet to a point on a line which is parallel with and 45.00 feet Northerly from the aforementioned South line;

Thence North 89°52'05" East, departing said Westerly line, a distance of 496.36 feet to the True Point of Beginning.

Containing 22,336 Square Feet or 0.513 Acres, more or less.



VAN BUREN STREET

S89°53'47"W 2627.04'

1967.04'

660.00'

NW. COR.
SEC. 9
T.1N., R.1W.

N. 1/4 COR.
SEC. 9
T.1N., R.1W.
POINT OF
COMMENCEMENT

-ALL BEARINGS ARE NAD 1983, STATE PLANE GRID,
ARIZONA CENTRAL ZONE (0202)
- ALL DISTANCES ARE GROUND DISTANCES

APN 500-10-732A

N89°53'00"E 497.60'

APN
500-09-016

$\Delta=3^{\circ}08'54"$
R=780.00'
L=42.86'

145TH AVENUE

N00°07'55"W 536.55'

491.55'

APN 500-10-731C
CITY OF GOODYEAR
DOC. NO. 2015-0072235 MCR

30' R/W
DOC. NO.
2015-0456749
MCR

30' R/W
BOOK 1183,
PAGE 48
MCR

534.18'

S00°07'55"E 579.18'

143RD AVENUE

N00°07'55"W
45.00'

N89°52'05"E 496.36'

S89°52'05"W 496.36'

APN 500-10-859


TRUE POINT
OF BEGINNING

S00°07'55"E
45.00'


LEGEND




EASEMENT AREA



PROPERTY/PARCEL LINE



SECTION LINE



CENTERLINE



PROPERTY CORNER



SECTION CORNER



POLE LOCATION



MARICOPA COUNTY
RECORDER

TOTAL EASEMENT AREA:
22,336 S.F. (0.513 AC.)



EXHIBIT "B"

JOB # WE015826 DATE: 07/19/23

NW1/4 SEC 9 T 1N R 1W

SCALE: N.T.S. INDEX:

R/W: J. GENEROSO

SURVEY: RINDA-HUTTON

DRAWN BY: J. KITCHEN SHEET 6 OF 6

EXHIBIT 'C'

Approved Improvements

[On the Following Pages]

ARCHITECT'S SUPPLEMENTAL INSTRUCTIONS

OWNER	☒
ARCHITECT	☒
CONSULTANT	☐
CONTRACTOR	☒
FIELD	☐
OTHER	☐

PROJECT:

GOODYEAR POLICE DEPARTMENT - PHASE 2
11 N. 145TH AVE
GOODYEAR, AZ 85338

ASI NO: 012R

DATE: 4/17/2023

OWNER:

CITY OF GOODYEAR
14455 143RD AVE
GOODYEAR, AZ 85338

ARCHITECT:

ARCHITEKTON
464 S. FARMER AVE STE. 101
TEMPE, AZ 85281

TO:

CORE CONSTRUCTION
3036 E. GREENWAY RD.
PHOENIX, AZ 8503

ARCHITECT'S PROJECT NO:

18118

The work shall be carried out in accordance with the following supplemental instructions issued in accordance with the Contract Documents without change in the Contract Sum or Contract Time. Proceeding with the Work in accordance with these instructions indicates your acknowledgement that there will be no change in the Contract Sum or Contract Time.

Description:

Revisions to the Building GMP II Package dated 03/07/2022.

1. To accommodate the 45' APS easement, revise the trees at the southern portion of the site per L001 and L002, dated 4/17/2023, delta 2.



the MOORE/SWICK partnership
landscape architects and planners
414 s. mill avenue, suite 207
tempe, arizona 85281
phone 480.894.9284
fax 480.894.9301
CONTACT: GREG SWICK
E-MAIL: gswick@mooreswick.com

LANDSCAPE PLAN
SHEET L004
IRRIGATION PLAN
SHEET L008

LANDSCAPE PLAN
SHEET L002
IRRIGATION PLAN
SHEET L006

LANDSCAPE PLAN
SHEET L003
IRRIGATION PLAN
SHEET L007

THIS SHEET
LANDSCAPE PLAN
SHEET L001
IRRIGATION PLAN
SHEET L005



KEY MAP

VICINITY MAP

PLANT LIST


SYMBOL	BOTANICAL NAME COMMON NAME	SIZE	QTY.	REMARKS	MATURE HEIGHT
TREES:					
	ACACIA ANEURA MULGA	24" BOX	6	6'-7"HX2'-3"W X 1.25"-1.5" CAL.	18'-20'H
	ACACIA SALICINIA WILLOW ACACIA	24" BOX	9	7'-8"HX2.5'-3.5"W X 1.25"-1.5" CAL.	20'-40'H
	CAESALPINIA CACALACO 'SMOOTHIE' SMOOTHIE THORNLESS CASCALOTE	24" BOX	11	5'-8"HX3'-4"WX1"-1.5" CAL.	15'-18'H
	CORDIA BOISSIERI TEXAS OLIVE	24" BOX	6	5'-7"HX3'-4"W MULTI-TRUNK	11'-20'H
	FRAXINUS VELUTINA 'ARIZONA' VELVET ASH	24" BOX	6	8'-9"HX3'-4"WX1"-1.5" CAL.	20'-40'H
	PARKINSONIA HYBRID 'AZT' 'AZT' THORNLESS HYBRID PALO VERDE	24" BOX	18	5'-8"HX3'-4"WX1"-1.5" CAL. MULTI-TRUNK, LOW BREAKING	20'-30'H
	PARKINSONIA FLORIDA BLUE PALO VERDE	24" BOX	4	5'-7"HX3'-4"W MULTI-TRUNK	20'-35'H
	PISTACHE LENTISCUS MASTIC TREE	24" BOX	6	7'-9"HX2.5'-3.5"WX1"-1.5" CAL.	15'-20'H
	PROSOPIS THORNLESS HYBRID 'AZT' 'AZT' THORNLESS HYBRID MESQUITE	24" BOX	36	5'-8"HX3'-4"WX1"-1.5" CAL. MULTI-TRUNK, LOW BREAKING	20'-40'H
SHRUBS:					
	CAESALPINIA PULCHERRIMA RED BIRD OF PARADISE	5 GALLON	28		
	EREMOPHILA HYGROPHANA BLUE BELLS	5 GALLON	158		
	JUSTICIA SPICIGERA MEXICAN HONEY SUCKLE	5 GALLON	13		
	LEUCOPHYLLUM LANGMANIAE 'RIO BRAVO' RIO BRAVO SAGE	5 GALLON	106		
	LEUCOPHYLLUM ZYGOPHYLLUM CIMARRON CIMARRON SAGE	5 GALLON	28		
	RUELLIA PENINSULARIS DESERT RUELLIA	5 GALLON	42		
	TECOMA X 'ORANGE JUBILEE' ORANGE JUBILEE	5 GALLON	6		
ACCENTS:					
	AGAVE 'BLUE FLAME' BLUE FLAME AGAVE	5 GALLON	41		
	DASYLIRION WHEELERI DESERT SPOON	5 GALLON	16		
	OPUNTIA ENGELMANNI ENGELMANN PRICKLY PEAR	5 GALLON 3 PAD MIN.	21		
	OPUNTIA FICUS-INDICA INDIAN FIG CACTUS	15 GALLON 4 PAD MIN.	12		
	PACHYCEREUS MARGINATUS MEXICAN FENCE POST	24" BOX	8	3 COLUMN MIN.	
	PEDILANTHUS MACROCARPUS SLIPPER PLANT	5 GALLON	1		
AS NOTED IN REMARKS	SANSEVIERIA TRIFASCIATA MOTHER-IN-LAW'S TONGUE	1 GALLON	4	MOTHER-IN-LAW'S TONGUE TO BE INSTALLED IN INTERIOR PLANTERS - SEE POT INSTALLATION NOTE ON THIS SHEET AND ARCHITECTURAL PLANS	
	YUCCA PALLIDA PALE LEAF YUCCA	5 GALLON	17		
GROUND COVER:					
	EREMOPHILA GLABRA 'MINGENEW GOLD' OUTBACK SUNRISE EMU	5 GALLON	51		
	PORTULACARIA AFRA ELEPHANT'S FOOD	5 GALLON	23		
TURF:					
	CYNODON DACTYLON TIF 419 BERMUDA HYBRID GRASS	SOD			
	PET PLATINUM SYNTHETIC TURF AS MANUFACTURED BY SYNLAWN PH: 1.866.796.5296				
HEADER:					
	CONCRETE HEADER				
ROCK MULCH:					
AS NOTED	MATCH EXISTING DECOMPOSED GRANITE COLOR	3/4" MINUS		ALL LANDSCAPE AREAS TO RECEIVE A 2" LAYER OF DECOMPOSED GRANITE UNLESS OTHERWISE NOTED ON PLANS.	
AS NOTED ON PLAN	WHITE POLISHED BEACH PEBBLES 3" MIN. DEPTH	2" DIAMETER			
	STABILIZED DECOMPOSED GRANITE MATCH ROCK MULCH COLOR	1/4" MINUS		INSTALL PER MANUFACTURER'S RECOMMENDATIONS	
	MISCELLANEOUS: POURED-IN-PLACE RESILIENT SAFETY SURFACE				

GOODYEAR POLICE DEPARTMENT PHASE 2

CITY OF GOODYEAR POLICE
DEPARTMENT
11 N. 145TH AVE.
GOODYEAR, AZ 85338
APN: xxx-xx-xxxx
CITY OF GOODYEAR

DELTA REVISIONS

#	DESCRIPTION	DATE
1	GMP #2	03/07/22
2	APS EASEMENT, TREE REVISION, CONTROLLER REVISION	4/17/23



PROJECT # 18118
ISSUE DATE 02/17/2023
ISSUE NAME DELTA 2
PLOT DATE 04/17/2023


L001

LANDSCAPE PLAN

Call at least two full working days
before you begin excavation.
ARIZONA
Arizona Blue State, Inc.
Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
in Maricopa County: (602) 263-1100

LANDSCAPE PLAN

1"=20'-0" 0 4' 10' 20'



APS EASEMENT

TREES LOCATED WITHIN THE APS EASEMENT SHALL NOT
HAVE A MATURE HEIGHT GREATER THAN 25' MAX. AND
SHALL BE MAINTAINED AT LESS THAN A 25' MAX. HEIGHT.

POT INSTALLATION NOTE

POTS (4): NEW PORT SERIES MODEL NO. NPF8
BLACK COLOR
AS MANUFACTURED BY SONORAN STONECRETE
PH: 602.258.6302

SEE ARCHITECTURAL PLANS FOR LOCATION. FILL WITH
POTTING SOIL AND TOP DRESS WITH 2" LAYER OF WHITE
POLISHED BEACH PEBBLES

MATCHLINE - SEE SHEET L003

ROOSEVELT IRRIGATION
DISTRICT 30" LINE
BELOW GRADE.
PROTECT IN PLACE

EXISTING LANDSCAPE
TO REMAIN - PROTECT
FROM DAMAGE DURING
CONSTRUCTION

LIMIT OF
DECOMPOSED
GRANITE

R.O.W. LINE

SIGHT DISTANCE
TRIANGLE

EXISTING ADA
ACCESSIBLE RAMP

SIGHT DISTANCE
TRIANGLE

EXISTING FIRE HYDRANT

EXISTING CURB/GUTTER

EXISTING SIDEWALK

LIMIT OF
DECOMPOSED
GRANITE

8'-0" SITE WALL

RIP RAP - SEE CIVIL
ENGINEER'S PLANS

CONCRETE
HEADER

CONCRETE PATH FOR
OBSTACLE COURSE

DECOMPOSED
GRANITE

RETENTION

CONCRETE PATH FOR
OBSTACLE COURSE

EXISTING DRY
WELLS

45' APS EASEMENT

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE



8'-0" SITE WALL

CONCRETE HEADER

STABILIZED
DECOMPOSED GRANITE
RUNNING TRACK

PROPERTY LINE

the MOORE/SWICK partnership
landscape architects and planners
414 s. mill avenue, suite 207
tempe, arizona 85281
phone 480.894.9284
fax 480.894.9301
CONTACT: GREG SWICK
E-MAIL: gswick@mooreswick.com



PLANT KEY

SYMBOL	BOTANICAL NAME	COMMON NAME
--------	----------------	-------------

- TREES:**
- ACACIA ANEURA
MULGA
 - ACACIA SALICINIA
WILLOW ACACIA
 - CAESALPINIA CACALAGO 'SMOOTHIE'
SMOOTHIE THORNLESS CASCALOTE
 - CORDIA BOISSIERI
TEXAS OLIVE
 - FRAXINUS VELUTINA 'ARIZONA'
VELVET ASH
 - PARKINSONIA HYBRID 'AZT'
'AZT' THORNLESS HYBRID PALO VERDE
 - PARKINSONIA FLORIDA
BLUE PALO VERDE
 - PISTACHE LENTISCUS
MASTIC TREE
 - PROSOPIS THORNLESS HYBRID 'AZT'
'AZT' THORNLESS HYBRID MESQUITE

- SHRUBS:**
- CAESALPINIA PULCHERRIMA
RED BIRD OF PARADISE
 - EREMOPHILA HYGROPHANA
BLUE BELLS
 - JUSTICIA SPICIGERA
MEXICAN HONEY SUCKLE
 - LEUCOPHYLLUM LANGMANIAE 'RIO BRAVO'
RIO BRAVO SAGE
 - LEUCOPHYLLUM ZYGOPHYLLUM CIMARRON
CIMARRON SAGE
 - RUELLIA PENINSULARIS
DESERT RUELLIA
 - TECOMA X 'ORANGE JUBILEE'
ORANGE JUBILEE

- ACCENTS:**
- AGAVE 'BLUE FLAME'
BLUE FLAME AGAVE
 - DASYLIRION WHEELERI
DESERT SPOON
 - OPUNTIA ENGELMANNI
ENGELMANN PRICKLY PEAR
 - OPUNTIA FICUS-INDICA
INDIAN FIG CACTUS

- PACHYCREUS MARGINATUS
MEXICAN FENCE POST
- PEDILANTHUS MACROCARPUS
SLIPPER PLANT

- AS NOTED ON
SHEET L001
- SANSEVIERIA TRIFASCIATA
MOTHER-IN-LAW'S TONGUE
 - YUCCA PALLIDA
PALE LEAF YUCCA

- GROUND COVER:**
- EREMOPHILA GLABRA 'MINGENEW GOLD'
OUTBACK SUNRISE EMU
 - PORTULACARIA AFRA
ELEPHANT'S FOOD

- TURF:**
- CYNODON DACTYLON TIF 419
BERMUDA HYBRID GRASS
 - PET PLATINUM SYNTHETIC TURF
AS MANUFACTURED BY SYNLAWN
PH: 1.866.796.5296


- HEADER:**
- CONCRETE HEADER

- ROCK MULCH:**
- MATCH EXISTING DECOMPOSED
GRANITE COLOR


- AS NOTED ON
SHEET L001
- WHITE POLISHED BEACH PEBBLES
3" MIN. DEPTH

- STABILIZED DECOMPOSED GRANITE:**
- STABILIZED DECOMPOSED GRANITE
MATCH ROCK MULCH COLOR

- MISCELLANEOUS:**
- POURED-IN-PLACE RESILIENT SAFETY
SURFACE



LANDSCAPE PLAN



APS EASEMENT

TREES LOCATED WITHIN THE APS EASEMENT SHALL NOT HAVE A MATURE HEIGHT GREATER THAN 25' MAX. AND SHALL BE MAINTAINED AT LESS THAN A 25' MAX. HEIGHT.

GOODYEAR POLICE DEPARTMENT PHASE 2

CITY OF GOODYEAR POLICE DEPARTMENT
11 N. 145TH AVE.
GOODYEAR, AZ 85338
APN: xxx-xx-xxxx
CITY OF GOODYEAR

DELTA REVISIONS

#	DESCRIPTION	DATE
1	GMP #2	03/07/22
2	APS EASEMENT, TREE REVISION, CONTROLLER REVISION	4/17/23



PROJECT # 18118

ISSUE DATE 02/17/2023

ISSUE NAME DELTA 2

PLOT DATE 04/17/2023

L002

LANDSCAPE PLAN

