

**HINOJOSA ENGINEERING, INC.**  
**STRUCTURAL & CIVIL ENGINEERING**  
**LAND SURVEYING**

**Facsimile Transmittal**

Date: September 18, 2006

Attn: Daniel Flores

Company: Hidalgo County

Fax No: (956) 318-2648

Project: New Adult Probation Building

- From: ( ) Ricardo Hinojosa, P.E.  
 ( ) Mariano Garcia, P.E.  
 ( ) Miguel Chanin, P.E.  
 ( ) Jorge Rodriguez, R.P.L.S.  
 (X) Rey Robles, E.I.T.  
 ( ) Albert Treviño, E.I.T.  
 ( ) Hector Ramirez, E.I.T.  
 ( ) Other:

Project No : 05-228

Number of pages including cover: 2

Remarks: ( ) Urgent ( ) For your review ( ) Reply A.S.A.P. ( ) Please Comment

Engineers Estimate of Probable Cost

**CONFIDENTIALITY NOTICE: The information contained in this transmission and following page(s) is intended for the address named above only and use or disclosure by any other person is strictly prohibited.**

Engineers Estimate of Probable Cost  
05-228 New Adult Probation Building

**RECEIVED**  
4/18/06  
BAG

Date: April 17, 2006

ITEM NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	UNIT TOTAL
<b>Paving Improvements</b>					
1	1 1/2" H.M.A.C. Overlay	11,042	SY	=	\$0.00
2	1 1/2" H.M.A.C.	6,306	SY	=	\$0.00
3	8" Compacted Flexible Base	6,380	SY	=	\$0.00
4	6" Subgrade	6,380	SY	=	\$0.00
5	18" Concrete Curb and Gutter	700	LF	=	\$0.00
6	4" Concrete Curb	50	LF	=	\$0.00
Subtotal					\$0.00
<b>Miscellaneous</b>					
1	Remove Existing Concrete Walks, Curb, and Retaining Wall	1	LS	=	\$0.00
2	4" Reinforced Concrete Sidewalk	695	SY	=	\$0.00
3	24" Sidewalk Drainage Opening	11	EA	=	\$0.00
4	Handicap Access Ramp	7	EA	=	\$0.00
Subtotal					\$0.00
<b>Drainage Improvements</b>					
1	24" PVC	195	LF	=	\$0.00
2	24" RCP	110	LF	=	\$0.00
3	Grate Inlet	2	EA	=	\$0.00
4	Adjust Grate Inlet	1	EA	=	\$0.00
5	Beehive Inlet	8	EA	=	\$0.00
Subtotal					\$0.00
<b>Waterline Improvements</b>					
1	8" PVC	1,162	LF	=	\$0.00
2	8" x 4" Tee	1	EA	=	\$0.00
3	8" x 6" Tee	1	EA	=	\$0.00
4	8" x 8" Tee	1	EA	=	\$0.00
5	8" 90 degree Bend	1	EA	=	\$0.00
6	3" x 4" Reducer	1	EA	=	\$0.00
7	Fire Hydrant w/ 6" Valve	1	EA	=	\$0.00
8	Water Meter Assembly w/Box and Cover	1	EA	=	\$0.00
9	Back Flow Preventor (Within Vault)	2	EA	=	\$0.00
Subtotal					\$0.00
<b>Sanitary Sewer Improvements</b>					
1	48" Man Hole	1	EA	=	\$0.00
2	Clean Out	3	EA	=	\$0.00
3	8" Sanitary Sewer Line	890	LF	=	\$0.00
Subtotal					\$0.00
<b>Erosion and Sediment Control</b>					
1	Erosion and Sediment Control	12	MO	=	\$0.00
Subtotal					\$0.00
<b>PROJECT TOTAL</b>					<b>\$0.00</b>