

# CHANGE ORDER #1

NO. 1

DATE OF ISSUANCE February 6, 2007

EFFECTIVE DATE \_\_\_\_\_

OWNER HIDALGO COUNTY PRECINCT NO. 1

CONTRACTOR SASCON INC.

Contract: BORDER COLONIA ACCESS PROJECT

Project: "ROAD & DRAINAGE CONSTRUCTION OF OLD REBEL HEIGHTS  
I SUBDIVISION"

OWNER's Contract No. C-CAP-06-007-01-23

ENGINEER's Contract No. 2C-1080-509

ENGINEER TEDSI INFRASTRUCTURE GROUP

You are directed to make the following changes in the Contract Documents:

**Description:**

- 1) Removed quantities for Item 2600

**Reason for Change Order:**

- 1) As per PI Tests results, Subgrade stabilization is not required.

**Attachments:** (List documents supporting change)

Schedule of Quantities

Revised Estimate and Quantities

CHANGE IN CONTRACT PRICE:
Original Contract Price
<u>\$145,014.50</u>
Net Increase (Decrease) from previous Change Orders No. _____ to _____:
<u>\$ N/A</u>
Contract Price prior to this Change Order:
<u>\$145,014.50</u>
Net (decrease) of this Change Order:
<u>\$14,881.50</u>
Contract Price with all approved Change Orders:
<u>\$130,133.50</u>

**REVISED**  
**ESTIMATE AND QUANTITIES**

**OLD REBEL HEIGHTS #1 (CSJ: 2C-1080-509)**

**CONTRACT : C-CAP-06-007-01-23**

Item	Code	Item Description	Unit	Qty.	Unit Price	Bid Amount
100	502	Preparing ROW	STA	24.07	\$ 500.00	\$ 12,035.00
134	502	Backfill (TY B)	STA	24.07	\$ 300.00	\$ 7,221.00
247	699	FL BS (Rdwy Del)(TYD, GR6, CL4)	CY	1136	\$ 18.00	\$ 20,448.00
310	501	ASPH Material (MC-30)	GAL			\$ -
340		ASPH Concrete (TY D)	TON			\$ -
500	501	Mobilization	LS	1	\$ 6,000.00	\$ 6,000.00
502	501	Barricades, Signs and Traffic Handling	MO	2	\$ 4,500.00	\$ 9,000.00
2500		EN-1 Treat. Flexbase (DC)(6")	SY	6954	\$ 2.00	\$ 13,908.00
2500		EN-1 Roadbond	GAL	39	\$ 75.00	\$ 2,925.00
2600		EN-1 Treat. Subgrade (DC)(8")	SY		\$ 1.50	\$ -
2600		EN-1 Roadbond	GAL		\$ 75.00	\$ -
5249	501	Temporary Sediment Control Fence	LF	80	\$ 8.00	\$ 640.00
5249	503	Temporary Sediment Control Fence (REMOVE)	LF	80	\$ 5.00	\$ 400.00
464	503	18' RCP (CL III)	LF	40	\$ 40.00	\$ 1,600.00
467	676	Safety End Treatment (TY II) (18") (RCP)(3:1)(C)	EA	4	\$ 450.00	\$ 1,800.00
530	540	Driveways (CONC)(4")	SY	178	\$ 46.00	\$ 8,188.00
530	542	Driveways (ASPH-CONC-PAV)(PB-1)	SY	838	\$ 24.00	\$ 20,112.00
530	655	Turnout (ASPH-CONC-PAV)(PBS-2)	SY	216	\$ 26.00	\$ 5,616.00
556		15" ADS Corrugated Pipe	LF	920	\$ 22.00	\$ 20,240.00

**\$ 130,133.00**

**Removed as per Change Order # 1**

**SCHEDULE OF QUANTITIES**

**OLD REBEL HEIGHTS #1 SUBDIVISION (CSJ: 2C-1080-509)**

**CONTRACT: C-CAP-06-007-01-23**

**ORIGINAL QUANTITIES**

2600	503	EN-1 Treat. Subgrade (DC)(8")	SY	7221	\$	1.50	\$	10,831.50	
2600		EN-1 Roadbord	GAL	54	\$	75.00	\$	4,050.00	
<b>TOTAL</b>								<b>\$</b>	<b>14,881.50</b>

**REVISED QUANTITIES AS PER CHANGE ORDER # 1**

2600	503	EN-1 Treat. Subgrade (DC)(8")	SY		\$	1.50	\$	-	
2600		EN-1 Roadbord	GAL		\$	75.00	\$	-	
<b>TOTAL</b>								<b>\$</b>	<b>-</b>

\$ 14,881.50 Original  
 \$ - Revised  
 \$ 14,881.50 Net Decrease

\$ 145,014.50 Original Contract Price  
 \$ 14,881.50 Net Decrease  
 \$ 130,133.00 Contract Price with Approved Change Order

REPORT OF ATTERBERG LIMITS & LIME DETERMINATION

TESTED FOR: HIDALGO COUNTY PRECINCT #1 PROJECT: OLD REBEL HEIGHTS SUBD.  
1902 JOE STEPHENS STREET  
WESLACO, TX 78596

DATE: January 25, 2007 PSI REPORT NO.: 328-60088-2

REMARKS: On January 25, 2007, PSI representative, Gabriel Loya was present at the above referenced project to obtain soil samples for an Atterberg Limits Determination in accordance with ASTM D4318 and Lime Determination. Test results are as follows:

Location: 200' East of Mile 2 East on Rebel Rd.  
Description: Medium Brown Silty Clay (Subgrade)

Liquid Limit: 36  
Plastic Limit: 17  
Plasticity Index: 19

\*In accordance with TxDot Method 121-E, 0.0% of hydrated lime by weight would be required to stabilize subgrade material. Base unit weight of soil on 100 PSF.

Respectfully submitted,  
Professional Service Industries, Inc.

Rudy Martinez  
Branch Manager

cc: 1-ABOVE

REPORT OF ATTERBERG LIMITS & LIME DETERMINATION

TESTED FOR: *Attn: John Paul* HIDALGO COUNTY PRECINCT #1 PROJECT: OLD REBEL HEIGHTS SUBD.  
1902 JOE STEPHENS STREET  
WESLACO, TX 78596

DATE: January 25, 2007 PSI REPORT NO.: 328-60088-1

REMARKS: On January 25, 2007, PSI representative, Gabriel Loya, was present at the above referenced project to obtain soil samples for an Atterberg Limits Determination in accordance with ASTM D4318 and Lime Determination. Test results are as follows:

Location: 200' East of Mile 2 East of Mesquite Dr.  
Description: Medium Brown Silty Clay (Subgrade)

Liquid Limit: 40  
Plastic Limit: 20  
Plasticity Index: 20

\*In accordance with TxDot Method 121-E, 0.0% of hydrated lime by weight would be required to stabilize subgrade material. Base unit weight of soil on 100 PSF.

Respectfully submitted,  
Professional Service Industries, Inc.

Rudy Martinez  
Branch Manager

RECEIVED

FEB 05 2007

PRECINCT 1

COMMISSIONER SYLVIA S. HANDY

cc: 1-ABOVE

# CHANGE ORDER #1

NO. 1

DATE OF ISSUANCE February 6, 2007

EFFECTIVE DATE \_\_\_\_\_

OWNER HIDALGO COUNTY PRECINCT NO. 1

CONTRACTOR SASCON INC.

Contract: BORDER COLONIA ACCESS PROJECT

Project: "ROAD & DRAINAGE CONSTRUCTION OF OLD REBEL HEIGHTS  
II SUBDIVISION"

OWNER's Contract No. C-CAP-06-008-01-23

ENGINEER's Contract No. 2C-1080-510

ENGINEER TEDSI INFRASTRUCTURE GROUP

You are directed to make the following changes in the Contract Documents:

**Description:**

- 1) Removed quantities for Item 2600

**Reason for Change Order:**

- 1) As per PI Tests results, Subgrade stabilization is not required.

**Attachments:** (List documents supporting change)

Schedule of Quantities

Revised Estimate and Quantities

CHANGE IN CONTRACT PRICE:
Original Contract Price
<u>\$141,558.00</u>
Net Increase (Decrease) from previous Change Orders No. _____ to _____:
<u>\$ N/A</u>
Contract Price prior to this Change Order:
<u>\$141,558.00</u>
Net (decrease) of this Change Order:
<u>\$14,649.00</u>
Contract Price with all approved Change Orders:
<u>\$126,909.00</u>

CHANGE ORDER #1

<b>CHANGE IN CONTRACT TIMES:</b>
Original Contract Times: Substantial Completion: <u>120 days</u> Ready for final payment: _____
Net change from previous Change Orders No. _____ to _____: Substantial Completion: <u>N/A</u> Ready for final payment: _____
Contract Times prior to this Change Order: Substantial Completion: <u>120 days</u> Ready for final payment: _____
Net increase (decrease) this Change Order: Substantial Completion: <u>N/A</u> Ready for final payment: _____
Contract Times with all approved Change Orders: Substantial Completion: <u>120 days</u> Ready for final payment: _____

RECOMMENDED:

By: [Signature]  
Engineer (Authorized Signature)

Date: February 6, 2007

APPROVED:

By: \_\_\_\_\_  
Owner (Authorized Signature)

Date: \_\_\_\_\_

ACCEPTED:

By: [Signature]  
Contractor (Authorized Signature)

Date: 2-7-07

CONCURRENCE:

By: \_\_\_\_\_  
TxDOT District Colonia Manager  
(Authorized Signature)

Date: \_\_\_\_\_

**ORIGINAL**  
**ESTIMATE AND QUANTITIES**

**OLD REBEL HEIGHTS #2 (CSJ: 2C-1080-510)**

**CONTRACT : C-CAP-06-008-01-23**

Item	Code	Item Description	Unit	Qty.	Unit Price	Bid Amount
100	502	Preparing ROW	STA	23.72	\$ 500.00	\$ 11,860.00
134	502	Backfill (TY B)	STA	23.72	\$ 300.00	\$ 7,116.00
247	699	FL BS (Rdwy Del)(TYD, GR6, CL4)	CY	1121	\$ 18.00	\$ 20,178.00
310	501	ASPH Material (MC-30)	GAL			\$ -
340		ASPH Concrete (TY D)	TON			\$ -
500	501	Mobilization	LS	1	\$ 6,000.00	\$ 6,000.00
502	501	Barricades, Signs and Traffic Handling	MO	2	\$ 4,500.00	\$ 9,000.00
2500		EN-1 Treat. Flexbase (DC)(6")	SY	6852	\$ 2.00	\$ 13,704.00
2500		EN-1 Roadbond	GAL	39	\$ 75.00	\$ 2,925.00
2600		EN-1 Treat. Subgrade (DC)(8")	SY	7116	\$ 1.50	\$ 10,674.00
2600		EN-1 Roadbond	GAL	53	\$ 75.00	\$ 3,975.00
5249	501	Temporary Sediment Control Fence	LF	80	\$ 8.00	\$ 640.00
5249	503	Temporary Sediment Control Fence (REMOVE)	LF	80	\$ 5.00	\$ 400.00
464	503	18' RCP (CL III)	LF	0	\$ 40.00	\$ -
467	676	Safety End Treatment (TY II) (18") (RCP)(3:1)(C)	EA	2	\$ 450.00	\$ 900.00
530	540	Driveways (CONC)(4")	SY	89	\$ 46.00	\$ 4,094.00
530	542	Driveways (ASPH-CONC-PAV)(PB-1)	SY	1075	\$ 24.00	\$ 25,800.00
530	655	Turnout (ASPH-CONC-PAV)(PBS-2)	SY	122	\$ 26.00	\$ 3,172.00
556		15" ADS Corrugated Pipe	LF	960	\$ 22.00	\$ 21,120.00

**\$ 141,558.00**

**REVISED  
ESTIMATE AND QUANTITIES**

**OLD REBEL HEIGHTS #2 (CSJ: 2C-1080-510)**

**CONTRACT : C-CAP-06-008-01-23**

Item	Code	Item Description	Unit	Qty.	Unit Price	Bid Amount
100	502	Preparing ROW	STA	23.72	\$ 500.00	\$ 11,860.00
134	502	Backfill (TY B)	STA	23.72	\$ 300.00	\$ 7,116.00
247	699	FL BS (Rdwy Del)(TYD, GR6, CL4)	CY	1121	\$ 18.00	\$ 20,178.00
310	501	ASPH Material (MC-30)	GAL	-		\$ -
340		ASPH Concrete (TY D)	TON	-		\$ -
500	501	Mobilization	LS	1	\$ 6,000.00	\$ 6,000.00
502	501	Barricades, Signs and Traffic Handling	MO	2	\$ 4,500.00	\$ 9,000.00
2500		EN-1 Treat. Flexbase (DC)(6")	SY	6852	\$ 2.00	\$ 13,704.00
2500		EN-1 Roadbond	GAL	39	\$ 75.00	\$ 2,925.00
2600		EN-1 Treat Subgrade (DC)(8")	SY		\$ 1.50	\$ -
2600		EN-1 Roadbond	GAL		\$ 75.00	\$ -
5249	501	Temporary Sediment Control Fence	LF	80	\$ 8.00	\$ 640.00
5249	503	Temporary Sediment Control Fence (REMOVE)	LF	80	\$ 5.00	\$ 400.00
464	503	18' RCP (CL III)	LF	0	\$ 40.00	\$ -
467	676	Safety End Treatment (TY II) (18") (RCP)(3:1)(C)	EA	2	\$ 450.00	\$ 900.00
530	540	Driveways (CONC)(4")	SY	89	\$ 46.00	\$ 4,094.00
530	542	Driveways (ASPH-CONC-PAV)(PB-1)	SY	1075	\$ 24.00	\$ 25,800.00
530	655	Turnout (ASPH-CONC-PAV)(PBS-2)	SY	122	\$ 26.00	\$ 3,172.00
556		15" ADS Corrugated Pipe	LF	960	\$ 22.00	\$ 21,120.00
<b>\$</b>						<b>126,909.00</b>

**Removed as per Change Order # 1**

**SCHEDULE OF QUANTITIES**

**OLD REBEL HEIGHTS #2 SUBDIVISION (CSJ: 2C-1080-509)**

**CONTRACT: C-CAP-06-008-01-23**

**ORIGINAL QUANTITIES**

2600	503	EN-1 Treat. Subgrade (DC)(8")	SY	7116	\$	1.50	\$	10,674.00
2600		EN-1 Roadbond	GAL	53	\$	75.00	\$	3,975.00
<b>TOTAL</b>								<b>\$ 14,649.00</b>

**REVISED QUANTITIES AS PER CHANGE ORDER # 1**

2600	503	EN-1 Treat. Subgrade (DC)(8")	SY		\$	1.50	\$	-
2600		EN-1 Roadbond	GAL		\$	75.00	\$	-
<b>TOTAL</b>								<b>\$ -</b>

\$ 14,649.00 Original  
 \$ - Revised  
 \$ 14,649.00 Net Decrease

\$ 141,558.00 Original Contract Price  
 \$ 14,649.00 Net Decrease  
 \$ 126,909.00 Contract Price with Approved Change Order

REPORT OF ATTERBERG LIMITS & LIME DETERMINATION

TESTED FOR: *Attn: John Paull*  
HIDALGO COUNTY PRECINCT #1 PROJECT: OLD REBEL HEIGHTS II  
1902 JOE STEPHENS STREET  
WESLACO, TX 78596

DATE: January 25, 2007 PSI REPORT NO.: 328-60087-1

REMARKS: On January 25, 2007, PSI representative, Gabriel Loya, was present at the above referenced project to obtain soil samples for an Atterberg Limits Determination in accordance with ASTM D4318 and Lime Determination. Test results are as follows:

Location: 200' East of Mile 2 East on Ebony  
Description: Medium Brown Silty Clay (Subgrade)

Liquid Limit: 40  
Plastic Limit: 21  
Plasticity Index: 19

\*In accordance with TxDot Method 121-E, 0.0% of hydrated lime by weight would be required to stabilize subgrade material. Base unit weight of soil on 100 PSF.

Respectfully submitted,  
Professional Service Industries, Inc.

RECEIVED

FEB 05 2007

PRECINCT 1

COMMISSIONER SYLVIA S. HANDY

Rudy Martinez  
Branch Manager

cc: 1-ABOVE

REPORT OF ATTERBERG LIMITS & LIME DETERMINATION

TESTED FOR: HIDALGO COUNTY PRECINCT #1 PROJECT: OLD REBEL HEIGHTS II  
1902 JOE STEPHENS STREET  
WESLACO, TX 78596

DATE: January 25, 2007 PSI REPORT NO.: 328-60087-2

REMARKS: On January 25, 2007, PSI representative, Gabriel Loya, was present at the above referenced project to obtain soil samples for an Atterberg Limits Determination in accordance with ASTM D4318 and Lime Determination. Test results are as follows:

Location: 250' West of Cul de Sac on Fresno  
Description: Medium Brown Silty Clay (Subgrade)

Liquid Limit: 33  
Plastic Limit: 16  
Plasticity Index: 17

\*In accordance with TxDot Method 121-E, 0.0% of hydrated lime by weight would be required to stabilize subgrade material. Base unit weight of soil on 100 PSF.

Respectfully submitted,  
Professional Service Industries, Inc.

Rudy Martinez  
Branch Manager

cc: 1-ABOVE