

STATE OF TEXAS
COUNTY OF HIDALGO

OWNER'S DEDICATION, CERTIFICATION, AND ATTESTATION

I, GARY BURCH, AS OWNER OF THE 20 ACRE TRACT OF LAND ENCOMPASSED WITHIN PROPOSED ELLIS NO. 5 SUBDIVISION, HEREBY SUBDIVIDE THE LAND AS DEPICTED IN THIS SUBDIVISION PLAT AND DEDICATE TO PUBLIC USE THE STREETS, PARKS AND EASEMENTS SHOWN HEREIN.

- I CERTIFY THAT I HAVE COMPLIED WITH THE REQUIREMENTS OF TEXAS LOCAL GOVERNMENT CODE § 232.032 AND THAT:
(A) THE WATER QUALITY AND CONNECTION TO THE LOTS MEET, OR WILL MEET, THE MINIMUM STATE STANDARDS;
(B) SEWER CONNECTION TO THE LOTS OR SEPTIC TANK MEET, OR WILL MEET, THE MINIMUM REQUIREMENTS OF STATE STANDARDS;
(C) ELECTRICAL CONNECTION PROVIDED TO THE LOTS MEET, OR WILL MEET, MINIMUM STATE STANDARDS; AND
(D) GAS CONNECTION, IF AVAILABLE, PROVIDED TO THE LOTS MEET, OR WILL MEET, THE MINIMUM STATE STANDARDS.
I ATTEST THAT THE MATTERS ASSERTED IN THIS PLAT ARE TRUE AND COMPLETE.

GARY BURCH CONSTRUCTION INC.
PRESIDENT: GARY BURCH

STATE OF TEXAS
COUNTY OF HIDALGO

BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, ON THIS DAY PERSONALLY APPEARED GARY BURCH, PROVED TO ME THROUGH THEIR TEXAS DEPARTMENT OF PUBLIC SAFETY DRIVER LICENSE TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT WHO, BY MY BUILT SWORN, DECLARED THAT HIS STATEMENT THEREIN IS TRUE AND CORRECT AND ACKNOWLEDGE THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATION THEREBY EXPRESSED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS _____ DAY OF _____ 2008.

NOTARY PUBLIC

**CITY OF MISSION
CERTIFICATE OF PLAT APPROVAL
UNDER LOCAL GOVERNMENT CODE § 212.009(C) AND § 212.015(B)**

WE THE UNDERSIGNED CERTIFY THAT THIS PLAT OF THE ELLIS NO. 5 SUBDIVISION WAS REVIEWED AND APPROVED BY THE CITY COUNCIL OF THE CITY OF MISSION ON _____ 2008.

MAYOR OF THE CITY OF MISSION DATE
ATTEST: SECRETARY OF THE CITY OF MISSION DATE

THIS PLAT OF ELLIS NO. 5 SUBDIVISION HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING AND ZONING COMMISSION OF THE CITY OF MISSION, TEXAS AND IS HEREBY APPROVED BY SUCH COMMISSION.

DATED THIS _____ DAY OF _____ 2008

CHAIRMAN

THIS PLAT IS HEREBY APPROVED BY HIDALGO COUNTY IRRIGATION DISTRICT NO. 16, SUBJECT TO THE CONDITION THAT IF IRRIGATION FROM SAID SUBDIVISION IS DESIRED TO THE INDIVIDUAL LOTS IN SAID SUBDIVISION PROVISION SHALL BE MADE FOR APPROPRIATE EASEMENTS FOR THE INSTALLATION OF NECESSARY IRRIGATION FACILITIES TO SUCH LOTS FROM THE CLOSEST WATER DISTRICT DELIVERY POINT AND IT SHALL BE THE RESPONSIBILITY OF THE OWNER OF THE PROPERTY TO INSTALL AND MAINTAIN SUCH NECESSARY FACILITIES.

DATED THIS _____ DAY OF _____ 2008.

PRESIDENT ATTEST: SECRETARY

HIDALGO COUNTY DRAINAGE DISTRICT NO. 1 HEREBY CERTIFIES THAT THE DRAINAGE PLANS FOR THIS SUBDIVISION COMPLY WITH THE MINIMUM STANDARDS OF THE DISTRICT ADOPTED UNDER TEX. WATER CODE § 49.211 (C). THE DISTRICT HAS NOT REVIEWED AND DOES NOT CERTIFY THAT THE DRAINAGE STRUCTURES DESCRIBED ARE APPROPRIATE FOR THE SPECIFIC SUBDIVISION, BASED ON GENERALLY ACCEPTED ENGINEERING CRITERIA. IT IS THE RESPONSIBILITY OF THE DEVELOPER OF THE SUBDIVISION AND ITS ENGINEER TO MAKE THESE DETERMINATIONS.

HIDALGO COUNTY DRAINAGE DISTRICT NO. 1 DATE

**HIDALGO COUNTY
CERTIFICATE OF PLAT APPROVAL
UNDER LOCAL GOVERNMENT CODE § 232.026(A)**

WE THE UNDERSIGNED CERTIFY THAT THIS PLAT OF THE ELLIS NO. 5 SUBDIVISION WAS REVIEWED AND APPROVED BY THE HIDALGO COUNTY COMMISSIONERS COURT ON _____ 2008.

HIDALGO COUNTY JUDGE DATE

ATTEST: HIDALGO COUNTY CLERK DATE

I, PABLO PENA, JR., A REGISTERED PROFESSIONAL LAND SURVEYOR IN TEXAS, HEREBY CERTIFY THAT THE ABOVE PLAT AND DESCRIPTION OF THE ELLIS NO. 5 SUBDIVISION WERE PREPARED FROM A SURVEY OF THE PROPERTY MADE ON THE GROUND BY ME OR UNDER MY SUPERVISION ON MAY 26, 2004.

PABLO PENA, JR. 04-26-04 DATE SURVEYED
R.P.L.S. NO. 5242

I, THE UNDERSIGNED, A REGISTERED ENGINEER IN THE STATE OF TEXAS, HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATIONS HAVE BEEN GIVEN TO THIS PLAT.

PABLO F. PENA, JR. 04-26-04 DATE OF PREPARATION
P.E. NO. 34985

COUNTY CLERK'S RECORDING CERTIFICATE

I, _____, COUNTY CLERK OF HIDALGO COUNTY, CERTIFY THAT THE PLAT BEARING THIS CERTIFICATE WAS FILED FOR RECORD AT _____ O'CLOCK _____ M ON _____ AND WAS RECORDED IN BOOK _____ SHEET(S) _____ THE PLAT RECORDS OF HIDALGO COUNTY AT _____ O'CLOCK _____ M ON _____

HIDALGO COUNTY CLERK

PRINCIPAL CONTACTS:

Table with columns: NAME, ADDRESS, CITY & ZIP, PHONE, FAX. Includes Gary Burch, Pablo Pena, Jr., and Pablo F. Pena, Jr.

SUBDIVISION PLAT OF

"ELLIS NO. 5 SUBDIVISION"

A 20.0 ACRE TRACT OF LAND BEING ALL OF LOTS 25 AND 26, BLOCK 8 TEXAN GARDENS SUBDIVISION, HIDALGO COUNTY, TEXAS AS PER MAP THEREOF RECORDED IN VOLUME 8 PAGE 57-58 OF THE MAP RECORDS OF SAID COUNTY;




SCALE: 1"=100'
CAD: ELLISSPT

NOTE: BASIS OF BEARING, IS THE WEST LINE OF LOTS 18 TO 34, BLOCK 8 TEXAN GARDENS SUBD. V. 8 P. 57-58 MAP REC.

AT EACH SUBDIVISION CORNER MONUMENTS ARE SHOWN IN LEGEND. EACH CORNER IS FLAGGED WITH A PLASTIC FLAG MARKED PENIA ENGINEERING 1000 WHITEWING McALLEN, TX 78501 (956) 682-8812

- LEGEND:
F1 - FOUND 1/2" DIAMETER IRON ROD
S - SET 1/2" DIAMETER IRON ROD
BM - BENCHMARK
S.E.C. - SOUTHEAST CORNER
N.E.C. - NORTHEAST CORNER
S.W.C. - SOUTHWEST CORNER
L.J.W.S.C. - LA JOYA WATER SUPPLY CORP.
H.C.I.D. - HIDALGO COUNTY IRRIGATION DISTRICT
PC - POINT OF CURVATURE
P.R.C. - POINT OF REVERSE CURVATURE
PT - POINT OF TANGENT
G-G - EL PASO FIELD SERVICE PETROLEUM PIPELINE (800) 895-2398



MEASUREMENTS AND BOUNDS DESCRIPTION:

A 20.00 ACRE TRACT OF LAND BEING ALL OF LOTS 25 AND 26, BLOCK 8 TEXAN GARDENS SUBDIVISION, HIDALGO COUNTY, TEXAS AS PER MAP THEREOF RECORDED IN VOLUME 8 PAGE 57-58 OF THE MAP RECORDS OF SAID COUNTY;

BEGINNING AT THE SOUTHEAST CORNER OF SAID LOT 25, FOR THE SOUTHEAST CORNER HEREOF;

THENCE WITH THE SOUTH LINE OF SAID LOT (25), N 81°-1'W, AT 40.00 FEET FOUND A 1/2 INCH DIAMETER IRON ROD FOUND AT THE WEST RIGHT OF WAY OF SAID ROAD, AT 1452.00 FEET IN ALL TO A 1/2 INCH DIAMETER IRON ROD FOUND FOR THE SOUTHWEST CORNER HEREOF;

THENCE WITH THE WEST LINE OF SAID LOT (26), N 08°-59'E AT 300.00 FEET PASS THE NORTHWEST CORNER OF LOT 26, AT 600.00 FEET IN ALL TO THE NORTHWEST CORNER OF LOT 25, TO A ONE-HALF (1/2) INCH DIAMETER IRON ROD FOUND FOR THE NORTHWEST CORNER HEREOF;

THENCE WITH THE NORTH LINE OF SAID LOT (25) S 81°-1'W, AT 1402.00 FEET SET A 1/2 INCH DIAMETER IRON ROD AT THE PROPOSED WEST RIGHT OF WAY OF SAID ROAD, AT 1452.00 FEET IN ALL TO THE NORTHEAST CORNER OF LOT 25, FOR THE NORTHEAST CORNER HEREOF;

THENCE WITH THE EAST LINE OF SAID LOT, THE CENTERLINE OF ABRAM ROAD, S 81°-59'W, AT 300.00 FEET PASS THE SOUTHEAST CORNER OF LOT 25, AT 600.00 FEET IN ALL TO THE PLACE OF BEGINNING, CONTAINING TWENTY (20) ACRES, MORE OR LESS, OF WHICH 2.78 ACRES LIES IN ROADS, LEAVING 17.22 ACRES NET.

**HIDALGO COUNTY
CERTIFICATE OF PLAT APPROVAL**

I, THE UNDERSIGNED CERTIFY THAT THIS PLAT OF ELLIS NO. 5 SUBDIVISION WAS REVIEWED AND APPROVED BY THE HIDALGO COUNTY RIGHT OF WAY DEPARTMENT ON _____ 2008.

HIDALGO COUNTY RIGHT OF WAY DIRECTOR DATE

I, FRANK FLORES, MANAGER, HEREBY CERTIFY THAT THE LA JOYA WATER SUPPLY CORPORATION HAS APPROVED THE POTABLE WATER POTABLE WATER SUPPLY FOR THE ELLIS NO. 5 SUBDIVISION, HIDALGO COUNTY, TEXAS. THE LA JOYA WATER SUPPLY CORPORATION IS THE HOLDER OF A CERTIFICATION OF PUBLIC CONVENIENCE AND NECESSITY ISSUED BY THE STATE OF TEXAS TO FURNISH POTABLE WATER TO AN AREA IN HIDALGO COUNTY, TEXAS, THAT INCLUDES THIS SUBDIVISION, AND IS THEREFORE OBLIGATED TO SERVE THIS SUBDIVISION WITH POTABLE WATER TO THE EXTENT REQUIRED BY THE LAWS OF THE STATE OF TEXAS. THE LA JOYA WATER SUPPLY CORPORATION AGREES THAT IT WILL PROVIDE WATER TO THIS SUBDIVISION AT THE TIME WHEN ALL OF THE INFRASTRUCTURE REQUIREMENTS FOR THE SUBDIVISION ARE MET. WATER METERS ARE IMMEDIATELY AVAILABLE FOR THIS PURPOSE UPON COMPLETION OF THE WATER FACILITIES SHOWN ON THE PLAT OF THE SUBDIVISION.

INDEX TO SHEET OF ELLIS NO. 5 SUBDIVISION PLAT:

SHEET 1: HEADINGS, INDEX, LOCATION MAP AND E.I.P. PRINCIPAL CONTACTS; MAP: LOT, STREETS, AND EASEMENTS LAYOUT; METES & BOUNDS DESCRIPTION; SURVEYOR'S CERTIFICATION; PLAT NOTES AND RESTRICTIONS; OWNER'S DEDICATION, CERTIFICATION, ATTESTATION; CITY APPROVAL CERTIFICATE; COUNTY CLERK'S RECORDING CERTIFICATE; REVISED NOTES; IRRIGATION DISTRICT CERTIFICATION; ENGINEER'S CERTIFICATION; H.C.I.D. NO. 1, L.J.W.S.C. CERTIFICATION.
SHEET 2: ENGINEERING REPORT, INCLUDING DESCRIPTION OF WATER AND WASTE WATER/OSSF AND ENGINEER'S CERTIFICATION (ENGLISH AND SPANISH VERSION); DRAINAGE REPORT INCLUDING DESCRIPTION OF DRAINAGE AND DRAINAGE SWALES, MAP OF TOPOGRAPHY AND DRAINAGE, AND ENGINEERING CERTIFICATION.
SHEET 3: CONSTRUCTION DETAILS

LINE DATA table with columns: LINE, BEARING, DISTANCE. Includes lines A through F with bearings and distances.


REVISION NOTES table with columns: NO., SHEET, REVISION, DATE, APPROVED.

GENERAL PLAT NOTES & RESTRICTIONS:

- 1. FLOOD ZONE DESIGNATION: ZONE "X" (UNSHADED) - AREAS DETERMINED TO BE OUTSIDE OF 500-YEAR FLOOD PLAIN COMMUNITY PANEL NUMBER 480334 0290 0 MAP REVISED: JUNE 8, 2000. THE AREAS WITHIN THE DRAINAGE EASEMENTS AND THE PROPOSED STREET RIGHT OF WAY ARE WITHIN THE 100-YEAR FLOOD PLAIN. THE FEDERAL EMERGENCY MANAGEMENT AGENCY MAP FOR HIDALGO COUNTY, TEXAS, AND THE LOCAL FLOOD PLAIN ADMINISTRATOR IDENTIFIES NO OTHER AREA WITHIN THE PROPOSED SUBD TO BE WITHIN THE 100-YEAR FLOOD PLAIN. CONSTRUCTION OF RESIDENTIAL HOUSING WITHIN ANY AREA OF THE SUBDIVISION THAT IS IN THE 100-YEAR FLOOD PLAIN IS PROHIBITED UNLESS THE HOUSING QUALIFIES FOR INSURANCE UNDER THE NATIONAL FLOOD INSURANCE ACT OF 1988 (42 U.S.C. SECTIONS 4001 THROUGH 4127).
2. MINIMUM BUILDING SETBACK LINES ARE AS FOLLOWS:
FRONT: 30.00 FEET / CURB-54' / 25.00 FEET
SIDES: 6.00 FEET / SIDE CORNER TO CLARABOYA LANE: 10.00 FEET
REAR: 25.00 FEET / REAR: 25.00 FEET
3. GENERAL NOTE FOR SINGLE FAMILY RESIDENCES: NO MORE THAN ONE SINGLE FAMILY DWELLING SHALL BE LOCATED ON EACH LOT. DEVELOPMENT PERMITS ARE REQUIRED PRIOR TO OCCUPANCY OF THE LOT. THE LOT OWNER SHALL STATE THE INTENDED USE OF THE LOT AT THE TIME OF APPLICATION IF NOT DESIGNATED ON THE SUBDIVISION PLAT. ANY DEVIATION FROM SINGLE FAMILY USE SHALL REQUIRE THE APPROVAL FROM THE DEVELOPER, IN WRITING, AND THE PLANNING AND FIRE MARSHALL OSSF DEPARTMENTS. ONLY LOTS 1 AND 33 MAY BE USED FOR COMMERCIAL AND/OR RESIDENTIAL. ALL OTHER LOTS SHALL BE RESIDENTIAL USE ONLY.
4. OFF-STREET PARKING SITE PLAN APPROVAL SHALL BE REQUIRED BY THE COUNTY OF HIDALGO PRIOR TO BUILDING PERMIT ISSUANCE WHERE SPECIAL ASSESSMENT SHALL BE MADE TO CONTROLLING ACCESS (DRIVEWAYS) TO ABRAM ROAD AND CRYSTAL DRIVE, AND WHERE SUCH SITE PLAN APPROVAL MAY INCLUDE PAVED FIRE LANES, PAVED 5' SIDEWALKS ALONG THE SITE'S PERIMETER, AND 6' FENCE BUFFERS ADJACENT TO RESIDENTIALLY USED LOTS.
5. MINIMUM FINISH FLOOR ELEVATION SHALL BE 18" ABOVE CRYSTAL DRIVE OR 12" ABOVE NATURAL GROUND, WHICHEVER IS GREATER.
ELEVATION CERTIFICATE MAY BE REQUIRED FOR LOTS LOCATED OUTSIDE A DESIGNATED FLOOD ZONE AT THE TIME FOR A DEVELOPMENT PERMIT APPLICATION TO VERIFY PRE AND POST CONSTRUCTION FINISH FLOOR ELEVATIONS. AN ELEVATION CERTIFICATE SHALL BE REQUIRED FOR ALL LOTS WITHIN A DESIGNATED FLOOD ZONE AT THE TIME FOR A DEVELOPMENT PERMIT APPLICATION.
6. BENCHMARK NOTE:
B.M. NO. 1 - ELEV. 210.33 N.G.V.D. '29, DESCRIPTION: 60-1/2" NAIL IN BASE OF POWER POLE LOCATED 144.03 FEET NORTH AND EAST 8.80 FEET FROM THE SOUTHWEST CORNER OF LOT 26 BLOCK 8, TEXAN GARDENS SUBDIVISION.
B.M. NO. 2 - ELEV. 210.62 N.G.V.D. '29, DESCRIPTION: FOUND 1/2" DIAMETER IRON ROD AT THE SOUTHWEST CORNER OF LOT 8, TEXAN GARDENS SUBDIVISION.
7. DRAINAGE IN ACCORDANCE WITH THE HIDALGO COUNTY DRAINAGE DISTRICT NO. 1 AND MODEL SUBDIVISION RULES POLICIES AND REGULATIONS THIS DEVELOPMENT WILL BE REQUIRED TO DETAIN A TOTAL OF 30,958 CUBIC FEET (0.71 ACRE FEET), 938 C.F. PER LOT OF STORM WATER RUNOFF.
8. DRAINAGE SWALE EASEMENTS NOTE: NO FILL OR PERMANENT STRUCTURES SHALL BE ALLOWED WITHIN ANY EASEMENT. EACH DRAINAGE SWALE EASEMENT SHALL BE KEPT CLEAR OF FENCES, BUILDINGS, PLANTINGS, AND OTHER OBSTRUCTIONS THAT WOULD INTERFERE WITH THE OPERATION AND MAINTENANCE OF THE DRAINAGE SWALE EASEMENT BY LOT OWNER.
9. ON SITE SEWAGE FACILITIES (OSSF) NOTE: THIS SUBDIVISION SHALL USE ON-SITE SEWAGE FACILITIES IN ACCORDANCE WITH THE HIDALGO COUNTY REGULATIONS FOR SEWAGE DISPOSAL.
A) OSSF SYSTEM IS BEING DESIGNED FOR DISPOSAL OF DOMESTIC SEWAGE ONLY. A SEPARATE DESIGN SHALL BE SUBMITTED FOR COMMERCIAL USE.
B) EACH LOT ON THIS PLAT COMPLIES WITH THE MINIMUM 21,780 SQUARE FEET LOT AREA WITH POTABLE WATER SUPPLY.
C) OSSF SYSTEM SHALL REQUIRE INSPECTION AND APPROVAL BY HIDALGO COUNTY AUTHORIZED DEPARTMENT.
D) SOIL ANALYSIS HAVE BEEN SUBMITTED TO THE AUTHORIZED HIDALGO COUNTY DEPARTMENT AND EXCERPTS MAY BE ALSO SEEN ON THE UTILITY LAYOUT FOR THIS SUBDIVISION AS SUBMITTED TO THE HIDALGO COUNTY PLANNING DEPARTMENT.
E) "OSSF" PERMIT IS REQUIRED PRIOR OF OCCUPANCY OF A LOT.
10. THERE ARE NO WATER WELLS WITHIN 150 FEET FROM THE BOUNDARIES ON THIS SUBDIVISION.
11. NO STRUCTURE SHALL BE PERMITTED OVER ANY EASEMENT. EASEMENTS SHALL BE KEPT CLEAR OF FENCES, BUILDINGS, SHEDS, SHRUBS, TREES, AND OTHER PLANTINGS (EXCEPT LOW, LESS THAN 18 INCHES MATURE HEIGHT, COVER, OR SPREAD) AND OTHER OBSTRUCTIONS TO THE OPERATIONS AND MAINTENANCE OF THE EASEMENT.
12. EACH PURCHASED CONTRACT MADE BETWEEN A SUBDIVIDER AND PURCHASER OF A LOT IN THIS SUBDIVISION DESCRIBING HOW AND WHEN WATER, SEWER, ELECTRICITY AND GAS SERVICES WILL BE MADE AVAILABLE TO THE SUBDIVISION.
13. ALL PUBLIC UTILITIES EASEMENTS DEDICATED BY THIS PLAT SHALL BE A MINIMUM WIDTH OF 15.00 FEET AS PER THE HIDALGO COUNTY MODEL SUBDIVISION RULES. BY SIGNING THIS PLAT DEVELOPER AGREES THAT ALL OTHER EASEMENTS SHOWN COMPLY WITH THE SIZE REQUIRED BY EACH UTILITY PROVIDER OCCUPANCY AN EASEMENT.
14. NO SIDEWALKS REQUIRED BY THIS PLAT.
15. NO ACCESS ON TO LOTS 1 & 33 FROM ABRAM ROAD IS ALLOWED UNLESS USE FOR COMMERCIAL AND LOT SITE PLAN AND DRAINAGE PLANS ARE APPROVED BY THE HIDALGO COUNTY PLANNING DEPARTMENT AT THE TIME OF APPLICATION FOR CONSTRUCTION. FOR CONSTRUCTION OF A BUILDING AND/OR DEVELOPMENT PERMIT.
16. IF AND WHEN THE 15.00 FOOT EXCLUSIVE EASEMENT TO H.C.I.D. NO. 16 IS ABANDONED, IT SHALL REVERT TO A 15.00 FOOT EXCLUSIVE EASEMENT TO LA JOYA WATER SUPPLY CORPORATION ACCORDING TO THIS PLAT.
17. AN OFF-STREET PARKING LOT SITE PLAN AND DRAINAGE PLAN APPROVED BY THE HIDALGO COUNTY PLANNING DEPARTMENT SHALL BE REQUIRED FOR COMMERCIAL INDUSTRIAL & MULTI-FAMILY USE AT THE TIME OF APPLICATION FOR CONSTRUCTION PRIOR TO THE ISSUANCE OF A BUILDING AND/OR DEVELOPMENT PERMIT. NO WATER OR LIGHT CLEARANCES SHALL BE UNTIL THE SITE PLAN, DRAINAGE PLAN AND OSSF PLAN ARE APPROVED AND PROPOSED IMPROVEMENTS ARE CONSTRUCTED IN ACCORDANCE WITH COUNTY AND STATE STANDARDS.
18. IF THE PURCHASER(S) OF A LOT REQUIRES A COMMERCIAL LOT AND SUBSEQUENTLY DETERMINE THAT A LARGER METER IS REQUIRED, THEN THE LUE WILL NEED TO BE CALCULATED AND APPROPRIATE FEES ON THE UPGRADE MUST BE PAID TO THE CORPORATION PRIOR TO THE INITIATION OF SERVICE ON SUCH LARGER METER(S). THE DEVELOPER WILL NEED TO ADVISE PURCHASERS OF THIS OBLIGATION.
19. FIRE HYDRANTS INSTALLED WITHIN THE CORPORATION'S DISTRIBUTION SYSTEM ARE PROVIDED AT THE CONVENIENCE OF THE CORPORATION AND DO NOT IMPLY ANY RESPONSIBILITY ON THE PART OF THE CORPORATION TO MEET FIRE FLOW REQUIREMENTS.
20. GARY BURCH THE OWNER & SUBDIVIDER OF ELLIS NO. 5 SUBDIVISION RETAINS AN EASEMENT UPON EACH LOT FOR THE PURPOSE OF INSTALLING AN APPROVED OSSF ON THE LOTS AS DESCRIBED ON SHEET NO. 2 OF THIS PLAT.
21. ANY OTHER LOT USE THAN SINGLE FAMILY REQUIRES PLANNING, HEALTH AND FIRE MARSHAL DEPARTMENTS APPROVAL.
22. IF LOT 1 AND 3 ARE TO BE USED FOR COMMERCIAL PURPOSES, THEN IT SHOULD COMPLY WITH CITY OF MISSION MINIMUM REQUIREMENTS FOR COMMERCIAL LOTS.

HIDALGO COUNTY IRRIGATION DISTRICT NO. 16 EASEMENT LANGUAGE

- 1. ALL IRRIGATION EASEMENTS ARE EXCLUSIVE TO HIDALGO COUNTY IRRIGATION DISTRICT NO. 16, AND THE DISTRICT ALLOWS NO OTHER UTILITIES OR USE WITHOUT EXPRESS APPROVAL.
2. NO UTILITY COMPANY OR OTHER PERSON IS ALLOWED TO CROSS ABOVE OR BELOW GROUND ANY DISTRICT EASEMENT OR RIGHT OF WAY WITH LINES, POLES, OPEN DITCHES OR OTHER USE WITHOUT FIRST OBTAINING A CROSSING PERMIT FROM THE DISTRICT.
3. NO PERMANENT STRUCTURE, (EXAMPLE: FENCES, OR DRIVEWAYS OF ANY CONSTRUCTION) WILL BE ALLOWED TO BE CONSTRUCTED OR EXIST ON ANY DISTRICT EASEMENT OR RIGHT OF WAY WITHOUT WRITTEN APPROVAL BY THE DISTRICT. ANY UNAUTHORIZED STRUCTURE IN THE EASEMENT AREA IS SUBJECT TO REMOVAL.
4. NO UTILITY COMPANY OR OTHER PERSON IS ALLOWED TO CONNECT TO ANY DISTRICT FACILITY WITHOUT FIRST OBTAINING A PERMIT FROM THE IRRIGATION DISTRICT. ANY CONNECTION NOT AUTHORIZED BY THE DISTRICT IS SUBJECT TO REMOVAL.



VICINITY MAP SCALE: 1"=2000'

PENA ENGINEERING logo and contact information: POST OFFICE BOX 4320, McALLEN TEXAS 78502, OFFICE (956) 682-8812, FAX (956) 631-7362.