



The Leader in the Manufacture of Environmentally-safe Roofing & Waterproofing Systems

### Hydro-Stop Premium Coat Product Bid

**Company Name** Facilities Management - Hidalgo County, Texas

**Property Name** Old Juvy / County Medical Examiner Roof by HS

**Building Name or #** Roofs - A, B, C, D & E

**Contract** #08-021JC-01 (Choice Facility Partners - Harris County - HCDE)

**Date** October 18, 2010

**Technical Sales Rep.** Wayne Burtch - 361-739-7586 - 901 Quetzal St, Corpus Christi, TX

Thank you for the opportunity to provide you with a bid for the County to purchase the materials necessary for it to install the Hydro-Stop PremiumCoat system to the roofs identified as Old Juvy/County Medical Examiner roofs. Hydro-Stop's representative has walked the roofs and the list below contains all the material necessary to complete the roofing projects.

The roofs are an estimated 18,830 square feet.

| <u>Quantity</u> | <u>Material Description</u>      | <u>Unit Price</u>   | <u>Line Total</u>  |
|-----------------|----------------------------------|---------------------|--------------------|
| 11              | 6" PremiumCoat Fabric            | \$32.77             | \$360.47           |
| 7               | 12" PremiumCoat Fabric           | \$58.65             | \$410.55           |
| 18              | 40" PremiumCoat Fabric           | \$165.38            | \$2,976.84         |
| 124             | PremiumCoat Foundation 5 gal.    | \$135.70            | \$16,826.80        |
| 53              | PremiumCoat Finish Coat 5 gal.   | \$152.29            | \$8,071.37         |
|                 | Additional Materials from page 2 |                     | \$9,341.50         |
|                 |                                  | <b>Sub-Total</b>    | <b>\$37,987.53</b> |
|                 | *(O&P on non HS items only)      | <b>O&amp;P(20%)</b> | <b>1,505.22*</b>   |
|                 |                                  | <b>Freight</b>      | <b>\$1,343.31</b>  |
|                 |                                  | <b>Total</b>        | <b>\$40,836.06</b> |

| <u>Quantity</u>           | <u>Product</u>            | <u>Unit Price</u>   | <u>Line Total</u> |
|---------------------------|---------------------------|---------------------|-------------------|
| 3                         | BarrierGuard              | 5 gal. \$156.96     | \$470.88          |
| 3                         | StableRust Primer         | 5 gal. \$198.83     | \$596.49          |
| 2                         | ButterGrade               | 5 gal. \$118.45     | \$236.90          |
| 1                         | ClearGuard Plus           | 5 gal. \$162.01     | \$162.01          |
| 148                       | X-board Tapered Poly Iso  | Each \$6.40         | \$947.20          |
| 148                       | Y-board Tapered Poly Iso  | Each \$12.80        | \$1,894.40        |
| 174                       | 2" Poly Iso               | Each \$19.52        | \$3,396.48        |
| 12                        | Brush 4" Flashing         | Each \$3.16         | \$37.92           |
| 6                         | Brush 6" Block            | Each \$4.33         | \$25.98           |
| 18                        | Brush 10" Block           | Each \$8.10         | \$148.80          |
| 24                        | Brush Handle              | Each \$5.81         | \$139.44          |
| 5                         | OlyBond Adhesive          | Case \$225.00       | \$1,125.00        |
| 1                         | Dispensing Gun            | Each \$163.00       | \$163.00          |
| <b>215</b>                | <b>1/2" Densdeck</b>      | <b>Each \$18.24</b> | <b>\$0**</b>      |
| <b>5</b>                  | <b>#12x6" deck screws</b> | <b>Box \$146.60</b> | <b>\$0**</b>      |
| <b>5</b>                  | <b>#12x8" deck screws</b> | <b>Box \$267.75</b> | <b>\$0**</b>      |
| <b>10</b>                 | <b>3" plates</b>          | <b>Box \$68.00</b>  | <b>\$0**</b>      |
| <b>Total from Page 2-</b> |                           |                     | <b>\$9,341.50</b> |

Material sale only. Installation by County, inspections by HS rep.

Conway Trucking (3 days- Shipping is broken into three sections)

|               |                 |
|---------------|-----------------|
| Buildings A&B | \$712.09        |
| Building C    | \$255.68        |
| Buildings D&E | <u>\$375.54</u> |
| Total         | \$1,343.31      |

Total Cost including shipping is **\$40,836.06**

Thank you for this opportunity. Please let me know when you would like to proceed.



John Follis

\*This is added to the non Hydro-Stop products only

**\*\*We will not deliver this. The Quantity section shows what you have to purchase**