

March 15, 2011

RE: ADDENDUM NO. 1
FOR BID No: 5010-65-0311-5000-6500-
UCP-GVG “HIDALGO COUNTY
URBAN COUNTY PROGRAM –
“PROGRESO STREET
IMPROVEMENTS (SHELBY AVENUE)”

Dear Gentlemen:

Attached you will find **ADDENDUM NO. 1, PAGE 1 OF 1** in connection with “**URBAN COUNTY**” - request for sealed bids for “**HIDALGO COUNTY URBAN COUNTY PROGRAM – “PROGRESO STREET IMPROVEMENTS (SHELBY AVENUE)”**”.


Please add this **ADDENDUM NO. 1** to your packet so as to permit your company to submit a complete bid. See original bid packet REQUEST FOR BIDS pages 4 and 5.

Acknowledge receipt of **ADDENDUM No. 1** by signing and returning this notice to us VIA FAX AT (956) 782-2558.

If you do not receive all pages of **ADDENDUM NO. 1** please notify us immediately at (956) 782-2557.


Please be advised that this **ADDENDUM NO. 1** will complete your bid packet for “**HIDALGO COUNTY URBAN COUNTY PROGRAM – “PROGRESO STREET IMPROVEMENTS (SHELBY AVENUE)”**”.

Thank you for your prompt attention on this matter.



Diana Serna, UCP Director

BY: _____
ADDENDUM NO. 1
ACKNOWLEDGEMENT OF RECEIPT



Ramiro Gutierrez, P.E.
R. Gutierrez Engineering Corporation

ADDENDUM NO. 1

October 18, 2010

“HIDALGO COUNTY URBAN COUNTY PROGRAM – “PROGRESO STREET IMPROVEMENTS (SHELBY AVENUE)”.

BID NO.: 5010-65-0311-5000-6500-UCP-GVG
Bid Opening Date: Wednesday, March 23, 2011

PLEASE NOTE CHANGES AS FOLLOWS:

1. Response to questions received:

- Removal of existing concrete pipes is to be considered preparation of Right-of-Way and is not to be paid for directly but shall be considered subsidiary to the various bid items.
- The proposed concrete riprap at the proposed outfall shown on Sheet 5 of 13 is to be constructed as shown on the plan sheet. It will cover both the west and east banks and the bottom of the existing drain ditch.
- Bonds are required for this project.
- Engineer's Estimate for the construction is \$132,000.
- All pipe shall be rubber gasket.
- Backfill for pipe shall be constructed in 6" lifts and shall be tested for compaction. Compaction requirement shall be 95%.
- Lime is to be applied to flexible base course at a rate of 2% by weight. Bid items in the bid proposal include items for lime treating 2,838 SY of subgrade, lime treating 2,742 SY of new base, and for supplying 44 Tons of lime.



3-15-11

FIRM # F-486

I, _____, acknowledge receipt of **ADDENDUM NO. 1** dated, March 15, 2011, for **BID No: 5010-65-0311-5000-6500-UCP-GVG “HIDALGO COUNTY URBAN COUNTY PROGRAM – “PROGRESO STREET IMPROVEMENTS (SHELBY AVENUE)”**

Printed Bidder Name

Date

NOTE: PLEASE SUBMIT THIS ADDENDUM WITH YOUR PACKET, IN ORDER TO COMPLETE THE BID.....