

CHANGE ORDER #2

PROJECT: ROAD & DRAINAGE CONSTRUCTION FOR LA MESA SUBDIVISION

DATE OF ISSUANCE: April 12, 2011 **EFFECTIVE DATE:** _____

OWNER: HIDALGO COUNTY
OWNER's Contract No. C-CAP-10-357-12-13

CONTRACTOR: Asago LLC dba Asago Construction **ENGINEER:** TEDSI INFRASTRUCTURE GROUP

You are directed to make the following changes in the Contract Documents.

Description:

1. Added quantities for two additional driveways/ADS
- 2.
- 3.
- 4.
- 5.
- 6.

Reason for Change Order:

1. Driveways added by residents after surveying/completion of plans
- 2.
- 3.
- 4.
- 5.
- 6.

Attachments: Change Order No 2 Tabulations La Mesa Subdivision

Change in Contract Price:		CHANGE IN CONTRACT TIME:
Original Contract Price \$ 236,531.30		Original Contract Time for Substantial Completion: 210 calendar days or dates
Net Changes from previous Change Order \$ 460.00		Net change from previous Change Orders calendar days
Contract Price prior to this Change Order \$ 236,991.30		Contract Time prior to this Change Order Substantial Completion: 210 calendar days or dates
Net Increase (decrease) of this Change Order \$ 1,200.00		Net Increase (decrease) of this Change Order calendar days
Contract Price with all approved Change Orders \$ 238,191.30	Net % increase (decrease) from original contract price. 0.70 %	Contract Time with all approved Change Orders Substantial Completion: 210 calendar days or dates

RECOMMENDED:
 By: 
 Engineer (Authorized Signature)
 Date: 04/13/2011

APPROVED:
 By: _____
 Owner (Authorized Signature)
 Date: _____

ACCEPTED:
 By: 
 Contractor (Authorized Signature)
 Date: 4/12/11

CHANGE ORDER NO. 2 TABULATION
HIDALGO COUNTY PRECINCT NO. 1 - LA MESA SUBDIVISION (C-CAP-10-357-12-13)

Item	Original Plan Qty	Change Order #1 Qty	Change Order #2 Qty	Revised Plan Qty	Unit	Item Description	Unit Price	Revised Unit Price	Original Contract Cost	Change in Contract Cost of C.O.#1	Revised Contract Cost after C.O.#1	Change in Contract Cost of C.O.#2	Revised Contract Cost after C.O.#2
(905) ROADWAY													
100	26.07			26.07	STA	PREPARING ROW	\$500.00		\$13,035.00	\$0.00	\$13,035.00	\$0.00	\$13,035.00
110	232	-133		99	CY	EXCAVATION (ROADWAY)	\$5.00		\$1,160.00	-\$665.00	\$495.00	\$0.00	\$495.00
132	1139	-707		432	CY	EMBANKMENT (FINAL)(DENS CONT)(TY C)	\$10.00		\$11,390.00	-\$7,070.00	\$4,320.00	\$0.00	\$4,320.00
164	7487			7487	SY	CELL FBR MLCH SEED(PERM)(URBAN)(CLAY)	\$0.40		\$2,994.80	\$0.00	\$2,994.80	\$0.00	\$2,994.80
168	375			375	MG	VEGETATIVE WATERING	\$3.00		\$1,125.00	\$0.00	\$1,125.00	\$0.00	\$1,125.00
247	8321			8321	SY	FL BS (CMP IN PLC)(TY E GR 4)(FNAL POS)	\$5.00		\$41,605.00	\$0.00	\$41,605.00	\$0.00	\$41,605.00
251	8321			8321	SY	REWORK BS MTL (TY D)(5")(DENS CONT)	\$2.00		\$16,642.00	\$0.00	\$16,642.00	\$0.00	\$16,642.00
260	93.8			93.8	TON	LIME(HYD,COM OR QK)(SLRY)OR QK(DRY)	\$160.00		\$15,008.00	\$0.00	\$15,008.00	\$0.00	\$15,008.00
260	8321			8321	SY	LIME TRT(MIX EXST MATL & NEW BASE)(8")	\$2.00		\$16,642.00	\$0.00	\$16,642.00	\$0.00	\$16,642.00
310	1412			1412	GAL	PRIME COAT (MC-30)	\$1.00		\$1,412.00	\$0.00	\$1,412.00	\$0.00	\$1,412.00
340	7055			7055	SY	D-GR HMA(METH) TY-D SAC-B PG76-22	\$7.50		\$52,912.50	\$0.00	\$52,912.50	\$0.00	\$52,912.50
420	5			5	SY	CL A CONC (MISC)(4")	\$50.00		\$250.00	\$0.00	\$250.00	\$0.00	\$250.00
500	1			1	LS	MOBILIZATION	\$1,000.00		\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00
502	4			4	MO	BARRICADES, SIGNS AND TRAFFIC HANDLING	\$700.00		\$2,800.00	\$0.00	\$2,800.00	\$0.00	\$2,800.00
666	4990			4990	LF	REFL PAV MRK TY I (W) 4" (SLD)(100MIL)	\$1.00		\$4,990.00	\$0.00	\$4,990.00	\$0.00	\$4,990.00
666	90			90	LF	REFL PAV MRK TY I (W) 24"(SLD)(100MIL)	\$6.00		\$540.00	\$0.00	\$540.00	\$0.00	\$540.00
666	510			510	LF	REFL PAV MRK TY I (Y) 4" (BRK)(100MIL)	\$1.00		\$510.00	\$0.00	\$510.00	\$0.00	\$510.00
666	960			960	LF	REFL PAV MRK TY I (Y) 4" (SLD)(100MIL)	\$1.00		\$960.00	\$0.00	\$960.00	\$0.00	\$960.00
Total Roadway:									\$184,976.30	-\$7,735.00	\$177,241.30	\$0.00	\$177,241.30
(906) DRAINAGE													
110	0	135		135	CY	EXCAVATION (ROADWAY)	\$5.00		\$0.00	\$675.00	\$675.00	\$0.00	\$675.00
132	0	752		752	CY	EMBANKMENT (FINAL)(DENS CONT)(TY C)	\$10.00		\$0.00	\$7,520.00	\$7,520.00	\$0.00	\$7,520.00
464	288			288	LF	RC PIPE (CL III)(18 IN)	\$30.00		\$8,640.00	\$0.00	\$8,640.00	\$0.00	\$8,640.00
506	156			156	LF	TEMPORARY SEDIMENT CONTROL FENCE	\$2.00		\$312.00	\$0.00	\$312.00	\$0.00	\$312.00
530	521			521	SY	DRIVEWAYS (CONC)	\$18.00		\$9,378.00	\$0.00	\$9,378.00	\$0.00	\$9,378.00
530	940		40	980	SY	DRIVEWAYS (ACP)	\$15.00		\$14,100.00	\$0.00	\$14,100.00	\$600.00	\$14,700.00
556	1275		40	1315	LF	15" ADS CORRUGATED PIPE	\$15.00		\$19,125.00	\$0.00	\$19,125.00	\$600.00	\$19,725.00
Total Drainage:									\$51,555.00	\$8,195.00	\$59,750.00	\$1,200.00	\$60,950.00
GRAND TOTAL:									\$236,531.30	\$460.00	\$236,991.30	\$1,200.00	\$238,191.30