



PLANNING DEPARTMENT
County Of Hidalgo

Raul E. Sesin, P.E., CFM
PLANNING ADMINISTRATOR

June 21, 2011

Commissioner Hector "Tito" Palacios
Hidalgo County Precinct No. 2
301 W. Hall Acres Road
Pharr, Texas 78577

RE: Tower Road Phase 1 Road and Drainage Improvements Project
Bid No. 2011-044-06-15-MSS

Dear Commissioner Palacios;

Bids were received and opened for the Tower Road Phase I Road and Drainage Improvements Project, Bid No. 2011-044-06-15-MSS on June 15, 2011. A total of four bids were received with Saenz Utility Contractors, Ltd., being the low bidder for the base bid and Alternate No. 3 and Mission Paving Company, Inc. being the low bidder for Alternate No. 1. Saenz Utility Contractors, Ltd. Base bid is \$223,262.97 and Alternate No. 3 bid is \$42,550.00. Mission Paving Company, Inc. Alternate No. 1 bid is \$225,690.90. Attached is a copy of the bid comparison for your review.

This project involves the reconstruction of Tower Road with Drainage Improvements from Minnesota Road North to Owassa Road. Saenz Utility Contractors, Ltd., and Mission Paving Company, Inc. have constructed several projects within Hidalgo County. We recommend awarding Saenz Utility Contractors, Ltd. for the base bid in the amount of \$223,262.97 and Alternate No. 3 in the amount of \$42,550.00 and Mission Paving Company, Inc. for Alternate No. 1 in the amount of \$225,690.90.

If you have any questions or require further information, please feel free to contact me at your convenience.

Respectfully,
HIDALGO COUNTY PLANNING DEPARTMENT

Raul E. Sesin, P.E., C.F.M.
Planning Administrator

BID COMPARISON FORM
HIDALGO COUNTY PRECINCT No. 2
PROJECT # 2011-044-06-15-MSS
TOWER ROAD PHASE I ROAD AND DRAINAGE IMPROVEMENTS

BASE BID

BASE BID											
SAENZ UTILITY ASAGO CONST. MISSION PAVING DOS LOGISTICS											
Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
1	PRIME COAT (MC-30) ENTIRE BASE AND LEAVE READY FOR HMAC INSTALLATION (ESTIMATED 3,760 GAL.)	18,802	SY	\$ 0.80	\$ 15,041.60	\$ 1.50	\$ 28,203.00	\$ 1.35	\$ 25,382.70	\$ 1.45	\$ 27,262.90
2	10" COMPACTED CALICHE (LABOR ONLY)	11,380	SY	\$ 2.00	\$ 22,760.00	\$ 5.00	\$ 56,900.00	\$ 3.59	\$ 40,854.20	\$ 0.97	\$ 11,038.60
3	5" COMPACTED CALICHE (LABOR ONLY)	9,896	SY	\$ 2.92	\$ 28,896.32	\$ 3.00	\$ 29,688.00	\$ 2.05	\$ 20,286.80	\$ 1.61	\$ 15,932.56
4	6" CONCRETE APRON AROUND TYPE "CC" INLET CONNECTED TO CURB AND GUTTER	2	EA	\$ 500.00	\$ 1,000.00	\$ 3,000.00	\$ 6,000.00	\$ 715.00	\$ 1,430.00	\$ 619.14	\$ 1,238.28
5	EXCAVATE, TREAT AND REWORK EXISTING ROAD SECTION TO ACHIEVE PROPOSED 10" FINISHED BASE	21,275	SY	\$ 2.90	\$ 61,697.50	\$ 2.00	\$ 42,550.00	\$ 4.65	\$ 98,928.75	\$ 3.66	\$ 77,866.50
6	TRAFFIC CONTROL	1	LS	\$ 8,000.00	\$ 8,000.00	\$ 8,000.00	\$ 8,000.00	\$ 22,765.00	\$ 22,765.00	\$ 10,658.19	\$ 10,658.19
7	TYPE "A" BARRIER CONCRETE CURB AND GUTTER	7,901	LF	\$ 5.25	\$ 41,480.25	\$ 8.00	\$ 63,208.00	\$ 5.00	\$ 39,505.00	\$ 8.76	\$ 69,212.76
8	4" COMPACTED CALICHE BASE FOR ASPHALT DRIVEWAY WITH PRIME COAT	1,274	SY	\$ 4.05	\$ 5,159.70	\$ 8.00	\$ 10,192.00	\$ 12.15	\$ 15,479.10	\$ 6.27	\$ 7,987.98
9	4" CONCRETE DRIVEWAY	2,352	SF	\$ 3.30	\$ 7,761.60	\$ 4.00	\$ 9,408.00	\$ 3.65	\$ 8,584.80	\$ 33.40	\$ 78,556.80
10	6 FT CONCRETE VALLEY GUTTER	252	LF	\$ 20.50	\$ 5,166.00	\$ 35.00	\$ 8,820.00	\$ 26.10	\$ 6,577.20	\$ 26.84	\$ 6,763.68
11	PERMANENT PAVEMENT MARKINGS INCLUDING BUT NOT LIMITED TO THERMOPLASTIC 4" YELLOW SOLID AND CENTER LINES, 4" WHITE EDGE LINE, 24" WHITE STOP LINE, LEFT HAND TURN WITH WORDING, TYPE I-C OR II-C-R AND TYPE IIAA RAISED PAVEMENT MARKERS, AND 24" YELLOW SOLID LINES AND TRAFFIC DIRECTION ARROWS	1	LS	\$ 13,800.00	\$ 13,800.00	\$ 10,000.00	\$ 10,000.00	\$ 21,835.00	\$ 21,835.00	\$ 33,248.47	\$ 33,248.47
12	EROSION AND SEDIMENT CONTROL STRUCTURAL	1	LS	\$ 12,500.00	\$ 12,500.00	\$ 2,000.00	\$ 2,000.00	\$ 7,500.00	\$ 7,500.00	\$ 4,698.15	\$ 4,698.15
BASE BID TOTAL					\$ 223,262.97		\$ 274,969.00		\$ 309,128.55		\$344,464.87
ADD ALTERNATE No. 1											
1	18" RCP-RJ CL III	846	LF	\$ 38.00	\$ 32,148.00	\$ 30.00	\$ 25,380.00	\$ 35.25	\$ 29,821.50	\$ 21.73	\$ 18,383.58
2	24" RCP-RJ CL III	254	LF	\$ 42.00	\$ 10,668.00	\$ 40.00	\$ 10,160.00	\$ 30.10	\$ 7,645.40	\$ 24.48	\$ 6,217.92
3	30" RCP-RJ CL III	2,646	LF	\$ 52.00	\$ 137,592.00	\$ 50.00	\$ 132,300.00	\$ 37.50	\$ 99,225.00	\$ 41.60	\$110,073.60

Item No.	Item Description	Estimated Quantity	Unit	SAENZ UTILITY		ASAGO CONST.		MISSION PAVING		DOS LOGISTICS	
				Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
4	TRENCH PROTECTION	3,746	LF	\$ 2.00	\$ 7,492.00	\$ 2.00	\$ 7,492.00	\$ 1.50	\$ 5,619.00	\$ 1.16	\$ 4,345.36
5	MANHOLES	2	EA	\$ 2,800.00	\$ 5,600.00	\$ 3,000.00	\$ 6,000.00	\$ 1,800.00	\$ 3,600.00	\$ 3,059.71	\$ 6,119.42
6	TYPE "F" INLETS WITH ONE EXTENSION	14	EA	\$ 4,500.00	\$ 63,000.00	\$ 4,000.00	\$ 56,000.00	\$ 4,025.00	\$ 56,350.00	\$ 3,717.03	\$ 52,038.42
7	18" SAFETY END TREATMENT	6	EA	\$ 1,000.00	\$ 6,000.00	\$ 1,000.00	\$ 6,000.00	\$ 800.00	\$ 4,800.00	\$ 882.87	\$ 5,297.22
8	RE-GRADE ROADSIDE DITCH AND RE-LAY CULVERT PIPES AS PER PLANS	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 12,000.00	\$ 12,000.00	\$ 3,430.00	\$ 3,430.00	\$ 10,686.79	\$ 10,686.79
9	TYPE "F" SPL - 1 INLETS WITH ONE EXTENSION	4	EA	\$ 5,500.00	\$ 22,000.00	\$ 4,000.00	\$ 16,000.00	\$ 3,800.00	\$ 15,200.00	\$ 3,871.00	\$ 15,484.00
ADD ALTERNATE NO. 1 TOTAL					\$ 299,500.00		\$ 271,332.00		\$ 225,690.90		\$228,646.31
ADD ALTERNATE No. 2											
1	TENSAR TX 5 TriAx GEOGRID (LABOR ONLY)	21,275	SY	\$ 1.20	\$ 25,530.00	\$ 2.00	\$ 42,550.00	\$ 0.35	\$ 7,446.25	\$ 0.32	\$ 6,808.00
ADD ALTERNATE NO. 2 TOTAL					\$ 25,530.00		\$ 42,550.00		\$ 7,446.25		\$ 6,808.00
ADD ALTERNATE No. 3											
1	TENSAR TX 5 TriAx GEOGRID (MATERIAL AND LABOR)	21,275	SY	\$ 2.00	\$ 42,550.00	\$ 7.00	\$ 148,925.00	\$ 3.80	\$ 80,845.00	\$ 4.35	\$ 92,546.25
ADD ALTERNATE NO. 3 TOTAL					\$ 42,550.00		\$ 148,925.00		\$ 80,845.00		\$ 92,546.25
ADD ALTERNATE No. 4											
1	CELL FIBER MULCH SEEDING (PERM)(URBAN)(CLAY)	13,922	SY	\$ 0.50	\$ 6,961.00	\$ 0.60	\$ 8,353.20	\$ 1.50	\$ 20,883.00	\$ 0.48	\$ 6,682.56
ADD ALTERNATE NO. 4 TOTAL					\$ 6,961.00		\$ 8,353.20		\$ 20,883.00		\$ 6,682.56
ADD ALTERNATE No. 5											
1	PERMANENT STOP TRAFFIC SIGN (RI-4)	11	EA	\$ 500.00	\$ 5,500.00	\$ 350.00	\$ 3,850.00	\$ 351.00	\$ 3,861.00	\$ 78.59	\$ 864.49
2	PERMANENT STOP AHEAD TRAFFIC SIGN (W3-1)	4	EA	\$ 500.00	\$ 2,000.00	\$ 350.00	\$ 1,400.00	\$ 330.00	\$ 1,320.00	\$ 152.81	\$ 611.24
3	PERMANENT CENTER LANE TURN ONLY TRAFFIC SIGN (R3-9B)	2	EA	\$ 300.00	\$ 600.00	\$ 350.00	\$ 700.00	\$ 310.00	\$ 620.00	\$ 74.10	\$ 148.20
4	PERMANENT RIGHT LANE MUST TURN RIGHT TRAFFIC	1	EA	\$ 300.00	\$ 300.00	\$ 350.00	\$ 350.00	\$ 330.00	\$ 330.00	\$ 77.01	\$ 77.01
ADD ALTERNATE NO. 5 TOTAL					\$ 8,400.00		\$ 6,300.00		\$ 6,131.00		\$ 1,700.94

