

CHANGE ORDER NUMBER ONE (1)

PROJECT: ROAD & DRAINAGE CONSTRUCTION OF EL GATO ROAD IMPROVEMENTS

DATE OF ISSUANCE: ~~January 11, 2012~~ 2/7/12 **EFFECTIVE DATE:** ~~January 11, 2012~~ 2/7/12

OWNER: HIDALGO COUNTY PRECINCT No. 2

CONTRACTOR: ASAGO CONSTRUCTION **ENGINEER:** R. Gutierrez Engineering Corporation
 2113 Pecos 130 E. Park Ave.
 Mission, TX 78572 Pharr, TX 78577

You are directed to make the following changes in the Contract Documents.

Description:

1. Conc. Curb & Gutter (Ty A)(Barrier) reduced by 139 LF
2. Conc. Valley Gutter (6-Ft) reduced by 110 LF
3. Turnout (Asphalt Concrete Pavement) reduced by 78 SY
4. Curb Ramps (TY 9) reduced by 2 EA
5. Sidewalk (Conc) (5-Ft) reduced by 40 SY
6. Add 7939 LF 4" Solid Yellow (Temp.)
7. Add 610 LF 4" Broken White (Temp.)
8. Add 2325 LF 4" Solid White (Temp.)
9. Add 98 LF 8" Solid White (Temp.)
10. Add 117 LF 24" Solid White (Temp.)
11. Add 428 LF Elim. Exist. Marking (4")
12. Relocate Fence at station 40+00
13. Relocate Structures at station 41+50
14. 57 additional days added to contract time

Reason:

1. thru 5. Items reduced due to field modifications due to work being done by other contractor.
6. thru 11. Items added due to the need for temporary striping during construction that was not part of original plans.
12. thru 13. Items need to be relocated for construction of north half of road
14. Time added to contract for following reasons:
 - 15 days where it either rained or conditions were to wet to work between start of project and January 10, 2012
 Raining on: 10/7, 11/15, 12/10, 12/11, 12/12, and 12/15/2011
 To wet to work on: 10/8, 10/9, 11/3, 12/13, 12/14, 12/15, and 12/19/2011
 - 11 days for County Holidays (Thanksgiving, Christmas, & New Years) where county could not deliver materials required for construction
 - 21 days major construction of project delays due to delay by TXDOT to issue driveway permit for FM907
 - 10 days for delay due to "poles to be moved by others" not being removed in a timely manner

Attachments:

Change in Contract Price:		CHANGE IN CONTRACT TIME:	
Original Contract Price	Original Contract Time for		
\$ 643,798.80	Substantial Completion:	120	calendar days or dates
Net Changes from previous Change Order	Net change from previous Change Orders	0	calendar days
\$ 0.00	Contract Time prior to this Change Order		
Contract Price prior to this Change Order	Substantial Completion:	120	calendar days or dates
\$ 643,798.80	Net Increase (decrease) of this Change Order	57	calendar days
Net Increase (decrease) of this Change Order	Contract Time with all approved Change Orders		
\$ 6,413.00	Substantial Completion:	177	calendar days or dates
Contract Price with all approved Change Orders	Net % increase (decrease) from original contract price.	1.00	%
\$ 650,211.80			

RECOMMENDED:
 By: *Ram [Signature]* P.E.
 Engineer (Authorized Signature)
 Date: January 11, 2012

APPROVED:
 By: _____
 Owner (Authorized Signature)
 Date: _____

ACCEPTED:
 By: *[Signature]*
 Contractor (Authorized Signature)
 Date: January 11, 2012

CHANGE ORDER NO. 1 TABULATION
HIDALGO COUNTY PRECINCT No. 2
ROAD & DRAINAGE CONSTRUCTION OF EL GATO ROAD IMPROVEMENTS

Item Number	Original Plan Quantity	Change Order #1 Quantities	Unit	Item Description	Unit Price	Revised Unit Price	Original Contract Cost	Change in Contract Cost of C.O.#1	Revised Contract Cost after C.O.#1
ROADWAY									
100	38.98	38.98	STA	Preparation of Right-of-Way	\$ 60.00	\$ 60.00	\$ 2,338.80	0.00	2,338.80
110	18,717.00	18,717.00	CY	Excavation (Roadway)	\$ 2.00	\$ 2.00	\$ 37,434.00	0.00	37,434.00
132	318.00	318.00	CY	Embankment (Final) (Esns. Cont.) (Ty C)	\$ 15.00	\$ 15.00	\$ 4,770.00	0.00	4,770.00
164	6,705.00	6,705.00	SY	Cell Fbr Mlch Seed (Temp)(Warm)	\$ 0.50	\$ 0.50	\$ 3,352.50	0.00	3,352.50
164	6,705.00	6,705.00	SY	Cell Fbr Mlch Seed (Temp)(Cool)	\$ 0.50	\$ 0.50	\$ 3,352.50	0.00	3,352.50
164	13,410.00	13,410.00	SY	Cell Fbr Mlch Seed (Perm)(Rural)(Clay)	\$ 0.50	\$ 0.50	\$ 6,705.00	0.00	6,705.00
247	23,067.00	23,067.00	SY	Flexible Base (Mat'l Supplied by County) (8")	\$ 1.00	\$ 1.00	\$ 23,067.00	0.00	23,067.00
260	24,309.00	24,309.00	SY	Lime Trt (Exst Mat'l)(12")	\$ 1.50	\$ 1.50	\$ 36,463.50	0.00	36,463.50
260	23,067.00	23,067.00	SY	Lime Treat(New Base)(8")	\$ 1.50	\$ 1.50	\$ 34,600.50	0.00	34,600.50
260	716.00	716.00	TON	Lime (Slurry or Commercial Slurry)	\$ 170.00	\$ 170.00	\$ 121,720.00	0.00	121,720.00
310	6,265.00	6,265.00	GAL	Prime Coat (MC-30)	\$ 6.00	\$ 6.00	\$ 37,590.00	0.00	37,590.00
400	55.20	55.20	SY	Cut & Restore Pavement	\$ 50.00	\$ 50.00	\$ 2,760.00	0.00	2,760.00
402	1,034.00	1,034.00	LF	Trench Excav Protection	\$ 1.00	\$ 1.00	\$ 1,034.00	0.00	1,034.00
432	2.00	2.00	CY	Concrete Riprap (CL C)	\$ 2,000.00	\$ 2,000.00	\$ 4,000.00	0.00	4,000.00
464	132.00	132.00	LF	RC Pipe (CL III) (18")	\$ 50.00	\$ 50.00	\$ 6,600.00	0.00	6,600.00
464	146.00	146.00	LF	RC Pipe (CL III) (24")	\$ 55.00	\$ 55.00	\$ 8,030.00	0.00	8,030.00
464	667.00	667.00	LF	RC Pipe (CL III) (30")	\$ 75.00	\$ 75.00	\$ 50,025.00	0.00	50,025.00
464	345.00	345.00	LF	RC Pipe (CL III) (36")	\$ 100.00	\$ 100.00	\$ 34,500.00	0.00	34,500.00
465	1.00	1.00	EA	Inlet (Complete) (Ty A)	\$ 3,500.00	\$ 3,500.00	\$ 3,500.00	0.00	3,500.00
465	8.00	8.00	EA	Inlet (Complete) (Ty F)	\$ 5,000.00	\$ 5,000.00	\$ 40,000.00	0.00	40,000.00
465	5.00	5.00	EA	Inlet Extension	\$ 700.00	\$ 700.00	\$ 3,500.00	0.00	3,500.00
465	3.00	3.00	EA	Manhole (Complete) (Ty A)	\$ 3,000.00	\$ 3,000.00	\$ 9,000.00	0.00	9,000.00
506	168.00	168.00	SY	Construction Exits (TY 2) (Install)	\$ 8.00	\$ 8.00	\$ 1,344.00	0.00	1,344.00
506	168.00	168.00	SY	Construction Exits (Remove)	\$ 4.00	\$ 4.00	\$ 672.00	0.00	672.00
529	7,749.00	7,610.00	LF	Conc. Curb & Gutter (Ty A)(Barrier)	\$ 8.00	\$ 8.00	\$ 61,992.00	(1,112.00)	60,880.00
529	600.00	490.00	LF	Conc. Valley Gutter (6-Ft)	\$ 8.00	\$ 8.00	\$ 4,800.00	(880.00)	3,920.00
530	878.00	878.00	SY	Driveways (Asphalt Concrete Pavement)	\$ 20.00	\$ 20.00	\$ 17,560.00	0.00	17,560.00
530	18.70	18.70	SY	Driveways (Brick Pavers)	\$ 50.00	\$ 50.00	\$ 935.00	0.00	935.00
530	429.60	351.60	SY	Turnout (Asphalt Concrete Pavement)	\$ 20.00	\$ 20.00	\$ 8,592.00	(1,560.00)	7,032.00
531	10.00	8.00	EA	Curb Ramps (TY 9)	\$ 700.00	\$ 700.00	\$ 7,000.00	(1,400.00)	5,600.00
531	520.00	480.00	SY	Sidewalk (Conc) (5-Ft)	\$ 40.00	\$ 40.00	\$ 20,800.00	(1,600.00)	19,200.00
644	14.00	14.00	EA	Install Small Roadside Sign Supp & Assem Ty S80 (1) SA(P)	\$ 400.00	\$ 400.00	\$ 5,600.00	0.00	5,600.00
644	8.00	8.00	EA	Remove Small Roadside Sign Supp & Assem	\$ 100.00	\$ 100.00	\$ 800.00	0.00	800.00
666	1,930.00	1,930.00	LF	Refl Pav Mrk Ty 1 (W)(4") (Brk)(100Mil)	\$ 1.00	\$ 1.00	\$ 1,930.00	0.00	1,930.00
666	250.00	250.00	LF	Refl Pav Mrk Ty 1 (W)(8") (Slid)(100 Mil)	\$ 3.00	\$ 3.00	\$ 750.00	0.00	750.00
666	8,900.00	8,900.00	LF	Refl Pav Mrk Ty 1 (Y) (4") (Slid) (100Mil)	\$ 1.00	\$ 1.00	\$ 8,900.00	0.00	8,900.00
666	568.00	568.00	LF	Refl Pav Mrk Ty 1 (W) (24") (Slid) (100Mil)	\$ 7.00	\$ 7.00	\$ 3,976.00	0.00	3,976.00
666	152.00	152.00	LF	Refl Pav Mrk Ty 1 (Y) (24") (Slid) (100Mil)	\$ 7.00	\$ 7.00	\$ 1,064.00	0.00	1,064.00
668	4.00	4.00	EA	Prefab Pav Mrk Ty B (W) (Word)	\$ 300.00	\$ 300.00	\$ 1,200.00	0.00	1,200.00
668	10.00	10.00	EA	Prefab Pav Mrk Ty B (W) (Arrow)	\$ 300.00	\$ 300.00	\$ 3,000.00	0.00	3,000.00
672	193.00	193.00	EA	Refl Pav Mrk (Ty 1-C)	\$ 3.00	\$ 3.00	\$ 579.00	0.00	579.00
672	222.00	222.00	EA	Refl Pav Mrk (Ty II A-A)	\$ 3.00	\$ 3.00	\$ 666.00	0.00	666.00
8531	2.00	2.00	EA	Solar Powered School Zone Sign & Assembly	\$ 6,000.00	\$ 6,000.00	\$ 12,000.00	0.00	12,000.00
502	4.00	4.00	MO	Barricades, Signs and Traffic Handling	\$ 1,000.00	\$ 1,000.00	\$ 4,000.00	0.00	4,000.00
506	324.00	324.00	LF	Temporary Sediment Control Fence	\$ 4.00	\$ 4.00	\$ 1,296.00	0.00	1,296.00
662	0.00	7,939.00	LF	4" Solid Yellow (Temp.)	\$ 1.00	\$ 1.00	\$ -	7,939.00	7,939.00
662	0.00	610.00	LF	4" Broken White (Temp.)	\$ 1.00	\$ 1.00	\$ -	610.00	610.00
662	0.00	2,325.00	LF	4" Solid White (Temp.)	\$ 1.00	\$ 1.00	\$ -	2,325.00	2,325.00
662	0.00	98.00	LF	8" Solid White (Temp.)	\$ 3.00	\$ 3.00	\$ -	294.00	294.00
662	0.00	117.00	LF	24" Solid White (Temp.)	\$ 7.00	\$ 7.00	\$ -	819.00	819.00
677	0.00	428.00	LF	Elim. Exist. Marking (4")	\$ 1.00	\$ 1.00	\$ -	428.00	428.00
550	0.00	1.00	LS	Relocate Fence (Sta 40 + 00)	\$ 350.00	\$ 350.00	\$ -	350.00	350.00
496	0.00	1.00	LS	Relocate Structures (Sta 41 + 50)	\$ 200.00	\$ 200.00	\$ -	200.00	200.00
TOTAL BASE AMOUNTS:							\$ 643,798.80	\$ 6,413.00	\$ 650,211.80