

**CHANGE ORDER #1**

**PROJECT:** ROAD & DRAINAGE CONSTRUCTION FOR MID VALLEY ESTATES SUBDIVISION

**DATE OF ISSUANCE:** August 31, 2012 **EFFECTIVE DATE:** September 11, 2012

**OWNER:** HIDALGO COUNTY  
**OWNER's Contract No.** C-CAP-12-049-05-01

**CONTRACTOR:** Asago, LLC dba Asago Construction **ENGINEER:** TEDSI INFRASTRUCTURE GROUP

**You are directed to make the following changes in the Contract Documents.**

- Description:**
1. Alma - split driveway 13 (35SY ACP+25'ADS) into 13 (20SY ACP+20'ADS) and 13A (20SY ACP+20'ADS)
  2. Alma - change driveways 5 from 20 SY ACP to 20 SY CONC and 18 from 23 SY CONC to 23 SY ACP
  3. Alma - add driveway 28 at STA 8+25 RT (20SY ACP+20'ADS)
  4. Carol - remove driveways 8 (20SY ACP+20'ADS) and 16 (23SY ACP+20'ADS). Existing drwys to remain.
  5. Evelyn - add driveway 1A at STA 0+50 RT (20SY ACP). Ditch to start north of driveway 1A
  6. Evelyn - add driveway 5A at STA 2+75 RT (20SY ACP+20'ADS)

- Reason for Change Order:**
1. Driveway constructed after survey/design was completed
  2. Match existing driveway type
  3. Driveway constructed after survey/design was completed
  4. Driveway improvements not needed
  5. Driveway constructed after survey/design was completed
  6. Driveway constructed after survey/design was completed

**Attachments:** Change Order No 1 Tabulations Mid Valley Estates Subdivision.

Change in Contract Price:		CHANGE IN CONTRACT TIME:	
Original Contract Price \$ 327,181.08		Original Contract Time for Substantial Completion: <u>210</u> calendar days or dates	
Net Changes from previous Change Order \$ 0.00		Net change from previous Change Orders calendar days	
Contract Price prior to this Change Order \$ 327,181.08		Contract Time prior to this Change Order Substantial Completion: <u>210</u> calendar days or dates	
Net Increase (decrease) of this Change Order \$ 685.00		Net Increase (decrease) of this Change Order <u>0</u> calendar days	
Contract Price with all approved Change Orders \$ 327,866.08	Net % increase (decrease) from original contract price. 0.21 %	Contract Time with all approved Change Orders Substantial Completion: <u>210</u> calendar days or dates	

**RECOMMENDED:**  
 By: [Signature]  
 Engineer (Authorized Signature)

**APPROVED:**  
 By: \_\_\_\_\_  
 Owner (Authorized Signature)

**ACCEPTED:**  
 By: [Signature]  
 Contractor (Authorized Signature)

Date: 08/31/2012

Date: \_\_\_\_\_

Date: 8/31/2012

**CHANGE ORDER NO. 1 TABULATION**  
**HIDALGO COUNTY PRECINCT NO. 1 - MID VALLEY ESTATES SUBDIVISION (C-CAP-12-049-05-01)**

Item	Original Plan Qty	Change Order #1 Qty	Unit	Item Description	Unit Price	Revised Unit Price	Original Contract Cost	Change in Contract Cost of C.O.#1	Revised Contract Cost after C.O.#1	
<b>(905) ROADWAY</b>										
100	21.37		STA	PREPARING ROW	\$540.00		\$11,539.80	\$0.00	\$11,539.80	
110	1405		CY	EXCAVATION (ROADWAY)	\$9.00		\$12,645.00	\$0.00	\$12,645.00	
132	56		CY	EMBANKMENT (FINAL)(ORD COMP)(TY C)	\$10.00		\$560.00	\$0.00	\$560.00	
164	6376		SY	CELL FBR MLCH SEED (PERM)(URBAN)(CLAY)	\$0.50		\$3,188.00	\$0.00	\$3,188.00	
168	321		MG	VEGETATIVE WATERING	\$3.00		\$963.00	\$0.00	\$963.00	
247	6885		SY	FL BS (CMP IN PLC)(TY E GR 4)(FNAL POS)	\$8.00		\$55,080.00	\$0.00	\$55,080.00	
251	5354		SY	REWORKS BS MTL (TY D)(8")(DENS CONT)	\$2.00		\$10,708.00	\$0.00	\$10,708.00	
260	1652		SY	LIME TRT(EXST MATL)(6")-SUBGRADE	\$3.00		\$4,956.00	\$0.00	\$4,956.00	
260	51.8		TON	LIME(HYD,COM OR QK)(SLRY)OR QK(DRY)-FLEXBASE	\$200.00		\$10,360.00	\$0.00	\$10,360.00	
260	12.3		TON	LIME(HYD,COM OR QK)(SLRY)OR QK(DRY)-SUBGRADE	\$200.00		\$2,460.00	\$0.00	\$2,460.00	
260	1531		SY	LIME TRT(NEW BASE)(8")-FLEXBASE	\$2.00		\$3,062.00	\$0.00	\$3,062.00	
260	5354		SY	LIME TRT(MIX EXST MATL&NEW BASE)(8")-REWOR	\$2.00		\$10,708.00	\$0.00	\$10,708.00	
310	1379		GAL	PRIME COAT (MC-30)	\$7.00		\$9,653.00	\$0.00	\$9,653.00	
340	5831		SY	D-GR HMA(METH) TY-D SAC-B PG64-22	\$6.00		\$34,986.00	\$0.00	\$34,986.00	
500	1		LS	MOBILIZATION	\$2,027.28		\$2,027.28	\$0.00	\$2,027.28	
502	5		MO	BARRICADES, SIGNS AND TRAFFIC HANDLING	\$200.00		\$1,000.00	\$0.00	\$1,000.00	
666	3950		LF	REFL PAV MRK TY I (W) 4" (SLD)(100MIL)	\$0.75		\$2,962.50	\$0.00	\$2,962.50	
666	54		LF	REFL PAV MRK TY I (W) 24" (SLD)(100MIL)	\$7.00		\$378.00	\$0.00	\$378.00	
666	430		LF	REFL PAV MRK TY I (W) 4" (BRK)(100MIL)	\$0.75		\$322.50	\$0.00	\$322.50	
666	772		LF	REFL PAV MRK TY I (W) 4" (SLD)(100MIL)	\$0.75		\$579.00	\$0.00	\$579.00	
<b>Total Roadway:</b>								<b>\$178,138.08</b>	<b>\$0.00</b>	<b>\$178,138.08</b>
<b>(906) DRAINAGE</b>										
402	1019		LF	TRENCH EXCAVATION PROTECTION	\$1.00		\$1,019.00	\$0.00	\$1,019.00	
464	76		LF	RC PIPE (CL III)(18 IN)	\$35.00		\$2,660.00	\$0.00	\$2,660.00	
464	418		LF	RC PIPE (CL III)(24 IN)	\$45.00		\$18,810.00	\$0.00	\$18,810.00	
464	561		LF	RC PIPE (CL III)(30 IN)	\$60.00		\$33,660.00	\$0.00	\$33,660.00	
465	4		EA	INLET (COMPL)(TY H)	\$4,500.00		\$18,000.00	\$0.00	\$18,000.00	
465	1		EA	MANH (COMPL)(TY M)	\$4,500.00		\$4,500.00	\$0.00	\$4,500.00	
465	3		EA	MANH (COMPL)(TY A)	\$3,500.00		\$10,500.00	\$0.00	\$10,500.00	
506	169		LF	TEMPORARY SEDIMENT CONTROL FENCE	\$1.00		\$169.00	\$0.00	\$169.00	
530	124	-3	SY	DRIVEWAY (CONC)	\$30.00		\$3,720.00	-\$90.00	\$3,630.00	
530	1395	25	SY	DRIVEWAY (ACP)	\$19.00		\$26,505.00	\$475.00	\$26,980.00	
556	1475	15	LF	15" ADS CORRUGATED PIPE	\$20.00		\$29,500.00	\$300.00	\$29,800.00	
<b>Total Drainage:</b>								<b>\$149,043.00</b>	<b>\$685.00</b>	<b>\$149,728.00</b>
<b>GRAND TOTAL:</b>								<b>\$327,181.08</b>	<b>\$685.00</b>	<b>\$327,866.08</b>