

**EXHIBIT "B"**

**BID PAGE**

**HIDALGO COUNTY-URBAN COUNTY PROGRAM**  
**"HILLCREST TERRACE SUBDIVISION AND SANTA CRUZ RANCHETTES -**  
**SANITARY SEWER IMPROVEMENT PROJECT"**  
**BID NO.: 6539-67-6590-5000-6700-UCP-EG**

**SCOPE OF WORK DESCRIPTION:**  
**PROVIDE BIDS FOR THE INSTALLATION OF FIRST TIME SEWER SERVICE,**  
**SEPTIC TANK DECOMMISSION, AND YARD LINES FOR TWO ECONOMICALLY**  
**DISADVANTAGE COMMUNITIES IN NORTHEAST HIDALGO COUNTY**

BID PRICE: \$ 443,425.<sup>65</sup>

ALTERNATE PRICE: \$ 18,251.<sup>03</sup>

**OPENED**  
9:39  
10-03-12  
**Witnessed**

BIDDER/COMPANY NAME: REM Construction Inc.

ADDRESS: 9612 N. Stewart Rd.

CITY/STATE/ZIP CODE: MISSION TX 78573

PHONE & FAX NO.'S: (956) 580-2675, (956) 580-4032

CELLULAR & BEEPER NO.'S: (956) 537-1287

AUTHORIZED SIGNATURE: *Miguel A. Ramos*

PRINTED NAME: Miguel A. Ramos

TITLE: President

Document 00405

## SCHEDULE OF UNIT PRICE WORK

This Document, constitutes a Supplement to Document 00310 - Form of Proposal.  
When a Contract is awarded, this Document becomes a supplement to the CONTRACT Between Owner and Contractor.

ITEM NO.	ITEM DESCRIPTION	UNIT	UNIT QTY.	UNIT PRICE IN FIGURES <sup>(1)</sup>	TOTAL FIGURES
General Project					
1-1	Mobilization, Bonds and Insurance (not to exceed 3% of Total Bid) and project signage.	LS	1	8,800. <sup>00</sup>	8,800. <sup>00</sup>
1-2	Construction Staking	LS	1	2,700. <sup>00</sup>	2,700. <sup>00</sup>
1-3	Trench Safety Plan signed and sealed by a professional engineer licensed in Texas	LS	1	6,750. <sup>00</sup>	6,750. <sup>00</sup>
1-4	Traffic control plan signed and sealed by a professional engineer licensed in Texas	LS	1	1,000. <sup>00</sup>	1,000. <sup>00</sup>
1-5	Installation and maintenance of barricades, signs and traffic handling per approved Traffic Control Plan.	LS	1	7,000. <sup>00</sup>	7,000. <sup>00</sup>
Total General Project					\$ 26,250. <sup>00</sup>
Sanitary Sewer Lines A, B and C w/ Service Lateral Connections					
2-1	Furnish and Install 8-inch PVC SDR-35 gravity pipe according to the plans and specifications; complete in place.	LF	1345	28. <sup>75</sup>	38,668. <sup>75</sup>
2-2	Furnish and Install 12-inch PVC SDR-26 gravity pipe according to the plans and specifications; complete in place.	LF	2584	38. <sup>00</sup>	98,192. <sup>00</sup>
2-3	Furnish and Install directional bores with 12-inch casings for 6-inch PVC double service connection; according to the plans and specifications; complete in place.	LF	174	186. <sup>00</sup>	32,364. <sup>00</sup>
2-4	Furnish and Install directional bores with 16-inch casings for 8-inch PVC sanitary sewer line; according to the plans and specifications; complete in place.	LF	40	221. <sup>00</sup>	8,840. <sup>00</sup>
2-5	Furnish and Install directional bores with 24-inch casings for 12-inch PVC sanitary sewer line; according to the plans and specifications; complete in place.	LF	207	283. <sup>00</sup>	58,581. <sup>00</sup>
2-6	Furnish and Install 48-inch diameter fiberglass manhole; according to the plans and specifications; complete in place.	EA	13	4,030. <sup>00</sup>	52,390. <sup>00</sup>
2-7	Furnish and Install single service connection; according to the plans and specifications; complete in place.	EA	35	433. <sup>00</sup>	15,155. <sup>00</sup>
2-8	Furnish and Install double service connection; according to the plans and specifications; complete in place.	EA	3	746. <sup>00</sup>	2,238. <sup>00</sup>
2-9	Disconnect, pump and decommission existing septic tank or cesspool, haul and dispose of spoil material and Furnish and Install 4" PVC SDR-35 sewer service lateral including: connecting new 4" pipe to existing sewer and gray water pipes; landscape	EA	49	2,078. <sup>00</sup>	101,822. <sup>00</sup>

STANDARD SPECIFICATION

SCHEDULE OF UNIT PRICE WORK

	and/or other surface media repair; and all appurtenant work as shown or as specified, complete in place.				
2-10	Remove and Replace and compact existing caliche driveway as needed for trenching operations; according to the plans and specifications; complete in place.	SY	161	11.15	1,795.15
2-11	Saw-cut, Remove and Replace existing asphalt driveway as needed for trenching operations; according to the plans and specifications; complete in place.	SY	56	23.50	1,316.00
2-12	Saw-cut, Remove and Replace existing base, sub-base, HMAC asphalt roadway pavement; as needed for trenching operations according to the plans and specifications; complete in place.	SY	183	28.25	5,169.75
2-13	Saw-cut, Remove and Replace existing base, sub-base, HMAC asphalt pavement (TxDOT Specifications); as needed for trenching operations according to the plans and specifications; complete in place.	SY	14	35.00	490.00
2-14	Saw-cut, Remove and Replace, and existing concrete sidewalk as needed for trenching operations; according to the plans and specifications; complete in place.	SY	2	77.00	154.00
Sanitary Sewer Lines A, B and C w/ Service Lateral Connections					\$ 417,175.65
<b>SUMMARY</b>					
Total General Project					\$ 26,250.00
Sanitary Sewer Lines A, B and C w/ Service Lateral Connections					\$ 417,175.65

**TOTAL BID PRICE (Total Unit Prices Plus Cash Allowance, if any)**

\$ 443,425.65

Notes:

(1) United States Dollars. In the event of a discrepancy, this column shall govern.

Project: Hillcrest Terrace Subdivision + Santa Cruz Ranchettes  
 Project No. 6539676590 - Bidder's Signature: [Signature]  
 Company: REM Construction Name: Miguel A. Ramos  
 Date: 10-03-12 Title: President

**OPENED**

9.39

10-03-12

**Witnessed**

END OF DOCUMENT

Document 00407

SCHEDULE OF ALTERNATES

This Document, constitutes a Supplement to Document 00405 - Schedule of Unit Price Work. When a Contract is awarded, this Document becomes a supplement to the CONTRACT Between Owner and Contractor.

- A. Alternate bids will be reviewed and accepted or rejected at the discretion of the Owner.
- B. Any Alternate not listed below will not be considered.

**TOTAL BID PRICE (Total Unit Prices from Document 00405)**

\$ 443,425.65

ITEM NO.	ITEM DESCRIPTION	UNIT	UNIT QTY.	UNIT PRICE IN FIGURES <sup>(1)</sup>	TOTAL FIGURES
<b>Alternate No. 1</b>					
And ADD the following Unit Price Bid Items to replace them:					
2-3	Furnish and Install directional bores with 12-inch casings for 6-inch PVC double service connection; according to the plans and specifications; complete in place.	LF	32	185.29	( 5,929.38 )
2-3a	Furnish and Install directional bores with 8-inch casings for 4-inch PVC service connection; according to the plans and specifications; complete in place.	LF	32	149.00	( 4,768.00 )
2-8	Furnish and Install single service connection; according to the plans and specifications; complete in place.	EA	14	396.00	( 5,544.00 )
2-9	Furnish and Install double service connection; according to the plans and specifications; complete in place.	EA	1	683.00	( 683.00 )
2-9a	Furnish and Install commercial service connection; according to the plans and specifications; complete in place.	EA	1	683.00	( 683.00 )
2-13	Saw-cut, Remove and Replace existing base, sub-base, HMAC asphalt roadway pavement; as needed for trenching operations according to the plans and specifications; complete in place.	SY	25	25.75	( 643.75 )

**TOTAL ALTERNATE BID PRICE (Including All Alternate Bids)** \$ 18,251.03

Notes:

<sup>(1)</sup> United States Dollars. In the event of a discrepancy, this column shall govern.

Project: HILLCREST TERRACE SUBDIVISION + SANTA CRUZ RANCHETTES.  
 Project No. 6539-67-6590-5000-6700 Bidder's Signature: [Signature] 9:39  
 Company: REIM Construction Name: MIGUEL A. RAMOS 10-03-12  
 Date: 10-03-12 Title: PRESIDENT

END OF DOCUMENT

**OPENED**  
**Witnessed**

[Signature]