



## Hidalgo County Autopsy Facility

Edinburg, TX, 78539




Date: 28-Feb-14

Autopsy Heppa Filter Installation-2  
Year 2013 Quarter 4  
Unit Detail Report

Oscar Garza  
Prepared By:  
Purchasing Department  
Hidalgo County

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
<b>Division 01 General Requirements</b>					
013113200240	Field personnel, superintendent, minimum	3.00	Week	\$2,975.00	\$8,925.00
<b>Division 01 General Requirements Subtotal</b>					<b>\$8,925.00</b>
<b>Division 02 Existing Conditions</b>					
024119162440	Selective demolition, cutout, concrete block, to 4 S.F. opening, 8" thick, excludes loading and disposal	5.00	Ea.	\$80.36	\$401.80
024119200100	Selective demolition, dump charges, typical urban city, building construction materials, includes tipping fees only	1.00	Ton	\$90.00	\$90.00
024119251220	Selective demolition, saw cutting, masonry walls, block, solid, per inch of depth	40.00	L.F.	\$7.23	289.60 \$289.20
<b>Division 02 Existing Conditions Subtotal</b>					<b>\$781.00</b>
<b>Division 06 Wood, Plastics, and Composites</b>					
061110305960	Wood framing, roof curbs, untreated, 2" x 6"	40.00	L.F.	\$1.49	\$59.60
<b>Division 06 Wood, Plastics, and Composites Subtotal</b>					<b>\$59.60</b>
<b>Division 22 Plumbing</b>					
221113744216	Pipe, plastic, ABS, foam core, 2" diameter, DWV, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	20.00	L.F.	\$10.68	\$213.60
221113764570	Elbow, 1/4 bend, plastic, ABS, non-pressure, socket joint, 2", type DWV	2.00	Ea.	\$19.49	\$38.98
221316606722	Traps, ABS, P trap, solvent weld joint, 2" pipe size, type DWV	2.00	Ea.	\$32.73	\$65.46
<b>Division 22 Plumbing Subtotal</b>					<b>\$318.04</b>
<b>Division 23 Heating, Ventilating, and Air Conditioning (HVAC)</b>					
230505101400	Air conditioner, ductwork, rigid, 18" x 24", selective demolition	30.00	L.F.	\$2.21	\$66.30
233113130540	Metal ductwork, fabricated rectangular, galvanized steel, 500 to 1000 lb., includes fittings, joints, supports and allow for a flexible conn. field sketches, excludes as-built dwgs. and insul.	1,200.00	Lb.	\$3.28	\$3,936.00

LineNumber		Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
233113131040		Metal ductwork, fabricated rectangular, 1000 to 2000 lb., stainless steel, type 304, includes fittings, joints, supports and allow for a flexible conn. field sketches, excludes as-built dwgs. and insul.	1,200.00	Lb.	\$6.60	\$7,920.00
233113131040	⊘	Metal Ductwork, fabricated rectangular, for welded ductwork, add	1.00	Lb.	\$2.69	\$3,223.20
233113131040	⊘	Metal Ductwork, fabricated rectangular, for 50% fittings, add	1.00	Lb.	\$1.77	\$2,123.52
233346101640		Ductwork, flexible coated fiberglass fabric on corrosion resistant metal helix, non-insulated, 10" diameter, pressure to 12"(WG) UL-181	25.00	L.F.	\$5.26	\$131.50
233416105540		Fans, industrial exhauster, 2000 CFM, 3 H.P.	1.00	Ea.	\$4,182.92	\$4,182.92
233616105530		Duct accessories, mixing box, variable air volume, cool only, pneumatic pressure independent, 1100 to 2000 CFM, includes electric or pneumatic motor	1.00	Ea.	\$965.88	965.87 \$965.88
233713100160		Diffuser, aluminum, ceiling, also for sidewall, 4" wide, includes opposed blade damper	2.00	L.F.	\$33.65	\$67.30
233713304020		Grille, aluminum, eggcrate, framed, 22" x 22" opening	4.00	Ea.	\$73.38	\$293.52
234213100070		Air filter, activated charcoal type, HEPA filter & frame for field erection	10.00	MCFM	\$357.39	\$3,573.90
<b>Division 23 Heating, Ventilating, and Air Conditioning (HVAC) Subtotal</b>						<b>\$26,484.04</b>
<b>Division 26 Electrical</b>						
260140513000		Switch cover, maintenance, remove and replace (reinstall), incl. remove, store, and reinstall	8.00	Ea.	\$3.76	\$30.08
260505100220		Conduit, electric metallic tubing (EMT), 1-1/4" to 1-1/2" diameter, electrical demolition, remove conduit to 15' high, including fittings & hangers	30.00	L.F.	\$0.69	\$20.70
260505101760		Switch boxes, electrical demolition, remove, including removal of supports and terminations	1.00	Ea.	\$2.11	\$2.11
260505205080		Conduit nipples, 1-1/4" diameter, electrical demolition, remove, incl locknuts and bushings	6.00	Ea.	\$3.27	\$19.62
260505350160		Circuit breakers, 3 pole, 600 V, 100 A, in enclosure (NEMA 1), electrical demolition, remove	1.00	Ea.	\$30.97	\$30.97
260519900120		Wire, copper, stranded, 600 volt, #10, type THW, in raceway	4.00	C.L.F.	\$45.67	\$182.68
260519900220		Wire, copper, stranded, 600 volt, #2, type THW, in raceway	1.00	C.L.F.	\$212.90	212.91 \$212.90
260529200200		Strap, steel, 2 holes, rigid steel conduit, 1" diameter	12.00	Ea.	\$0.88	\$10.56
260533131230		Aluminum conduit elbows, 1" diameter, to 15' H	8.00	Ea.	\$28.23	\$225.84

LineNumber				Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
260533132300			<input type="checkbox"/>	Rigid galvanized steel conduit couplings, 1" diameter, to 15' high	12.00	Ea.	\$5.95	71.52 \$71.40
260533140240			<input type="checkbox"/>	Electric metallic tubing, 1" diameter, to 15' high, includes 11 CLP per 100'	120.00	L.F.	\$2.43	\$291.60
260533140280			<input type="checkbox"/>	Electric metallic tubing, 1-1/2" diameter, to 15' high, includes 11 CLP per 100'	40.00	L.F.	\$4.62	\$184.80
260533180180			<input type="checkbox"/>	Pull boxes, sheet metal, type SC, 8" W x 6" H x 4" D, NEMA 1	2.00	Ea.	\$46.63	\$93.26
260533950130			<input type="checkbox"/>	Hole drilling, concrete wall, 8" thick, 1" pipe size, to 10' high	8.00	Ea.	\$29.42	\$235.36
260580100050			<input type="checkbox"/>	Motor connections, flexible conduit and fittings, 1 phase, 115 volt, 2 HP motor	1.00	Ea.	\$51.14	\$51.14
262416200700			<input type="checkbox"/>	Circuit breakers, bolt-on, 10 k A I.C., 3 pole, 240 volt, 15 to 60 amp	1.00	Ea.	\$137.23	\$137.23
262923100100			<input type="checkbox"/>	Variable frequency drives, enclosed, 460 volt, 3 HP motor size, NEMA 1	1.00	Ea.	\$1,622.81	\$1,622.81
263613101000			<input type="checkbox"/>	Non-automatic transfer switch, enclosed, manual operated, 3 pole, 250 volt, 30 amp	1.00	Ea.	\$1,297.92	\$1,297.92
263613101600			<input type="checkbox"/>	Non-automatic transfer switch, enclosed, electrically operated, 3 pole, 480 volt, 100 amp	1.00	Ea.	\$2,573.55	\$2,573.55
<b>Division 26 Electrical Subtotal</b>								<b>\$7,294.53</b>
<b>Subtotal</b>								<b>\$43,862.21</b>
<b>General Contractor's Markup on Subs</b>						<b>0.00%</b>		<b>\$0.00</b>
<b>Subtotal</b>								<b>\$43,862.21</b>
<b>General Conditions</b>						<b>0.00%</b>		<b>\$0.00</b>
<b>Subtotal</b>								<b>\$43,862.21</b>
<b>General Contractor's Overhead and Profit</b>						<b>0.00%</b>		<b>\$0.00</b>
<hr/>								
<b>Grand Total</b>								<b>\$43,862.21</b>