

**BID COMPARISON**  
**HIDALGO COUNTY PRECINCT No. 2**  
**PROJECT No. 2014-078-04-02-MSS**  
**GEARHART DRIVE PAVING AND DRAINAGE IMPROVEMENTS PROJECT**

**BASE BID**

Sanco General Contracting Inc.						Rojas Construction		Jimmy Closner & Sons		2GS, LLC	
Item No.	Item Description	Estimated Quantity	Unit	Unit Price	TOTAL	Unit Price	TOTAL	Unit Price	TOTAL	Unit Price	TOTAL
1	PRIME COAT (MC-30) ENTIRE BASE AND LEAVE IT READY FOR HMAC INSTALLATION (ESTIMATED 830 GAL.)	4,141	SY	\$ 1.40	\$ 5,797.40	\$ 3.00	\$ 12,423.00	\$ 1.20	\$ 4,969.20	\$ 2.00	\$ 8,282.00
2	8" COMPACTED CALICHE (LABOR ONLY)	4,822	SY	\$ 4.00	\$ 19,288.00	\$ 2.00	\$ 9,644.00	\$ 3.20	\$ 15,430.40	\$ 5.00	\$ 24,110.00
3	BIAXIAL GEOGRID	4,822	SY	\$ 2.00	\$ 9,644.00	\$ 4.00	\$ 19,288.00	\$ 2.50	\$ 12,055.00	\$ 5.00	\$ 24,110.00
4	EXCAVATE STOCKPILE & TREAT CALICHE WITH 2% LIME AND REWORK EXISTING ROAD SECTION TO ACHIEVE PROP BASE	2,103	SY	\$ 5.00	\$ 10,515.00	\$ 10.00	\$ 21,030.00	\$ 8.00	\$ 16,824.00	\$ 20.00	\$ 42,060.00
5	EROSION AND SEDIMENT CONTROL STRUCTURAL PRACTICES TO COMPLY WITH COUNTY AND TCEQ REQUIREMENTS FOR STORM WATER POLLUTION PREVENTION	1	LS	\$ 6,000.00	\$ 6,000.00	\$ 3,000.00	\$ 3,000.00	\$ 2,500.00	\$ 2,500.00	\$ 2,200.00	\$ 2,200.00
6	18" LAYDOWN CURB & GUTTER	2,442	LF	\$ 8.00	\$ 19,536.00	\$ 8.50	\$ 20,757.00	\$ 6.50	\$ 15,873.00	\$ 7.20	\$ 17,582.40
7	CONCRETE APRON AROUND "C-C" INLET	8	EA	\$ 500.00	\$ 4,000.00	\$ 500.00	\$ 4,000.00	\$ 1,000.00	\$ 8,000.00	\$ 200.00	\$ 1,600.00
8	ASPHALT DRIVEWAYS (3" CALICHE BASE & 1" ACP)	210	SY	\$ 6.00	\$ 1,260.00	\$ 20.00	\$ 4,200.00	\$ 10.50	\$ 2,205.00	\$ 25.00	\$ 5,250.00
9	4" CONCRETE DRIVEWAYS	771	SY	\$ 38.00	\$ 29,298.00	\$ 27.00	\$ 20,817.00	\$ 50.00	\$ 38,550.00	\$ 35.00	\$ 26,985.00
10	GRADE ROADISE DITCH	200	LF	\$ 7.50	\$ 1,500.00	\$ 7.50	\$ 1,500.00	\$ 7.50	\$ 1,500.00	\$ 10.00	\$ 2,000.00
11	TRAFFIC CONTROL	1	LS	\$ 6,000.00	\$ 6,000.00	\$ 2,000.00	\$ 2,000.00	\$ 3,500.00	\$ 3,500.00	\$ 2,200.00	\$ 2,200.00
12	24" THERMOPLASTIC STOP BAR	1	EA	\$ 300.00	\$ 300.00	\$ 500.00	\$ 500.00	\$ 950.00	\$ 950.00	\$ 500.00	\$ 500.00
13	STOP SIGN	1	EA	\$ 400.00	\$ 400.00	\$ 500.00	\$ 500.00	\$ 180.00	\$ 180.00	\$ 275.00	\$ 275.00
<b>BASE BID TOTAL:</b>					<b>\$ 113,538.40</b>		<b>\$ 119,659.00</b>		<b>\$ 122,536.60</b>		<b>\$ 157,154.40</b>

<b>ALTERNATE #1 BID</b>											
Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures
1	2" HMAC TYPE "D" (MATERIAL & LABOR)	4,141	SY	\$ 12.00	\$ 49,692.00	\$ 10.12	\$ 41,906.92	\$ 11.35	\$ 47,000.35	\$ 12.15	\$ 50,313.15
<b>ALT. BID #1 TOTAL:</b>					<b>\$ 49,692.00</b>		<b>\$ 41,906.92</b>		<b>\$ 47,000.35</b>		<b>\$ 50,313.15</b>

<b>ALTERNATE #2 BID</b>											
Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures	Unit Price In Figures	Total Extension In Figures
1	8" COMPACTED CALICHE (MATERIAL ONLY)	4,822	SY	\$ 7.00	\$ 33,754.00	\$ 5.00	\$ 24,110.00	\$ 4.00	\$ 19,288.00	\$ 4.00	\$ 19,288.00
<b>ALT. BID #2 TOTAL:</b>					<b>\$ 33,754.00</b>		<b>\$ 24,110.00</b>		<b>\$ 19,288.00</b>		<b>\$ 19,288.00</b>
<b>BASE BID TOTAL</b>					<b>\$ 113,538.40</b>		<b>\$ 119,659.00</b>		<b>\$ 122,536.60</b>		<b>\$ 157,154.40</b>
<b>ALTERNATE NO. 1 TOTAL</b>					<b>\$ 49,692.00</b>		<b>\$ 41,906.92</b>		<b>\$ 47,000.35</b>		<b>\$ 50,313.15</b>
<b>ALTERNATE NO. 2 TOTAL</b>					<b>\$ 33,754.00</b>		<b>\$ 24,110.00</b>		<b>\$ 19,288.00</b>		<b>\$ 19,288.00</b>
<b>GRAND TOTAL</b>					<b>\$ 196,984.40</b>		<b>\$ 185,675.92</b>		<b>\$ 188,824.95</b>		<b>\$ 226,755.55</b>