



Old Admin Renovations

Facilities
Edinburg, TX, 78539
Date: 28-Oct-14

RSMeans -Price Verification

Prepared By:
Purchasing Department
Hidalgo County

Old Admin -Roof Drains -Additional Drains
Year 2014 Quarter 3
Unit Detail Report

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 01 General Requirements					
013113200260	Field personnel, superintendent, average	0.40	Week	\$3,350.00	\$1,340.00
Division 01 General Requirements Subtotal					\$1,340.00
Division 22 Plumbing					
220505101980	Pipe hanger / support, selective demolition	20.00	Ea.	\$5.40	\$108.00
220505102100	Pipe, metal pipe, 4" to 6" diam., selective demolition	75.00	L.F.	\$8.61	\$645.75
220719108220	Insulation, pipe covering (price copper tube one size less than I.P.S.), rubber tubing flexible closed cell foam, 1/2" wall, 4" iron pipe size	75.00	L.F.	\$8.18	\$613.50
220719108440	Insulation, pipe covering (price copper tube one size less than I.P.S.), rubber tubing flexible closed cell foam, 3/4" wall, 6" iron pipe size	33.00	L.F.	\$12.84	\$423.72
221113741150	Pipe, plastic, PVC, high impact/pressure, 4" diameter, schedule 80, includes couplings 10' OC, and hangers 3 per 10'	75.00	L.F.	\$60.70	\$4,552.50
Division 22 Plumbing Subtotal					\$6,343.47
Subtotal					\$7,683.47
General Contractor's Markup on Subs			0.00%		\$0.00
Subtotal					\$7,683.47
General Conditions			0.00%		\$0.00
Subtotal					\$7,683.47
General Contractor's Overhead and Profit			0.00%		\$0.00
Grand Total					\$7,683.47



Old Admin Renovations
Facilities
Edinburg, TX, 78539
Date: 28-Oct-14

Old Admin -Roof Drains -Additional Drains
Year 2014 Quarter 3
Unit Summary Report

Prepared By:
Purchasing Department
Hidalgo County

Division Description		Total
Division 01	General Requirements	\$1,340.00
Division 22	Plumbing	\$6,343.47
Subtotal		\$7,683.47
General Contractor's Markup on Subs		0.00%
Subtotal		\$0.00
Subtotal		\$7,683.47
General Conditions		0.00%
Subtotal		\$0.00
Subtotal		\$7,683.47
General Contractor's Overhead and Profit		0.00%
Subtotal		\$0.00
Grand Total		\$7,683.47