

HERRERA & HUNT, INC.
 PO BOX 49
 ALAMO, TX 78516



JOC - 09-040JC-07

DELIVERY ORDER REQUEST

Client: HIDALGO COUNTY


Date: 9/26/2014

Project: Administration Building Roof Drains #2

Location: Edinburg, TX

Project Summary: Installation of two additional roof drains

Order Calculation Criteria: Facilities & Commercial Renovation / Unit / Repair & Remodeling / McAllen / Year 2014 Qtr 3

Averages based on quantity and unit prices from RS Means			\$ 7,683.47
Competitive Bid Coefficient	0.87	X	
Choice Facilities			\$ 6,684.62
Adjustments			
Customer Credit			\$ -\$1,396.23
			\$ 5,288.39
Permits & Fees (If any, otherwise \$0.00)	2%		\$ 5,288.39
Architectural & Engineering Fees	___%		\$ 5,288.39
		Sub Total	5,288.39
Payment Bond	3%		\$ 0.00
		Delivery Order Request Quote	\$ 5,288.39
 Gilbert Herrera			
Date <u>9/26/14</u>			
Herrera & Hunt, Inc. - Choice Partners Contract # 09-040JC-07			



Date: 26-Sep-14

Hidalgo County Admin Bldg Roof Drains Phc
Year 2014 Quarter 3
Unit Detail Report

Prepared By:
Gilbert Herrera
Herrera and Hunt Inc

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 01 General Requirements					
013113200260	Field personnel, superintendent, average	0.40	Week	\$3,350.00	\$1,340.00
Division 01 General Requirements Subtotal					\$1,340.00
Division 22 Plumbing					
220505101980	Pipe hanger / support, selective demolition	20.00	Ea.	\$5.40	\$108.00
220505102100	Pipe, metal pipe, 4" to 6" diam., selective demolition	75.00	L.F.	\$8.61	\$645.75
220719108220	Insulation, pipe covering (price copper tube one size less than I.P.S.), rubber tubing flexible closed cell foam, 1/2" wall, 4" iron pipe size	75.00	L.F.	\$8.18	\$613.50
220719108440	Insulation, pipe covering (price copper tube one size less than I.P.S.), rubber tubing flexible closed cell foam, 3/4" wall, 6" iron pipe size	33.00	L.F.	\$12.84	\$423.72
221113741150	Pipe, plastic, PVC, high impact/pressure, 4" diameter, schedule 80, includes couplings 10' OC, and hangers 3 per 10'	75.00	L.F.	\$60.70	\$4,552.50
Division 22 Plumbing Subtotal					\$6,343.47
Subtotal					\$7,683.47
General Contractor's Markup on Subs			0.00%		\$0.00
Subtotal					\$7,683.47
General Conditions			0.00%		\$0.00
Subtotal					\$7,683.47
General Contractor's Overhead and Profit			0.00%		\$0.00
Grand Total					\$7,683.47