


# DIAZ RESIDENCE



URBAN COUNTY PROGRAM  
427 E. DURANTA AVE. ALAMO  
(956) 787-8127

MARIA DIAZ  
4806 FOX LN - EDINBURG  
(956) 570-6761


URBAN COUNTY PROGRAM  
OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
4806 FOX LN. EDINBUR, TX

TOTAL AREA  
1055 SQ. FT.

DAMIAN ACRES PH II LOT 59

142.50' X 152.85'



NOTE:

Please verify with city/county on setbacks and for any requirements regarding sidewalk, landscaping and any other obligations as per city regulations/ordinances. HOWEVER, any house that is made for handicap accessibility WILL ALWAYS require driveway with connecting sidewalk to ramp.

Remember to provide 6" of landscape dirt around house with sufficient grass seed up to 10' of perimeter. Install both a ramp, steps and railings as per owners request of location. In addition, remember to replace septic tank if needed and is more than 10 yrs old. House to be built on original location.

Driveway to be 12' X 25' minimum, remain distance is to street if any is to be of asphalt, caliche or concrete.

1

ROOF / PLOT PLAN



XREF

SCALE: NTS


URBAN COUNTY PROGRAM  
OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
4806 FOX LN. EDINBUR, TX


LIVING AREA  
1055 SQ. FT.



**A-EXTERIOR BEAM**  
 -EXTERIOR BEAMS TO BE 12" X 30" WITH 4 #5 BARS  
 CONT. TOP & BOTTOM WITH #3 STRIPPS AT 24" O.C.  
 AND A MIN. OF 6" IN DEPTH TO UNDISTURBED SOIL.



**B-INTERIOR BEAM**  
 -INTERIOR BEAMS TO BE 12" X 24" WITH 4 #5 BARS  
 CONT. TOP & BOTTOM WITH #3 STRIPPS AT 24" O.C.  
 AND A MIN. OF 6" IN DEPTH TO UNDISTURBED SOIL.



**C-INTERIOR BEAM**  
 -INTERIOR BEAMS TO BE 12" X 24" WITH 4 #5 BARS  
 CONT. TOP & BOTTOM WITH #3 STRIPPS AT 24" O.C.  
 AND A MIN. OF 6" IN DEPTH TO UNDISTURBED SOIL.

**GENERAL NOTES**


- 4" THICK SLAB ON GRADE W/ #3 BARS @ 16" O.C. EACH WAY AT MIN. DEPTH OF SLAB OVER 6 MIL. W/STEN OVER APPROVED COMPACTED FILL
- EXTERIOR BEAMS TO BE 12" X 30" WITH 4 #5 BARS CONT. TOP & BOTTOM WITH #3 STRIPPS AT 24" O.C. AND A MIN. OF 6" IN DEPTH TO UNDISTURBED SOIL.
- INTERIOR BEAMS TO BE 12" X 24" WITH 4 #5 BARS CONT. TOP & BOTTOM WITH #3 STRIPPS AT 24" O.C. AND A MIN. OF 6" IN DEPTH TO UNDISTURBED SOIL.
- CORNER BARS AT ALL CORNERS & INTERSECTIONS 2"x2" - #5
- APPLY 6x6 #6 WIRE MESH AT PERIMETER AT 4' O.C.
- INSTALL ANCHOR BOLTS AT PERIMETER AT 4' O.C.
- USE ONLY COMPACTED SELECTED FILL. FINISH FLOOR TO BE 18" FROM TOP OF CURB, UNLESS OTHERWISE NOTED.

1 FOUNDATION PLAN SCALE: NTS

URBAN COUNTY PROGRAM  
 OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
 4806 FOX LN. EDINBUR, TX

TOTAL AREA  
 1055 SQ. FT.



35'-2"

35'-2"

**SQUARE FOOTAGE**

LIVING AREA	980
PORCH/PATIO	75
TOTAL SQ. FT.	1055

**ELECTRICAL LEGEND**

	WATER HEATER		LIGHT FIXTURE
	DUPLEX ELECTRICAL RECEPT.		LIGHT SWITCH
	220V ELECTRICAL RECEPTACLE		THERMOSTAT
	SMOKE DETECTOR		SMOKE DETECTOR
	BATHROOM EXHAUST FAN		SECURITY LED LIGHT

**DOOR SCHEDULE**

DR#	TASK	SIZE	TYPE	LOCKS
1	INSTALL NEW UNIT W/ OVAL REGRASS	3'0x6'8"	METAL V/LOW PROFILE HINGED	LEVER TYPE ENTRY LOCK W/ DEADBOLT
2	INSTALL NEW UNIT	2'6x6'8"	HOLLOW CORE	LEVER TYPE PRIVACY
3	INSTALL NEW UNIT	2'0x4'0"	HOLLOW CORE	PASSAGE FOR A/C CLOSET
4	INSTALL NEW UNIT	2'6x6'8"	HOLLOW CORE	PASSAGE
5	INSTALL NEW UNIT	(2)2'0x2'9"	HOLLOW CORE	PASSAGE
6	INSTALL NEW UNIT	2'6x6'8"	HOLLOW CORE	PASSAGE
7	INSTALL NEW UNIT	2'0x6'8"	HOLLOW METAL	LOCK W/ DEADBOLT

**GENERAL NOTES**

- 5/12 SLOPE WITH 1/8" OVERHANG
- SUPPLY RIDGE/SOFT VENTS WHERE NEEDED
- INSTALL PORCH RAILING WHERE FINISH GRADE IS LOWER THAN 1" FROM PORCH FLOOR.
- INSTALL PORCH STEPS WHERE FINISH GRADE IS LOWER THAN 6" FROM PORCH FLOOR.
- CLIENT IS REQUESTING CONNECTIONS FOR A GAS ELECTRIC STOVE
- INSTALL WITH OPERATING PHONE JACKS & CABLE CONNECTIONS AS PER OWNERS REQUESTS.
- EXTERIOR COLOR CHOICES TO BE OR MATCH: MAVIELEND GOLD CONTRACTOR CORAL
- INTERIOR COLOR CHOICES TO BE OR MATCH: SW 6170 SW 6325
- INTERACTING LEMON INTERACTIVE LEMON

I HAVE READ AND FULLY AGREE WITH THE WRITE-UP AND PLANS AS PRESENTED TO ME THIS 30 DAY OF JAN. 2015

*Maria Diaz*

1 FLOOR PLAN


XREF

SCALE: NTS


URBAN COUNTY PROGRAM  
OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
4806 FOX LN. EDINBUR, TX

TOTAL AREA  
1055 SQ. FT.



1  
 FRONT ELEVATION PLAN  
 XREF  
 SCALE: NTS




2  
 REAR ELEVATION PLAN  
 XREF  
 SCALE: NTS


URBAN COUNTY PROGRAM  
 OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
 4806 FOX LN. EDINBUR, TX

TOTAL AREA  
 1055 SQ. FT.



1  
LEFT ELEVATION PLAN  
XREF  
SCALE: NTS



2  
RIGHT ELEVATION PLAN  
XREF  
SCALE: NTS

URBAN COUNTY PROGRAM  
OWNER OCCUPIED HOUSING REHABILITATION PROGRAM

MARIA DIAZ  
4806 FOX LN. EDINBUR, TX

TOTAL AREA  
1055 SQ. FT.

**SPECIFICATIONS**

ALL SPECIFICATIONS SHALL ASSUME THE USE OF CONTRACTOR'S MINIMUM GENERAL SPECIFICATIONS MANUAL  
OWNER (S) Martha Diaz CASE NO.: CW 88-15-01 DATE: 1-30-15 ADDRESS: 4806 Fox Lane Edinburg, TX PHONE: 956-570-6761 BY: ERIC TREVINO

**1. FOUNDATION WORK:**

- BUILD A NEW CONCRETE FOUNDATION TO COMPLY WITH PLANS, SPECS, CITY AND COUNTY REQUIREMENTS. PROJECTS TO BE 18" ABOVE FINISHED LINE OF STREET OR 18" ABOVE NATURAL GROUND, WHICHEVER IS GREATER. PROVIDE CONCRETE SLAB FOR A/C UNIT & A MIN. OF 12 X 26 DRIVEWAY (depending on city).

**2. PLUMBING GENERAL: (SEE SPECS)**

- ALL PLUMBING ROUGH SHALL BE AS FOLLOWS:
  - > WATER SUPPLY TO HOUSE SHALL HAVE A 1/2" CUTOFF VALVE BEFORE ENTRY TO HOUSE.
  - > INTERIOR WATER SUPPLY LINES FOR HOUSE SHALL BE ALL NEW PER OF APPROPRIATE DIAMETER
  - > NEW EX PIPES AND FITTINGS:
    - OF 1" MINIMUM DIAMETER FOR ALL EXTERIOR WATER SUPPLY LINES BELOW GROUND.
    - OF APPROPRIATE DIAMETER FOR DWV (DRAIN, WASTE, AND VENTS).
  - > SEWER CONNECTION SHALL HAVE (1) PLASTIC PVC SEWER CLEAN OUT.
- ALL PLUMBING FINISH SHALL BE AS FOLLOWS:
  - > RELATED PLUMBING ITEMS:
    - (2) EXTERIOR HOSE BRASS BIB FAUCETS.
    - 1/2" CUTOFF VALVES WITH ESCUTCHEONS FOR ALL FIXTURES, FIXTURES.
  - > PLUMBING SEALANT FOR ALL DRAINS, AND SINK PERIMETERS
  - ALL OTHER RELATED PLUMBING (SEE SPECS)
  - KITCHEN SINK W/ RELATED PLUMBING & FAUCETS
  - PEDESTAL SINK W/ RELATED PLUMBING & FAUCETS
  - TOILET OF MATCHING COLOR
  - SHOWER W/ RELATED PLUMBING AND HANDICAP ACCESSIBLE
  - SHOWER FAUCETS & REMOVE/RE SHOWER HEAD.
  - MEDICINE CABINET/STOVEL, RACKS/ TP DISPENSER/ TOOTHBRUSH & SOAP HOLDER, & SHOWER ROD (SEE SPECS)
  - WATER HEATER INSTALLED AS PER SPECS. (GAS OR ELECTRIC AS PER OWNER REQUEST)
- OTHER RELATED ITEMS
  - RANGE CONNECTIONS AS PER OWNERS REQUEST (SEE SECTION 2A).
  - 4" DRYER EXHAUST VENT.
  - IN WALL WASHING MACHINE BOX, WITH BRASS FAUCETS & RELATED PLUMBING.
  - HOOK UP ALL DRAINAGE LINES TO CITY SEWER SYSTEM IF AVAILABLE. SEE CITY FOR INFORMATION, TEST SEPTIC SYSTEM IF EXISTING FOR INTEGRITY AND REPLACE IF NECESSARY AND MORE THAN 10 YEARS OF AGE

**3. INTERIOR/EXTERIOR WALLS & CEILING:**

- ALL INTERIOR AND EXTERIOR WALL FRAMING:
  - > 2x4" (4x8 OR BETTER) FOR USE IN: SOLE PLATES (TREATED LUMBER)
  - DOUBLE TOP PLATES
  - 2x6" PRE-CUT STUDS @ 16" O.C.
  - WINDOW SILLS
  - CEILING JOIST CHAIN BLOCKING @ 48" O.C.
  - 2x6" (4x8 OR BETTER) FOR USE IN:
    - WINDOW & DOOR HEADERS WITH 1 1/2" SPACER.
    - CEILING JOIST @ 24" O.C., FOR CLEARANCES LARGER THAN 12'
    - CEILING JOIST SHALL BE @ 16" O.C.

- INSTALL BOOT TIES IN EVERY CORNER OF THE HOUSE ALONG WITH METAL ANCHORS ON BOTH BOTTOM AND TOP PLATES OF HOME
- ALL EXTERIOR CEILING COVERINGS:
  - 3/8" OD EXTERIOR PLYWOOD FOR PORCH CEILING.
  - ALL INTERIOR WALL & CEILING COVERINGS:
    - 1/2" SHEETROCK FINISHED AS PER SPECS.
    - 1/2" DAMP RESISTANT SHEETROCK FOR BATH AREAS.
- ALL INTERIOR WALLS SHALL HAVE ORANGE PEEL TEXTURE
- ALL INTERIOR WALL SURFACES SHALL HAVE ORANGE PEEL TEXTURE
- ALL EXTERIOR TRIMMINGS SHOULD CONSIST OF CEDAR WOOD.

**4. ROOF: (SLOPE=9/12)**

- ROOF SHALL HAVE:
  - A HIRGABLE STYLE ROOF WITH 16" OVERHANGS.
  - A HIRGABLE STYLE FRONT PORCH AS PER PLANS.
  - PORCH COLUMNS MUST BE FASTENED TO CONCRETE
  - AN ADEQUATE COMBINATION OF RIDGE & SOFFIT VENTS WITH AIR CHUTES.
  - ADEQUATE RAIN GUTTERS WITH DOWN SPOUTS FOR THE ROOF AREA THAT MAY AFFECT OTHERS.
  - SHINGLES TO BE OF LIGHT COLOR (no black shingles)

**5. PORCH & CANOPY FLOORS:**

- THE HOUSE SHALL HAVE PORCH FLOORS AS FOLLOWS:
  - A FRONT PORCH FLOOR.
  - A SIBERBACK PORCH FLOOR.
  - PROVIDE RAMP & (2)-HANDRAILS TO EACH FRONT AND/OR SIDE PORCH STEPS

**6. INSULATION:**

- INSULATE:
  - > ALL LIVING AREA, CEILING, WITH BLOWN IN INSULATION TO AN R-49 FACTOR. (blend a combined R-30 & R-19 to meet requirement)
  - > FEET BEFORE FINISHING AND ROUGH-IN INSPECTION IS SCHEDULED.
  - > INFILTRATION FOAM SHALL BE USED AROUND ALL WINDOWS, WIRES, PLUMBING, ELECTRICAL, 2X4 BOTTOM PLATES, AND ALL PENETRATED AREAS.
  - > ALL PERIMETER WALLS WITH R-4.5 F.G. BATT.
  - > ALL EXTERIOR PIPES EXPOSED TO WEATHER.

**7. INTERIOR FINISH:**

- ALL TRIM SHALL BE INSTALLED AS PER SPECS.
- ALL PAINT SHALL BE APPLIED AS PER SPECS (2-COATS) WITH PAINT COMPARABLE IN QUALITY TO SHERWIN WILLIAMS. ALLOW A VARIETY OF DIFFERENT COLORS FOR CLIENT TO CHOOSE FROM. (2 COLOR CHOICE MIN).

**8. EXTERIOR FINISH:**

- PAINT ENTIRE HOUSE AS PER SPECS WITH PAINT COMPARABLE IN QUALITY TO SHERWIN WILLIAMS PRIMER TO BE OIL BASED & PAINT MUST BE EQUIVALENT TO A-100 (2 COLOR CHOICE MIN).

**9. SIDING:**

- THE SIDING SHALL BE 5/8" FIBER CEMENT WITH ALL CEDAR TRIM TO ENTIRE HOUSE.

**10. WINDOWS:**

- SHALL BE NEW 1/2" DOUBLE PANE INSULATED ALUMINUM WINDOWS, SIZE AS PER PLAN, KEEP LABELS ON WINDOWS UNTIL FINAL INSPECTION HAS BEEN CLEARED.

**11. CABINETS GENERAL:**

- BUILD AND/OR INSTALL NEW KITCHEN CABINETS TO INCLUDE:
  - > A RANGE CABINET
  - > A KITCHEN/BATHROOM FORMICA COUNTER TOP OF MATCHING COLOR
- BUILD AND/OR INSTALL A NEW VANITY CABINET (IF APPLICABLE) FOR BATHROOM WITH FORMICA TO MATCH LAVATORY SINK AND WALLS. ALL CABINETRY PIECES SHOULD BE NEW AND COMPLETE AND BUILT TO PROFESSIONAL STANDARDS.

**12. FLOOR, SUBFLOOR, & FINISH**

- FLOORING:
  - > APPLY VCT FLOOR TILE TO ALL LIVING AREA HOUSE FLOORS.

**13. ELECTRICAL GENERAL**

- ALL ELECTRICAL INSTALLATIONS & WORK AS PER ELECTRICAL CODE WITH THE FOLLOWING CONDITIONS:
  - > PROVIDE RANGE OUTLET AS PER OWNERS REQUEST.
  - > PROVIDE APPROPRIATE WASHER & DRYER CONNECTION.
  - > (2) 52 CEILING FANS (CEILING HUGGER STYLE) COMPARABLE IN QUALITY TO THE HUNTER BRAND. THE CONTRACTOR SHALL ALLOW \$120.00 FOR MATERIAL & LABOR, LOCATION AS PER OWNER REQUEST.
  - > INSTALL GFCI OUTLETS IN BATHROOMS, KITCHEN, AND EXTERIOR WALLS.
  - > EACH ELECTRICAL PANE OR BREAKERBOX, LIGHT SWITCH & THERMOSTAT NO HIGHER THAN 48" ABOVE FLOOR.
  - > EACH ELECTRICAL PLUG TO BE 18" ABOVE THE FLOOR
  - > ANY OUTLET'S WITHIN 8' FROM KITCHEN OR BATHROOM SINKS MUST BE GFCI.

**14. RANGE HOOD:**

- INSTALL A RANGE HOOD TO FIT OWNERS RANGE SIZE (30" OR 36") AND VENT TO EXTERIOR.

**15. BATHROOM ACCESSORIES:**

- ALL ACCESSORIES & MEDICINE CABINETS AS PER SPECS. INCLUDE CURTAIN ROD & PLASTIC RETAINING DAM TO HELP PREVENT WATER FROM ESCAPING SHOWER. INSTALL PEDESTAL SINK AND CABINET ABOVE TOILET. (ALSO INCLUDE TOILET PAPER, TOOTHBRUSH, AND SOAP HOLDER.)

**16. ACCESS FOR PHYSICAL DISABILITIES:**

- INSTALL ONE CONC. RAMP AS PER OWNERS REQUEST THAT CONNECTS WITH 12 X 23 DRIVEWAY AND STEPS WITH HANDRAILS
- BATHROOM SHOULD ACCOMMODATE GRAB BARS WHERE INDICATED IN PLANS

**17. HEATING & A/C:**

- PROVIDE & INSTALL A 16 SEER CENTRAL AIR CONDITIONING COMPAREBLE IN QUALITY TO A CARRIER BRAND UNIT FOR THE ENTIRE HOUSE. INCLUDE DIGITAL THERMOSTAT.

**18. SMOKE DETECTORS:**

- INSTALL A SMOKE DETECTOR INSIDE EACH SLEEPING ROOM, OUTSIDE SLEEPING ROOMS, ALL WIRED IN SERIES.

**19. GENERAL NOTES.**

**CONTRACTOR IS RESPONSIBLE FOR:**

- > YOUR BID TO INCLUDE ANY COST RELATED TO REQUIREMENTS FROM CITY, CHANGE ORDERS FOR THIS PARTICULAR PURPOSE WILL NOT BE ACCEPTED OR PROCESSED TO CORRECT THE ABOVE MENTIONED.
- > YOUR BID TO INCLUDE ANY COST RELATED TO RES-CHECK & ENERGY COMPLIANCE REQUIREMENTS.
- > THE DEMOLISH AND DISPOSAL EXISTING STRUCTURE. THE COMPLIANCE OF ALL THE REQUIRED BUILDING ELEVATIONS.
- > PROVIDE 6" OF LANDSCAPE DIRT AROUND THE HOUSE ALONG WITH SUFFICIENT GRASS SEEDS UP TO 10' OF PERIMETER.
- > PROVIDING THE APPROPRIATE ELECTRICAL AND/OR GAS CONNECTIONS FOR RANGE AS PER APPOINT'S REQUEST AND ACCORDING TO APPLICABLE PLUMBING/ELECTRICAL CODE.
- > PROVIDE PHONE JACKS & CABLE CONNECTIONS IN EVERY BDR & LIVING SPACE. KITCHEN PHONE IF REQUESTED.
- > PROVIDE TERTIARY PRE-TREATMENT TO ENTIRE HOUSE, OBTAINING, DISPLACING, AND SUBMITTING ALL PROPER PERMITS & INSPECTIONS.
- > ALL CONTRACTORS WILL BE RESPONSIBLE FOR ANY ADDITIONAL PLANS, SPECIFICATIONS AND/OR DETAILS THAT ARE REQUIRED BY CITIES OR COUNTY AT THE TIME OF ATAINING PERMITS.
- > MINIMUM 12x26 CONC. DRIVEWAY WITH CONNECTING SIDEWALK TO RAMP FOR HANDICAP APPLICANTS.
- > ALL THE GENERAL INFORMATION CONTAINED WITHIN SECTION 2A GENERAL NOTES OF THE CONTRACTORS GENERAL SPECIFICATIONS MANUAL.
- > PROVIDE AND INSTALL PROJECTS SIGNS AT EACH CONSTRUCTION SITE
- > CONTRACTOR IS RESPONSIBLE FOR SUPPLYING PORT A POTTY THROUGHOUT CONSTRUCTION PROCESS (same to final inspection)
- > SHOWER ENTRANCES TO BE 36" WIDE
- > ALL UCP HOMES MUST COMPLY WITH TEXAS GOVERNMENT CODE §2306.514

THE HOMEOWNER SHALL BE RESPONSIBLE FOR REMOVE AND DISPOSE OF ALL DEBRIS ON SITE BEFORE THE BEGINNING OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO TREES, ABANDONED VEHICLES, OLD LUMBER, ETC. MAKING NECESSARY DEPOSITS FOR ANY UTILITIES TO BE CONNECTED TO THE NEW DWELLING.

I HAVE READ AND FULLY AGREE WITH THE WRITE-UP AND PLANS AS PRESENTED TO ME.

*Martha Diaz*  
NAME OF APPLICANT

NAME OF CO-APPLICANT