









FACILITIES MANAGEMENT -PRICE VERIF
Year 2015 Quarter 1
Unit Detail Report

Prepared By:
Purchasing Department
Hidalgo County

LineNumber				Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 08 Openings								
080505103900				Door demolition, special doors, storefront swing door, remove	1.00	Ea.	\$224.27	\$224.27
081213133000				Frames, steel, knock down, hollow metal, 14 gauge, up to 5-3/4" D, 3'-0" x 6'-8"	1.00	Ea.	\$235.92	\$235.92
081313131020				Doors, commercial, steel, flush, full panel, hollow core, hollow metal, 18 ga., 3'-0" x 6'-8" x 1-3/4" thick	1.00	Ea.	\$638.06	\$638.06
081313131212				Hollow metal, for vision lite add	1.00	Ea.	\$118.14	\$118.14
087120300220				Door closer, electric automatic operators, surface mounted, light duty, parallel arm	1.00	Ea.	\$210.95	\$210.95
087120350020				Door hardware, panic device, for rim locks, single door, outside key and pull	1.00	Ea.	\$734.45	\$734.45
087120350203				Door hardware, panic device, install	1.00	Ea.	\$1,098.87	\$1,098.87
087120652040				Threshold, wood oak, ADA, 4-1/2" wide x 36" long	1.00	Ea.	\$47.97	\$47.97
087120901440				Door hardware, hinges, full mortise, high frequency, brass base, US26D, 4-1/2" x 4-1/2"	1.50	Pr.	\$118.61	\$177.92
087125109000				Weatherstripping, mechanical seals, minimum labor/equipment charge	1.00	Job	\$112.14	\$112.14
Division 08 Openings Subtotal								\$3,598.69
Division 09 Finishes								
099113709000				Paints & coatings, doors & windows, exterior, minimum labor/equipment charge	1.00	Job	\$126.39	\$126.39
Division 09 Finishes Subtotal								\$126.39

LineNumber	  	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
		Subtotal				\$3,725.08
		General Contractor's Markup on Subs		0.00%		\$0.00
		Subtotal				\$3,725.08
		General Conditions		0.00%		\$0.00
		Subtotal				\$3,725.08
		General Contractor's Overhead and Profit		0.00%		\$0.00
		Grand Total				\$3,725.08

FACILITIES MANAGEMENT -PRICE VERIFICATION
Year 2015 Quarter 1
Unit Summary Report

Prepared By:
Purchasing Department
Hidalgo County

Division Description		Total
Division 08	Openings	\$3,598.69
Division 09	Finishes	\$126.39
Subtotal		\$3,725.08
General Contractor's Markup on Subs		0.00% \$0.00
Subtotal		\$3,725.08
General Conditions		0.00% \$0.00
Subtotal		\$3,725.08
General Contractor's Overhead and Profit		0.00% \$0.00
Grand Total		\$3,725.08