



HIDALGO COUNTY PLANNING DEPARTMENT

1304 SOUTH 25TH STREET
EDINBURG TEXAS 78539
Tel. 956-318-2840 Fax. 956-318-2844

T.J. Arredondo, CFM
Director of Planning

HIDALGO COUNTY COMMISSIONERS COURT MEETING

DATE: 06-23-2015

PROPOSED EVG FARMS SUBDIVISION, PRECINCT No. 4.

ENGINEER: GARZA-GARZA CONSULTING ENGINEERING DEVELOPER: EDGAR E. GONZALEZ

PRELIMINARY APPROVAL FINAL APPROVAL FINAL APPROVAL WITH FINANCIAL GUARANTEE WITH VARIANCE

NUMBER OF LOTS: 1 *SINGLE FAMILY *MULTI-FAMILY COMMERCIAL INSTITUTIONAL

LOCATION DESCRIPTION: North of Iowa Road approximately 1/4 mile west of Alamo Road (F.M. 907).

SUBDIVISION LIES WITHIN THE: ETJ of Edinburg and was approved administratively by said City.

DRAINAGE REPORT WAS APPROVED BY HCDD#1: ON 01-22-2015 PROPERTY LIES WITHIN FLOOD ZONE: "B" AS PER FEMA.

DRAINAGE DESIGN: Drainage will be detained within depressed green areas of property.

ROAD R.O.W. DEDICATION: 30 feet on to Iowa Road.

H.C.R.O.W. FINAL APPROVAL DATE: 05-20-2015 By, Jose Ochoa, Pct. 4 R.O.W. AGENT

H.C.H.D. FINAL APPROVAL DATE: 06-09-2015 By, Elizardo "Chardo" Ramos Environmental Health Division Manager

OSSF & SOIL ANALYSIS WERE CONDUCTED BY: Jose A. Gonzalez
SEWER SYSTEM: OSSF HAVE BEEN INSTALLED AND INSPECTED BY HCHD

WATER SERVICE PROVIDER: NAWSC LINE SIZE: 2 1/2" LOCATION: Iowa Road

H.C.O.E.C. FINAL APPROVAL DATE: 05-19-2015 : By Martin Ramirez Environmental Compliance Coordinator

SMALL CONSTRUCTION

The applicant has submitted the required small construction site notice as per Part II, Section E of the TPDES General Permit for Construction Activities (TXR150000) along with a copy of the Erosion Control Plan for the proposed project.

REQUEST FOR FINAL APPROVAL WITH: **Cash Deposit:** Amount: \$ _____ For: OSSF(S) _____ PAVING DRAINAGE STREET SIGNS
 A Letter of Credit Financial Institution: _____ L.O.C No. _____
Amount: \$ _____ For: OSSF(S) _____ PAVING DRAINAGE STREET SIGNS

FINAL PRELIMINARY FROM THE
HIDALGO COUNTY COMMISSIONERS COURT ON: 5-05-2015

STAFF RECOMMENDS: **Preliminary Approval** subject to comments and future recommendations by planning,
Other departments and the approval of the City of Edinburg.

Final Approval subject to recommendations other departments

*This subdivision plat has been reviewed and complies with the Hidalgo County Subdivision Rules,
* Texas Water Development Board Model Subdivision Rules and The Texas Local Government Code.*

GENERAL PLAT NOTES & RESTRICTIONS

- FLOOD ZONE DESIGNATION: ZONE "B" ZONE "B" IS DEFINED AS AREAS BETWEEN LIMITS OF THE 100-YEAR FLOOD AND 500-YEAR FLOOD; OR CERTAIN AREAS SUBJECT TO 100-YEAR FLOODING WITH AVERAGE DEPTHS LESS THAN ONE (1) FOOT OR WHERE THE CONTRIBUTING DRAINAGE AREA IS LESS THAN ONE SQUARE MILE; OR AREAS PROTECTED BY LEVEES FROM THE BASE FLOOD. COMMUNITY-PANEL NUMBER 480334 0425 C MAP REVISED: NOVEMBER 16, 1982.
- THE AREAS WITHIN THE DRAINAGE EASEMENTS AND THE PROPOSED STREET RIGHT-OF-WAY ARE WITHIN THE 100-YEAR FLOOD PLAN. COMMUNITY-PANEL NUMBER 480334 0425 C MAP REVISED: NOVEMBER 16, 1982. THE FEDERAL EMERGENCY MANAGEMENT AGENCY MAPS FOR HIDALGO COUNTY, TEXAS AND THE LOCAL FLOOD PLAN ADMINISTRATOR HAVE IDENTIFIED NO OTHER AREAS AS SHOWN ON THIS PLAT ARE WITHIN THE PROPOSED SUBDIVISION TO BE WITHIN THE 100-YEAR FLOOD PLAN.
- CONSTRUCTION OF RESIDENTIAL HOUSING WITHIN ANY AREA OF THE SUBDIVISION THAT IS IN THE 100-YEAR FLOOD PLAN IS PROHIBITED UNLESS THE HOUSING QUALIFIES FOR INSURANCE UNDER THE NATIONAL FLOOD INSURANCE ACT OF 1968 (42 U.S.C. SECTIONS 4001 THROUGH 4127).
- SETBACKS: FRONT: 50.00 FEET (OR TO EASEMENT, WHICHEVER IS GREATER) REAR: 15.00 FEET (OR TO EASEMENT, WHICHEVER IS GREATER) SIDE: 6.00 FEET (OR TO EASEMENT, WHICHEVER IS GREATER)
- GENERAL NOTE FOR SINGLE FAMILY RESIDENCES: NO MORE THAN ONE-SINGLE FAMILY DETACHED DWELLING SHALL BE LOCATED ON EACH LOT. THIS MUST BE STIPULATED ON ALL DEEDS AND CONTRACTS FOR DEEDS OR OTHER INSTRUMENTS. THE OFFICE OF ENVIRONMENTAL PLANNING DEPARTMENT, THE OFFICE OF ENVIRONMENTAL COMPLIANCE, HEALTH DEPARTMENT AND FIRE MARSHALL APPROVALS, APPLICATIONS FOR CONSTRUCTION ARE REQUIRED PRIOR TO OCCUPANCY OF THE LOT.
- MINIMUM FINISH FLOOR NOTE: MINIMUM FINISH FLOOR ELEVATION SHALL BE 18" ABOVE TOP OF CENTERLINE OF ROAD OR 18" ABOVE NATURAL GROUND, WHICHEVER IS GREATER. ELEVATION CERTIFICATE MAY BE REQUIRED FOR LOTS LOCATED OUTSIDE A DESIGNATED FLOOD ZONE AT THE TIME FOR APPLICATION FOR CONSTRUCTION TO VERIFY PRE AND POST CONSTRUCTION FINISH FLOOR ELEVATIONS. AN ELEVATION CERTIFICATE SHALL BE REQUIRED FOR ALL LOTS WITHIN A DESIGNATED FLOOD ZONE AT THE TIME FOR A DEVELOPMENT PERMIT APPLICATION.
- BENCHMARKS (B.M.): THE FOLLOWING BENCHMARKS ARE IDENTIFIED ON THE FACE OF THE PLAT AND ON THE ATTACHED ENGINEERING PLANS. B.M. NO. 1: ELEVATION=91.18, N.A.V.D. 83. DESCRIPTION: PK NAIL ALONG THE CENTERLINE OF EXISTING IOWA ROAD BEING 198.00 FEET WEST AND SOUTHWEST CORNER OF LOT 6. B.M. NO. 2: ELEVATION=90.75, N.A.V.D. 83. DESCRIPTION: PK NAIL ALONG THE CENTERLINE OF EXISTING PAVEMENT OF IOWA ROAD BEING 198.00 FEET WEST OF SOUTHWEST CORNER OF LOT 6.
- DRAINAGE: IN ACCORDANCE WITH THE HIDALGO COUNTY DRAINAGE DISTRICT NO. 1 AND HIDALGO COUNTY REQUIREMENTS, THIS DEVELOPMENT WILL BE REQUIRED TO OBTAIN A TOTAL OF 1,850 CUBIC FEET OF STORAGE CAPACITY FOR WATER RUNOFF. DRAINAGE RETENTION IN ACCORDANCE WITH THE LOCAL REQUIREMENTS WILL BE OBTAINED WITHIN DEPRESSED / GREEN AREAS OF PROPOSED LARGE LOTS.
- ON-SITE SEWAGE FACILITIES (OSSF) NOTE: THIS SUBDIVISION SHALL USE ON-SITE SEWAGE FACILITIES IN ACCORDANCE WITH THE HIDALGO COUNTY REGULATIONS FOR SEWAGE DISPOSAL. THE SUBDIVIDER IS RESPONSIBLE FOR PROVIDING AN OSSF ON ALL LOTS. A. OSSF SYSTEM IS BEING DESIGNED FOR DISPOSAL OF DOMESTIC SEWAGE ONLY. A SEPARATE DESIGN SHALL BE SUBMITTED FOR COMMERCIAL USE. B. EACH LOT ON THIS PLAT COMPLIES WITH THE MINIMUM 21,780 SQUARE FEET LOT AREA WITH POTABLE WATER SUPPLY. C. OSSF SYSTEM SHALL REQUIRE INSPECTION AND APPROVAL BY HIDALGO COUNTY AUTHORIZED DEPARTMENT. D. SOIL ANALYSIS HAS BEEN SUBMITTED TO THE AUTHORIZED HIDALGO COUNTY HEALTH DEPARTMENT AND EXCERPTS MAY BE ALSO SEEN ON THE UTILITY LAYOUT FOR THIS SUBDIVISION AS SUBMITTED TO THE HIDALGO COUNTY PLANNING DEPARTMENT. THE ENGINEER HAS DETERMINED THAT THE SOIL IS SUITABLE FOR A STANDARD SEPTIC TANK AND ABSORPTIVE DRAINFIELD SYSTEM. E. APPROVED "OSSF" PERMIT APPLICATION IS REQUIRED, INCLUDING INDIVIDUAL LOT PLANNING MATERIALS PRIOR TO OCCUPANCY A LOT.


LEGEND	
●	FOUND 1/2" IRON ROD
○	FOUND 5/8" IRON ROD
⊙	FOUND RAIL ROAD SPIKE
⊙	SET 1/2" IRON ROD
⊙	SET PK NAIL
○	FOUND CPS
⊙	POWER POLE
⊙	TELEPHONE PEDESTAL
⊙	ELECTRICAL BOX
⊙	WATER METER
⊙	IRRIGATION STAND PIPE
⊙	MAIL BOX
—x—	FENCE
—	DRAINAGE NATURAL FLOW
ELEVATIONS	
○	NATURAL GROUND
—	EDGE OF PAVEMENT (TOP)
—	TOP OF ASPHALT

NORTH ALAMO WATER SUPPLY CORPORATION RIGHT OF WAY EASEMENT:

KNOW ALL MEN BY THESE PRESENTS, THAT THE UNDERSIGNED, OWNERS OF THE PROPERTY SHOWN ON THIS PLAT, THEIR SUCCESSORS, ASSIGNS, AND TRANSFERREES (hereinafter called "Grantor") WHETHER ONE OR MORE PERSONS ARE NAMED, IN CONSIDERATION OF ONE DOLLAR (\$1.00) AND OTHER GOOD AND VALUABLE CONSIDERATION PAID BY NORTH ALAMO WATER SUPPLY CORPORATION, (hereinafter called "Grantee"), THE RECEIPT AND SUFFICIENCY OF WHICH IS HEREBY ACKNOWLEDGED, DOES HEREBY GRANT, BARGAIN, SELL, TRANSFER, AND CONVEY TO SAID GRANTEE, ITS SUCCESSORS, AND ASSIGNS, AN EXCLUSIVE PERPETUAL EASEMENT WITH THE RIGHT TO ERECT, CONSTRUCT, INSTALL AND THEREAFTER USE, OPERATE, INSPECT, REPAIR, MAINTAIN, REPLACE, AND REMOVE WATER DISTRIBUTION LINES AND APPURTENANCES OVER AND ACROSS THE LANDS SHOWN ON THIS PLAT, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS OF THE PURPOSE FOR WHICH THE ABOVE MENTIONED RIGHTS ARE GRANTED, THE EASEMENT HEREBY GRANTED SHALL NOT EXCEED 15' IN WIDTH, AND GRANTEE IS HEREBY AUTHORIZED TO DESIGNATE THE COURSE OF THE EASEMENT HEREIN CONVEYED EXCEPT THAT WHEN THE PIPELINE(S) IS INSTALLED, THE EASEMENT HEREIN GRANTED SHALL BE LIMITED TO A STRIP OF LAND 15' IN WIDTH, THE CENTER LINE THEREOF BEING THE PIPELINE INSTALLED. IN THE EVENT THE EASEMENT HEREBY GRANTED ABUTS ON A PUBLIC ROAD AND THE CITY, COUNTY OR STATE HEREAFTER WIDENS OR RELOCATES THE PUBLIC ROAD SO AS TO REQUIRE THE RELOCATION OF THIS WATER LINE AS INSTALLED, GRANTEE FURTHER GRANTS TO GRANTEE ADDITIONAL EASEMENT OVER AND ACROSS THE LAND SHOWN ON THIS PLAT FOR THE PURPOSE OF LATERALLY RELOCATE SAID WATER LINE AS MAY BE NECESSARY TO CLEAR THE ROAD IMPROVEMENTS, WHICH EASEMENT HEREBY GRANTED SHALL BE LIMITED TO A STRIP OF LAND 15' IN WIDTH, THE CENTER LINE THEREOF BEING THE PIPELINE AS RELOCATED. THE CONSIDERATION RECITED HEREIN SHALL CONSTITUTE PAYMENT IN FULL FOR ALL DAMAGES SUSTAINED BY GRANTEE BY REASON OF THE INSTALLATION, MAINTENANCE, REPAIR, REPLACEMENT AND RELOCATION OF THE STRUCTURES REFERRED TO HEREIN, THUS AGREEMENT TOGETHER WITH OTHER PROVISIONS OF THIS GRANT SHALL CONSTITUTE AN EASEMENT FOR THE BENEFIT OF THE GRANTEE, ITS SUCCESSORS, AND ASSIGNS. THE GRANTEE COVENANTS THAT IT IS THE OWNER OF THE ABOVE-DESCRIBED LANDS AND THAT SAID LANDS ARE FREE AND CLEAR OF ALL ENCUMBRANCES AND LIENS EXCEPT THE FOLLOWING: THE EASEMENT CONVEYED HEREIN WAS OBTAINED OR IMPROVED THROUGH FEDERAL FINANCIAL ASSISTANCE. THIS EASEMENT IS SUBJECT TO THE PROVISIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AND THE REGULATIONS ISSUED PURSUANT THERETO FOR SO LONG AS THE EASEMENT CONTINUES TO BE USED FOR THE SAME OR SIMILAR PURPOSE FOR WHICH FINANCIAL ASSISTANCE WAS EXTENDED OR FOR LONG AS THE GRANTEE OWNS IT, WHICHEVER IS LONGER.

IN WITNESS WHEREOF THE SAID GRANTEE EXECUTED THIS INSTRUMENT THIS 8th Day of May, 2015.

Edgar E. Gonzalez
 EDGAR E. GONZALEZ
 2219 S. CESAR CHAVEZ RD
 EDINBURG, TX 78542



STATE OF TEXAS - COUNTY OF HIDALGO
 OWNER'S DEDICATION, CERTIFICATION, AND ATTESTATION

I (WE), **EDGAR E. GONZALEZ**, AS OWNER(S) OF THE 3.00 ACRE TRACT OF LAND ENCOMPASSED WITHIN THE PROPOSED **EVG Farms SUBDIVISION** HEREBY SUBDIVIDE THE LAND AS DEPICTED IN THIS SUBDIVISION PLAT AND DEDICATE TO PUBLIC USE OF STREETS, PARK, AND EASEMENTS SHOWN HEREIN.

I CERTIFY THAT I HAVE COMPLIED WITH THE REQUIREMENTS OF TEXAS LOCAL GOVERNMENT CODE 232.032 AND THAT:

(A) THE WATER QUALITY AND CONNECTIONS TO THE LOTS MEET, OR WILL MEET, THE MINIMUM STATE STANDARDS;

(B) SEWER CONNECTIONS TO THE LOTS OR SEPTIC TANKS MEET, OR WILL MEET, THE MINIMUM REQUIREMENTS OF STATE STANDARDS;


(C) ELECTRICAL CONNECTIONS PROVIDED TO THE LOTS MEET, OR WILL MEET, THE MINIMUM STATE STANDARDS; AND

(D) GAS CONNECTIONS, IF AVAILABLE, PROVIDED TO THE LOTS MEET, OR WILL MEET, THE MINIMUM STATE STANDARDS.

I ATTEST THAT THE MATTERS ASSERTED IN THIS PLAT ARE TRUE AND COMPLETE.

Edgar E. Gonzalez
 EDGAR E. GONZALEZ
 2219 S. CESAR CHAVEZ RD
 EDINBURG, TX 78542

Meredith Gonzalez
 MEREDITH GONZALEZ
 MY COMMISSION EXPIRES



STATE OF TEXAS - COUNTY OF HIDALGO
 PLAT APPROVAL CERTIFICATE

UNDER LOCAL GOVERNMENT CODE § 232.028(a)

WE, THE UNDERSIGNED CERTIFY THAT THIS PLAT OF THE EVG Farms SUBDIVISION WAS REVIEWED AND APPROVED BY THE HIDALGO COUNTY COMMISSIONERS COURT ON _____ 20____.

HIDALGO COUNTY JUDGE _____ HIDALGO COUNTY CLERK _____

I, THE UNDERSIGNED CERTIFY THAT THIS PLAT OF THE EVG Farms SUBDIVISION WAS REVIEWED AND APPROVED BY THE HIDALGO COUNTY ENVIRONMENTAL HEALTH DIVISION MANAGER ON _____ 20____.

HIDALGO COUNTY ENVIRONMENTAL HEALTH DIVISION MANAGER _____

DRAINAGE DISTRICT CERTIFICATE


HIDALGO COUNTY DRAINAGE DISTRICT NO. 1 HEREBY CERTIFIES THAT THE DRAINAGE PLANS FOR THIS SUBDIVISION COMPLY WITH THE MINIMUM STANDARDS OF THE DISTRICT ADOPTED UNDER TEXAS WATER CODE NO. 49.211(C). THE DISTRICT HAS NOT REVIEWED AND DOES NOT CERTIFY THAT THE DRAINAGE STRUCTURES DESCRIBED ARE APPROPRIATE FOR THE SPECIFIC SUBDIVISION, BASED ON GENERALLY ACCEPTED ENGINEERING CRITERIA. IT IS THE RESPONSIBILITY OF THE DEVELOPER OF THE SUBDIVISION AND ITS ENGINEER TO MAKE THESE DETERMINATIONS.

BY _____ DATE _____

ENGINEER CERTIFICATE

I, THE UNDERSIGNED, A REGISTERED ENGINEER IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THE PROPER ENGINEERING CONSIDERATIONS HAVE BEEN GIVEN TO THIS PLAT.

Inez B. Garza 5/8/15
 INEZ B. GARZA JR.
 REG. PROFESSIONAL ENGINEER NO. 60824
 DATE



SURVEYOR CERTIFICATE

I, THE UNDERSIGNED, CERTIFY THAT THE ABOVE PLAT IS AN ACTUAL SURVEY MADE ON THE GROUND UNDER MY SUPERVISION AND THAT THERE ARE NO VISIBLE EASEMENTS OR ENCROACHMENTS EXCEPT AS SHOWN AND THAT ALL CORNERS HAVE BEEN LOCATED AS INDICATED.

Jose Mario Gonzalez
 JOSE MARIO GONZALEZ
 REG. PROFESSIONAL LAND SURVEYOR NO. 5571
 DATE 5-8-15



HIDALGO COUNTY IRRIGATION DISTRICT NO. 2 CERTIFICATE

THIS PLAT APPROVED BY THE HIDALGO COUNTY IRRIGATION DISTRICT NO. 2 ON THIS _____ DAY OF _____, 2015.

NO IMPROVEMENTS OF ANY KIND (INCLUDING WITHOUT LIMITATION, TREES, FENCES, AND BUILDINGS) SHALL BE PLACED UPON HIDALGO COUNTY IRRIGATION DISTRICT NO. 2 RIGHTS-OF-WAYS OR EASEMENTS.

PRESIDENT _____ SECRETARY _____

STATE OF TEXAS - CITY OF EDINBURG
 PLAT APPROVAL CERTIFICATE

I, THE UNDERSIGNED, MAYOR TO THE CITY OF EDINBURG, HEREBY CERTIFY THAT THIS SUBDIVISION PLAT CONFORMS TO ALL REQUIREMENTS OF THE SUBDIVISION REGULATIONS OF THIS CITY WHEREIN MY APPROVAL IS REQUIRED.

CITY MAYOR _____ DATE _____ ATTEST: CITY SECRETARY _____ DATE _____

I, THE UNDERSIGNED CHAIRMAN OF THE PLANNING AND ZONING COMMISSION OF THE CITY OF EDINBURG, TEXAS HEREBY CERTIFY THAT THIS SUBDIVISION PLAT CONFORMS TO ALL REQUIREMENTS OF THE SUBDIVISION REGULATIONS OF THE CITY WHEREIN MY APPROVAL IS REQUIRED.


PLANNING AND ZONING COMMISSION CHAIRMAN _____ DATE _____

METES AND BOUNDS DESCRIPTION

THE WEST 3 ACRES OF THE SOUTH 20 ACRES OF LOT SIX (6), BLOCK 60 (SIXTY), ALAMO LAND AND SUGAR COMPANY SUBDIVISION, HIDALGO COUNTY, TEXAS, AS PER MAP RECORDED IN VOLUME 1, PAGE 24-25, MAP RECORDS OF HIDALGO COUNTY, TEXAS, SAID 3 ACRE TRACT OF LAND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

- COMMENCING AT A PK-NAIL SET AT THE SOUTHWEST CORNER OF LOT 6, BLOCK 60, FOR THE SOUTHWEST CORNER OF THIS TRACT OF LAND AND THE POINT OF BEGINNING;
- THENCE NORTH 08°45'00" EAST, WITH THE WEST LINE OF SAID LOT 6, AT 20.00 FEET PASS A 1/2" ROD FOUND AT THE NORTH RIGHT-OF-WAY LINE OF IOWA ROAD, AT 660.00 FEET IN ALL TO A 1/2" ROD FOUND FOR THE NORTHWEST CORNER OF THIS TRACT OF LAND;
- THENCE SOUTH 81°15'00" EAST, A DISTANCE OF 198.00 FEET TO A 1/2" ROD SET FOR THE NORTHEAST CORNER OF THIS TRACT OF LAND;
- THENCE SOUTH 08°45'00" WEST, AT 640.00 FEET PASS A 1/2" ROD SET AT THE NORTH RIGHT-OF-WAY LINE OF SAID IOWA ROAD, AT 660.00 FEET IN ALL TO THE SOUTH LINE OF SAID LOT 6 TO A PK-NAIL SET FOR THE SOUTHEAST CORNER OF THIS TRACT OF LAND;
- THENCE NORTH 81°15'00" WEST, WITH THE SOUTH LINE OF SAID LOT 6, A DISTANCE OF 198.00 FEET TO THE POINT OF BEGINNING, CONTAINING 3.0 ACRES OF LAND MORE OR LESS.

LOCATION OF SUBDIVISION WITH RESPECT TO THE EXTRATERRITORIAL JURISDICTION OF A MUNICIPALITY: **EVG Farms SUBDIVISION** IS LOCATED WITHIN HIDALGO COUNTY PRECINCT NO. 4 IN THE CENTRAL PART OF HIDALGO COUNTY, ALONG THE NORTH SIDE OF IOWA ROAD, APPROXIMATELY 1,122 FEET WEST OF ALAMO ROAD. THE ONLY NEARBY MUNICIPALITY IS THE CITY OF EDINBURG. ACCORDING TO THE U.S. CENSUS BUREAU, THE POPULATION IS 72,424 - 2010 CENSUS. **EVG Farms SUBDIVISION** LIES APPROXIMATELY 4,200 FEET (0.80 MILES) FROM EDINBURG'S CITY LIMITS AND IS WITHIN THE CITY'S 2-MILE EXTRATERRITORIAL JURISDICTION (E.T.J.) UNDER LOCAL GOVERNMENT CODE § 42.021.



SUBDIVISION PLAT OF
EVG Farms

THE WEST 3 ACRES OF THE SOUTH 20 ACRES OF LOT SIX (6), BLOCK 60 (SIXTY), ALAMO LAND AND SUGAR COMPANY SUBDIVISION, HIDALGO COUNTY, TEXAS, AS PER MAP RECORDED IN VOLUME 1, PAGE 24-25, MAP RECORDS OF HIDALGO COUNTY, TEXAS.

DATE OF PREPARATION: MAY 8, 2015

GARZA-GARZA CONSULTING ENGINEERS
 FIRM REGISTRATION NO. F-004983
 3011 SAN FELIPE ST. - SAN JUAN, TX 78589
 OFFICE: (956) 905-2360
 CELL: (956) 451-4729

CITY OF EDINBURG ETJ - HIDALGO COUNTY PAGE: 1 OF 2

INDEX OF SHEETS	
SHEET 1	PLAT WITH LOT, EXISTING STREETS, EXISTING R.O.W., AREA MAP, DESCRIPTION OF LOCATION OF SUBDIVISION WITH RESPECT TO THE ETJ OF A MUNICIPALITY, METES AND BOUNDS, METES AND BOUNDS, PLAT NOTES AND RESTRICTIONS, OWNERS' ACKNOWLEDGMENT, N.A.W.S.C. EASEMENT, AND THE FOLLOWING CERTIFICATE: PUBLIC USE OF STREETS, PLAT APPROVAL, H.C.D.D. No. 1, HIDALGO COUNTY IRRIGATION DISTRICT No. 2, SURVEYOR'S, ENGINEER'S, H.C.H.D., CITY OF EDINBURG P&Z, AND CITY OF EDINBURG STAFF.
SHEET 2	UTILITY LAYOUT, WATER AND SANITARY SEWER SYSTEMS, TOPOGRAPHY & DRAINAGE LAYOUT, DRAINAGE REPORT, ENGINEER'S CERTIFICATION

PRINCIPAL CONTACTS:				
OWNER	NAME	ADDRESS	PHONE(S)	
	EDGAR E. GONZALEZ	2219 S. CESAR CHAVEZ RD EDINBURG, TX 78542	(956) 325-7777	
ENGINEER	INEZ B. GARZA JR.	3011 SAN FELIPE ST. - SAN JUAN, TX 78589	(956) 905-2360 (956) 451-4729	
SURVEYOR	JOSE MARIO GONZALEZ	R.P.L.S. 24593 FM 88 - MONTE ALTO, TX 78538	(956) 380-5154 (956) 380-5156	

RIO DELTA SURVEYING

24693 FM 88, MONTE ALTO, TX 78538
 (TEL) 956-380-5154 (FAX) 956-380-5156
 EMAIL: MARIO@RIODELTASURVEYING.COM
 TBPIS FIRM # 10019000

DRAINAGE STATEMENT
 REVISED JANUARY 19, 2015
 PREPARED BY: INEZ B. GARZA JR., P.E.
 EVG Farms SUBDIVISION
 CITY OF EDINBURG E.T.J.
 HIDALGO COUNTY, TEXAS

EVG Farms SUBDIVISION IS A (1) ONE LOT SINGLE-FAMILY RESIDENTIAL SUBDIVISION CONSISTING OF THE WEST 3 ACRES OF THE SOUTH 20 ACRES OF LOT SIX (6), BLOCK 60 (SIXTY), ALAMO LAND AND SUGAR COMPANY SUBDIVISION, HIDALGO COUNTY, TEXAS, AS PER MAP RECORDED IN VOLUME 1, PAGE 24-25, MAP RECORDS OF HIDALGO COUNTY, TEXAS.

THE SUBDIVISION IS IN ZONE "B"; ZONE "B" IS DEFINED AS AREAS BETWEEN LIMITS OF THE 100-YEAR FLOOD AND 500-YEAR FLOOD; OR CERTAIN AREAS SUBJECT TO 100-YEAR FLOODING WITH AVERAGE DEPTHS LESS THAN ONE (1) FOOT OR WHERE THE CONTRIBUTING DRAINAGE AREA IS LESS THAN ONE SQUARE MILE; OR AREAS PROTECTED BY LEVEES FROM THE BASE FLOOD, ACCORDING TO FEMA'S FLOOD INSURANCE RATE MAP COMMUNITY PANEL No. 480334 0425 C, MAP REVISED NOVEMBER 16, 1982.

ACCORDING TO THE SOIL SURVEY REPORT PREPARED FOR HIDALGO COUNTY BY THE U.S.D.A. SOIL CONSERVATION SERVICE, THE SITE CONSISTS OF HIDALGO SANDY CLAY LOAM (28) AND RACOMBES SANDY CLAY LOAM (48) WITH 0 TO 1% SLOPES. THESE SOILS ARE MODERATELY WELL-DRAINED TO WELL-DRAINED, SURFACE RUNOFF IS MODERATE, PERMEABILITY IS MODERATE TO HIGH, AND THE WATER CAPACITY IS HIGH.


THERE IS NO ROADSIDE DITCH ON FRONT OF THIS PROPERTY ALONG THE NORTH SIDE OF IOWA ROAD. EXISTING RUNOFF SHEET FLOWS IN A SOUTHEASTERLY DIRECTION TO A ROADSIDE DITCH ALONG THE SOUTH SIDE OF IOWA ROAD AND THEN FLOWS EASTERLY TO ALAMO ROAD ROADSIDE DITCH, APPROXIMATELY 1,100 FEET FROM THIS PROPERTY. STORM WATER IS THEN CONVEYED TO THE SOUTH MAIN DRAIN, MAIN FLOODWATER CHANNEL, AND TO A FINAL OUTFALL AT THE LAGUNA MADRE.

USING THE RATIONAL METHOD, WE HAVE DETERMINED THAT A 10-YEAR RAINFALL EVENT WILL GENERATE APPROXIMATELY 3.14 CFS OF STORM RUNOFF ON THIS PROPERTY. WE HAVE ALSO USED THE RATIONAL METHOD TO DETERMINE THAT THE IMPROVED SUBDIVISION WILL GENERATE AN ESTIMATED 4.42 CFS OF RUNOFF FOR THE SAME 10-YEAR RAINFALL EVENT.

IN ACCORDANCE WITH HIDALGO COUNTY'S AND CITY OF EDINBURG'S DRAINAGE REQUIREMENTS, WE HAVE CALCULATED THAT APPROXIMATELY 1,652 CF OR 0.039 AC-FT OF STORM RUNOFF WILL NEED TO BE DETAINED ONSITE. THIS RUNOFF WILL BE DETAINED WITHIN DEPRESSED / GREEN AREAS OF PROPOSED LARGE LOT. OVERFLOW WILL BE RELEASED TO FOLLOW THE NATURAL DRAINAGE PATTERNS OF THE AREA. A DRAINAGE PLAN TO BE APPROVED BY THE CITY OF EDINBURG AND/OR BY HIDALGO COUNTY PLANNING DEPARTMENT BEFORE ISSUANCE OF A BUILDING PERMIT FOR THIS LOT.

BY MY SIGNATURE BELOW, I CERTIFY THAT THIS SUBDIVISION LIES IN ZONE "B"; ZONE "B" IS DEFINED AS AREAS BETWEEN LIMITS OF THE 100-YEAR FLOOD AND 500-YEAR FLOOD; OR CERTAIN AREAS SUBJECT TO 100-YEAR FLOODING WITH AVERAGE DEPTHS LESS THAN ONE (1) FOOT OR WHERE THE CONTRIBUTING DRAINAGE AREA IS LESS THAN ONE SQUARE MILE; OR AREAS PROTECTED BY LEVEES FROM THE BASE FLOOD, ACCORDING TO FEMA'S FLOOD INSURANCE RATE MAP COMMUNITY PANEL No. 480334 0425 C, MAP REVISED NOVEMBER 16, 1982.

INEZ B. GARZA JR., P.E.
 REGISTERED PROFESSIONAL ENGINEER NO. 60824
 DATE 5/18/15




LEGEND


- FOUND 1/2" IRON ROD
- FOUND 5/8" IRON ROD
- FOUND RAIL ROAD SPIKE
- SET 1/2" IRON ROD
- SET PK NAIL
- ▲ FOUND CPS
- POWER POLE
- TELEPHONE PEDESTAL
- ELECTRICAL BOX
- WATER METER
- IRRIGATION STAND PIPE
- MAIL BOX
- FENCE
- DRAINAGE NATURAL FLOW

ELEVATIONS



- NATURAL GROUND
- EDGE OF PAVEMENT (TOP)
- TOP OF ASPHALT



- GENERAL NOTES:**
- DRAWINGS INDICATE COPPER SERVICE LINES.
 - FOR P.V.C. SERVICE LINES REFER TO SMALLER TYPE NOTES.
 - ALL COMPRESSION OR PACK TYPE FITTINGS & JOINTS REQUIRE STAINLESS STEEL INSERTS OF REQUIRED SIZE.
 - WATER SERVICE CONNECTIONS CROSSING A STREET SHALL BE ENCASED IN A P.V.C. SLOPE CASING. LENGTH OF CASING SHALL BE WIDTH OF STREET PLUS 10.0 FEET.



TYPICAL DUAL WATER SERVICE CONNECTION



TYPICAL ROAD SIDE DITCH DETAIL

**FINAL ENGINEERING REPORT FOR
 EVG Farms SUBDIVISION**
 WATER SUPPLY: DESCRIPTION, COSTS, AND OPERABILITY DATE

EVG Farms SUBDIVISION WILL BE PROVIDED WITH POTABLE WATER BY NORTH ALAMO WATER SUPPLY CORPORATION (NAWSC). THE SUBDIVIDER AND NAWSC HAVE ENTERED INTO A CONTRACT IN WHICH NAWSC HAS PROMISED TO PROVIDE A WATER METER FOR THIS LOT AND TO PROVIDE SUFFICIENT WATER TO THIS SUBDIVISION FOR AT LEAST 30 YEARS AND NAWSC HAS PROVIDED DOCUMENTATION TO SUFFICIENTLY ESTABLISH THE LONG TERM QUANTITY AND QUALITY OF THE AVAILABLE WATER SUPPLIES TO SERVE THE FULL DEVELOPMENT OF EVG Farms SUBDIVISION. N.A.W.S.C. HAS AN EXISTING 2 1/2" (63.50) WATER LINE ON THE SOUTH SIDE OF IOWA ROAD. THIS LOT WILL BE SERVICED BY (1) 3/4" (1.91) DIAMETER SERVICE LINE GOING TO THE METER BOX, TOTALING (1) METER. THE SUBDIVIDER HAS PAID A TOTAL OF \$1,600.00 OR \$1,600.00 PER LOT FOR THE CONSTRUCTION OF THE AFORESAID WATER DISTRIBUTION SYSTEM, WHICH IT HAS BEEN INSTALLED. IN ADDITION, THE SUBDIVIDER HAS PAID "N.A.W.S.C." A TOTAL OF \$1,375.00 OR \$1,375.00 PER LOT, AS STATED IN THE 30 YEAR WATER SERVICE AGREEMENT, WHICH COVERS THE COSTS OF WATER RIGHTS, WATER METERS, METER BOXES, WATER SUPPLY FEES, AND ALL OTHER FEES ASSOCIATED WITH WATER SUPPLY. THE ENTIRE WATER FACILITIES HAVE BEEN APPROVED AND ACCEPTED BY N.A.W.S.C. AND SAID DISTRIBUTION SYSTEM IS OPERABLE AS OF THE DATE OF THE RECORDING OF THE PLAT.

SEWER FACILITIES: DESCRIPTION, COSTS, AND OPERABILITY DATE

SEWAGE FOR EVG Farms SUBDIVISION WILL BE TREATED BY INDIVIDUAL ON-SITE SEWAGE FACILITY ("OSSF") CONSISTING OF STANDARD DESIGN DUAL COMPARTMENT SEPTIC TANKS AND DRAIN FIELDS ON THIS LOT. THE UNDERSIGNED PROFESSIONAL ENGINEER HAS EVALUATED THE SUITABILITY OF THE SUBDIVISION SITE FOR OSSF AND SUBMITTED A REPORT CONCLUDING THAT THE SITE IS SUITABLE FOR OSSF. THE REPORT WAS REVIEWED AND APPROVED BY THE HIDALGO COUNTY HEALTH DEPARTMENT. THIS LOT HAS ADEQUATE AREA FOR A REPLACEMENT DRAINFIELD.

THE SEPTIC TANK SYSTEMS FOR THIS LOT HAS BEEN INSTALLED AS OF THE TIME OF APPLICATION FOR FINAL PLAT APPROVAL. THE SUBDIVIDER HAS PAID A TOTAL OF \$1,200.00 OR \$1,200.00 PER LOT FOR THE SEPTIC TANK SYSTEM. THE PRICE IS INCLUDING THE COSTS FOR THE REQUIRED PERMITS AND LICENSES. THE SUBDIVIDER WILL INCLUDE THE COST OF A SEPTIC TANK SYSTEM IN THE SALE PRICE OF THE LOT.

CERTIFICATION:

BY MY SIGNATURE BELOW, I CERTIFY THAT THE WATER AND SEWAGE SERVICE FACILITIES DESCRIBED ABOVE ARE IN COMPLIANCE WITH THE MODEL SUBDIVISION RULES ADOPTED UNDER SECTION 16.343, WATER CODE.


I CERTIFY THAT THE ACTUAL COSTS FOR THE INSTALLED WATER AND ON-SITE SEWAGE FACILITIES, DISCUSSED ABOVE, ARE AS FOLLOWS:

WATER FACILITY: THESE FACILITIES ARE FULLY CONSTRUCTED, INCLUDING WATER METERS AND WATER METER BOXES. THE TOTAL COST FOR THIS WATER SYSTEM INCLUDING ALL N.A.W.S.C. FEES WAS \$2,975.00 FOR THE ENTIRE SUBDIVISION, WHICH EQUALS TO \$2,975.00 PER LOT.

SEWAGE FACILITIES: SEPTIC TANK SYSTEM ARE FULLY CONSTRUCTED AND THE TOTAL COST WAS \$1,200.00 FOR THE ENTIRE SUBDIVISION, WHICH EQUALS TO \$1,200.00 PER LOT (ALL INCLUSIVE).

COST OF IMPROVEMENTS

ROADSIDE DITCH CONSTRUCTION	\$ 500.00
WATER SERVICE INSTALLATION W/FEES	\$ 2,975.00
SEPTIC TANK SYSTEM	\$ 1,200.00
TOTAL	\$ 4,675.00



THESE LOTS IN THIS PROPOSED SUBDIVISION ARE AT LEAST 1/2 ACRE IN SIZE. THE NATURAL RESOURCE CONSERVATION SERVICE SOIL SURVEY BOOK INDICATED A CLAY LOAM SOIL. AT LEAST TWO SOIL EXCAVATIONS WERE PERFORMED ON THE SITE. AT OPPOSITE ENDS OF THE PROPOSED DISPOSAL AREA. (ADDITIONAL BORINGS WERE UNNECESSARY BECAUSE THE SOILS ARE VERY UNIFORM WITHIN THIS LIMITS AREA). THE SOIL IS A UNIFORM SANDY EXTENDING UP TO 36" BELOW THE BOTTOM OF ANY PROPOSED EXCAVATIONS. THERE IS NO INDICATION OF GROUNDWATER OR A RESTRICTIVE LAYER WITHIN 24" OF BOTTOM OF THE PROPOSED EXCAVATIONS. THE SUBDIVISION DRAINS WELL.

CADA SOLAR MIDE POR LO MENOS MEDIO ACRE. SE HICIERON POR LO MENOS DOS EXCAVACIONES EN LUGARES OPUESTOS EN LA SUBDIVISION (EXCAVACIONES ADICIONALES NO FUERON NECESARIAS PORQUE EL TERRENO EN ESTA AREA ES SIGNIFICATIVAMENTE UNIFORME). EL TERRENO ES UNIFORME (TERRENO ARCILLOS Y SUELOS LABRADOS) Y SE EXTIENDE A 36 PULGADAS BAJO TODAS LAS EXCAVACIONES PROPUESTAS. NO EXISTE EVIDENCIA DE AGUA 24 PULGADAS MAS ARRIBA DE LO MAS BAJO DE LAS EXCAVACIONES PROPUESTAS. EL AGUA EN ESTA AREA FLUYE BIEN.

SUBDIVIDER CERTIFICATION:


BY COMPLETING THE IMPROVEMENTS DESCRIBED ON THE PLAT, SUBDIVIDER WILL COMPLY WITH MINIMUM STATE STANDARDS AND THAT (a) WATER QUALITY AND CONNECTIONS INCLUDING WATER METERS TO THE LOTS MEET SUCH STANDARDS AND (b) SEWER CONNECTIONS TO THE LOTS OR SEPTIC TANKS MEET OR WILL MEET SUCH STANDARDS AND WILL BE CONSTRUCTED IN ACCORDANCE WITH STATE AND COUNTY REGULATIONS.

SUBDIVIDER STATEMENT:

WE, EDGAR E. GONZALEZ SUBDIVIDER(S) OF EVG Farms SUBDIVISION HEREBY CERTIFY SEWER PERMITS HAVE BEEN PAID AND ARE ON FILE WITH THE HIDALGO COUNTY HEALTH DEPARTMENT AND THAT AN ADEQUATE DRINKING WATER SOURCE IS IMMEDIATELY AVAILABLE TO EACH LOT OF THE TYPE, QUALITY & QUANTITY TO ENABLE EACH PERSON PURCHASING A LOT TO HAVE ADEQUATE WATER TO COMPLY WITH THE REGULATIONS AND THE LAWS OF THE STATE AS REQUIRED BY STATE AND COUNTY REGULATIONS.

BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, ON THIS DAY PERSONALLY APPEARED EDGAR E. GONZALEZ PROVED TO ME THROUGH HIS/HER/THEIR TEXAS DEPARTMENT OF PUBLIC SAFETY DRIVER LICENSE(S) TO BE THE PERSON(S) WHOSE NAME(S) ARE SUBSCRIBED TO THE FOREGOING INSTRUMENT, WHO, BEING BY ME FIRST DULY SWORN, DECLARED THAT THE STATEMENTS THEREIN ARE TRUE AND CORRECT AND ACKNOWLEDGED THAT THEY EXECUTED THE SAME FOR THE PURPOSED AND CONSIDERATION THEREBY EXPRESSED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 8th DAY OF May, 2015.



**REPORTE FINAL DE INGENIERIA PARA LA SUBDIVISION
 "EVG Farms SUBDIVISION"**
 PROVISION DE AGUA: DESCRIPCION, GASTOS Y FECHA DE INICIO

LA SUBDIVISION "EVG Farms SUBDIVISION" RECIBIRA SU PROVISION DE AGUA DE "NORTH ALAMO WATER SUPPLY CORPORATION" (LA COMPANIA DE AGUA NAWSC). EL DUEÑO DE LA SUBDIVISION Y LA COMPANIA NAWSC HAN FIRMADO UN CONTRATO DONDE NAWSC HA PROMETIDO A RESERVAR UN MEDIDOR DE AGUA PARA CADA SOLAR, POR EL CUAL LA SUBDIVISION RECIBIRA SU PROVISION DE AGUA POR LOS PROXIMOS 30 AÑOS. NAWSC HA PRESENTADO DOCUMENTACION DEMONSTRANDO A LARGO PLAZO LA CANTIDAD Y CALIDAD DE AGUA ACCESIBLE PARA SERVIR EN EL FUTURO A ESTE DESARROLLO DE EVG Farms SUBDIVISION. N.A.W.S.C. TIENE UNA LINEA DE 2 1/2" (PULGADAS) DE DIAMETRO EN EL LADO SUR DE LA CALLE "IOWA". ESTE SOLAR SERA SERVIDO POR (1) SERVICIO SINGULAR DE 3/4" (PULGADAS) DE DIAMETRO CONECTANDO ALA CAJA DEL MEDIDOR, CON UN TOTAL DE (1) MEDIDOR. EL SUBDIVIDER A PAGADO UNA CANTIDAD TOTAL DE \$1,600.00 O \$1,600.00 POR SOLAR. PARA LA CONSTRUCCION DE TODO EL SISTEMA DE AGUA YA MENCIONADO, EL SERVICIO DE AGUA CON LA CAJA DE MEDIDOR YA HAN SIDO INSTALADAS. EL SUBDIVIDER TAMBIEN HA PAGADO HA "NAWSC" UNA SUMA DE \$1,375.00 TOTAL, \$1,375.00 POR SOLAR, COMO LO INDICA EL CONTRATO DE GARANTIA DE SERVICIO DE AGUA POR 30 AÑOS DE NAWSC, QUE INCLUYE LOS COSTOS DE DERECHOS DE AGUA, LOS MEDIDORES DE AGUA, LAS CAJAS PARA LOS MEDIDORES, CUOTAS DE SERVICIO DE AGUA, Y CUALQUIER OTRO TIPO DE CUOTAS RELACIONADAS CON EL SERVICIO DE AGUA. TODO EL SISTEMA DE SERVICIO DE AGUA HA SIDO APROBADO Y ACEPTADO POR "NAWSC" Y TAMBIEN, EL SISTEMA DE DISTRIBUCION DE AGUA ESTA FUNCIONANDO DESDE LA FECHA QUE ESTE MAPA O "PLAT" FUE REGISTRADO.

DRENAJE: DESCRIPCION, GASTOS Y FECHA DE INICIO

EL SISTEMA DE DRENAJE PARA EVG Farms SUBDIVISION ES DE FOSAS SEPTICAS EN CADA SOLAR. CADA SISTEMA DE FOSA SEPTICA CONSISTE DE UN TANQUE SEPTICO DE MODELO DUAL Y DE UN CAMPO DE DRENAJE PARA ESTE SOLAR. EL INGENIERO AUTOR DE ESTE DOCUMENTO HA EVALUADO EL AREA DONDE SE ENCUENTRA LA SUBDIVISION Y HA PREPARADO UN REPORTE QUE CONCLUYE QUE ESTE TERRENO ES ADECUADO PARA ESTAS FOSAS SEPTICAS ("OSSF"). EL REPORTE FUE APROBADO POR EL DEPARTAMENTO DE SALUBRIDAD DEL CONDADO DE HIDALGO (HIDALGO COUNTY HEALTH DEPARTMENT) SEGUN EL REPORTE ESTE SOLAR TIENE SUFICIENTE AREA PARA REPLACAMIENTO DEL CAMPO DE DRENAJE.

EL SISTEMA SEPTICO PARA TODOS LOS SOLARES HAN SIDO INSTALADOS ANTES DEL TIEMPO DE APLICACION PARA APROBACION FINAL DEL "PLAT". EL SUBDIVIDER A PAGADO UNA CANTIDAD TOTAL DE \$1,200.00 O \$1,200.00 POR CADA SOLAR PARA LA INSTALACION DE EL SISTEMA SEPTICO. ESTE PRECIO YA INCLUYE LOS PERMISOS REQUERIDOS Y LICENSAS. EL SUBDIVIDER INCLUIRA EL COSTO DEL SISTEMA DE FOSA SEPTICA EN EL PRECIO DE VENTA DEL SOLAR.


CERTIFICACION:

CON MI FIRMA, CERTIFICO QUE LOS SERVICIOS Y SISTEMAS DE AGUA Y DE DRENAJE, DESCRITOS EN ESTE DOCUMENTO, CUMPLEN CON LAS MODEL SUBDIVISION RULES (LAS REGLAS GOBERNANDO A LAS SUBDIVISIONES), ADOPTADAS EN LA SECCION 16.343 DEL TEXAS WATER CODE (CODIGO DE AGUA DE TEXAS).

CERTIFICO QUE LOS GASTOS DE INSTALACION DE LOS SISTEMAS DE AGUA Y DE DRENAJE FUERON:

AGUA: EL SISTEMA/SERVICIO DE AGUA FUE INSTALADO Y COMPLETAMENTE CONSTRUIDO, INCLUYENDO LA INSTALACION DEL MEDIDOR DE AGUA CON CAJA. EL COSTO PARA ESTE SISTEMA INCLUYENDO TODAS LAS CUOTAS DE N.A.W.S.C. FUE UN TOTAL DE \$2,975.00 PARA TODA LA SUBDIVISION, QUE ES IGUAL HA \$2,975.00 POR SOLAR.

DRENAJE: LOS SISTEMAS DE LAS FOSAS SEPTICAS TAMBIEN HAN SIDO INSTALADAS Y COMPLETAMENTE CONSTRUIDAS CON UN TOTAL DE \$1,200.00 PARA TODA LA SUBDIVISION, QUE ES IGUAL A \$1,200.00 POR SOLAR (1000 INCLUSO).



SOIL EVALUATION REPORT INFORMATION


SOIL BORING NUMBER: 1

DEPTH (FEET)	TEXTURE CLASS	SOIL TEXTURE	STRUCTURE FOR CLASS IN BLOCCY, PLATTY OR MASSIVE	DRAINAGE (MOISTURE WATER TABLE)	RESTRICTIVE HORIZON	OBSERVATIONS
1	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
2	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
3	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
4	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
5	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.

SOIL EVALUATION REPORT INFORMATION

SOIL BORING NUMBER: 2

DEPTH (FEET)	TEXTURE CLASS	SOIL TEXTURE	STRUCTURE FOR CLASS IN BLOCCY, PLATTY OR MASSIVE	DRAINAGE (MOISTURE WATER TABLE)	RESTRICTIVE HORIZON	OBSERVATIONS
1	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
2	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
3	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
4	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.
5	II	SANDY LOAM	N/A	NONE	NONE	SOIL SUITABLE FOR O.S.S.F.



AREA MAP - SCALE: 1"=1,000'

**SUBDIVISION PLAT OF
 EVG Farms**
 THE WEST 3 ACRES OF THE SOUTH 20 ACRES OF LOT SIX (6), BLOCK 60 (SIXTY), ALAMO LAND AND SUGAR COMPANY SUBDIVISION, HIDALGO COUNTY, TEXAS, AS PER MAP RECORDED IN VOLUME 1, PAGE 24-25, MAP RECORDS OF HIDALGO COUNTY, TEXAS

AS INSTRUMENT NUMBER:
 OF THE MAP RECORDS OF HIDALGO COUNTY, TEXAS

PRINCIPAL CONTACTS:

NAME	ADDRESS	PHONE(S)
OWNER: EDGAR E. GONZALEZ	2219 S. CESAR CHAVEZ RD EDINBURG, TX 78542	(956) 325-7777
ENGINEER: INEZ B. GARZA JR. P.E.	3011 SAN FELIPE ST. - SAN JUAN, TX 78589	(956) 905-2380 (956) 451-4728
SURVEYOR: JOSE MARIO GONZALEZ R.P.L.S.	24593 FM 88 - MONTE ALTO, TX 78538	(956) 380-5154 (956) 380-5156

RIO DELTA SURVEYING
 24593 FM 88, MONTE ALTO, TX 78538
 (TEL) 956-380-5154 (FAX) 956-380-5156
 EMAIL: MARIO@RIODELTASURVEYING.COM
 TPLS FIRM # 10013800

DATE OF PREPARATION: MAY 8, 2015
GARZA-GARZA CONSULTING ENGINEERS
 FIRM REGISTRATION NO. F-004983
 3011 SAN FELIPE ST. - SAN JUAN, TX 78589
 OFFICE: (956) 905-2360
 CELL: (956) 451-4729