



CHUBB GROUP OF INSURANCE COMPANIES

STATEMENT OF LOSS

	VALUE	LOSS	CLAIM
Insured: Hidalgo County			
Cause: Hail			
Claim No: 040515032700			
Building Coverage Limit	\$ 229,098,497.00		
Admin, Alpha/Bravo, Charlie Visitation	\$ 9,967.40		
Central Fence & Supply	\$ 1,150.00		
Sheriff Dept. Gas Pump Canopy	\$ 49,236.22		
Total Building Loss	\$ 60,353.62	\$ 60,353.62	
Less Deductible	(\$25,000.00)		
Less Prior Payments	\$ -		
Balance Due	\$ 35,353.62		\$ 35,353.62
Total Value, Loss, Claim	\$ 229,098,497.00	\$ 60,353.62	\$ 35,353.62

Estimate For Damages in Administration and Alpha/Bravo, Charlie Visitation

Ceiling Tiles-3 boxes	138.00
Sheet Rock(4 x 8)	84.00
Lights-4	14.40
Ballast-1	12.00
Cover Base-1 box	114.00
Adhesive-1 pail	65.00
Carpet	9,540.00

Total: 9,967.40



504 E. Ferguson
 P.O. Box 827
 Pharr, TX 78577
 (956) 783-7959 / 800-491-7923
 Fax # (956) 787-4311
 www.CentralFenceLtd.com

Estimate

Date	Estimate #
8/31/2015	32849

Name / Address		Estimator	Project
Hidalgo County (Jail) 701 El Cibolo Rd Edinburg, Tx 381-7931		Ernie	
Qty	Description		
	Replace 25' LF of 24' Razor Ribbon on top of 8' chain link fence 9GA.		
	Out-of-state sale, exempt from sales tax		
Thank you for your business.		Total	\$1,150.00

Estimate given is not final until a Central Fence representative has visited the job site and verified project information. A 50% down payment is required prior to initiation of project. Please sign & fax back to us, if in agreement with price. Estimate is good for 15 days, unless noted otherwise.

Signature _____

Sheriff Dept Gas Pumps Canopy
 Year 2015 Quarter 1
 Unit Detail Report

Prepared By:
 Gilbert Herrera

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 01 General Requirements					
013113200260	Field personnel, superintendent, average	1.00	Week	\$3,450.00	\$3,450.00
013113200260	Field personnel, superintendent, average	1.00	Week	\$3,450.00	\$3,450.00
015419500200	Crate crew, daily use for small jobs, 25-ton truck-mounted hydraulic crane, portal to portal	3.00	Day	\$1,432.08	\$4,296.24
015436501300	Mobilization or demobilization, delivery charge for equipment, hauled on 3-ton capacity towed trailer	4.00	Ea.	\$207.76	\$831.04
Division 01 General Requirements Subtotal					\$12,027.28
Division 03 Concrete					
033053401420	Structural concrete, in place, column (4000 psi), round, 2% - 3% reinforcing, 24" diameter, includes forms(4 uses), Grade 60 rebar, concrete (Portland cement Type I), placing and finishing	3.50	C.Y.	\$1,056.36	\$3,697.26
Division 03 Concrete Subtotal					\$3,697.26
Division 05 Metals					
050505100240	Selective metals demolition, structural framing members, 1/4 - 2 tons, remove whole or cut up into smaller pieces, incl loading, excl shoring, bracing, cutting, hauling, dumping	12.00	Ea.	\$106.15	\$1,273.80
050505100500	Selective metals demolition, steel roof decking, uncovered, bare, excl shoring, bracing, cutting, hauling, dumping	1,604.00	S.F.	\$0.38	\$609.52
051223174650	Column, structural tubing, square, 10" x 10" x 1/2" x 16'-0", incl shop primer, cap & base plate, bolts	4.00	Ea.	\$1,629.96	\$6,519.84
051223630500	Steel plate, structural, for connections & stiffeners, 1" T, shop fabricated, incl shop primer	4.00	S.F.	\$57.30	\$229.20
051223750502	Structural steel beam or girder, 100-ton project, 1 to 2 story building, W8x31, A992 steel, shop fabricated, incl shop primer, bolted connections	80.00	L.F.	\$57.52	\$4,601.60
051223752902	Structural steel beam or girder, 100-ton project, 1 to 2 story building, W16x31, A992 steel, shop fabricated, incl shop primer, bolted connections	40.00	L.F.	\$53.71	\$2,148.40

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
053123503050	Metal roof decking, steel, open type B wide rib, galvanized, under 50 Sq, 1-1/2" D, 16 gauge	0.00	S.F.	\$5.03	\$0.00
054113104100	Bridging, continuous galvanized angle through load bearing studs, per row, studs 12" O.C., 18 ga x 2" x 2"	8.00	C.L.F.	\$145.69	\$1,165.52
Division 05 Metals Subtotal					\$16,547.88
Division 07 Thermal and Moisture Protection					
074113200900	Steel roofing panels, on steel frame, flat profile, standard finish, 2" x 2" batten, 12" wide, 22 gauge	1,604.00	S.F.	\$8.30	\$13,313.20
Division 07 Thermal and Moisture Protection Subtotal					\$13,313.20
Division 26 Electrical					
260505100100	Conduit, rigid galvanized steel, 1/2" to 1" diameter, electrical demolition, remove conduit to 15' high, including fittings & hangers	100.00	L.F.	\$1.02	\$102.00
260505100320	Armored cable, (BX), #10, 2 wire, average 50' runs, electrical demolition, remove	500.00	L.F.	\$0.48	\$240.00
260533132550	Intermediate metal conduit, 1" diameter, to 15' high, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	60.00	L.F.	\$7.17	\$430.20
265633108120	Walkway luminaire, exterior, cube 16" opal, high pressure sodium, 70 watt	4.00	Ea.	\$719.60	\$2,878.40
Division 26 Electrical Subtotal					\$3,650.60
Subtotal					\$49,236.22
General Contractor's Markup on Subs			0.00%		\$0.00
Subtotal					\$49,236.22
General Conditions			0.00%		\$0.00
Subtotal					\$49,236.22
General Contractor's Overhead and Profit			0.00%		\$0.00
Grand Total					\$49,236.22