

CHANGE ORDER NUMBER TWO (2)

Project: **ELDORA ROAD IMPROVEMENTS**
 DATE OF ISSUANCE: May 19, 2016 EFFECTIVE DATE: _____

OWNER: **HIDALGO COUNTY**
 OWNER'S CONTRACT NO: C-16-061-01-19

CONTRACTOR: 2GS, LLC, dba Earthworks Enterprise ENGINEER: Jose N. Saldivar, P. E.
P.O. BOX 595 Project Engineer
PENITAS, TEXAS 78576 Jose N. Saldivar, P. E.
902 North Doolittle Road
Edinburg, TX 78542

You are directed to make the following changes in the Contract Documents.

- Description:
1. Add 1,149 SY to Item 1 (1 1/2" HMAC Type "D" 1,149 SY @ \$9.00 = \$10,341.00)
 2. Add 1,134 SY New Item (Subgrade Excavation and Removal 1,134 SY @ \$6.00 = \$6,804.00)
 3. Add 1,134 SY New Item 10" Caliche Base (6" Existing Lime Treated Salvage and 4" New Caliche 1,134 SY @ \$ 7.50 = \$8,505.00)
 - 4.
 - 5.
 - 6.

- Reason for Change Order:
1. The roadway section was modified to account for heavier traffic entering and exiting transportation/trucking company located along Eldora Road.
 2. An additional amount of days have been granted to allow for the delivery of the Metal Beam Guard Fence for the bridge section.

Attachments:

CHANGE IN CONTRACT PRICE:		CHANGE IN CONTRACT TIME:	
Original Contract Price		Original Contract Time for	
\$ 279,192.75		Substantial Completion:	60
			<small>calendar days or dates</small>
Net Changes from previous Change Order		Net Change from previous Change Orders	
\$ 6,030.00		14	
		<small>calendar days</small>	
Contract Price prior to this Change Order		Contract Time prior to this Change Order	
\$ 285,222.75		Substantial Completion:	74
			<small>calendar days or dates</small>
Net Increase(decrease) of this Change Order		Net Increase(decrease) of this Change Order	
\$ 25,650.00		21	
		<small>calendar days</small>	
Contract Price with all approved Change Orders	Net % increase(decrease)from original contract price.	Contract Time with all approved Change Orders	
\$ 310,872.75	8%	Substantial Completion:	95
			<small>calendar days or dates</small>

RECOMMENDED:
 By: [Signature]
 Engineer (Authorized Signature)
 Date: 05/24/16

APPROVED:
 By: [Signature]
 Owner (Authorized Signature)
 Date: 5/24/16

ACCEPTED:
 By: [Signature]
 Contractor (Authorized Signature)
 Date: May 19, 2016

Exhibit E-B

HIDALGO COUNTY DRAINAGE DISTRICT NUMBER ONE



LETTER OF TRANSMITTAL

RAUL E. SESINHE, CFM
General Manager
Floodplain Administrator

902 N. Doolittle Road
Edinburg, Texas 78542
Off 956 292.7080
Fax 956 292.7089

DATE: 5/25/16

TO: Hidalgo County Pct. 2

FROM: MORA D CAENZOS

ATTENTION: Verika Zamora

JOB TITLE: _____

REASON FOR TRANSMITTAL CHECKED BELOW:

- | | | |
|--|---|--|
| <input type="radio"/> AS REQUESTED | <input type="radio"/> FOR APPROVAL | <input type="radio"/> REVIEW AND COMMENT |
| <input type="radio"/> RETURNED FOR CORRECTIONS | <input type="radio"/> APPROVED AS NOTED | <input type="radio"/> OTHER |
| <input type="radio"/> APPROVED AS SUBMITTED | <input type="radio"/> COPY OF LETTER | <input type="radio"/> HAND DELIVERED |

REMARKS: Original Change Order No. 2 for the Eldora Rd. improvements

Received By: Mary Meave