

August 3, 2016

Comm. A.C. Cuellar, Jr.
Hidalgo County Precinct No. 1
1902 Joe Stephens, Ste. 101
Weslaco, Texas 78596

**Re: Hidalgo County Precinct No. 1 – Goolie Road Paving Improvements
LEMC No. 194**


Dear Commissioner Cuellar:

On Wednesday, August 03, 2016, bids were received and opened for Goolie Road Paving Improvements Project located in Hidalgo County, Texas. A total of ten (10) bids were received, in which, LeFevre Engineering & Management Consulting, LLC (LEMC) reviewed the submitted proposals and compiled the bid tabulation as attached.

After the review of the Bid Tabulations, LeFevre Engineering & Management Consulting, LLC confirmed that RDH Site & Concrete, LLC was the lowest bidder for the Base Bid in the amount of **\$1,097,337.27**. In review of the tabulated items and provided information, LEMC recommends, **RDH Site & Concrete, LLC** in the amount of **\$1,097,337.27**.

It has been LEMC's pleasure to work with Hidalgo County Precinct No. 1 on this project, and look forward to continue to do so. Should you have any questions or concerns, please do not hesitate to contact our office at (956) 687-5362.

Sincerely,



Emigdio "Milo" Salinas, PE
Vice President

FINAL BID TABULATION
FOR
Goolie Road Paving Improvements
Hidalgo County Precinct No. 1



612 Nolana, Suite 520
McAllen, Texas 78504
Tel. 956.687.5362
Fax. 956.687.5363

Civil Engineering
Environmental Engineering
Planning
Project Management

Texas Registered Engineering Firm F-11722

ITEM NO.	DESCRIPTION	EST. QNTY.	UNIT	UNIT PRICE		TOTAL PRICE		UNIT PRICE		TOTAL PRICE		UNIT PRICE		TOTAL PRICE		UNIT PRICE		TOTAL PRICE		UNIT PRICE		TOTAL PRICE		UNIT PRICE		TOTAL PRICE	
				BIDDER #1		BIDDER #2		BIDDER #3		BIDDER #4		BIDDER #5		BIDDER #6		BIDDER #7		BIDDER #8		BIDDER #9		BIDDER #10					
				RDH Site and Concrete, LLC		Earthworks Enterprise		Bearthkat Construction, LLC		Saenz Brothers Construction		Foremost Paving, Inc.		IOC Company, LLC		Texas Cordia Construction		Jimmy Closner & Sons		Holmont, LLC		RO Engineering, PLLC					

P194 Goolie Road Paving Improvements

General Project																							
1-1	Traffic control plan signed and sealed by a professional engineer licensed in Texas	LS	1	\$ 5,000.00	\$ 5,000.00	\$ 5,500.00	\$ 5,500.00	\$ 5,000.00	\$ 5,000.00	\$ 8,500.00	\$ 8,500.00	\$ 5,000.00	\$ 5,000.00	\$ 25,000.00	\$ 25,000.00	\$ 1,600.00	\$ 1,600.00	\$ 2,500.00	\$ 2,500.00	\$ 1,241.65	\$ 1,241.65	\$ 16,500.00	\$ 16,500.00
1-2	Installation and maintenance of barricades, signs and traffic handling per approved Traffic Control Plan.	LS	1	\$ 5,000.00	\$ 5,000.00	\$ 16,000.00	\$ 16,000.00	\$ 10,000.00	\$ 10,000.00	\$ 6,500.00	\$ 6,500.00	\$ 35,000.00	\$ 35,000.00	\$ 11,000.00	\$ 11,000.00	\$ 10,000.00	\$ 10,000.00	\$ 7,500.00	\$ 7,500.00	\$ 6,773.20	\$ 6,773.20	\$ 40,000.00	\$ 40,000.00
Total General Project				\$ 10,000.00	\$ 21,500.00	\$ 15,000.00	\$ 15,000.00	\$ 40,000.00	\$ 36,000.00	\$ 11,600.00	\$ 10,000.00	\$ 8,014.85	\$ 56,500.00										

BASE BID - Goolie Road Paving Improvements

2-1	Place 2-inch Hot Mix Asphalt Concrete Type "D" (2-inch compacted thickness) according to the plans and specifications; complete in place.	SY	33896	\$ 10.00	\$ 338,960.00	\$ 10.00	\$ 338,960.00	\$ 11.00	\$ 372,856.00	\$ 9.55	\$ 323,706.80	\$ 8.80	\$ 298,284.80	\$ 8.65	\$ 293,200.40	\$ 10.00	\$ 338,960.00	\$ 11.80	\$ 399,972.80	\$ 11.78	\$ 399,294.88	\$ 13.25	\$ 449,122.00
2-2	Prime Coat (MC-30) (0.2 GAL/SY), according to the plans and specifications; complete in place.	GAL	6780	\$ 5.00	\$ 33,900.00	\$ 4.00	\$ 27,120.00	\$ 5.00	\$ 33,900.00	\$ 6.50	\$ 44,070.00	\$ 4.00	\$ 27,120.00	\$ 4.50	\$ 30,510.00	\$ 4.00	\$ 27,120.00	\$ 4.50	\$ 30,510.00	\$ 4.35	\$ 29,493.00	\$ 3.75	\$ 25,425.00
2-3	8-inch Caliche Base (8-inch compacted thickness) according to the plans and specifications; complete in place.	SY	39837	\$ 7.00	\$ 278,859.00	\$ 6.65	\$ 264,916.05	\$ 8.00	\$ 318,696.00	\$ 6.00	\$ 239,022.00	\$ 7.80	\$ 310,728.60	\$ 7.70	\$ 306,744.90	\$ 7.00	\$ 278,859.00	\$ 9.00	\$ 358,533.00	\$ 17.87	\$ 711,887.19	\$ 8.50	\$ 338,614.50
2-4	10-inch Lime treated Sub-Grade (6%) according to the plans and specifications; complete in place.	SY	39837	\$ 4.75	\$ 189,225.75	\$ 6.90	\$ 274,875.30	\$ 5.00	\$ 199,185.00	\$ 7.70	\$ 306,744.90	\$ 6.50	\$ 258,940.50	\$ 6.95	\$ 276,867.15	\$ 9.50	\$ 378,451.50	\$ 8.30	\$ 330,647.10	\$ 4.90	\$ 195,201.30	\$ 8.90	\$ 354,549.30
2-5	Furnish and Install 4" Concrete Sidewalk, according to the plans and specifications; complete in place.	SY	7	\$ 200.00	\$ 1,400.00	\$ 50.00	\$ 350.00	\$ 36.00	\$ 252.00	\$ 55.00	\$ 385.00	\$ 210.00	\$ 1,470.00	\$ 262.26	\$ 1,835.82	\$ 169.00	\$ 1,183.00	\$ 80.00	\$ 560.00	\$ 55.87	\$ 391.09	\$ 75.00	\$ 525.00
2-6	Furnish and Install 5-ft Concrete Flume	EA	1	\$ 600.00	\$ 600.00	\$ 350.00	\$ 350.00	\$ 1,500.00	\$ 1,500.00	\$ 1,200.00	\$ 1,200.00	\$ 3,000.00	\$ 3,000.00	\$ 1,519.52	\$ 1,519.52	\$ 1,267.00	\$ 1,267.00	\$ 1,200.00	\$ 1,200.00	\$ 682.91	\$ 682.91	\$ 350.00	\$ 350.00
2-7	6-inch Residential Concrete Driveway (3500 PSI), according to the plans and specifications; complete in place	SY	115	\$ 60.00	\$ 6,900.00	\$ 45.00	\$ 5,175.00	\$ 40.00	\$ 4,600.00	\$ 72.00	\$ 8,280.00	\$ 75.00	\$ 8,625.00	\$ 95.33	\$ 10,962.95	\$ 35.00	\$ 4,025.00	\$ 70.00	\$ 8,050.00	\$ 55.87	\$ 6,425.05	\$ 45.00	\$ 5,175.00
2-8	Remove and replace existing caliche driveways and asphalt driveways with asphalt driveway, according to the plans and specifications; complete in place	SY	1824	\$ 15.00	\$ 27,360.00	\$ 20.00	\$ 36,480.00	\$ 25.00	\$ 45,600.00	\$ 25.00	\$ 45,600.00	\$ 39.00	\$ 71,136.00	\$ 38.70	\$ 70,588.80	\$ 18.00	\$ 32,832.00	\$ 20.00	\$ 36,480.00	\$ 16.57	\$ 30,223.68	\$ 30.00	\$ 54,720.00
2-9	Remove and Replace existing dirt/caliche driveways with 6-inch caliche driveway, according to the plans and specifications; complete in place.	SY	212	\$ 5.00	\$ 1,060.00	\$ 15.00	\$ 3,180.00	\$ 25.00	\$ 5,300.00	\$ 17.00	\$ 3,604.00	\$ 25.00	\$ 5,300.00	\$ 26.37	\$ 5,590.44	\$ 10.00	\$ 2,120.00	\$ 8.35	\$ 1,770.20	\$ 1.13	\$ 239.56	\$ 23.00	\$ 4,876.00
2-10	Furnish and Install 15-inch HPP according to the plans and specifications; complete in place	LF	2143	\$ 21.00	\$ 45,003.00	\$ 18.00	\$ 38,574.00	\$ 20.00	\$ 42,860.00	\$ 20.00	\$ 42,860.00	\$ 25.00	\$ 53,575.00	\$ 29.02	\$ 62,189.86	\$ 19.00	\$ 40,717.00	\$ 35.00	\$ 75,005.00	\$ 16.55	\$ 35,466.65	\$ 36.00	\$ 77,148.00
2-11	Furnish and Install 18-inch RCP according to the plans and specifications; complete in place	LF	1069	\$ 45.00	\$ 48,105.00	\$ 23.00	\$ 24,587.00	\$ 22.00	\$ 23,518.00	\$ 45.00	\$ 48,105.00	\$ 44.00	\$ 47,036.00	\$ 62.32	\$ 66,620.08	\$ 46.00	\$ 49,174.00	\$ 40.00	\$ 42,760.00	\$ 44.80	\$ 47,891.20	\$ 44.00	\$ 47,036.00
2-12	Furnish and Install 24-inch RCP according to the plans and specifications; complete in place	LF	96	\$ 55.00	\$ 5,280.00	\$ 35.00	\$ 3,360.00	\$ 40.00	\$ 3,840.00	\$ 60.00	\$ 5,760.00	\$ 60.00	\$ 5,760.00	\$ 97.28	\$ 9,338.88	\$ 61.00	\$ 5,856.00	\$ 50.00	\$ 4,800.00	\$ 57.10	\$ 5,481.60	\$ 62.90	\$ 6,038.40
2-13	Furnish and Install 36-inch RCP according to the plans and specifications; complete in place	LF	78	\$ 99.00	\$ 7,722.00	\$ 40.00	\$ 3,120.00	\$ 48.00	\$ 3,744.00	\$ 70.00	\$ 5,460.00	\$ 95.00	\$ 7,410.00	\$ 143.79	\$ 11,215.62	\$ 118.00	\$ 9,204.00	\$ 70.00	\$ 5,460.00	\$ 114.21	\$ 8,908.38	\$ 85.00	\$ 6,630.00
2-14	Furnish and Install 5'x5' Type "M" Manhole according to the plans and specifications; complete in place	EA	1	\$ 3,500.00	\$ 3,500.00	\$ 3,500.00	\$ 3,500.00	\$ 4,500.00	\$ 4,500.00	\$ 3,500.00	\$ 3,500.00	\$ 4,500.00	\$ 4,500.00	\$ 4,560.42	\$ 4,560.42	\$ 3,600.00	\$ 3,600.00	\$ 4,500.00	\$ 4,500.00	\$ 1,129.90	\$ 1,129.90	\$ 4,000.00	\$ 4,000.00
2-15	Furnish and Install Gate Inlet Type "C" w/ concrete apron according to the plans and specifications; complete in place	EA	2	\$ 4,000.00	\$ 8,000.00	\$ 3,500.00	\$ 7,000.00	\$ 4,000.00	\$ 8,000.00	\$ 4,100.00	\$ 8,200.00	\$ 3,500.00	\$ 7,000.00	\$ 3,340.62	\$ 6,681.24	\$ 2,400.00	\$ 4,800.00	\$ 3,200.00	\$ 6,400.00	\$ 869.16	\$ 1,738.32	\$ 3,800.00	\$ 7,600.00
2-16	Furnish and Install Safety End Treatment Structure according to the plans and specifications; complete in place	EA	18	\$ 600.00	\$ 10,800.00	\$ 1,500.00	\$ 27,000.00	\$ 750.00	\$ 13,500.00	\$ 750.00	\$ 13,500.00	\$ 1,000.00	\$ 18,000.00	\$ 1,126.73	\$ 20,281.14	\$ 1,000.00	\$ 18,000.00	\$ 750.00	\$ 13,500.00	\$ 314.05	\$ 5,652.90	\$ 1,250.00	\$ 22,500.00
2-17	Furnish and Install Storm Discharge Structure according to the plans and specifications; complete in place	EA	8	\$ 600.00	\$ 4,800.00	\$ 900.00	\$ 7,200.00	\$ 2,500.00	\$ 20,000.00	\$ 3,500.00	\$ 28,000.00	\$ 4,200.00	\$ 33,600.00	\$ 2,800.00	\$ 22,400.00	\$ 3,000.00	\$ 24,000.00	\$ 1,300.00	\$ 10,400.00	\$ 2,607.47	\$ 20,859.76	\$ 1,500.00	\$ 12,000.00
2-18	Furnish and Install 24" Storm Discharge Structure according to the plans and specifications; complete in place	EA	1	\$ 600.00	\$ 600.00	\$ 900.00	\$ 900.00	\$ 2,500.00	\$ 2,500.00	\$ 4,500.00	\$ 4,500.00	\$ 6,000.00	\$ 6,000.00	\$ 3,431.61	\$ 3,431.61	\$ 3,700.00	\$ 3,700.00	\$ 800.00	\$ 800.00	\$ 2,607.47	\$ 2,607.47	\$ 4,500.00	\$ 4,500.00

