

**CHANGE ORDER NUMBER ONE(1)**

Project: La Joya Watershed Improvements - South Detention Basin Project

DATE OF ISSUANCE: 3/21/2017 EFFECTIVE DATE 3/28/2017

OWNER: County of Hidalgo  
 OWNER'S CONTRACT NO. \_\_\_\_\_ C 16-161-08-09

CONTRACTOR: L&G Construction Company ENGINEER: L&G Engineers  
 2100 W. Exprwy 83 900 S. Stewart Road  
 Mercedes, Texas 78570 Mission, Texas 78572

You are directed to make the following changes in the Contract Documents.

Description:

1. Introduce the Item 550-9001 for installation of 2900 lf of 8' chain link fence with dust containment screen (fabric). Also introduce Item 550-9002 for the removal of chain link fence (fabric only) after construction
2. Introduce Item 204-6003 Sprinkling (Dust Control)
3. Eliminate Item 400-6010 Struct Excav (Spl) on Base Bid work and Phase B & Phase C work.
4. Eliminate Item 506-6003 Rock Filter Dams (TY 3) on Base Bid work
- 5.

Reason for Change Order:

1. The installation of Item 550-9001 Chain Link Fence with Dust Containment Screen is necessary to address complaints received from adjacent property owners. The prevailing Southeastern winds pick up dust from the project site and blows it toward the adjacent neighborhood. Also, compensate contractor to remove Item 550-9002 Chain Link Fence (Remove)(Fabric Only) after construction.
2. The introduction of Item 204-6003 Sprinkling (Dust Control) is necessary to compensate the Contractor for additional watering needed to control blowing dust during construction operations.
3. Item 400-6010 Struct Excav (Spl) is not needed due to dry bedding conditions encountered during RCP installation.
4. Quantities (186 lf) for Item 506-6003 Rock Filter Dams (Ty 3) is being reduced on Base Bid work due to not needing SWPPP control measures at this time due to delay of TxDOT proposed work in this area.
- 5.

Attachments: Item and quantity change order table including new item unit cost TxDOT average bid prices.

CHANGE IN CONTRACT PRICE:		CHANGE IN CONTRACT TIME:	
Original Contract Price	\$ 4,645,975.00	Original Contract Time for	
		Substantial Completion:	380 calendar days or dates
Net Changes from previous Change Order	\$ 0.00	Net Change from previous Change Orders	0 calendar days
Contract Price prior to this Change Order	\$ 4,645,975.00	Contract Time prior to this Change Order	
		Substantial Completion:	380 calendar days or dates
Net Increase of this Change Order	\$ 16,266.00	Net Increase(decrease) of this Change Order	0 calendar days
Contract Price with all approved Change Order	\$ 4,662,241.00	Contract Time with all approved Change Orders	
	Net % increase(decrease) original contract price. 0.35%	Substantial Completion:	380 calendar days or dates

**RECOMMENDED:**  
 By: [Signature]  
 Engineer (Authorized Signature)  
 Date: 03/23/2017

**APPROVED:**  
 By: \_\_\_\_\_  
 Owner (Authorized Signature)  
 Date: \_\_\_\_\_

**ACCEPTED:**  
 By: [Signature]  
 Contractor (Auth. Signature)  
 Date: 3/22/17



# CONSTRUCTION CONTRACT CHANGE ORDER NUMBER: 1

Estimated Cost

CONTRACT No: C 16-161-08-09

Paid by Invoice? (  Yes  No )

TABLE A: Force Account Work and Materials Placed in Stock

LABOR	HOURLY RATE	DESCRIPTION	HOURLY RATE

TABLE B: Contract Items

ITEM	DESCRIPTION	UNIT	UNIT PRICE	ORIGINAL + PROPOSED		NEW		OVERRUN / UNDERRUN
				QUANTITY	ITEM COST	QUANTITY	ITEM COST	
204-9001	SPRINKLING (DUST CONTROL)(SPL)	MG	\$ 10.00	0.00	\$ -	3000.00	\$ 30,000.00	\$ 30,000.00
400-6010	STRUCT EXCAV (SPL)(PHASE A)	CY	\$ 62.00	389.00	\$ 24,118.00	0.00	\$ -	\$ (24,118.00)
400-6010	STRUCT EXCAV (SPL)(PHASE B)	CY	\$ 177.00	9.00	\$ 1,593.00	0.00	\$ -	\$ (1,593.00)
400-6010	STRUCT EXCAV (SPL)(PHASE C)	CY	\$ 177.00	9.00	\$ 1,593.00	0.00	\$ -	\$ (1,593.00)
506-6003	ROCK FILTER DAMS (TY 3)	LF	\$ 150.00	488.00	\$ 73,200.00	302.00	\$ 45,300.00	\$ (27,900.00)
550-9001	CHN LNK FNCE (INSTALL)(8')W/FABRIC	LF	\$ 13.30	0.00	\$ -	2900.00	\$ 38,570.00	\$ 38,570.00
550-9002	CHN LNK FNCE (REMOV FABRIC ONLY)	LF	\$ 1.00	0.00	\$ -	2900.00	\$ 2,900.00	\$ 2,900.00
<b>TOTALS</b>					\$ 100,504.00		\$ 116,770.00	\$ 16,266.00

