

## Standard Machine Equipment

**4045TF285 John Deere Diesel Engine - 99 hp (73.9 kW) – Tier 3**

**Fuel Reservoir 44 gal. (166.6 liter)**

**Hydraulic Oil Reservoir 105 gal. (397.5 liter)**

**One Oil Cooler**

**30 in. (762 mm) Wide Sectional Trimmerhead**

- \* with internal hydraulic radial piston drive motor
- \* with 12 in. (305 mm) hydraulic vertical adjustment
- \* with 48 in. (1,219 mm) hydraulic sideshift adjustment

**One Curb and Gutter Mold**

- \* up to 24 in. (610 mm) wide

**Two Hydraulic Vibrators**

**Four Hydraulic Vibrator Circuits with Individual Variable Controls**

**Hydraulic Pump System**

- \* two double-stage main hydraulic pumps
- \* one pressure-compensated lift circuit pump

**G+ Control System**

- \* self-diagnostic system with 6.5 in. (165 mm) anti-glare graphical display
- \* operates in multiple languages
- \* with CAN network controller for front and rear grade, steering and reverse steering with “Smart Cylinder” technology, cross slope and reverse steering

**Automatic On/Off Control for Vibrators Synchronized with Machine Movement**

**Three Crawler Tracks - Series One - With Two-Speed Hydraulic Motors**

- \* hydraulically driven and automatic tensioning
- \* 5 ft. 1.4 in. (1.56 m) long
- \* 3 ft. 4.5 in. (1.03 m) center-to-center of sprockets
- \* 11.8 in. (300 mm) wide pads with street grousers
- \* 100:1 gear reduction

**Piston-Style Leg Assemblies with 36 in. (914 mm) Stroke Lift Cylinders**

**Power-Swing Pivoting Left Front Track Mount**

**Hydraulically Extendible Right-Side Track and Rear Track Mounts**

**Water System**

- \* includes 100 gal. (378.5 liter) tank, hydraulically driven water pump, hose and nozzle

**Concrete Charging Conveyor and Mount**

- \* hydraulically driven
- \* 14 ft. 10.5 in. (4.53 m) between pulley centers
- \* 24 in. (610 mm) wide belt
- \* variable speed and reversible
- \* lateral swing mount with hydraulic adjustment for charging height

**Hook-and-Go Drawbar & Hold-Down Assembly**

- \* 18 in. (457 mm) pressure-compensated hydraulic vertical adjustment and 6 in. (152 mm) manual vertical adjustment
- \* 48 in. (1,219 mm) maximum hydraulic sideshift

**Modular Electronic Control Panel**

**Fiberglass Engine Shroud and Operator’s Console**

- \* improved operator visibility
- \* better access to engine, pumps, and valves
- \* roll top cover for operator’s console

**Operator’s Station**

- \* engineered for easy monitoring of all hydraulic controls and electronic sensing functions

**Emergency Stop Switches**

**LIST PRICE**

**\$ 252,325**

**F.O.B.: Ida Grove, Iowa**

**Delivery:**

**This price is good for 60 days.**

**All prices are list prices.**

**GOMACO reserves the right to correct all clerical and verbal quote errors.**

**LIST PRICE DEDUCTION FOR STANDARD MACHINE EQUIPMENT**

**24 in. (610 mm) Curb & Gutter Mold..... \$ 2,635**

**Optional Machine Equipment**

**4045HF285 John Deere Diesel Engine - 125 hp (93.3 kW) – Tier 3**

\* in lieu of standard engine..... **\$ 12,500**

**3.4 Caterpillar Diesel Engine - 120 hp (89.5 kW) – Tier 4**

\* in lieu of standard engine..... **\$ 29,000**

**Vulcanized Belt for 16 ft. (4.88 m) Conveyor**

\* in lieu of standard belt ..... **\$ 1,275**

**High-Pressure Water System**

- \* includes trigger gun control and adjustable pressure unloader for 0 to 2,000 psi

\* in lieu of standard water system ..... **\$ 2,225**

**Xtreme Package**

- \* includes rotary-sensored slew drives on each of the three tracks
- \* with smart cylinder sideshifting of the mold which provides G+ the ability for repeatable mold offset
- \* with smart hydraulic cylinders on all three legs which allows G+ to know the position of all three tracks

* with additional software for G+ to calibrate track angles and track speeds for the radius being slipformed.....	\$ 22,000
(Note: New machine factory installed. The machine needs to be equipped with Tier 4 engine.)	
<b>Machine Sidemount Attachment</b>	
* for barrier/parapet work	
* includes right-hand sensor bracket .....	\$ 9,020
<b>Additional Hydraulic Vibrator and Mount</b> .....	\$ 1,475
<b>Left-Hand Discharge Trimmerhead - Add Per Section</b> .....	\$ 455
<b>Trimmerhead Extensions - Straight Grade</b>	
<b>12 in. (305 mm) Wide Extension</b>	
* complete.....	\$ 3,130
* shroud and blade only .....	\$ 1,545
* wheel only.....	\$ 1,585
<b>18 in. (457 mm) Wide Extension</b>	
* complete.....	\$ 3,800
* shroud and blade only .....	\$ 1,670
* wheel only.....	\$ 2,130
<b>24 in. (610 mm) Wide Extension</b>	
* complete.....	\$ 4,510
* shroud and blade only .....	\$ 1,890
* wheel only.....	\$ 2,620
<b>30 in. (762 mm) Sectional Trimmerhead With Internal Hydraulic Drive</b> .....	\$ 24,400
<b>24 in. (610 mm) Sectional Trimmerhead In Lieu Of Standard 30 in. (762 mm) Trimmerhead</b> .....	N/C
<b>Polyurethane Track Pads</b>	
* clip onto metal grousers	
* 81 pads required - 610-48E86.....	Each \$ 100
<b>Polyurethane Track Pads</b>	
* bolt to chain	
* 81 pads required - 625-48G42 .....	Each \$ 125
<b>Two Additional Vibrator Circuits And Controls</b> .....	\$ 2,315
(Note: Does not include vibrators.)	
<b>Conveyor Covers</b> .....	\$ 3,280
<b>Mold Centermount Kit</b>	
* includes drawbar to mount in place of trimmerhead and extension for the rear leg	
* for molds 7 ft. (2.13 m) and 8 ft. (2.44 m) wide .....	\$ 8,720
<b>Mold Centermount Kit</b>	
* includes drawbar to mount in place of trimmerhead, extension for the rear leg, pivoting leg extension, and inner telescoping tube for right leg	
* for molds up to 10 ft. (3.05 m) wide .....	\$ 18,270

1,475+1,475=  
Total=\$2.950



<b>Two Additional Vibrator Circuits and Controls with Auger Circuit</b>	
* remote mounted to trimmerhead circuit	
* for molds 7 ft. (2.13 m) and 8 ft. (2.44 m) wide .....	\$ 6,330
<b>Right-Hand Sensor Bracket</b>	
* for sensing off an existing curb when pouring sidewalk adjacent to the back of curb	
* includes sensor mounts, sensor arms, and 2 ea. skate and ski assemblies for grade sensors.....	\$ 2,080
<b>Concrete Auger and Mount</b>	
* hydraulically driven	
* 16 ft. (4.88 m) long	
* 16 in. (406 mm) diameter full pitch auger	
* variable speed and reversible	
* lateral swing mount with hydraulic adjustment for charging height	
* in lieu of standard concrete charging conveyor and mount .....	\$ 12,175
<b>Additional Optional Machine Equipment - see Curb &amp; Gutter Accessories</b>	
<b>Spare Parts Kit - consult factory</b>	
<b>Sensor Line Kit - see Support Accessories</b>	

3,295+3,295  
Total=\$6,590

**Slipform molds for COMMANDER III, GT-6300, 4400, GT-3600, GT-3400, GT-3300, COMMANDER II (GT-6200), GT-6000 and GT-3200**

<b>Curb &amp; Gutter or Monolithic Molds</b>	
* to 36 in. (914 mm) wide.....	\$ 3,295
* 37 in. (940 mm) to 48 in. (1,219 mm) wide.....	\$ 5,300
* 49 in. (1,245 mm) to 60 in. (1,524 mm) wide.....	\$ 7,075
* 61 in. (1,549 mm) to 72 in. (1,829 mm) wide.....	\$ 8,520

<b>Sidewalk Molds</b>	
* 37 in. (940 mm) to 48 in. (1,219 mm) wide.....	\$ 4,715
* 49 in. (1,245 mm) to 60 in. (1,524 mm) wide.....	\$ 5,420
* 61 in. (1,549 mm) to 72 in. (1,829 mm) wide.....	\$ 6,765
* 73 in. (1,854 mm) to 84 in. (2,134 mm) wide.....	\$ 8,100
* 85 in. (2,159 mm) to 96 in. (2,438 mm) wide.....	\$ 9,455
* 97 in. (2,464 mm) to 108 in. (2,743 mm) wide.....	\$ 10,800
* 109 in. (2,769 mm) to 120 in. (3,048 mm) wide.....	\$ 12,145

<b>Sectional Sidewalk Molds</b>	
* 48 in. (1,219 mm) wide.....	\$ 6,295

6,295+2,320+2,320  
Total=\$10,935

<b>Inserts for Sectional Sidewalk Molds</b>	
* 12 in. (305 mm) wide insert.....	\$ 2,320

* 18 in. (457 mm) wide insert .....	\$ 2,665
* 24 in. (610 mm) wide insert .....	\$ 3,125
* 36 in. (914 mm) wide insert .....	\$ 3,790
<b>Auger Assembly for Monolithic, Sidewalk or Sectional Sidewalk Molds Wider Than 72 in. (1,829 mm) .....</b>	<b>\$ 2,230</b>

## Mold Options

<b>Height Extensions - Bolt-On.....</b>	<b>\$ 560</b>
<b>Blockout to Change Curb and Gutter Mold Width</b>	
* includes extra stainless section.....	\$ 1,435
<b>Blockout to Change Sidewalk Width</b>	
* includes bolt-on edger assembly .....	\$ 765
<b>Removable Sideplate</b>	
* for paving next to existing slab	
* includes extra stainless section.....	\$ 1,435
(Note: Machine must be equipped with hold-over assembly when ordering this option.)	
(Note: GT-3600 doesn't require the hold-over assembly when mold is ordered with removable sideplate.)	
<b>Curb Depressor for Driveway</b>	
* hydraulically powered	
* for use on curb and gutter molds.....	\$ 1,965
<b>Driveway Depressor for Monolithic Mold</b>	
* hydraulically powered	
* factory installed on new mold only.....	\$ 5,475
<b>Manual Adjustable Sideplate</b>	
* per side .....	\$ 1,715
<b>Auxiliary Stainless for GT-3600 Mold .....</b>	<b>\$ 750</b>
<b>Hydraulic Pressure-Compensated Sideplates</b>	
* requires manual adjustable sideplates	
* per side .....	\$ 3,560
<b>Hydraulic Pressure-Compensated Sideplates (No Pressure Comp. Control Box)</b>	
* requires manual adjustable sideplates	
* includes 2 ea. hydraulic cylinders, 4 ea. cylinder lugs and 4 ea. hoses with fittings	
* per side .....	\$ 1,315
<b>Barrier and Parapet Molds for GT-3300, GT-3600, COMMANDER II (GT-6200), COMMANDER III, GT-6300, and 4400</b>	
<b>Barrier or Parapet Mold</b>	
* includes barrier/parapet sidemount attachment	
* to 42 in. (1,067 mm) high with manual sideplates.....	\$ 11,565

1,965+1,965  
Total=\$3,3930

\$ 1,965

(Note: GT-6200 barrier or parapet maximum height 40 in. (1,016 mm).)	
(Note: GT-3300 barrier or parapet maximum height 40 in. (1,016 mm).)	
(Note: GT-3600 barrier or parapet maximum height 50 in. (1,270 mm).)	
<b>Barrier or Parapet Mold</b>	
* includes barrier/parapet sidemount attachment	
* from 43 in. (1,092 mm) to 68 in. (1,727 mm) height with manual sideplates..	<b>\$ 15,405</b>
<b>Hydraulic Pressure-Compensated Sideplates - Each Side</b> .....	<b>\$ 3,560</b>
<b>Hydraulic Pressure-Compensated Sideplates (No Pressure-Comp. Control Box)</b>	
* includes 2 ea. hydraulic cylinders, 4 ea. cylinder lugs and 4 ea. hoses with fittings	
* per side.....	<b>\$ 1,315</b>
<b>Front Shroud to Pour Over Caged Steel</b> .....	<b>\$ 1,310</b>
<b>Glare Screen Mold</b>	
* includes barrier/parapet sidemount attachment .....	<b>\$ 5,295</b>
<b>Sectional Barrier/Parapet Mold - consult factory</b>	
<b>GOMACO Umbrella</b>	
* 54 in. (1,372 mm) square with GOMACO logo .....	<b>\$ 350</b>
<b>GOMACO Remote Diagnostics</b>	
* GRD is GOMACO's version of telematics and carries a two year data plan	
* can download software from GOMACO directly to the machine	
* can see GSI readings from remote location	
* can troubleshoot machine through GRD .....	<b>\$ 3,750</b>
<b>Hardware and Software for 3-D Ready</b>	
* power conditioner, two prism masts (no prisms), electrical assembly, mount post assembly for computer and software for G+ controller .....	<b>\$ 8,125</b>
<b>Light System for Night Operation</b>	
* includes electrical wiring, four LED 9-32V 1950 LM non-glare lights, and mounts .....	<b>\$ 4,200</b>
(Note: Capable of mounting to COMMANDER III, GT-6300, 4400, GT-3600, 3300, GT-3400, and GT-3200.)	
<b>Sensor Line Kit - One Mile Package - Kit No. GT11-114</b>	
* 6 - Rolls of 1000 ft. (304.8 m) Sensor Line - 715-35A41	
* 200 - Line Rods - GT10-005	
* 200 - Aluminum Cast Clamps with Set Screws - GT10-117	
* 200 - Line and Winch Support Stakes - GT10-021	
* Kit Price .....	<b>\$ 3,035</b>
<b>Sensor Line Kit - One Mile Package - Kit No. GT10-129</b>	
* 6 - Rolls of 1000 ft. (304.8 m) Sensor Line - 715-35A41	
* 212 - Line Rods - GT10-005	
* 212 - Aluminum Cast Clamps with Set Screws - GT10-117	
* 224 - Line and Winch Support Stakes - GT10-021	
* 6 - Tension Winches - GT10-049	
* Kit Price .....	<b>\$ 3,885</b>



## Vendor Contract Information

[Back](#)

### Searches:

[Search by Vendor](#)

[Browse Contracts](#)

Search:

- All
- Vendor Discounts Only
- Catalog Pricing Only

### Refine Your Search:

#### Vendors

Closner Equipment Company, Inc.  
[X]

#### Price Range

Show all prices

#### Category

None Selected

#### Contract

Construction, Road/Bridge,  
Ditching, Trenching, Utility and  
Other Equipment[X]

**Vendor Name:** Closner Equipment Company, Inc.

**Address:** 21910 FM 2252  
Schertz, TX 78154

**Phone Number:** (210) 732-2131

**Email:** connie@closner.com

**Website:** <http://www.closner.com>

**Federal ID:** 74-1732932

**Contact:** Connie Furillo

**Accepts RFQs:** Yes

**Minority Owned:** No

**Women Owned:** No

**Service-Disabled Veteran Owned:** No

**EDGAR:** Yes

**Contract Name:** Construction, Road/Bridge, Ditching, Trenching, Utility and Other Equipment

**Contract Description:** Air compressors; articulated trucks; asphalt compactors, cutters, distributors, emulsion tan and pavers; chip spreaders; cold planers; conveyors; curb & gutter machines; forklifts; generators & electrical system equipment; hydraulic hammers; all types of general construction road & street, tree care, & trenching equipment; trommel screen/compost; compactors/roll street sweepers & road brooms; waste handling loaders & landfill compactors; paint striping equipment; service/repair

**Contract#:** 515-16

**Effective Date:** 12/01/2016

**Expiration Date:** 11/30/2019

**Payment Terms:** Net 30 days

**Delivery Days:** 120

**Shipping Terms:** Pre-paid and added to invoice

**Freight Terms:** FOB Destination

**Ship Via:** Common Carrier

**Region Served:** All Texas Regions

**States Served:** All States

**Additional Info:** EDGAR Vendor Certification Form (relating to 2 CFR Part 200 & Appendix II) is included in Vendor response document, and can be found in the Vendor Proposal File link near the bottom of the page. Vendor Certification form regarding Texas HB 89 and Texas SB 252 can be found under the "Vendor Proposal Files Documents" link below.

**Quote Reference Number:** 515-16

**Return Policy:** Return authorization required

**Additional Dealers:** Closner Equipment Company locations in: Manor TX, Fort Worth TX

### Contract Documents

**EDGAR Notice:** [Click to view EDGAR Notice](#)

**Proposal Documents:** [Click to view BuyBoard Proposal Documents](#)

**Regulatory Notice:** [Click to view Bonding Regulatory Notice](#)

**Proposal Files:** [Click to view Vendor Proposal Files Documents](#)

**Renewal Notice/Letter:** [Click to view Vendor Renewal Notice/Letter Documents](#)

Contact us 800.695.2919





## Vendor Contract Information

[Back](#)

### Searches:

[Search by Vendor](#)
[Browse Contracts](#)

 Search:
 

- All  
 Vendor Discounts Only  
 Catalog Pricing Only

### Refine Your Search:

#### Vendors

 Closner Equipment Company, Inc.  
 [X]

#### Price Range

Show all prices

#### Category

None Selected

#### Contract

 Construction, Road/Bridge,  
 Ditching, Trenching, Utility and  
 Other Equipment[X]

### Additional Resources

**Vendor Name:** Closner Equipment Company, Inc.

**Address:** 21910 FM 2252  
 Schertz, TX 78154

**Phone Number:** (210) 732-2131

**Email:** connie@closner.com

**Website:** <http://www.closner.com>
**Federal ID:** 74-1732932

**Contact:** Connie Furillo

**Accepts RFQs:** Yes

**Minority Owned:** No

**Women Owned:** No

**Service-Disabled Veteran Owned:** No

**EDGAR:** Yes

**Contract Name:** Construction, Road/Bridge, Ditching, Trenching, Utility and Other Equipment

**Contract Description:** Air compressors; articulated trucks; asphalt compactors, cutters, distributors, emulsion tan and pavers; chip spreaders; cold planers; conveyors; curb & gutter machines; forklifts; generators & electrical system equipment; hydraulic hammers; all types of general construction road & street, tree care, & trenching equipment; trommel screen/compost; compactors/rollers; street sweepers & road brooms; waste handling loaders & landfill compactors; paint striping equipment; service/repair

**Contract#:** 515-16

**Effective Date:** 12/01/2016

**Expiration Date:** 11/30/2019

**Payment Terms:** Net 30 days

**Delivery Days:** 120

**Shipping Terms:** Pre-paid and added to invoice

**Freight Terms:** FOB Destination

**Ship Via:** Common Carrier

**Region Served:** All Texas Regions

**States Served:** All States

**Additional Info:** EDGAR Vendor Certification Form (relating to 2 CFR Part 200 & Appendix II) is included in Vendor response document, and can be found in the Vendor Proposal File link near the bottom of the page. Vendor Certification form regarding Texas HB 89 and Texas SB 252 can be found under the "Vendor Proposal Files Documents" link below.

**Quote Reference Number:** 515-16

**Return Policy:** Return authorization required

**Additional Dealers:** Closner Equipment Company locations in: Manor TX, Fort Worth TX

### Contract Documents

**EDGAR Notice:** [Click to view EDGAR Notice](#)
**Proposal Documents:** [Click to view BuyBoard Proposal Documents](#)
**Regulatory Notice:** [Click to view Bonding Regulatory Notice](#)
**Proposal Files:** [Click to view Vendor Proposal Files Documents](#)
**Renewal Notice/Letter:** [Click to view Vendor Renewal Notice/Letter Documents](#)