


THE STATE OF TEXAS §  
§  
COUNTY OF HIDALGO §

SERVICE CONTRACT  
C-18-082-04-24



THIS CONTRACT is made and entered into this 24<sup>th</sup> day of April 2018 by and between the **County of Hidalgo, Texas** ("County"), and TIBH Industries, Inc. ("Company") acting by and through **CRP, RGR Industries, Inc.**, ("Provider"); and

**WHEREAS**, the Texas Human Resources Code, Section 122.017, authorizes the State to Purchase services and products produced by persons with disabilities under the provisions of Chapter 122 Tex. Human Res. Code and establishes procedures for such purchases (hereinafter referred to as the State Use Program); and

**WHEREAS**, the Texas Workforce Commission has promulgated rules for the State Use Program at Title 40, Texas Administrative Code, Chapter 806; and

**WHEREAS**, Hidalgo County desires to "**Purchase Guardrail Materials and/or Turnkey Solutions**", as more particularly described in the attached Exhibit "A" (the "Services"); and

**WHEREAS**, TIBH and the Texas Workforce Commission acting through Provider shall provide services in accordance with the specifications attached as Exhibits "A" and "B" ("CRP Pricing") respectively, and incorporated herein for all purposes; and

**WHEREAS**, in recognition of and in consideration of Company and Provider's agreement to perform the Services in accordance with specifications, the Commissioners Court of County awarded the project to Company.

**NOW, THEREFORE**, in mutual consideration of the foregoing and the further consideration of the following, the parties hereto agree as follows:

1. County, Company and Provider hereby agree that this Contract is entered into in

order to provide the Services to **Hidalgo County**. This Contract does not extend to any third parties any duties or benefits conferred in any manner hereunder or otherwise.

2. Company and Provider hereby promise and agree to render and provide, during the term of this Contract, and shall be obligated to render and provide the Services in accordance with the RFB Packet within **Hidalgo County** following a request for Services by the **County** or its designated agent. Company and Provider agree in performing the Services that it will use proper professional standards, comply with any and all appropriate laws and regulations in providing the Services, and devote such time as is necessary to safely and efficiently provide the Services.

3. This Contract shall be for a period of One (1) year, **(on an as needed basis)**, commencing on May 01, 2018 (or upon Commissioner's Court Approval and fully executed document), and expiring on April 30, 2019, and may be extended at the sole discretion of the County for an additional two (2) one (1) year term under the same rates, terms and conditions. Hidalgo County also reserves the right to continue this sealed bid for an additional sixty (60) day grace period at the end of the contract term for unforeseen delay of award for the next term and contingent upon cost remaining unchanged.

4. As a condition of this Contract, Company and Provider shall hold and maintain throughout the term of this Contract all licenses and permits required, or which may be required by any authority during the term hereof to provide the Services. If such license or permit is suspended or revoked, this Agreement shall automatically be terminated and Company and Provider shall immediately notify the County.

5. All trucks or vehicles operated by the Company/Provider to perform the Services shall contain all equipment required by any authority to operate on streets and roads and all persons in the employ of Company/Provider who operate such trucks or vehicles shall have the required licenses, qualifications, skill and expertise to perform such Services and shall comply with all laws, rules and regulations prescribed by any agency or authority having jurisdiction with regard to the operation of such trucks or vehicles in providing the Services.

6. As consideration for rendering the Services provided for in this Contract, the County agrees to pay Company the amounts specified in Exhibit "B" attached hereto payable against written invoice submitted by Company in accordance with the Texas Prompt Payment Act, Tex. Govt. Code Ch. 2251.

7. Company/Provider shall provide insurance in force on all its vehicles and all persons connected with providing services under this Contract naming County as an additional insured (with the coverages and in the amounts described in Exhibit "C" attached hereto and incorporated herein at this point for all purposes), and shall furnish to County certificates of such insurance coverage.

8. Company/Provider shall provide a sufficient number of trucks, vehicles, personnel, and equipment available to safely and efficiently provide the Services.

9. **Company/Provider shall indemnify and hold harmless County, its elected officials, employees and agents from any and all claims, damages, losses, and expenses including attorney's fees for the defense of any action against County arising out of, resulting from, or connected with the provision of the Service by Company/Provider under this Contract. Said indemnity shall cover any act or failure to act by the Company/Provider, its agents or employees.**

10. This Contract shall not be assignable in whole or in part by either party without the prior written consent of the other party.

11. It is expressly agreed that this Contract and the performance by the parties hereunder does not create any agency relationship or master-servant relationship that County has no supervision of the performance of the Services provided by Company/Provider, and that Company/Provider is an independent contractor under this Contract.

12. Any notice required or permitted to be given hereunder shall be in writing and shall be delivered personally or sent by certified mail, postage prepaid, as set forth below:

If to County:           **The County of Hidalgo**  
                                  **Attn: County Judge**  
                                  **100 E. Cano**  
                                  **Edinburg, Texas 78539**

If to Company:         **TIBH INDUSTRIES, INC.**  
                                  **Attn: Rosa M. Valdez**  
                                  **1011 E 53 ½ Street**  
                                  **Austin, TX 78751**

13.     In case any one or more of the provisions contained in this Agreement shall for any reason be held to be invalid, illegal or unenforceable in any respect, such invalidity, illegality, or unenforceability shall not affect any other provision thereof and this Agreement shall be construed as if such invalid, illegal, or unenforceable provision had never been contained herein.

14.     This Agreement may be terminated by County without cause upon thirty (30) days written notice.

15.     This Agreement shall be binding upon and inure to the benefit of and be enforceable by the parties hereto and their respective heirs, executors, administrators, legal representatives, successors, and assigns where permitted by this Agreement.

16.     This Agreement shall be governed by and construed in accordance with the laws of the State of Texas and shall be performable in Hidalgo County.

17.     In the event that, during any term hereof, the Commissioners Court does not appropriate sufficient funds to meet the obligations of County under this Agreement, County may terminate this Agreement upon ninety (90) days written notice to Provider and Company. County agrees, however, to use reasonable efforts to secure funds necessary for the continued performance of this Agreement. The parties intend this provision to be a continuing right to terminate this Agreement at the expiration of each budget period of County.

18. This Agreement contains the entire contract between the parties hereto, and each party acknowledges that neither has made (either directly or through any agent or representative) any representation or agreement in connection with this Agreement not specifically set forth herein. This Agreement may be modified or amended only by an agreement in writing executed by the parties hereto, and not otherwise.

19. Nothing in this Agreement is intended to and County does not hereby waive, release or relinquish any right to assert any of the defenses County enjoys by virtue of the state or federal constitution, laws, rules or regulations, and any sovereign, official or qualified immunity available to County as to any claim or action of any person, entity, or individual against County.

20. Company/Provider, including subcontractors, assignees and successors in interest, ensures that no person shall on the grounds of race, religion, color, national origin, sex, age, disability, or any other protected class under law, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination or retaliation under any federally or non-federally funded program or activity when providing any services described herein under this contract/agreement.

21. The parties hereto covenant and agree that they will execute each such other and further instruments and documents as are or may become necessary or convenient to effectuate and carry out the terms of this contract/agreement.

EXECUTED and effective as of the day and year first written above.

COUNTY OF HIDALGO

Ramon Marcia  
Ramon Garcia, County Judge

APPROVED BY  
COMMISSIONERS' COURT  
ON: 4/24/18 mrs

ATTEST

Arturo Guajardo  
Arturo Guajardo, County Clerk



*Note: Need signature for the Provider as well.*

Company: TIBH Industries, Inc.

By: Rosa M. Valdez

Printed Name: Rosa M. Valdez /

Title: Regional Marketing Manager / CEO

Provider: RGR Industries, Inc.

By: [Signature]

Printed Name: Ricardo Guerra

Title: President

Approved By Commissioners Court On: \_\_\_\_\_

APPROVED AS TO FORM:  
Hidalgo County Office of District Attorney  
Ricardo Rodriguez, Jr.

By: [Signature]  
Victor M. Garza  
Assistant District Attorney

# EXHIBIT “A”

# SPECIFICATIONS

#

## ATTACHMENT A SCOPE OF WORK

---

### HARDWARE:

Perform "Metal Beam Guard Fence and Elements Repair".

### GENERAL

Prior to beginning operations, a conference between representatives of the County and the Community Rehabilitation Program (CRP) will be arranged. In this meeting, the CRP will outline the proposed method of accomplishing this work.

The CRP is to visit the site to make its own examination of the work areas. The CRP will carefully examine these specifications and secure from the Department any additional information that may be essential for a clear and full understanding of the work.

Scheduled work that falls on a National Holiday will be performed on the following work day. National Holidays as defined in the "Texas Standard Specification 2014" are January 1, the last Monday in May, July 4, the first Monday in September, the fourth Thursday in November, December 24 and December 25.

The CRP is responsible for damage to County equipment, plants, shrubs, and County employee vehicles caused by its maintenance activities.

All lost and found items will be turned over to the County Representative.

The CRP is responsible for its employees reporting daily any needed repairs. This information will be reported to the County's representative.

All personal protective equipment (PPE) will be provided by the CRP.

Clear and remove from all work sites, surplus and waste materials and leave the site in a neat and aesthetically pleasing condition.

Work is on an as-needed basis and as directed by the County.

Perform work Monday through Friday during daylight hours unless otherwise approved. Close no more than one (1) lane at a time

If closing a lane is necessary, closure time will be Monday through Thursday, 9:00 A.M. to 3:00 P.M. and Friday, 9:00 A.M. to 12:00 P.M. (noon).

The CRP keeps all unusable salvaged material. Material that is deemed usable by the County shall be returned to Hidalgo County.

### EQUIPMENT AND LABOR

The CRP will not be allowed to begin work until all equipment has been inspected, and found to be in good working condition, and deemed safe by the County.

### BARRICADES, SIGNS, AND TRAFFIC HANDLING

The CRP will furnish and install all signs, barricades and other incidentals necessary for proper traffic control, in accordance with the 2011 "Texas Manual on Uniform Traffic Control Devices and as directed. All warning signs will be factory made and in satisfactory condition.

#

**ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING**

The CRP shall provide to the Engineer a letter certifying that all truck-mounted attenuators (TMA) used on the contract that were purchased on or after October 1, 1998, have been found to be crashworthy using the criteria outlined in the National Cooperative Highway Research Program (NCHRP) Report 350. If the TMA was purchased prior to October 1, 1998, a letter certifying crashworthiness using the criteria outlined in either (NCHRP) reports 230 or 350 shall be provided to the Engineer.

Provide flagmen properly attired in a white hard hat, approved safety vest and stop/slow paddle. Provide two-way radios in areas where flagmen do not have visual contact with one another or cannot communicate with one another.

Provide shadow vehicles equipped with Truck Mounted Attenuators (TMA) when performing work on the expressway as shown on Traffic Control Plan (TCP) standards (2 series).

Limit lane closures to a maximum of three (3) miles. If more than one (1) lane closure location is desired, provide a minimum of a 2 mile passing zone between locations. Provide a separate sign set up for each location.

Ensure equipment and materials are a minimum of 30 feet from the edge of the travel lane during non-working hours.

Erect signs in locations not obstructing the traveling public's view of the normal roadway signing or necessary sight distance at intersections and curves.

All signs will conform to the Roadside Traffic Control Plan (RS-TCP-05) (see attached).

**ITEM 544 "Guardrail End Treatments"**

Label "end treatment type" on backside of unit at time of installation.

**ITEM 545 CRASH CUSHION ATTENUATORS**

Damaged crash cushion attenuators beyond repair will be replaced with the same attenuator model or similar. Exemptions to the similar model replacements will be determined by the Engineer to satisfy crash test levels (TL-2 for roadways 45 mph or less and TL-3 for roadways greater than 50 mph).

Crash cushions needing to be moved and reset will be paid under Item 545-6003 regardless of attenuator model. Foundations, materials, incidentals, etc. is subsidiary to this item. Crash cushions needing to be removed will be paid under Item 545-6005 regardless of attenuator model. Removing, materials, hauling, incidentals, etc. is subsidiary to this item.

The CRP will have 24 hours to respond via e-mail, phone, fax, etc. confirming the request by the County to repair damaged facility. The CRP will have 24 hours to contact and advise Hidalgo County of timeline or schedule for work to be completed/performed This includes delivery of materials.

The CRP is to return any used materials to the County. Any material deemed salvageable by the State will also be returned.

The CRP is to avoid damaging utilities during guard fence operations by contacting utility companies and locating all underground lines in the vicinity of the work.

The CRP will furnish crew(s) and equipment capable of maintaining work in a continuous manner for the completion of the work on schedule, as approved.

The CRP will use care to avoid disturbing pavement surfaces. Any damaged caused by the normal operation outside the work area will be paid by the CRP.

#

Furnish and place topsoil to repair areas disturbed by construction operations, as approved. The topsoil and placement will not be paid for directly, but will be considered subsidiary to the various bid items. (?)

**ITEM 7650 CLEAN TRAFIC ATTENUATORS**

Remove debris at locations shown on the plans, or as directed by the Engineer. Dispose of debris off the right of way. (?)

**MEASUREMENT**

The unit of measurement for "Purchase Guardrail Materials and/or Turnkey Solutions" will be based upon the various Items of work as specified on Attachment B.

**PAYMENT**

Work performed as prescribed by this specification, measured as provided under "Measurement" will be paid for at the contract unit price, which will be full compensation for furnishing all labor, equipment, materials and incidentals necessary to complete the work. Payment will be made once each month after satisfactory completion of work.

**POINT OF CONTACT (?)**

	<b>Contact</b>	<b>Telephone No</b>
<b>H. C. Precinct 1</b>		
<b>H. C. Precinct 2</b>		
<b>H. C. Precinct 3</b>		
<b>H. C. Precinct 4</b>		



## Item 540 Metal Beam Guard Fence

### 1. DESCRIPTION

Furnish, install, replace, or adjust metal beam guard fence consisting of metal beam rail elements, hardware, blocks, and support posts.

### 2. MATERIALS

Provide samples of metal beam rail elements, terminal sections, bolts, and nuts for compliance testing according to Tex- 708-I and Tex-713-I to verify physical and chemical properties meet AASHTO M 180 when directed.

Obtain materials at the locations shown on the plans when the plans designate that the Department will furnish materials.

- 2.1. **Metal Beam Rail Elements.** Furnish new metal beam rail elements, transitions, anchor sections, and terminals that meet the requirements of Table 1 and are from a manufacturer on the Department's MPL of rail element manufacturers.

Type I or II is required, unless otherwise shown on the plans. Base metal for metal beam rail elements must not contain more than 0.04% phosphorous or more than 0.05% sulfur.

Warped or deformed rail elements will be rejected.

**Table 1  
Rail Element Requirements**

<b>Specification</b>	AASHTO M 180
<b>Class</b>	A— Base metal nominal thickness 0.105 in. B— Base metal nominal thickness 0.135 in.
<b>Type</b>	I— Zinc-coated 1.80 oz. per square foot minimum single-spot. II— Zinc-coated 3.60 oz. per square foot minimum single-spot. IV— Weathering Steel (required when shown on the plans).
<b>Shape</b>	W-Beam Thrie Beam W-Beam to Thrie Beam Transition
<b>Markings</b>	Permanently mark each metal beam rail element with the information required in AASHTO M 180. In addition, permanently mark all curved sections of metal beam rail element with the radius of the curved section in the format "R=XX ft." Markings must be on the back of the metal beam rail section away from traffic and visible after erection.

- 2.2. **Posts.** Furnish new round timber, rectangular timber, or rolled steel section posts in accordance with details shown on the plans and the following requirements:

- 2.2.1. **Timber Posts.** Meet the requirements of DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.

- 2.2.2. **Steel Posts.** Provide rolled sections conforming to the material requirements of ASTM A36. Drill or punch posts for standard rail attachment as shown on the plans. Galvanize according to Item 445, "Galvanizing." Low-fill culvert posts may be fabricated as galvanized "blanks" with the rail hole and the final height field
- fabricated. Treat all exposed post surfaces caused by the field fabrication in accordance with Section 445.3.5., "Repairs."
- 2.3. **Blocks.** Furnish new rectangular timber or composite blocks in accordance with details shown on the plans and the following requirements:
- 2.3.1. **Timber.** Meet the requirements of DMS-7200 "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.
- 2.3.2. **Composite.** Meet the requirements of DMS-7210 "Composite Material Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer on the Department's MPL of composite material blocks and posts.
- 2.4. **Fittings.** Furnish new fittings (bolts, nuts, and washers) according to the details shown on the plans and galvanized according to Item 445, "Galvanizing."
- 2.5. **Terminal Connectors.** Furnish new terminal connectors, where required, meeting the material and galvanizing requirements specified for metal beam rail elements.
- 2.6. **Concrete.** Furnish concrete for terminal anchor posts meeting the requirements for Class A concrete as required in Item 421, "Hydraulic Cement Concrete."
- 2.7. **Curb.** If indicated in the details, furnish the curb shown with metal beam guard fence transition as required by Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- 2.8. **Terminal Anchor Posts.** Furnish new terminal anchor posts from steel conforming to the material requirements of ASTM A36. Fabricate posts according to Item 441, "Steel Structures." Galvanize terminal anchor posts after fabrication according to Item 445, "Galvanizing."
- 2.9. **Driveway Terminal Anchor Posts.** Furnish new terminal anchor posts from steel conforming to the material requirements of ASTM A36. Fabricate posts according to Item 441, "Steel Structures." Galvanize terminal anchor posts after fabrication according to Item 445, "Galvanizing."
- 2.10. **Downstream Anchor Posts.** Furnish new terminal anchor posts consisting of new rectangular timber and new steel foundation tubes according to details shown on the plans.
- 2.11. **Downstream Anchor Hardware.** Furnish new hardware (brackets, plates, struts, cable, etc.) according to the details shown on the plans and galvanized according to Item 445, "Galvanizing."
- 2.12. **Controlled Released Terminal (CRT) Posts.** Furnish new CRT posts according to the details shown on the plans and conforming to the requirements of DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.

---

### 3. CONSTRUCTION

Install posts and rail elements according to details shown on the plans.

- 3.1. **Posts.** Install posts by either drilling or driving.
- 3.1.1. **Drilling.** Drill holes and set posts plumb and firm to the line and grade shown. Backfill posts by thoroughly compacting material to the density of adjacent undisturbed material.

- 3.1.2. **Driving.** Drive posts plumb with approved power hammers (steam, compressed air, vibratory, or diesel) or gravity hammers to the line and grade shown while preventing damage to the post. Use pilot holes when required and approved. Determine the size and depth of pilot holes based on results of the first few posts
- driven. Thoroughly tamp loosened soil around the post, fill voids with suitable material, and thoroughly compact to the density of adjacent undisturbed material.
- 3.2. **Rail Elements.** Erect metal beam rail elements to produce a smooth, continuous rail paralleling the line and grade of the roadway surface or as shown on the plans. Bolt rail elements end-to-end and lap splices in the direction of traffic. Field-drill or punch holes in rail elements for special details, only when approved.
- 3.3. **Short Radius.** Special rail fabrication with a required radius must be as shown on the plans.
- 3.4. **Terminal Anchor Posts.** Embed terminal anchor posts in concrete, unless otherwise shown on the plans.
- 3.5. **Galvanizing Repair.** Repair all parts of galvanized steel posts, washers, bolts, and rail elements after erection where galvanizing has become scratched, chipped, or otherwise damaged. Repair in accordance with Section 445.3.5., "Repairs."
- 3.6. **Guardrail Adjustment.** Work includes vertical adjustment, horizontal shift, and overlap of the rail element to meet the detail shown on the plans.
- 3.7. **Curb.** If indicated in the details, construct the curb shown with metal beam guard fence transition as required by Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- 3.8. **Driveway Terminal Anchor Posts.** Embed terminal anchor posts in concrete, unless otherwise shown on the plans.

---

#### 4. MEASUREMENT

- 4.1. **Guard Fence.** Measurement will be by the foot of fence. Fence will be measured on the face of the rail in place, from center-to-center of end splice locations.
- 4.2. **Terminal Anchor Sections.** Measurement will be by each section, complete in place, consisting of a terminal anchor post and one 25-ft. section of rail element.
- 4.3. **Transitions.** Transitions for rail connection will be measured by each transition.
- 4.4. **Short Radius.** Measurement will be by the foot to the nearest whole foot along the face of the rail in place, from beginning of radius (first CRT post) to the end of radius.
- 4.5. **Driveway Terminal Anchor Section.** Measurement will be by each section, complete in place, consisting of a driveway terminal anchor post and one 6-ft. section of rail element.
- 4.6. **Downstream Anchor Terminal.** Measurement will be by each section, complete in place, consisting of one W-Beam end section, 2 downstream anchor posts, and one rail section.
- 4.7. **Long Span System.** Measurement will be by the foot of fence. Fence will be measured on the face of the rail, in place, between the first CRT and last CRT posts in the system.

5. **PAYMENT**

The work performed and material furnished in accordance with this Item and measured as provided under "Measurement" will be paid at the unit price bid for "Metal W-Beam Guard Fence" of the post type specified; "Metal Thrie Beam Guard Fence" of the post type specified; "Terminal Anchor Section"; "Metal Beam Guard Fence Transition" of the type specified; "Metal W-Beam Guard Fence Adjustment"; "Metal Thrie Beam Guard Fence Adjustment"; "Terminal Anchor Section Adjustment"; "Transition Adjustment"; "Short Radius"; "Driveway Terminal Anchor Section"; "Downstream Anchor Terminal"; or "Metal Beam Guard Fence (Long Span System)." When weathering steel is required, Type IV will be specified.

Samples furnished to the Department for testing purposes, special backfill materials, and concrete curbs will not be paid directly but are subsidiary to this Item.

- 5.1. **Guard Fence.** The price bid for "Metal W-Beam Guard Fence" or "Metal Thrie Beam Guard Fence" is full compensation for materials, hauling, erection, setting posts in concrete, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.
- 5.2. **Terminal Anchor Section.** When a separate bid item is specified, the price bid for "Terminal Anchor Section" is full compensation for furnishing the rail element, anchor assembly, terminal anchor post, and foundations; installing the rail element anchor assembly and the terminal anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.3. **Transition.** The price bid for "Metal Beam Guard Fence Transition" is full compensation for furnishing nested sections of Thrie Beam; nested sections of W-Beam; Thrie Beam to W-Beam transitional rail piece, posts, concrete, curb, and connections to W-Beam guard fence and bridge rails; Thrie Beam terminal connectors; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.4. **Guardrail Adjustment.** The price bid for "Metal W-Beam Guard Fence Adjustment," "Metal Thrie Beam Guard Fence Adjustment," "Terminal Anchor Section Adjustment," and "Transition Adjustment" is full compensation for furnishing materials not supplied by the Department, drilling holes in posts, hauling, erection, blocks, excavation, backfill, cleaning, salvaging materials, setting rail element anchor assembly and terminal anchor post, removal of rail element, concrete, curb, equipment, labor, tools, and incidentals.
- 5.5. **Short Radius.** The price bid for "Short Radius" is full compensation for furnishing special rail fabricated metal beam guard fence, CRT posts, steel posts, sand barrels, end terminal, cable anchor, materials, hauling, erection, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.
- 5.6. **Driveway Terminal Anchor Section.** The price bid for "Driveway Terminal Anchor Section" is full compensation for furnishing the rail element, driveway anchor assembly, driveway terminal anchor post, and foundations; installing the rail element anchor assembly and the driveway terminal anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.7. **Downstream Anchor Terminal.** The price bid for "Downstream Anchor Terminal" is full compensation for furnishing the rail element, W-Beam end section, guardrail anchor bracket, shelf angle bracket, channel strut, downstream anchor posts, breakaway cable terminal (BCT) cable anchor assembly, and foundations; installing the BCT cable anchor assembly and the downstream anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.8. **Long Span System.** The price bid for "Metal Beam Guard Fence (Long Span System)" is full compensation for furnishing the rail element, CRT posts, materials, hauling, erection, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.



---

## Item 542

### Removing Metal Beam Guard Fence

---

#### 1. DESCRIPTION

Remove existing metal beam guard fence and store at locations shown on the plans or as directed.

---

#### 2. CONSTRUCTION

Remove rail elements in original lengths. Remove fittings from the posts and the metal rail and then pull the posts. Do not mar or damage salvageable materials during removal.

Completely remove posts and any concrete surrounding the posts. Furnish backfill material and backfill the hole with material equal in composition and density to the surrounding soil unless otherwise directed.

Cut off or bend down deadman eyebolts to an elevation at least 1 ft. below the new subgrade elevation and leave in place along with the deadman.

Neatly stack salvaged materials to be retained by the Department at designated sites shown on the plans. Properly dispose of unsalvageable materials in accordance with federal, state, and local regulations. Repair or replace Contractor-damaged salvageable material at the Contractor's expense.

---

#### 3. MEASUREMENT

This Item will be measured by the foot for "Remove Metal Beam Guard Fence" in its original position. Measurement will be made along the face of the rail, in place, including metal beam guard fence transitions, from center-to-center of end posts and from terminal points shown on the plans.

When "Remove Terminal Anchor Section" is specified as a separate bid item, measurement will be made for each removed section. A terminal anchor section consists of one post, one 25-ft. rail element, and associated hardware.

When "Remove Downstream Anchor Terminal" is specified as a separate bid item, measurement will be made for each removed section. Downstream anchor terminal consists of 2 posts, 1 section, and associated hardware.

---

#### 4. PAYMENT

The work performed and measured as provided under "Measurement" will be paid at the unit price bid for "Remove Metal Beam Guard Fence," "Remove Terminal Anchor Section," and "Remove Downstream Anchor Terminal." This price will be full compensation for removing materials; loading, hauling, unloading, and storing or disposal; furnishing backfill material; backfilling postholes; and equipment, labor, tools, and incidentals.

Removal of curb associated with the metal beam guard fence transitions will not be paid directly but will be subsidiary to this Item.



---

## Item 543

### Cable Barrier System

---

#### 1. DESCRIPTION

Furnish and install a cable barrier system and cable barrier terminal sections at the locations shown on the plans.

---

#### 2. MATERIALS

Furnish a new cable barrier system and cable barrier terminal sections in accordance with the details shown on the plans and on the manufacturer's shop drawings, or equal as approved. Cable barrier systems approved for use have passed NCHRP Report 350 or MASH of the test level specified (TL-3, TL-4, etc.) with a maximum deflection of 8 ft.

Furnish pre-stretched cable.

Furnish Class A concrete in accordance with Item 421, "Hydraulic Cement Concrete."

Furnish delineators as shown on the plans and in accordance with Item 658, "Delineator and Object Marker Assemblies."

---

#### 3. CONSTRUCTION

Install cable barrier system in accordance with the details, dimensions, and requirements shown on the plans and manufacturer's recommendations. Install cable barrier terminal sections in accordance with the details shown on the plans and manufacturer's recommendations.

Place posts into steel sleeves in a concrete foundation unless otherwise shown on the plans. Locate terminal sections at locations as shown on the plans. Repair or replace damaged parts immediately. Provide an installation and repair manual specific to the cable barrier system and cable barrier terminal sections.

Locate barrier delineators at a maximum spacing of 100 ft. and according to TMUTCD or as shown on the plans. Install barrier delineators in accordance with manufacturer's recommendations.

3.1. **Training.** Provide training as specified by the Department.

---

#### 4. MEASUREMENT

This Item will be measured by the foot of cable barrier system and by each cable barrier terminal section installed.

**5. PAYMENT**

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.), "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.) and post spacing specified, and "Cable Barrier Terminal Section" of the test level specified (TL-3, TL-4, etc.). This price is full compensation for furnishing cable barrier system, cable barrier terminal section, concrete, delineators, equipment, labor, tools, and incidentals. Delineators will not be measured or paid for directly but will be considered subsidiary to this Item



## Item 544

### Guardrail End Treatments

---

1. **DESCRIPTION**

Furnish and install, move, or remove guardrail end treatments.

---

2. **MATERIALS**

Furnish new materials from the Department's MPL of rail element manufacturers. Obtain materials at the location shown on the plans when furnished by the Department.

---

3. **CONSTRUCTION**

Install guardrail end treatments in accordance with manufacturer's assembly and installation requirements and the details shown on the plans. Provide the Engineer with manufacturer's installation and repair manuals specific to the guardrail end treatment.

Move or remove guardrail end treatments in accordance with the plans and as directed. Deliver salvageable materials in accordance with the plans or as directed. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.

---

4. **MEASUREMENT**

This Item will be measured by each guardrail end treatment.

---

5. **PAYMENT**

The work performed and the materials furnished in accordance with this Item and measured as provided for under "Measurement" will be paid for at the unit price bid for "Guardrail End Treatment (Install)" of the post and type specified where applicable, "Guardrail End Treatment (Move and Reset)," or "Guardrail End Treatment (Remove)." This price is full compensation for foundations, materials, stockpiling, disposal of unsalvageable materials, equipment, labor, tools, and incidentals.

Payment for "Guardrail End Treatment (Move and Reset)" will include each guardrail end treatment removed from a stockpile or from an existing location and reset in a new location as detailed on the plans or as directed.

Payment for "Guardrail End Treatment (Remove)" will include each guardrail end treatment removed from an existing location and stockpiled at the location designated on the plans, disposed, or as otherwise directed.



## Item 545

### Crash Cushion Attenuators

---

#### 1. DESCRIPTION

Furnish and install, move and reset, or remove crash cushion attenuators.

---

#### 2. MATERIALS

2.1. **Crash Cushion Attenuators.** Furnish new crash cushion attenuators in accordance with the details shown on the plans and on the manufacturer's shop drawings. Obtain crash cushion attenuators at the location shown on the plans when furnished by the Department.

2.2. **Concrete.** Furnish Class S concrete for pads that meets Item 421, "Hydraulic Cement Concrete."

---

#### 3. CONSTRUCTION

Perform the following as shown on the plans:

3.1. **Installation.** Assemble and install crash cushion attenuators in accordance with the details shown on the plans and manufacturer recommendations. Obtain assembly and installation information for the crash cushion attenuators from the manufacturer and provide the Engineer with an installation and repair manual specific to the crash cushion attenuators.

3.2. **Moving and Resetting.** Remove crash cushion attenuators from a stockpile or from an existing location and reset in a new location as shown on the plans or as directed. Install crash cushion attenuators in accordance with pertinent standards and manufacturer recommendations. Provide additional materials to complete the installation as needed. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.

3.3. **Removal.** Remove crash cushion attenuators from an existing location and stockpile in the area designated on the plans, as directed, or dispose. Clean and repair salvageable units before inspection and return them to the Department. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.

---

#### 4. MEASUREMENT

This Item will be measured by each crash cushion attenuator.

---

#### 5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided for under "Measurement" will be paid for at the unit price bid for "Crash Cushion Attenuator (Furnish and Install, Designated Source, Move and Reset, Stockpile, or Remove)" of the category, width (N or W), and test level. This price is full compensation for foundations; materials, stockpiling, moving and removing, hauling, installing and resetting, disposal of unsalvageable materials, equipment, labor, tools, and incidentals.

5.1. **Furnish and Install.** This price is full compensation for furnishing and installing crash cushion attenuator.

5.2. **Designated Source.** This price is full compensation for delivering and installing Department-furnished crash cushion attenuator from a designated source.

- 5.3. **Move and Reset.** This price is full compensation for moving crash cushion attenuator installations on the project from one location to another (including disassembly and reassembly costs), moving crash cushion attenuator from an installation on the project to a temporary storage area (including disassembly costs), and moving crash cushion attenuator from a temporary storage area to an installation site on the project (including assembly costs).
- 5.4. **Stockpile.** This price is full compensation for removing crash cushion attenuator from the project and delivering to the Department stockpile area shown on the plans or as directed.
- 5.5. **Remove.** This price is full compensation for removing crash cushion attenuator from the project and retained by the Contractor.



## Item 550

### Chain Link Fence

#### 1. DESCRIPTION

Furnish, install, remove, repair, or replace chain link fence and gates.

#### 2. MATERIALS

Furnish certification from the chain link fence materials manufacturer stating that all fencing materials comply with the requirements of this Item before installation of the fence. Use only new materials.

##### 2.1. General. Furnish materials in accordance with the following:

- Item 421, "Hydraulic Cement Concrete," Class B
- Item 445, "Galvanizing"

##### 2.2. Wire Fabric. Provide wire fabric with:

- 9 gauge (0.148 in. diameter) steel wire with a minimum breaking strength of 1,290 lb. meeting ASTM A392 Class I or ASTM A491;
- mesh size of 2 in.  $\pm$  1/8 in. between parallel wires with at least 7 meshes in a vertical dimension of 23 in. along the diagonals of the openings; and
- knuckled selvages at the top and bottom edge of the fabric, unless otherwise shown on the plans.

##### 2.3. Posts. Provide posts of the size and weight shown on the plans. Do not provide rerolled or open-seam posts. Use material for all posts meeting ASTM F1043 Group 1A Regular Grade or Group 1C High Strength.

##### 2.4. Post Caps. Provide malleable iron post caps designed to exclude all moisture. Furnish barbed wire support arms integral with the post caps if barbed wire is shown on the plans. Furnish post caps with an opening for the top rail if top rail is shown on the plans. Post caps must have a 2-in. skirt.

##### 2.5. Gates. Provide gates fabricated from round sections of pipe of the size and weight shown on the plans. Use material for all gate pipes meeting ASTM F1043 Group 1A Regular Grade or Group 1C High Strength. For each gate, include:

- corner and tee fittings of malleable iron or pressed steel with means for attaching diagonal bracing members;
- hinges of malleable iron allowing a full 180° swing, easily operated by one person;
- ball-and-socket-type bottom hinges that do not twist or turn from the action of the gate and prevent the closed gate from being lifted off the hinges;
- a positive stop that prevents any portion of the gate from swinging over an adjacent traffic lane;
- malleable iron pulley systems for roll type gate (only when required);
- diagonal braces consisting of 3/8-in. diameter cable with turnbuckles, 2 to each gate frame, and, for vehicle gates, a vertical pipe brace of the size and weight shown on the plans at the center of each gate leaf;
- latches of malleable iron or steel for single gates with a single-fork latch and padlock eye that will keep the gate closed;
- 2 fork latches mounted on a center plunger rod with a padlock eye for double-leaf gates;
- holdbacks for each leaf of vehicular gates, with a semi-automatic holdback catch anchored at least 12 in. into a 12-in. diameter by 24-in. deep concrete footing; and

- a malleable iron center rest, designed to receive the plunger rod anchored as shown on the plans for all double-leaf gates.
- 2.6. **Top Rail.** Use material meeting ASTM F1043 Group 1A or 1C for all top rail pipes. Provide 1.660 in. OD top rail manufactured from Group 1A standard weight (Schedule 40) steel pipe weighing 2.27 lb. per foot or from Group 1C high-strength pipe weighing 1.84 lb. per foot when shown on the plans. Provide pipe in sections at least 18 ft. long joined with outside steel sleeve couplings at least 6 in. long with a minimum wall thickness of 0.70 in. Use couplings designed to allow for expansion of the top rail.
- 2.7. **Tension Wire.** Use 7 gauge (0.177-in.) carbon steel wire with a minimum breaking strength of 1,950 lb. for the bottom edge of all fence fabric, and for the top edge of fence fabric when a top rail is not specified.
- 2.8. **Truss Bracing.** Provide truss bracing as shown on the plans.
- 2.9. **Cables.** Provide 7-wire strand cables manufactured of galvanized annealed steel at least 3/8 in. in diameter.
- 2.10. **Barbed Wire.** Provide 3 strands of twisted 12.5 gauge barbed wire with 2-point, 14 gauge barbs spaced approximately 5 in. apart conforming to ASTM A121 or ASTM A585 when specified on the plans.
- 2.11. **Barbed Wire Support Arms.** Provide support arms at an angle of 45° from vertical, with clips for attaching 3 strands of barbed wire to each support arm and sufficient strength to support a 200-lb. weight applied at the outer strand when barbed wire is specified on the plans.
- 2.12. **Stretcher Bars.** Provide stretcher bars made of flat steel at least 3/16 × 3/4 in. and not more than 2 in. shorter than the fabric height. Provide one stretcher bar for each gate and end post and 2 stretcher bars for each corner and pull post.
- 2.13. **Grounds.** Provide copper-clad steel rods 8 ft. long with a minimum diameter of 5/8 in., or other UL-listed ground rods.
- 2.14. **Miscellaneous Fittings and Fasteners.** Furnish enough fittings and fasteners to erect all fencing materials in a proper manner. Furnish fittings for posts from pressed or rolled steel, forged steel, malleable iron or wrought iron of good commercial quality spaced as shown on the plans.
- 2.15. **Coatings.** Hot-dip galvanize all materials unless specified otherwise in this Item or on the plans. Fabric, tension wire, and barbed wire may be aluminum-coated or alloy-coated if approved. Additionally coat all material except bolts, nuts, washers, and pipe material with thermally fused polyvinyl chloride (PVC) in accordance with ASTM F668, Class 2b, meeting the specified color when shown on the plans.
  - 2.15.1. **Fabric.**
    - 2.15.1.1. **Galvanizing.** Hot-dip galvanize in accordance with ASTM A392, Class I.
    - 2.15.1.2. **Aluminum Coating.** Aluminum-coat in accordance with ASTM A491.
    - 2.15.1.3. **Alloy Coating.** Coat with zinc-5% aluminum-mischmetal alloy (Zn-5Al-MM) in accordance with ASTM F1345, Class I.
  - 2.15.2. **Posts, Braces, and Gates.**
    - 2.15.2.1. **Standard Weight (Schedule 40) Pipe.** Hot-dip galvanize inside and outside according to ASTM F1043 (1.8 oz./sq. ft. galvanized zinc weight).
    - 2.15.2.2. **High Strength Pipe.** Hot-dip galvanize before or after forming pipe according to ASTM F1043 Group 1C and as follows:
      - Outside—minimum 0.9 oz./sq. ft. galvanized zinc weight with a verifiable polymer overcoat.

- Inside—minimum 0.9 oz./sq. ft. galvanized zinc weight before forming, or minimum 0.3 mils zinc-based coating after forming containing a minimum 90% zinc dust, by weight.

- 2.15.2.3. **Optional Additional Coating.** Additionally coat all pipe material with 10 mils minimum thermally fused PVC according to ASTM F1043, meeting the specified color when shown on the plans.
- 2.15.3. **Fittings, Bolts, and Other Miscellaneous Hardware.** Galvanize all fittings, bolts, and miscellaneous hardware in conformance with Item 445, "Galvanizing."
- 2.15.4. **Tension Wire.** Zinc-coat tension wire with a minimum coating of 0.80 oz./sq. ft. or aluminum-coat with a minimum coating of 0.30 oz./sq. ft.
- 2.15.5. **Barbed Wire.** Zinc-coat barbed wire in accordance with ASTM A121 (0.80 oz./sq. ft.) or aluminum-coat in accordance with ASTM A585 (0.30 oz./sq. ft.).
- 2.15.6. **Pull Cable.** Zinc-coat pull cable with a minimum coating of 0.80 oz./sq. ft. of individual-wire surface when tested in conformance with ASTM A116.

**3. CONSTRUCTION**

Erect the chain link fence to the lines and grades established on the plans. Overall height of the fence when erected is the height above the grade shown.

Repair or replace damaged fence or gates. Remove and replace the post and foundation if posts cannot be repaired by straightening. Return all salvageable material to the location shown on the plans when a fence installation is to be removed in its entirety and not replaced. Backfill all postholes with suitable material. Return the salvaged fence fabric in secured rolls not more than 50 ft. long. Dispose of unsalvageable material.

- 3.1. **Clearing and Grading.** Clear all brush, rocks, and debris necessary for the installation of this fencing.  
  
Stake the locations for corner posts and terminal posts unless otherwise shown on the plans. Follow the finished ground elevations for fencing panels between corner and terminal posts. Level off minor irregularities in the path of the fencing.
- 3.2. **Erection of Posts.** Install posts as shown on the plans. Plumb and permanently position posts with anchorages firmly set before fabric is placed. Brace corner and pull posts as shown on the plans.
- 3.2.1. **Post Spacing.** Space posts as shown in Table 1.

**Table 1  
Post Spacing and Placement**

Post Type	Required Spacing or Placement
Line posts	no more than 10 ft. apart
Pull posts	no more than 500 ft. apart and at each change in direction exceeding 20° vertically
Corner posts	at each horizontal angle point

Install cables on all terminal posts and extend to adjacent posts. Install cables on each side of corner and pull posts with a 3/8-in. drop-forged eye-and-eye or eye-and-clevis turnbuckle unless otherwise shown on the plans.

- 3.2.2. **Postholes.** Drill holes for concrete footings for all posts to provide footings of the dimensions shown on the plans.

Penetrate solid rock by at least 12 in. (18 in. for end, corner, gate, and pull posts) or to plan depth where the rock is encountered before reaching plan depth. Drill holes in the solid rock with a diameter at least 1 in. greater than the outside diameter of the post.

Fill the hole in the solid rock with grout consisting of 1 part hydraulic cement and 3 parts clean, well-graded sand after the posts are set and plumbed. If desired, other grouting materials may be used only if approved. Thoroughly work the grout into the hole, leaving no voids. Construct concrete footings from the solid rock to the top of the ground.

- 3.2.3. **Gate Posts.** Align the tops of all gate frames with the fencing top tension wire or top rail. Provide vehicular gates that are greater in overall height than the adjacent fencing by the height necessary to extend to within 2 in. of the pavement between the curbs if curbs are shown on the plans.
- 3.2.4. **Concrete Footings.** Center posts in their footings. Place concrete and compact by tamping or other approved methods. Machine mix all batches of concrete over 1/2 cu. yd. Hand mixing concrete is allowed on batches under 1/2 cu. yd.

Use forms for footings where the ground cannot be satisfactorily excavated to neat lines. Crown the concrete or grout (for solid rock) to carry water from the post. Keep the forms in place for at least 24 hr. Backfill the footing with moistened material as soon as each form is removed, and thoroughly tamp. Cover concrete with at least 4 in. of loose moist material, free of clods and gravel, immediately after placing concrete. No other curing is required.

Spread all excess excavated and loose material used for curing neatly and uniformly. Remove excess concrete and other construction debris from the site.

- 3.3. **Erection of Fabric.** Place the fabric with the cables drawn taut with the turnbuckles after all posts have been permanently positioned and anchorages firmly set. Secure one end and apply enough tension to the other end to remove all slack before making attachments. Cut the fabric and independently attach each span at all corner posts and pull posts unless otherwise shown on the plans.

Follow the finished contour of the site with the bottom edge of fabric located approximately 2 in. above the grade. Grade uneven areas so the maximum distance between the bottom of fabric and ground is 6 in. or less.

Fasten fabric at 12 in. intervals to the top and bottom tension wires between posts. Fasten the fabric in the same manner when top rail is shown on the plans. Fasten the fabric on gate frames to the top and bottom of the frame at 12 in. intervals. Use steel wire fabric ties of 9 gauge steel or larger. Fasten fabric to terminal posts by steel stretcher bars and stretcher bar bands fitted with carriage bolts and nuts of the size and spacing shown on the plans. Use stretcher bars to fasten end posts, pull posts, corner posts, and gateposts with stretcher bar bands at intervals of no more than 15 in. Attach stretcher bars to terminal posts with 1 x 1/8 in. flat steel bands with 3/8-in. carriage bolts at intervals up to 15 in.

- 3.4. **Electrical Grounds.** Provide at least one electrical ground for each 1,000 ft. of fence, located near the center of the run. Provide additional grounds directly under the point where power lines pass over the fence.

Vertically drive or drill in the grounding rod until the top of the rod is approximately 6 in. below the top of the ground. Connect a No. 6 solid copper conductor to the rod and to the fence by a UL-listed method so that each element of the fence is grounded.

- 3.5. **Repair of Coatings.** Repair damaged zinc coating in accordance with Section 445.3.5., "Repairs."

---

## 4. MEASUREMENT

Chain link fence will be measured by the foot of fence installed, repaired, replaced, or removed, measured at the bottom of the fabric along the centerline of the fence from center to center of posts, excluding gates.

Gates will be measured as each gate installed, repaired, replaced, or removed.

**5. PAYMENT**

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Chain Link Fence (Install)" or "Chain Link Fence (Repair)" of the height specified or "Chain Link Fence (Remove)" and "Gate (Install)" or "Gate (Repair)" of the type, height, and width of opening specified or "Gate (Remove)." Clearing and grading for fencing and gates will not be paid for directly but is subsidiary to this Item.

- 5.1. **Chain Link Fence (Install).** This price is full compensation for furnishing and installing fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus material; and equipment, labor, tools, and incidentals.
- 5.2. **Chain Link Fence (Repair).** This price is full compensation for furnishing materials; repairing or replacing fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus or damaged material; and equipment, labor, tools, and incidentals.
- 5.3. **Chain Link Fence (Remove).** This price is full compensation for removing all fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus material; and equipment, labor, tools, and incidentals.
- 5.4. **Gate (Install).** This price is full compensation for installing gate and for providing materials, center anchorages, equipment, labor, tools, and incidentals.
- 5.5. **Gate (Repair).** This price is full compensation for repairing or replacing gate and for furnishing materials; removing and disposing of damaged materials; and equipment, labor, tools, and incidentals.
- 5.6. **Gate (Remove).** This price is full compensation for removing gate and for materials, equipment, labor, tools, and incidentals.



## Item 770

### Guard Fence Repair

#### 1. DESCRIPTION

Repair guard fence elements, posts, terminal anchor sections, single guard fence terminals, and other appurtenances.

#### 2. MATERIALS

Furnish the following materials, unless otherwise shown on the plans:

- rail elements, posts, blockouts, fittings, and anchor concrete meeting Item 540, "Metal Beam Guard Fence";
- single guardrail terminal (SGT), in accordance with Item 544, "Guardrail End Treatments";
- steel posts with base plates or terminal anchor posts to match original design, meeting ASTM A36 or better;
- paint as required;
- concrete for structural repair, in accordance with Item 429, "Concrete Structure Repair";
- grout meeting the requirements of Item 421, "Hydraulic Cement Concrete"; and
- backfill material as approved.

Pick up materials furnished by the Department at the locations shown on the plans. Load and deliver furnished material to the project location. Pick up Department-furnished materials during normal business hours.

#### 3. WORK METHODS

Replace guard fence, including thrie beam, curb, and transitions, in accordance with Item 540, "Metal Beam Guard Fence," and as shown on the plans or as directed. Work requests are made on a callout basis. Begin physical work within 72 hr. of notification, unless otherwise shown on the plans. Replace end treatments in accordance with Item 544, "Guardrail End Treatments," and as shown on the plans or as directed. Weld in accordance with Item 448, "Structural Field Welding." Repair concrete in accordance with Item 429, "Concrete Structure Repair." Remove guard fence in accordance with Item 542, "Removing Metal Beam Guard Fence." Replace rail and posts removed during the same workday, unless otherwise approved.

- Protect traffic from exposure to unattached rail elements left overnight, as approved.
- Cover or fill postholes at the end of each day.
- Place rail to a smooth line and grade, with posts plumb to the correct height, in accordance with the plans.
- Remove salvageable rail elements in original lengths. Remove fittings from posts and rail elements. Deliver salvageable materials to a designated stockpile site and neatly stack as directed. Reuse salvageable materials in the repair as approved.
- Dispose of debris and damaged components in accordance with all federal, state, and local regulations.

- 3.1. **Repair of Rail Element.** Remove and replace rail elements as directed. Bolt rail elements end to end and lap in the direction of traffic in the lane adjacent to the guard fence. Provide prefabricated curved rail when needed. Field-drill,

punch, or use other approved methods to create holes for special details. Tighten nuts. Replace bridge end connection when required, in accordance with Item 540, "Metal Beam Guard Fence."

- 3.2. **Removal and Replacement of Timber or Steel Post.** Replace posts as directed. Dispose of any concrete removed. Drill new post holes as needed. Clean postholes free of loose dirt and debris, and thoroughly compact bottom of hole to the correct elevation for placement of post. Place post to the correct alignment, elevation, and plumb. Backfill with select material by thoroughly compacting material to the density of adjacent undisturbed material. Replace concrete foundations only as directed. Use grout to fill space between riprap and posts when replacing posts.
- 3.3. **Realignment of Posts.** Realign existing posts to a smooth line and grade.
- 3.4. **Repair of Terminal Anchor Post.** Repair the steel anchor post by straightening or welding to the existing post above the concrete foundation.
- 3.5. **Replacing Terminal Anchor Posts.** Remove and replace damaged anchor posts with foundation or install new anchor posts with foundation. Remove anchor and clean existing holes or drill new holes, as approved.
- 3.6. **Removal of Guardrail End Treatment and Replacement with SGT.** Remove damaged guard fence end treatment and replace with complete new SGT.
- 3.7. **Repair of SGT.** Remove damaged SGT components and replace with new components. Salvage and reuse components as approved.
- 3.8. **Repair of Steel Post with Base Plate.** Replace damaged steel posts with base plates. Drill anchor holes and install new bolts or weld new anchor bolts to existing bolts as directed. Field-weld in accordance with Item 448, "Structural Field Welding," or shop-weld in accordance with Item 441, "Steel Structures." Repair damaged galvanized coating in accordance with Section 445.3.5., "Repairs."
- 3.9. **Raise Rail Element.** Raise rail as shown on the plans.
- 3.10. **Repair of Blockouts.** Remove and replace damaged or deteriorated blockouts with new blockouts when shown on the plans or as directed.

---

#### 4. MEASUREMENT

This Item will be measured as follows:

- 4.1. **Repair of Rail Element (W-Beam, Thrie-Beam, or Thrie-Beam Transition to W-Beam).** By the foot along the face of the rail from center to center of the slotted hole at each end of the rail elements repaired, including the terminal anchor section and the rail with any bolt hole spacing, but excluding the first 2 rail elements of the SGT section.
- 4.2. **Removal and Replacement of Timber or Steel Posts without Concrete Foundation.** By each post replaced.
- 4.3. **Removal and Replacement of Timber or Steel Posts with Concrete Foundation.** By each post replaced.
- 4.4. **Realignment of Posts.** By each post realigned.
- 4.5. **Repair of Terminal Anchor Post.** By each post repaired.
- 4.6. **Replacement of Terminal Anchor Posts.** By each post replaced.
- 4.7. **Removal of Guardrail End Treatment and Replacement with SGT.** By each SGT.

- 4.8. **Replacement of SGT Impact Head.** By each head.
- 4.9. **Replacement of SGT Rail.** By the foot from center to center of posts, 2 rails.
- 4.10. **Replacement of SGT Post.** By each post replaced, includes metal sleeves.
- 4.11. **Remove and Replace Blockouts.** By each blockout replaced.
- 4.12. **Repair of Steel Post with Base Plate.** By each post repaired. Includes top or side mount posts.
- 4.13. **Remove and Reset SGT Impact Head.** By each head reset.
- 4.14. **Replace SGT Object Marker.** By each marker replaced, as directed, including the removal and disposal of the existing rubber bumpers.
- 4.15. **Replace SGT Cable Anchor.** By each cable anchor replaced.
- 4.16. **Replace SGT Cable Assembly.** By each cable assembly replaced.
- 4.17. **Replace SGT Strut.** By each strut replaced.
- 4.18. **Raise Rail.** By the foot along the face of the rail from center to center of the slotted hole at each end of the rail element raised.

---

**5. PAYMENT**

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid at the unit price bid for: "Repair Rail Element of the type specified," "Raise Rail of the type specified," "Remove Post of the type specified," "Replace Post of the type specified," "Repair Post of the type specified," "Realign Posts of the type specified," "Remove Guardrail End Treatment and Replace with SGT," "Replace SGT Impact Head," "Remove and Reset SGT Impact Head," "Remove and Replace Blockouts," "Replace SGT Object Marker," "Replace SGT Cable Anchor," "Replace SGT Cable Assembly," and "Replace SGT Strut."

This price is full compensation for repairing rail and furnishing equipment, materials, labor, tools, and incidentals. Realignment of existing rail without removing will not be paid for directly but considered subsidiary to realigning posts. Replacement of concrete riprap around posts, removal and replacement of curbs, and bridge end connection will not be paid for directly but considered subsidiary to the various bid items. Replacement of SGT components not mentioned above will not be paid for directly but considered subsidiary to the various bid items. Concrete repair will be paid for in accordance with pertinent Items. Payment for repair of steel posts with base plate includes work performed above the concrete foundation. Any rail removed and replaced to remove/replace posts will not be paid for directly but considered subsidiary to various bid items.

Coring new holes and furnishing new bolts and epoxy for the repair or replacement of posts with base plate will be considered subsidiary to various bid items.



## Item 772 Post and Cable Fence

### 1. DESCRIPTION

Install, repair, or remove post and cable fence.

### 2. MATERIALS

Furnish materials as follows, unless otherwise shown on the plans.

- 2.1. **Posts.** Furnish timber posts meeting DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence."
- 2.2. **Cable.** Furnish wire cable meeting ASTM A475 and the following requirements:
  - 3/8 in. nominal strand diameter,
  - 7-wire strand, common grade,
  - minimum breaking strength of 4,000 lb., and
  - 0.30 oz. per square foot minimum weight of zinc coating.
- 2.3. **Fittings and Anchors.** Furnish fittings and anchors galvanized in accordance with ASTM A153.
- 2.4. **Concrete.** Furnish concrete meeting Item 421, "Hydraulic Cement Concrete," of the class shown on the plans.
- 2.5. **Reflectors.** Furnish reflectors as shown on the plans.
- 2.6. **Backfill.** Furnish backfill material as approved.
- 2.7. **Gate.** Furnish gates as shown on the plans.

### 3. WORK METHODS

Install, repair, or remove post and cable fence, including reflectors and related items as shown on the plans.

- 3.1. **Removal.** Remove concrete anchors, posts, and cable. Backfill and thoroughly compact post and anchor holes. Accept ownership of removed materials, unless otherwise shown on the plans. Dispose of removed materials in accordance with federal, state, and local regulations.
- 3.2. **Installation.** Place new anchors, posts, and cable as shown on the plans. Set posts on firm foundation and plumb to the required lines and grades. Thoroughly compact backfill in 4-in. layers. Space pull posts as shown on the plans. Lengthen or shorten one pull post space per continuous section if necessary to accommodate site conditions. Cover or fill open holes at the end of each workday.

Maintain current pull post spacing of existing installations if approved. Straighten undamaged posts that are more than 1 in. out of plumb. Stretch cable to remove sag between posts. One cable splice will be allowed between posts, adjacent to the post, but no more than 2 splices in any 100 ft. of cable. Painting is not required, unless otherwise shown on the plans.

- 3.3. **Repair.** Plumb and realign post in a vertical and horizontal position. Stretch cable to remove sag between posts. One cable splice will be allowed between posts, adjacent to the post, but no more than 2 splices in any 100 ft. of cable. Removal and replacement of posts, anchors, or cable will be paid with the appropriate bid item.
- 

#### **4. MEASUREMENT**

This Item will be measured as follows:

- 4.1. **Post and Cable Fence Removal.** By the foot from center to center of pull posts.
- 4.2. **Concrete Anchor Removal.** By each anchor removed.
- 4.3. **New Installation of Post and Cable Fence.** By the foot of fence from center to center of pull posts for each continuous section installed.
- 4.4. **New Concrete Anchor.** By each anchor installed.
- 4.5. **Removal and Replacement of Posts.** By each post removed and replaced.
- 4.6. **Removal and Replacement of Concrete Anchors.** By each anchor removed and replaced.
- 4.7. **Removal and Replacement of Cable.** By the foot of cable removed and replaced.
- 4.8. **New Installation of Post and Cable Fence (Gate).** By each gate installed.
- 4.9. **Repair.** By the foot of fence from center to center of pull posts for each repair.
- 

#### **5. PAYMENT**

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Post and Cable Fence (Removal)," "Post and Cable Fence (Remove Concrete Anchor)," "Post and Cable Fence (New Installation)," "Post and Cable Fence (New Concrete Anchor)," "Post and Cable Fence (Remove and Replace Posts)," "Post and Cable Fence (Remove and Replace Concrete Anchors)," or "Post and Cable Fence (Remove and Replace Cable)," "Post and Cable Fence (Gate) (New Installation)," or "Post and Cable Fence (Repair)." This price is full compensation for cable splices, straightening posts, realignments of posts, tightening cable, backfilling posts and anchor holes, installation of reflectors, bollards, foundations, backfilling, gate and hardware, paint, materials, equipment, labor, tools, and incidentals.



---

## Item 774 Attenuator Repair

---

**1. DESCRIPTION**

Repair or replace damaged attenuators or crash cushions.

---

**2. MATERIALS**

Furnish materials in accordance with details shown on the plans.

---

**3. WORK METHODS**

Repair or replace attenuators as approved. Begin physical repair for Contracts with callout work within 72 hr. of notification, unless otherwise shown on the plans. Repair damaged components, such as foundation, concrete, anchors, and pavement, as necessary to ensure the final installation functions as designed. Sweep and clean area around attenuator. Dispose of debris and damaged components in accordance with federal, state, and local regulations. Weld in accordance with Item 448, "Structural Field Welding," as directed or approved. Salvage materials as directed.

3.1. **Removal and Replacement.** Remove existing attenuator and replace with a system shown on the plans or as directed.

3.2. **Repair.** Remove and replace damaged elements of attenuators and repair to meet the installation requirements of the system shown on the plans and the specifications that pertain to that appropriate system.

---

**4. MEASUREMENT**

4.1. **Removal and Replacement.** When replacing a complete unit, measurement will be by each unit.

4.2. **Repair.** Repair will be measured by the each for the component specified or by the foot.

---

**5. PAYMENT**

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Remove and Replace" or "Repair" of the type or component specified. This price is full compensation for repairing or replacing attenuators; furnishing materials; salvage and disposal; and equipment, labor, tools, and incidentals.



---

## Item 776

### Metal Rail Repair

---

**1. DESCRIPTION**

Repair metal traffic or pedestrian rail. Replace metal traffic or pedestrian rail if beyond repair as determined by the Engineer.

---

**2. MATERIALS**

Furnish materials in accordance with Item 450, "Railing," and details shown on the plans.

---

**3. WORK METHODS**

Remove damaged steel or aluminum rail and repair to match the original or details shown on the plans. Replace steel or aluminum rail to match the original or details shown on the plans if the damaged rail is beyond repair as determined by the Engineer. Begin physical repair for Contracts with callout work within 72 hr. of notification, unless otherwise shown on the plans. Repair damaged components, anchors, etc., as necessary to ensure the final installation functions as originally constructed. Drill anchor holes and install new bolts or weld new anchor bolts to existing bolts as directed. Weld in accordance with Item 441, "Steel Structures," or Item 448, "Structural Field Welding." Repair damaged galvanized coating in accordance with Section 445.3.5, "Repairs." Paint repaired areas of painted rail to match existing color, in accordance with Item 446, "Field Cleaning and Painting Steel." Repair railing removed for repair during the same workday unless otherwise approved. Deliver salvageable materials to a designated stockpile site and dispose of debris and damaged components in accordance with federal, state, and local regulations.

---

**4. MEASUREMENT**

Rail repair will be measured by the foot between centers of the first undamaged post on each side of the repair or to the end of the rail. Repairing metal post with base plate will be measured by each post repaired. Rail replacement will be measured by the foot between centers of the first undamaged post on each side of the replacement or to the end of the rail.

---

**5. PAYMENT**

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Repair" of the type specified, "Repair Metal Post with Base Plate" of the type specified, and "Replacement" of the type specified. This price is full compensation for removing and repairing rail; salvage and disposal; and materials, tools, equipment, labor, and incidentals. Concrete repair will be paid for in accordance with Item 429, "Concrete Structure Repair."

## INDEX OF SHEETS

SHEET NO.	DESCRIPTION	SHEET NO.	DESCRIPTION
<u>ATTACHMENT SHEETS</u>			
9-14	ATTACHMENT A	68	TAU-II-R(N)- 16
15	ATTACHMENT B	69	TAU-II-R(W)- 16
 <u>DETAIL SHEETS</u>			
40	GF (31)-14		
41	GF (31)DAT-14		
42	GF (31)LS-14		
43	GF (31)TR-14		
44	GF (31)TL2-11		
45	GF (31)T101-13		
46	GF (31)MS-11	70-75	<u>TRAFFIC CONTROL PLAN</u> TCP (1-1)-12 THRU (1-6)-12
47	SGT (8)31-14	76-83	TCP (2-1)-12 THRU (2-8)-12
48	SGT (8S)31-14	84-85	TCP (3-1)-13 THRU (3-2)-13
49	SGT (9S)31-14	86	TCP (3-3)-14
50	SGT (10S)31-16	87	TCP (3-4)-13
51	CATGR(2)- 17	88	TCP (5-1)-12
52	CATGR(2)- 17	89-95	TCP (6-1)-12 THRU (6-7)-12
53	CATCB(1)- 17	96	TCP (7-1)-13
54	CATCB(1)- 17	97	RS-TCP-05
55	BED-14		
56	REACT(N)- 16		
57	REACT(W)- 16		
58	PCF-05		
59	QUAD(N)- 17		
60	QUAD(W)- 17		
61	QGELITE(N)- 17		
62	QGELITE(W)- 17		
63	TRACC(N)- 16		
64	TRACC(W)- 16		
65	SSCC- 16		
66	TAU-II(N)- 16		
67	TAU-II(W)- 16		


The Standard Sheets specifically identified above have been selected by me or under my responsible supervision as being applicable to this project.

\_\_\_\_\_  
 Isaac Garza, P.E.  
 Transportation Engineer


\_\_\_\_\_  
 Date

**GENERAL NOTES**


- The type of post (round wood post, rectangular wood post, or steel post) will be as shown in the plans. The exact position of MBSP shall be shown in accordance with Item 445, "Galvanizing".
- Roll element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified in the plans. The contractor may have slotted holes of 1/2" x 3/4" or 3/4" x 1" (See Note 1). The roll element may have slotted holes of 1/2" x 3/4" or 3/4" x 1" (See Note 1). The roll element may be galvanized to accommodate the construction method (GAT) and the transition sections of guardrail.
- Buttons shall meet the requirements of Item 540, "Metal Beam Guard Fence" through the roll thickness of MBSP (ASTM A307) shall be of sufficient length to extend and not more than 1" beyond the button head "splices" bolts (ASTM A307) and 3/4" x 1 1/2" for 2" long at triple roll splices with a 3/4" double released bolt (ASTM A307). Triple beam "connections" 1/2" dia. (ASTM A325) hex bolts shall be used to attach the MBSP to the transition section of guardrail.
- Fittings (nuts, washers, and washers) shall be galvanized in accordance with Item 445, "Galvanizing". Fittings shall be subsidiary to the MBSP.
- The lateral approach to the guard fence, shall have a maximum slope of 1V:10H. If shown elsewhere in the plans or as directed by the Engineer, the guard fence may be flared at a rate of 2 1/2V:10H.
- Unless otherwise shown in the plans, guard fence placed in the vicinity of curves shall be installed on that side of the curve which is the most difficult to pass. The bolt is located approximately 25 inches above the gutter on or edge of shoulder.
- If solid rock is encountered within 0 to 18" of the finished grade, drill a 2" dia. hole, or drill two 1 1/2" dia. holes, from top back over the rock, drill a 2" dia. hole, or drill two 1 1/2" dia. holes, into the rock or to the standard embedment depth, whichever may be less. Any access post depth, clearing, or rock shall be field cut to ensure proper guardrail installation height. Backfill with a conventional material.
- Posts shall not be set in concrete, or any depth.
- Special fabrication will be required at installations having a curvature of 1488 than 150 ft. radius.
- Unless otherwise shown in the plans, a composite material post and/or block shall be used in lieu of MBSP. The composite material post and block shall be of similar dimensions. The Construction Division, MDOT maintains a Material Producer List (MPL) for producers of materials conforming to MS-7210. Only producers on the MPL may furnish composite material posts and/or blocks.
- For posts located partially or wholly between precast box culvert spans, the use of a cast-in-place concrete closure between spans is required. See Detail "A" on Bridge Standard 50P-90.




**WOOD BLOCK TO RECTANGULAR WOOD POST**




**WOOD BLOCK TO ROUND WOOD POST**




**TYPICAL POST**




**MID-SPAN RAIL SPLICE**




**TRIPLE-BEAM TERMINAL CONNECTION**




**LOW FILL CULVERT POST**




**MID-SPAN RAIL SPLICE**




**TRIPLE-BEAM TERMINAL CONNECTION**




**NON-SYMMETRICAL TRANSITION TO I-BEAM IIG GAUGE**




**RAIL SPLICE DETAIL**




**DOWNSTREAM RAIL ATTACHMENT**




**RAIL SPLICE DETAIL**




**MID-SPAN RAIL SPLICE**



**TRIPLE-BEAM TERMINAL CONNECTION**



**NON-SYMMETRICAL TRANSITION TO I-BEAM IIG GAUGE**



**RAIL SPLICE DETAIL**

**METAL BEAM GUARD FENCE**  
GF (31) - 14

THIS DRAWING IS THE PROPERTY OF THE PENNSYLVANIA DEPARTMENT OF TRANSPORTATION. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.

DATE	DESCRIPTION	BY	CHECKED
01/01/2014	ISSUED FOR BIDDING	SMY	SMY

**GENERAL NOTES**

- The detail shown is the minimum length of head (LCH) for a DAT connected to a concrete rail.
- The rail section at the end post is supported by the steel angle bracket, the rail element is not attached to the end post.
- The foundation tubes shall not project more than 3/4" above the finished grade.
- All hardware for DAT shall be ASTM A307 unless otherwise shown.
- Refer to GF (31) sheet for terminal connection details.

**LOW STRIP INSTALLATION**

If a low strip is required with the DAT installation the ice-out cord around the steel foundation tubes and the two channel struts may be omitted. This will require a full pour of the foundation tubes.


#	(DAT) PARTS LIST	QTY
1	Steel Foundation Tube	2
2	DAT Terminal Post	2
3	Channel Strut	2
4	Terminal Rail Element	1
5	Steel Angle Bracket	1
6	BCT Bearing Plate	1
7	BCT Post Sleeve	1
8	Quarrel Anchor Bracket	1
9	Roundoff-Beam End Section	1
10	BCT Cable Anchor	1
11	Recessed Nut, Quarrel	20
12	1 1/2" Button Head Bolt	4
13	10" Button Head Bolt	2
14	3/4" x 2" Hex Head Bolt	8
15	1/2" x 8" Hex Head Bolt	4
16	1/2" x 10" Hex Head Bolt	2
17	3/4" Flat Washer	16

**Texas Department of Transportation**  
Design Standard

**METAL BEAM GUARD FENCE**  
(Downstream Anchor Terminal)

**GF (31) DAT - 14**

DATE	DESIGNED BY	CHECKED BY	IN CHARGE	DATE




**DOWNSTREAM ANCHOR TERMINAL (DAT)**  
Only for downstream use, when located outside the horizontal clearance area of opposing traffic.


**GENERAL NOTES**

- The type of line post (round wood post, extensior wood post, or steel post) will be as shown in the plans. The exact position of the transitions shall be as shown according with Item 14, "Sizing".
- Post element shall meet all requirements of Item 540, "Metal Beam Guard Fence". The contractor may furnish full elements of 12 1/2' or 25' foot nominal lengths.
- Post spacing shall be 3' - 1 1/2' from standard guardrail to accommodate the transition spacing.
- Each end post shall be of sufficient length to extend through the full thickness of the post (ASTM A36) and no more than 3/4" beyond it. Rivon head splice bolts (ASTM A307) or 3/4" x 1 1/2" with a 3/4" double threaded end shall be used for transition. The transition shall be in accordance with Item 540, "Metal Beam Guard Fence". The transition shall be in accordance with Item 540, "Metal Beam Guard Fence".
- Where solid rock is encountered or where shown on the plans, the diameter of the holes shall be approximately 1/2" inches, the boring shall be with a compression material, and maximum depth shall be 1' - 0" or more as directed by the Engineer.
- Posts shall not be set in concrete, of any depth.
- Refer to GF(31) Standard Sheet for additional details.


NOTE: Field drilled holes shall be realized in accordance with Item 445, "Sizing".  
Punch cutting of holes in guardrail shall not be permitted.




**Rectangular CRT Post  
(6" x 6" x 5' Long)**  
(5) CRT Posts  
See Elevation Detail for locations.




**Standard Line Post Installation**



**Standard Line Post Installation**




<b>METAL BEAM GUARD FENCE (Long Span)</b> <b>GF (31) LS-14</b>	
FILED	DATE
PROJECT NO.	DATE
BY	BY
CHECKED	CHECKED
DATE	DATE



**GENERAL NOTES**

1. The type of post around wood post, rectangular wood post, or steel post will be as shown in the plans. The exact position of the post will be shown in the plans or as directed by the Engineer.
2. Roll element shall meet the requirements of Item 540, "Metal Beam Guard Fence" except as modified in the plans.
3. Curved metal beam guard fence shall be of sufficient length to extend a minimum of 12" beyond the guard post. The metal beam guard fence shall be installed with double recessed nuts (ASTM A563).
4. Fixings (bolts, nuts, and washers) shall be installed in accordance with the specifications for the substitution of the transition.
5. Crown will be viewed to accommodate roadways.
6. If metal post is substituted, see the GF(31) standard sheet for the proper installation details.
7. Posts shall not be set in concrete, or any depth.
8. Unless otherwise shown in the plans, the metal post section block shall meet the requirements of AASHTO, "Composite Metal Post and Bolt for Metal Beam Guard Fence" may be substituted for posts and bolts for metal beam guard fence. The metal post and bolt shall be of a minimum of 1/4" diameter. The metal post and bolt shall be made of a material that meets the requirements of the specification for metal beam guard fence.
9. Refer to GF(31) standard sheet for additional details.




Texas Department of Transportation  
 Title Block  
**METAL BEAM GUARD FENCE  
 TRANSITION (TL-2)  
 (Low Speed Transition)**  
 GF (31) TL-2-11

DATE	BY	CHKD	APP'D
01/10/12	JM	SM	SM
01/10/12	JM	SM	SM

SCALE: AS SHOWN

**GENERAL NOTES**

1. The type of post round wood post, rectangular wood post, or steel post will be shown elsewhere in the plans. The steel posts shall be shown elsewhere in the plans or as directed by the Engineer.
2. Metal beam guard fence sheets as modified on the plans.
3. Burdon head post bolts (ASTM A307) shall be of sufficient strength to support the weight of the sheets and any other loads. Beyond it, Burdon head "splitter" bolts (ASTM A307) shall be used. All bolts shall be galvanized with a 5% double passivated zinc (ASTM A583).
4. Fittings (bolts, nuts, and washers) shall be galvanized and shall be satisfactory to the bid then requiring construction of the transition.
5. Crown will be widened to accommodate transitions.
6. 1/4" bolts shall be used. See the official standard sheet for proper installation of concrete.
7. Posts shall not be set in concrete.
8. Unless otherwise shown in the plans, a composite material post and/or block that meets the requirements of DGS-7210, Form 1000, shall be used. The contractor shall be responsible for obtaining the necessary permits and approvals from the appropriate authorities. The contractor shall be responsible for obtaining the necessary permits and approvals from the appropriate authorities. The contractor shall be responsible for obtaining the necessary permits and approvals from the appropriate authorities.
9. Refer to GF (31) T101-13 for additional details.




**Texas Department of Transportation**  
Design Structure

**METAL BEAM GUARD FENCE  
TRANSITION  
(T101)**

**GF (31) T101-13**

NO.	DATE	BY	CHK'D	APP'D
1	10/10/13			
2	10/10/13			
3	10/10/13			
4	10/10/13			
5	10/10/13			
6	10/10/13			
7	10/10/13			
8	10/10/13			
9	10/10/13			
10	10/10/13			





**GENERAL NOTES**

- For additional information contact Interstate Steel Inc. (602) 283-3728
- The type of set unit will be specified elsewhere in the plans. The numbers in the circles indicate the steel specification to be used. The type of set unit shown is a maintenance consideration and does not affect the structural performance.  

Type	Notes
(1)	Interstate Steel
(2)	Interstate Steel
(3)	Interstate Steel
(4)	Interstate Steel
(5)	Interstate Steel
(6)	Interstate Steel
(7)	Interstate Steel
(8)	Interstate Steel
(9)	Interstate Steel
(10)	Interstate Steel
(11)	Interstate Steel
(12)	Interstate Steel
- 50T's placed within the "offset" 150 ft radius will be installed straight. Standard rail elements may be installed within the radius, without special justification.
- All bolts, nuts, coils, washers, coils, anchors, steel tubes & bearing plates shall be galvanized. If bolts, nuts, coils or washers are to be used, they shall be galvanized for specific installation, if directed by the Engineer.
- The steel tubes shall not protrude more than 4 inches above ground. Silt grouting may be necessary to meet this requirement.
- The steel tubes may be driven with an approved driving head. They shall not be driven with the use of a compressed air rammer. In drilled holes, the bearing material must be satisfactorily compacted to prevent tube settlement.
- Installation pullbacks. See the manufacturer's installation manual for the proper procedure.
- The breakdown coil assembly must be tight. A locking device (like a pin or channel lock pin) should be used to prevent the coils from rotating when tightening the nuts.
- The wood block shall be "top nailed" to the post at the top and bottom of the hole when the wood block is in place. The bearing plate on the front post shall also be "top nailed" to prevent rotation.
- For all installations, the steel tubes and posts shall be installed on the proper ground elevation and the top of the post shall be 1/4" above the ground surface. The post shall be installed on the proper ground elevation and the top of the post shall be 1/4" above the ground surface. The bearing plate on the front post shall also be "top nailed" to prevent rotation.
- The object number shall be installed on the front of the inset head as detailed on DRAWING 12.

Item No.	Type	Quantity	DESCRIPTION
1	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
2	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
3	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
4	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
5	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
6	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
7	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
8	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
9	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
10	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
11	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"
12	SKT	1	SKT (1) 1" x 1/2" x 1/2" x 1/2"




**THE Department of Transportation**  
**SINGLE GUARDRAIL TERMINAL**  
(SKT-31)  
**(WOOD POST)**  
**SGT (8) 31-14**

DATE: 10/18/11  
DRAWN: [Signature]  
CHECKED: [Signature]  
APP'D: [Signature]  
DATE: December 2011


**POST & BOLT OPTIONS**  
Type I, post thru  
Type II, post thru  
Type III, post thru

All measurements should be taken from bottom of post.



**GENERAL NOTES**

1. For additional information contact Inverness Steel Inc., 1429 263-3126.
2. All bolts, nuts, cable assemblies, cable anchors, steel parts & bearing plates shall be galvanneal.
3. SRT's placed within the "minimum" 150' ft. radius, shall be installed according to Standard rail statements to be installed within the radius without special permission.
4. A 270° curve of 2511 may be used to prevent the terminal head from encroaching on the equipment.
5. The floor may be increased or eliminated for specific installations, if checked by the engineer.
6. The lower section of the post shall not penetrate more than 4 inches above finished grade.
7. If the stationing of the ground is not available, the contractor shall provide a stationing on the ground. If the post is placed in a straight line, the stationing shall be appropriately equipped to prevent settlement.
8. If a bolt is encased, see manufacturer's specification request for the proper installation.
9. The zinc-coated cable shall not be used to install the cable. A locking device, lock pin or nut or channel lock pin shall be used to prevent the cable from translating when tensioning the cable.
10. High bolts shall not be set below finished grade. At any locations the cable and/or shall be installed to the proper grade elevation behind the curb. The post shall be installed to the proper height of the rail centerline.
11. The bearing plate shall be installed to the proper height of the rail centerline.
12. An object neither shall be installed on the front of the impact head as indicated on drawing (1).



ITEM NO.	QTY	BILL OF MATERIALS
010001	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010002	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010003	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010004	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010005	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010006	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010007	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010008	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010009	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010010	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010011	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010012	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010013	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010014	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010015	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010016	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010017	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010018	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010019	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010020	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010021	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010022	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010023	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010024	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010025	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010026	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010027	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010028	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010029	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010030	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010031	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010032	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010033	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010034	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010035	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010036	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010037	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010038	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010039	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010040	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010041	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010042	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010043	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010044	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010045	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010046	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010047	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010048	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010049	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010050	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010051	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010052	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010053	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010054	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010055	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010056	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010057	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010058	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010059	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010060	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010061	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010062	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010063	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010064	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010065	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010066	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010067	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010068	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010069	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010070	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010071	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010072	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010073	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010074	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010075	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010076	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010077	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010078	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010079	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV
010080	1	GUARDRAIL (12 GAL 12" x 6" - SRT) GALV

**INVERNESS**  
Inverness Department of Transportation

**SINGLE GUARDRAIL TERMINAL**  
(SKT-31)  
(STEEL POST)  
SGT (85) 31-14


R/S	C/S	DATE	DRAWN	CHECKED	BY

GENERAL NOTES

1. For detailed information contact: Linaway Transportation Solutions - Beam Systems, 180 River Road, #505, CA 94027, (907) 374-8800
2. All dimensions are shown in inches unless otherwise indicated.
3. All cables attached to the cable anchors, ground wires, teller cables, impact heads, nuts, bolts and all other components shall be galvanized unless otherwise indicated in notes.
4. X-LITE placed within the minimum 500 ft. radius will be installed straight. Standard rail treatments may be installed within the radius without special notification.
5. A flag rate of 37.5¢ may be used over the first 50 ft. of this system to protect the terminal head from encroaching on the shoulder (the flag may be observed or eliminated for specific installations, or as directed by the engineer).
6. At each location the cable shall be buckled at two proper areas of elevation behind the rail (see Note 2). The post will be anchored in concrete and the cable attached to the post connection box to maintain the proper height of the rail above the cable post. The clearance post length above the rail will be removed as directed by the engineer.
7. If track excavation is encountered, the soil poles might be modified if approved by the project engineer.
8. When site conditions permit, post may be driven. If poles are placed in a drilled hole, the bottom material must be satisfactorily compacted to prevent settlement.
9. An object marker shall be installed on the impact head as detailed on CHOWA(MA)
10. The X-LITE flat steel post (SCT) shall be suitable for locations calling for wood post or (When used with wood post guardrail system, post 17 may be replaced with CRT post).

Minimum length of MBGF shown. See current guard fence standards for further information.  
The hardware cable assembly must be tested. A locking device (Nose-pipe or channel lock-pipe) should be used to prevent the cable from twisting when tightening the nut.

ITEM	PART NO.	DESCRIPTION	QTY
1	X-LITE	EMBEDDED POST PROTECTOR ONLY	1
2	MBGF	MINIMUM GALVANIZED FENCE	1
3	MBGF	MINIMUM GALVANIZED FENCE	1
4	MBGF	MINIMUM GALVANIZED FENCE	1
5	MBGF	MINIMUM GALVANIZED FENCE	1
6	MBGF	MINIMUM GALVANIZED FENCE	1
7	MBGF	MINIMUM GALVANIZED FENCE	1
8	MBGF	MINIMUM GALVANIZED FENCE	1
9	MBGF	MINIMUM GALVANIZED FENCE	1
10	MBGF	MINIMUM GALVANIZED FENCE	1
11	MBGF	MINIMUM GALVANIZED FENCE	1
12	MBGF	MINIMUM GALVANIZED FENCE	1
13	MBGF	MINIMUM GALVANIZED FENCE	1
14	MBGF	MINIMUM GALVANIZED FENCE	1
15	MBGF	MINIMUM GALVANIZED FENCE	1
16	MBGF	MINIMUM GALVANIZED FENCE	1
17	MBGF	MINIMUM GALVANIZED FENCE	1
18	MBGF	MINIMUM GALVANIZED FENCE	1
19	MBGF	MINIMUM GALVANIZED FENCE	1
20	MBGF	MINIMUM GALVANIZED FENCE	1
21	MBGF	MINIMUM GALVANIZED FENCE	1
22	MBGF	MINIMUM GALVANIZED FENCE	1






**Linaway Transportation Solutions**  
Department of Transportation

**SINGLE GUARDRAIL TERMINAL (X-LITE) STEEL POST SGT(9S)31-14**

DATE: 07/23/2014	DESIGN: 001	PLAN: 001	DATE: 07/23/2014
SCALE: AS SHOWN	SCALE: AS SHOWN	SCALE: AS SHOWN	SCALE: AS SHOWN






SHEET 1 OF 2

Texas Department of Transportation		Division of Standards	
<b>TRINITY HIGHWAY ENERGY ABSORPTION CRASH CUSHION (GUARDRAIL)</b>			
<b>CATGR (2) - 17</b>			
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM
DATE: 01/15/01	BY: JMM	DATE: 12/07/00	BY: JMM





NOT ASSUME RESPONSIBILITY FOR THE CORRECTNESS OF THIS DRAWING OR THE CONSTRUCTION OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CORRECTNESS OF THE CONSTRUCTION OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CORRECTNESS OF THE CONSTRUCTION OF THE PROJECT.

**TEXAS DEPARTMENT OF TRANSPORTATION**  
TRINITY HIGHWAY  
ENERGY ABSORPTION  
CRASH CUSHION  
(CONCRETE BARRIER)  
CATCB(1) - 17





**SHEET 1 OF 2**

DATE: 10/1/87  
BY: [Signature]  
CHECKED BY: [Signature]  
DESIGNED BY: [Signature]



**GENERAL NOTES**

1. For more details See OF (31), SOT (31), OF (31)TR, and OF (31)TL2 standard sheets.
2. Quantities of cast-in-place beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
3. Use straight taper (SOT) for the amount near to determine MBGF length of need in accordance with the roadway design unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-100 ADT) highways, use length determinations for the higher volume category.
4. MBGF may not be required to shield departure end of bridge unless other methods with the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
5. Downstream anchor terminals (DAT) are only for downstream and enclosure use, outside the horizontal clearance area of opposing traffic.
6. Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. Connections shall be a minimum of three standard line posts plus the DAT terminal. See Detail A.
7. The crown shall be viewed to accommodate MBGF. Typically the "front slope" shall be viewed to accommodate MBGF. The MBGF shall be properly transitioned to be viewed to increase roadway width. This does not apply to rehab-ilitation work where existing roadway crown width is to be retained. Use typical cross section at MBGF.
8. For restrictive bridge widths, the MBGF should be properly transitioned to be viewed to increase roadway width. This does not apply to rehab-ilitation work where existing roadway crown width is to be retained. Use typical cross section at MBGF.
9. Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
10. A minimum 25' length of MBGF will be required.




**DETAIL A**  
Showing Downstream Rail Attachment

Texas Department of Transportation		Design District	
BRIDGE END DETAILS (METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)		BED-14	
NO. 100	NO. 100	NO. 100	NO. 100
DATE	DATE	DATE	DATE
BY	BY	BY	BY
CHKD	CHKD	CHKD	CHKD


TYPICAL PLAN VIEW

MODEL B (Self Contained Steel BackUp)




TYPICAL ELEVATION VIEW

MODEL B (Self Contained Steel BackUp)




TYPICAL PLAN VIEW

MODEL C (Concrete BackUp with Side Mount Anchors)



TYPICAL ELEVATION VIEW

MODEL C (Concrete BackUp with Side Mount Anchors)





GENERAL NOTES

1. For specific information regarding installation and technical guidance of the system, contact Trinity Highway Energy Absorption at 11881323-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60682.
2. The ribs of the REACT 350 shall be spaced with a plastic wrap with standard reflection on both sides of the unit. See site plan view for marker and plastic wrap color orientation.
3. All steel components to be hot dipped galvanized (except stakes); drive spikes, treated bolts in backup unit, and wedge fittings on cables.
4. The installation area should be free from curbs, elevated collectors, or depressions. If the REACT system is to span expansion joints contact the manufacturer.
5. The REACT system should be approximately parallel with the sagging or E of merging barriers. The maximum permissible cross-slope is 12.5%.
6. REACT 350 II has laminated concrete. In cylinders 1, 5, 6 & 7.

TYPE	REACT 350	REACT 350 II	REACT 350 II
Test Level	TL-2	TL-2	TL-3
OVERALL LENGTH	19'-3"	19'-3"	19'-5"

FOUNDATION TYPE	MINIMUM THICKNESS	ANCHORAGE
A CONCRETE PAD OR ROADWAY	6"	WP-3 WITH 1" STUDS 15-3" EMBEDMENT PLUS ASPHALT THICKNESS
B ASPHALT OVER CONCRETE PAVEMENT	6" CONCRETE PAVEMENT REQUIRED AS 7" STD. BASE	WP-3 WITH 1" STUDS 15-3" EMBEDMENT
C ASPHALT OVER BASE	8" ASPHALT OVER 6" BASE	WP-3 WITH 1" STUDS 15-3" EMBEDMENT
D ASPHALT ONLY	8"	WP-3 WITH 1" STUDS 15-3" EMBEDMENT



Trinity Highway Energy Absorption  
**TRINITY HIGHWAY ENERGY ABSORPTION (REACT 350 NARROW) (REACT 350 II NARROW) REACT(N)-16**

FIELD CEMENTAL DOS	PERCENT	PERCENT	PERCENT	PERCENT
① CURT FANCTRY 1002	100	100	100	100

FIELD NO. AND UNIT NUMBER  
 PROJECT NO. AND UNIT NUMBER

DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act, the terms of any bond or agreement for professional services, and the terms of any contract for professional services. The user assumes no responsibility for the preparation of this document or the accuracy of the information contained therein. The user assumes no responsibility for the preparation of this document or the accuracy of the information contained therein.





- GENERAL NOTES**
1. For specific information regarding installation and technical details for this system, contact Trinity Highway - Energy Absorption at 11888 33-63-42, 70 N. Madison St., Suite 2300, Chicago, IL 60602.
  2. The back-up of the REACT 350 shall be clad with a plastic wrap which is to be attached to the back-up and the REACT 350. See the plan view for markers and plastic wrap color orientation.
  3. For bi-directional traffic, appropriate transition details will be as shown on the manufacturer's shop drawings.
  4. Details of components for the REACT(W) and back-up and reinforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
  5. If the cross-slope varies more than 2% over the length of the system, the concrete pad will require leveling. Maximum permissible cross-slope is 2%.
  6. The installation area should be free from curbs, elevated objects, or depressions.
  7. The REACT(W) system should be approximately parallel with the barrier or E of carrying barriers.
  8. All steel components to be hot-dipped galvanized, except spikes, anchor plates, threaded bolts in backup unit, and wedge fittings on casters.

WIDE REACT SYSTEMS			
SYSTEM TYPE	BACKUP WIDTH	TEST SYSTEM LENGTH	EFFECTIVE LENGTH
W60	60"	18'-10"	16'-3"
W60	60"	30'-10"	29'-3"
W60	60"	18'-10"	17'-8"
W60	60"	30'-10"	32'-10"
W120	120"	33'-10"	32'-2"
W120	120"	33'-10"	35'-6"

See the manufacturer's shop drawings for additional details.

**ANCHOR SYSTEM TYPE**  
W60\* cast-in-place, embedded system with 1.5" spikes, 5/8" rebar.

**FOUNDATION TYPES**  
Minimum 8" reinforced concrete pad required for concrete pad. See details for manufacturer's shop drawings. Minimum 8" non-reinforced concrete roadway. Minimum 7" concrete stock structure, 30" diameter. Minimum 5" reinforced concrete roadway.



**MONORAIL ASSEMBLY DETAIL**  
See the manufacturer's shop drawings for details of steel backup option.

TRINITY HIGHWAY  
ENERGY ABSORPTION  
CRASH CUSHION  
(REACT 350 WIDE)  
REACT(W) -16

TRINITY HIGHWAY  
ENERGY ABSORPTION  
CRASH CUSHION  
(REACT 350 WIDE)  
REACT(W) -16

DATE: \_\_\_\_\_

SCALE: \_\_\_\_\_

PROJECT: \_\_\_\_\_

NO. \_\_\_\_\_

REV. \_\_\_\_\_

DATE: \_\_\_\_\_


SCALE: \_\_\_\_\_

PROJECT: \_\_\_\_\_

NO. \_\_\_\_\_

REV. \_\_\_\_\_

LOW MAINTENANCE




**GENERAL NOTES**

1. For specific information regarding installation and technical details, refer to the system manufacturer's literature - Energy Absorption of (NSA) 325-874, 70th Edition, 5th Series 2550, Chicago, IL 60602.
2. For all directions, install, appropriate transition panels will be required.
3. Details of components for the QAD and backstop, and reinforcing furnished to the fabricator.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. If the cross-section under stress, 22' over the length of the system, the concrete shall require leveling, leveling.
6. The installation area should be free from curbs, elevated objects, or obstructions.
7. The QAD system should be approximately parallel with the barrier or edge of the roadway.
8. Unit width selected should be adequate to protect an errant vehicle, traveling at 15 degrees to the roadway from the face or corner of the fixed object.
9. For the permanent steel backup (Type A), the distance between the back of backup and the barrier wall should not exceed 7 inches in any case.

Typical Level	NO. OF BAYS	EFFECTIVE LENGTH	QAD UNIT LENGTH	QAD UNIT WIDTH
TL-2	2	8'-0"	9'-0"	4'-6"
TL-3	5	17'-0"	18'-0"	17'-0"

Additional base may be added if special application or conditions exist and if the QAD unit is used in a non-standard configuration. The QAD unit shall be specified elsewhere in the plans.






**TYPE A TENSION STRUT BACKUP**

TENSION STRUT. Consists of diagonal struts, connected to the concrete slab by the manufacturer, located at the rear of the QAD unit. Typical application is for QAD units attached to concrete curb. The front portion of the concrete pad, except where the QAD unit is to be placed on or bridge deck, shall be supported by a non-reinforced concrete pavement (minimum, 4,000 p.s.i.).

Anchor requirements are as follows:

WITH FOUNDATION TYPE	ANCHOR WITH
MINIMUM six inch diameter concrete pad	Embedment with 7" studs, 5.5" embedment
MINIMUM three inch diameter concrete over minimum three inch portland cement concrete	Spiky anchoring system with 1/2" studs, 16.5" embedment
MINIMUM six inch diameter concrete over minimum six inch portland cement concrete	Spiky anchoring system with 1/2" studs, 16.5" embedment
MINIMUM eight inch diameter concrete	Spiky anchoring system with 1/2" studs, 16.5" embedment

If the unit is anchored to asphaltic concrete, it should be rebarbed to the concrete with 1/2" studs to ensure adequate future performance. A zero clearance between the backstop and barrier wall is recommended in no case, should this distance exceed 7 inches.



TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD II) (NARROW)

QUAD (N) - 17

REUSABLE


1901 design or responsibility for the conversion of this drawing to other units or for its reproduction in any form is made by the user. The use of this standard is covered by the American Institute of Steel Construction, Inc. No warranty is made by the Institute of Steel Construction, Inc. for the use of this standard in any other way.

**GENERAL NOTES**

1. For specifications regarding installation and technical details of the QUAD system, refer to the Energy Absorption at 148881323-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60602.
2. For bidirectional traffic, appropriate transition details will be required.
3. Details of components for the QUAD and backup and venting for the manufacturer's shop drawings are to be furnished to the Engineer.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. If the cross-slope varies more than 2% over the length of the system, the access pad will require leveling, maximum accessible cross-slope is 2%.
6. The installation area should be free from curbs, elevated objects, or depressions.
7. The QUAD system should be approximately parallel with the barrier or % of meeting barriers.
8. Unit width selected should be adequate to protect an entire vehicle traveling at 15 degrees to the roadway from the face or corner of the fixed object.

Level	QUADGUARD II WIDEBAY SYSTEM	UNIT LENGTH	NO. OF BAYS	NO. OF EXPOSED REINFORCING STEEL	TYPE & TYPE B	BACKUP LENGTH	BACKUP TYPE & TYPE B
TL-2	3'-11" - 3'	12'-0"	11	0	TYPE B	12'-0"	TYPE B
TL-3	5'-11" - 5'	18'-0"	17	0	TYPE B	18'-0"	TYPE B

Additional details may be added if special conditions warrant and site conditions will accommodate additional length. QUAD II units are available in 30" and 36" unit widths. Number of bays, and backup type shall be specified elsewhere in the plans.




**TYPE A TENSION STRUT BACKUP**


TENSION STRUT: Consists of diagonal struts, end anchors and a top chord. The manufacturer, located on the rear of the QUAD unit. Typical application is for QUAD units attached to curb-face concrete. The anchor block shall be provided beneath the front portion of the concrete pad, except where the QUAD unit is to be placed on a bridge deck. Minimum length of concrete pad shall be 4,000 p.s.i. (minimum, 4,000 p.s.i.).

**TYPE B CAST-IN-PLACE CONCRETE WALL BACKUP**


CAST-IN-PLACE CONCRETE WALL BACKUP: If cast-in-place structures such as bridge bents, columns, or special walls are used as backup structures, when immediately adjacent to the QUAD unit, the QUAD unit shall be secured to the backup structure. Intermediate walls shall be secured with a steel rod with a minimum diameter of 1/2 inch. The rod shall be secured to the backup structure from the standard barrier section to the standard backup section. Details for the intermediate walls, cast-in-place structures in the plan, concrete walls backup may be placed continuously reinforced concrete pavement or bridge deck (minimum, 4,000 p.s.i.) for non-reinforced concrete pavement. The steel rod shall be secured to the backup structure and placed prior to pouring proposed deck as approved by the Engineer.




**PLAN VIEW**



**ELEVATION VIEW**



**PLAN VIEW**



**ELEVATION VIEW**

THESE DRAWINGS ARE THE PROPERTY OF THE ENGINEER. THE USER OF THIS DRAWING IS ADVISED THAT THE ENGINEER'S LIABILITY IS LIMITED TO THE DESIGN OF THIS STRUCTURE. THE USER OF THIS DRAWING IS ADVISED THAT THE ENGINEER'S LIABILITY IS LIMITED TO THE DESIGN OF THIS STRUCTURE. THE USER OF THIS DRAWING IS ADVISED THAT THE ENGINEER'S LIABILITY IS LIMITED TO THE DESIGN OF THIS STRUCTURE.


Illinois Department of Transportation  
**TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD II) (WIDE)**  
**QUAD (W) - 17**

DATE: 08/11/11	BY: [Signature]	CHECKED: [Signature]	DATE: 08/11/11
PROJECT NO. 6314-60-001	SHEET NO. 17	TOTAL SHEETS 17	DATE: 08/11/11

REUSABLE


**GENERAL NOTES:**

1. For specific information regarding installation and technical details, refer to the **Trinity Highway Energy Absorption** (D-11888) 323-8374, 70 W. McAllister St., Suite 2550, Charlotte, N.C. 28202.
2. After each shop drawing is issued, the manufacturer shall be taken of the shop drawing and this diameter is reduced from its original 32" to 28" diameter. When the shop drawing is issued, the manufacturer shall be taken of the shop drawing and this diameter will need to be replaced, including the nose cylinder. All the shop drawings will need to be replaced, including the nose cylinder. All the shop drawings will need to be replaced, including the nose cylinder.
3. For bi-directional traffic, appropriate transition details will be required.
4. Details of components for the GCELLITE and backups and reinforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
5. Concrete shall be class "3" with a minimum compressive strength of 4,000 p.s.i.
6. If the cross-section varies more than 2% over the length of the system, the concrete shall require (existing) Minimum Permissible Cross-Section is 30".
7. The installation area should be free from bumps, elevated objects, or depressions.
8. The GCELLITE system should be approximately parallel with the barrier 3'-6" of existing barriers.
9. All width setbacks should be adequate to protect an errant vehicle. The setback is defined as the distance from the face or corner of the fixed object.




**TENSION STRUT:**  
Consists of diagonal struts, connections, and accessories, as shown in the manufacturer's literature, located at the rear of the GCELLITE unit.

**Typical Application:**  
GCELLITE units attached to double-face Guard-Rails: When used a 4'-0" x 4'-0" x 3'-0" concrete for anchor block shall be provided beneath the front portion of the concrete pad, except where the GCELLITE units is to be placed on continuously reinforced concrete pavement or bridge deck (minimum 4,000 psi) or non-reinforced concrete pavement (minimum 4,000 psi).



Concrete job anchor block required, unless used on steel bridge deck or in front of concrete barrier.

Concrete Pad, Required (unless actual for manufacturer's shop drawings on the manufacturer's shop drawings).



**MONORAIL ASSEMBLY: DETAIL**  
(See the manufacturer's literature for monorail hardware installation details)

Note: Monorail & Backup assembly must be installed within one-half inch.

**QUADGUARD ELITE (NARROW) SYSTEM**

Test Level	No. of Spacing Bars	System Length	Unit Effective Length	Pad Length	Rail Length	Obstacle Width
TL-2	5	17'-0"	17'-0"	17'-0"	12'-0"	24" to 36"
TL-3	8	28'-0"	25'-0"	27'-0"	21'-0"	24" to 36"

SEE MANUFACTURER'S SHOP DRAWINGS FOR TYPE A BACKUP INFORMATION.

ANCHORAGE REQUIREMENTS ARE AS FOLLOWS:

**WITH FOUNDATION TYPE:**

WITH FOUNDATION TYPE	ANCHOR WITH
Minimum of 12" x 12" concrete reinforcement with 7" x 7" studs and 5.5" embedment	Epoxy anchoring system with 7" studs and 5.5" embedment

Concrete job anchor block required, unless used on steel bridge deck or in front of concrete barrier.

**Trinity Highway Energy Absorption (QUADGUARD ELITE) (NARROW) GCELLITE (N) - 17**

Trinity Highway Energy Absorption (QUADGUARD ELITE) (NARROW) GCELLITE (N) - 17


DATE: 08/11/03  
DRAWN BY: J. H. HARRIS  
CHECKED BY: J. H. HARRIS  
SCALE: AS SHOWN

**LOW MAINTENANCE**

DISCLAIMER: This set of drawings is provided by the Texas Engineering Experiment Station (TEXES) for the use of the user. TEXES does not assume any responsibility for the accuracy or completeness of the information provided. The user is responsible for the accuracy and completeness of the information provided. The user is responsible for the accuracy and completeness of the information provided.

**GENERAL NOTES**

- For specific information regarding installation and technical guidance of the system, contact Trinity Highway Energy Absorption at (488) 325-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60602.
- After each impact, measurements should be taken at the shortest outside diameter of the last cylinder (closest to the backup). When the cylinder is reduced from its original diameter, the manufacturer will need to be replaced, including the case if it is required.
- For bi-directional traffic, appropriate transition details will be required.
- Details of components for the QCELITE and backup and reinforcing details will be shown on the manufacturer's shop drawings.
- Concrete shall be class "5" with a minimum compressive strength of 4,000 psi.
- The vertical bars shall be spaced at the length of the system, the concrete and will require twisting. Maximum permeable cross-section is 3".
- The installation area should be free from curbs, streets, collectors, or obstructions.
- The QCELITE system should be approximately parallel with the barrier or E of merging barriers.
- Unit width selected should be adequate to protect on corner vehicle traveling at 15 degrees to the roadway from the face of corner of the fixed object.



**TENSION STRUT**  
Consists of diagonal struts, connections, and compressor, as detailed by the manufacturer, located on the face of the QCELITE unit.


**Typical application**  
QCELITE units attached to CDQuate-Elite Guard-Rail, J When used a 4'-0" x 4'-0" x 3'-0" concrete toe and/or block shall be provided beneath the front portion of the concrete side, secured by rebar. The concrete shall be placed directly against the concrete pavement or bridge deck (7' minimum, 4,000 psi) or non-reinforced concrete pavement (8' minimum, 4,000 psi).

Test Level	NO. OF DAYS	QUADGUARD ELITE (WIDE) SYSTEM			UNSTABLE WIDTH	
		UNIT LENGTH	PAD LENGTH	RAIL LENGTH		
TL-2	7	17'-11"	17'-3"	14'-0"	12'-0"	69" to 90"
TL-3	8	26'-7"	25'-11"	27'-11"	21'-0"	

SEE MANUFACTURER'S SHOP DRAWINGS FOR TYPE A BACKUP INFORMATION.


**WITH FOUNDATION TYPES**  
Minimum 6" portland cement reinforced concrete pad or 8" non-reinforced concrete pad with 75 # rebar and 1.5" embedment ANCHORAGE REQUIREMENTS ARE AS FOLLOWS:

Concrete side anchor block, pedestal, unless used on corner bridge deck or in front of concrete barrier.




**QUADGUARD ELITE SYSTEM DETAIL**

6" concrete pad, reinforced-reinforcing steel for concrete pad shall be shown on the manufacturer's shop drawings.



**MONORAIL ASSEMBLY DETAIL**

Notes: Monorail & chain assembly must be provided within specified limits. (See the manufacturer's shop drawings for monorail hardware, install details.)



**Type A Backup**

**LOW MAINTENANCE**


TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD ELITE) (WIDE) QCELITE (W) - 17

TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD ELITE) (WIDE) QCELITE (W) - 17


TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD ELITE) (WIDE) QCELITE (W) - 17

**GENERAL NOTES:**

1. For assistance information regarding installation and technical guidance of the system, contact Trinity Highway at 1(888)323-6374, 2825 W. Stemmons Freeway, Dallas, TX 75207
2. For bleed-traction traffic, appropriate traction panels will be required.
3. Details of components for the TRACC and backup and reinforcing details will be shown on the manufacturer's shop drawing furnished to the Engineer.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. The connections shall be more than 2x over the length of the embedment and shall require lap splicing.
6. The installation area should be free from obstructions, rebar, objects, or depressions.
7. The TRACC system shall be approximately parallel with the barrier or edge of merging barrier.



Attachment shown is to ensure with all plates, parapets and modified concrete Traffic Barriers, traffic flow is unidirectional.



Attachment and rebar details to ensure with all plates, parapets and modified concrete Traffic Barriers, traffic flow is unidirectional. (See manufacturer's product manual)

TRACC #	QTY	QTY	DESCRIPTION
24938A	1	1	FASTRACC UNIT ASSEMBLY
24938B	1	1	TRACC UNIT ASSEMBLY
33100	4	4	SHORTRACC UNIT ASSEMBLY
33100	4	4	1/2" Dia x 6" Section Embedment
44510	4	4	1/2" Dia x 6" Section Embedment
65210	1	1	Plastic Staples
66580	4	4	Reflective Sheet Pile
* ANCHOR HARDWARE (CONCRETE BASE)			
32040	32	24	1/2" Dia x 7 1/2" x 1/2" Stud Rod
33100	32	18	3/4" Lockwasher
33610	32	18	3/4" Hex Nut
33000	32	24	1/2" Flat Washer
32000	3	3	2" TRACC ANCHOR W/ 1/2" DIA X 1/2"
* ANCHOR HARDWARE (ASPHALT BASE)			
63800	32	24	1/2" Dia x 7 1/2" x 1/2" Stud Rod
33100	32	18	3/4" Lockwasher
33610	32	18	3/4" Hex Nut
33000	32	24	1/2" Flat Washer
32000	3	3	2" TRACC ANCHOR W/ 1/2" DIA X 1/2"

\* See manufacturer's product manual.


TYPE (NARROW)	TEST LEVEL	SYSTEM LENGTH	EFFECTIVE LENGTH	PAD LENGTHS
FASTRACC (1 Stage System)	TL-2	26'	27'-0"	26'-0"
TRACC (2 Stage System)	TL-3	21'-3"	23'-0"	22'-0" 23'-0" 24'-0"
SHORTRACC (2 Stage System)	TL-2	14'-3"	14'-0"	13'-0" 14'-0" 17'-0"

The Stage System refers to number of replaceable steel sections that could be replaced independently. Concrete pad length on TRACC & SHORTRACC depends on backup type.

FOUNDATION OPTIONS:
6" Reinforced concrete
8" Unreinforced concrete
3" Min. Asphalt over 3" Min. Concrete
6" Asphalt over 3" Compact Subbase
8" Minimum Asphalt

For steel placement in concrete foundations, (See manufacturer's product manual)

BACKUP SUPPORT OPTIONS:
Square Concrete Backup
Concrete Barrier (CBB) Backup
Single Slope Concrete Barrier (SSCB)
Quadrant Backup (Beehive Post)
Quadrant Backup (Drum Post)



TRANSITION OPTIONS:  
Vertical Wall  
Modified (CBB) to Vertical Wall  
Concrete Barrier (CBB)  
Quadrant (Drum Post)  
Quadrant (Beehive)

For bidirectional transition panel details (See manufacturer's product manual)  
Backup and transition types are shown elsewhere on the plans, (i.e. Retarder location details on the General Notes).

Trinity Highway  
Texas Department of Transportation  
Product Standard


**TRINITY HIGHWAY  
CRASH CUSHION  
(NARROW)  
TRACC (N) - 16**

DESIGN DIVISION	DATE	BY	CHKD
PROJECT NO.	SECTION NO.	DATE	BY
ISSUE NO.	DATE	BY	CHKD

REUSABLE

**GENERAL NOTES:**

- For specific information regarding prices, test results and specifications, contact the System Manufacturer, Trinity Highway at 11863/323-6374, 2525 N. Stearns Freeway - Dallas, TX 75203.
- Contact the company for custom widths from 31' up to 87'-wide, and transition panels for bi-directional traffic applications.
- Details of components for the wide-trace, backups and re-inforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class "5" with a min. compressive strength 4,000 P.S.I.
- If the cross-structure varies more than 24" over the length of the system, the concrete pad will require leveling. Maximum permissible cross-slope is 1%.
- The installation area should be free from curbs, elevated objects, or depressions.
- The wide-trace system should be approximately centered with the barrier on E. of existing barriers.
- The unit shown is fixed on both sides, but can be fixed on a single side either left or right. The fixings will effect the length and width of the system. (See King Extension Manual)



Attachment and transitions to other widths, barriers, railings and bi-directional traffic flows are available. (See manufacturer's product manual).

BACKUP SUPPORT OPTIONS
SQUARE CONCRETE BACKUP
CONCRETE BARRIER (CBI) BACKUP
SINGLE SLOPE CONCRETE GABRIEL (SSG)
GABRIEL BACKUP (BASE-PLATED POST)
GABRIEL BACKUP (DRIVER POST)

TRANSITION OPTIONS
VERTICAL WALL
MODIFIED TIE-TO-VERTICAL WALL
CONCRETE BARRIER (CBI)
GABRIEL (TIE-TO-BEAM)
GABRIEL (TIE-TO-WALL)

FOR BI-DIRECTIONAL TRANSITIONS: PANEL DETAILS, BACKUP AND TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS. SEE ATTACHMENT LOCATION DETAILS ON THE GENERAL NOTES.

FOUNDATION OPTIONS
6" UNREINFORCED CONCRETE
3" WITH ASPHALT OVER 3" MIN. CONCRETE
6" ASPHALT OVER 6" COMPACT SUBGRADE
8" MANTLE ASPHALT

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.


WIDE-TRACE - BILL OF MATERIAL		
PART #	QTY	DESCRIPTION
299774	1	WIDE-TRACE UNIT ASSEMBLY
299774	1	WIDE-TRACE UNIT ASSEMBLY
33106	4	3/4" LOCKWASHER
43726	4	3/4" FLATWASHER
44816	4	3/4" DIA X 6" EXP. WEDGE ANCHOR
55319	1	PLASTIC NOSERFLEX
55488	4	REFLECTIVE SHEETING
32048	72	5/8" DIA X 7-1/2" THD ANCHOR STUD
43726	72	3/4" FLATWASHER
33106	72	3/4" LOCKWASHER
33110	72	3/4" HEX NUT
32068	5	2 ACTIVATING MIXES KIT HT-150
52806	72	50 18 3/4" DIA X 18" THD ANCHOR STUD
43726	72	50 18 3/4" Flatwasher
33106	72	50 18 3/4" Lockwasher
33110	72	50 18 3/4" Hex Nut
52068	15	2 ACTIVATING MIXES KIT HT-150
52078	15	ANCHOR HARDWARE (OPTIONAL - ITEMS ARE NEEDED)
52088	15	ANCHOR HARDWARE (OPTIONAL - ITEMS ARE NEEDED)
52098	15	ANCHOR HARDWARE (OPTIONAL - ITEMS ARE NEEDED)
52098	15	ANCHOR HARDWARE (OPTIONAL - ITEMS ARE NEEDED)

Trinity Highway  
CRASH CUSHION (WIDE UNIT)  
TRACC (W) - 16

Division  
Location  
Contract No.  
Sheet No.

DATE  
BY  
CHECKED  
APPROVED

NUMBER OF WING EXTENSIONS (BASE UNITS)	WIDE-TRACE WING EXTENSIONS		WIDE-SHORTTRACE WING EXTENSIONS	
	WIDTH	EFFECTIVE LENGTH	WIDTH	EFFECTIVE LENGTH
1	58"	21'-4"	46"	15'-4"
2	58"	21'-4"	46"	15'-4"
3	58"	21'-4"	46"	15'-4"
4	58"	21'-4"	46"	15'-4"
5	58"	21'-4"	46"	15'-4"
6	58"	21'-4"	46"	15'-4"
7	58"	21'-4"	46"	15'-4"
8	58"	21'-4"	46"	15'-4"
9	58"	21'-4"	46"	15'-4"
10	58"	21'-4"	46"	15'-4"
10*	58"	21'-4"	46"	15'-4"




TYPE (WIDE)	TEST LEVEL
WIDE-TRACE SYSTEM	TL-3
SHORTTRACE SYSTEM	TL-2

NOTE: The Short-Trace System refers to number of fabrications. "Wide" fabrications that could be installed "in-between".

**GENERAL NOTES**

1. See specific information regarding the SSSC in the technical package of the SSSC, Road Systems, Inc., at 13301 146th Ave. N.W., Old House County Airport, Big Lake, MN 55129.
2. Due to the SSSC's design, the SSSC is not recommended for use at locations where median locations where backslope adjacent to the SSSC are possible. In such areas, if narrow end and other steel components shall be galvanized, unless otherwise noted.
3. All bolts, nuts, cable assemblies, bearing plates, cables, posts, impact heads, and other steel components shall be galvanized, unless otherwise noted.
4. The bracket cable assembly must be installed in a location where the cable will be driven with the upper post section attached, if posts are placed in a drilled hole. The bracket material must be fastidiously connected to prevent settlement.
5. If rock excavation is encountered, see manufacturer's installation booklet for installation recommendations.
6. Post shall not be set full depth in concrete.
7. The appropriate connection at the SSSC to the field bridge's field structure is at which the system to insure proper performance of the system. The length of the cable used to attach the system to the field structure will vary with the wall thickness and will need to be determined in the field.
8. The compression area in front of the SSSC and the area within the system itself shall be free of high or water.
9. Unless otherwise shown in the plans, SSSC shall be placed in the vicinity of cables shall be placed on so that the side of cable is located directly above the post. The SSSC shall be installed on or in front of the ground elevation, make the gutter run or roadway surface, grade located along or in front of the SSSC system shall not be greater than 4 inches in height.
10. An object marker shall be installed on the front of the impact head on detailed on P. 4, 24, 24, 24, 24.

ITEM NO.	DESCRIPTION
1	1/2" Dia. x 12" Long, Impact Head
2	1/2" Dia. x 12" Long, Impact Head
3	1/2" Dia. x 12" Long, Impact Head
4	1/2" Dia. x 12" Long, Impact Head
5	1/2" Dia. x 12" Long, Impact Head
6	1/2" Dia. x 12" Long, Impact Head
7	1/2" Dia. x 12" Long, Impact Head
8	1/2" Dia. x 12" Long, Impact Head
9	1/2" Dia. x 12" Long, Impact Head
10	1/2" Dia. x 12" Long, Impact Head
11	1/2" Dia. x 12" Long, Impact Head
12	1/2" Dia. x 12" Long, Impact Head
13	1/2" Dia. x 12" Long, Impact Head
14	1/2" Dia. x 12" Long, Impact Head
15	1/2" Dia. x 12" Long, Impact Head
16	1/2" Dia. x 12" Long, Impact Head
17	1/2" Dia. x 12" Long, Impact Head
18	1/2" Dia. x 12" Long, Impact Head
19	1/2" Dia. x 12" Long, Impact Head
20	1/2" Dia. x 12" Long, Impact Head
21	1/2" Dia. x 12" Long, Impact Head
22	1/2" Dia. x 12" Long, Impact Head
23	1/2" Dia. x 12" Long, Impact Head
24	1/2" Dia. x 12" Long, Impact Head
25	1/2" Dia. x 12" Long, Impact Head
26	1/2" Dia. x 12" Long, Impact Head
27	1/2" Dia. x 12" Long, Impact Head
28	1/2" Dia. x 12" Long, Impact Head
29	1/2" Dia. x 12" Long, Impact Head
30	1/2" Dia. x 12" Long, Impact Head
31	1/2" Dia. x 12" Long, Impact Head
32	1/2" Dia. x 12" Long, Impact Head
33	1/2" Dia. x 12" Long, Impact Head
34	1/2" Dia. x 12" Long, Impact Head
35	1/2" Dia. x 12" Long, Impact Head
36	1/2" Dia. x 12" Long, Impact Head
37	1/2" Dia. x 12" Long, Impact Head
38	1/2" Dia. x 12" Long, Impact Head
39	1/2" Dia. x 12" Long, Impact Head
40	1/2" Dia. x 12" Long, Impact Head
41	1/2" Dia. x 12" Long, Impact Head
42	1/2" Dia. x 12" Long, Impact Head
43	1/2" Dia. x 12" Long, Impact Head
44	1/2" Dia. x 12" Long, Impact Head
45	1/2" Dia. x 12" Long, Impact Head
46	1/2" Dia. x 12" Long, Impact Head
47	1/2" Dia. x 12" Long, Impact Head
48	1/2" Dia. x 12" Long, Impact Head
49	1/2" Dia. x 12" Long, Impact Head
50	1/2" Dia. x 12" Long, Impact Head






NOTE: Concrete bridge piers may require a modified and/or reinforced connection. Contact the Bridge Division for details.

Design Division  
Standard

Minnesota Department of Transportation  
**ROAD SYSTEMS INC**  
**CRASH CUSHION**  
**(BEAT)**

SSCC-16

DATE: 10/11/01  
DRAWN: J. H. H. / J. H. H.  
CHECKED: J. H. H. / J. H. H.  
SCALE: AS SHOWN



GENERAL NOTES

1. For specific information regarding the installation and technical outline of the system, contact: Liberty Transportation Solutions - Barrier Systems, Inc., or (707) 374-6600, 180 River Road, Rio Vista, CA 94071
2. Refer to the installation manual and configuration chart for system assembly and element orientation. For bi-directional traffic, appropriate transition details will be required.
3. Additional details for the backup support option, transition option and foundation option will be shown on the manufacturer's and drawings furnished to the engineer.
4. Concrete shall be class "C" with a minimum compressive strength of 4,000 p.s.i.
5. Maximum permissible cross-slope is 2%.
6. The installation area should be free from other elevated objects, or depressions.
7. The TAU-II system should be approximately parallel with the barrier or center line of merging barriers.
8. 30-inch (30") model shown, also available in 36-inch (36") configuration.

ATTACHMENTS AND TRANSITIONS TO USE FOUR BARRIER OPTIONS: BARRIER TYPE I AND BARRIER TYPE II FOR BI-DIRECTIONAL TRAFFIC FLOW ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

ROAD LENGTH (VARIES) ROAD LENGTH FOR TAU-II SYSTEMS DEPENDS ON DESIGN SPEED AND BACKUP TYPE

TRAFFIC FLOW

**BILL OF MATERIAL**

PRODUCT CODE	QTY	DESCRIPTION
B03070A	1	Frame Support
B03071A	1	Wedge Support Diaphragm
B03072A	1	Backup Support Diaphragm
B01002A	1	Energy Absorbing Cartridge Type A
B01002B	1	Energy Absorbing Cartridge Type B
B01003A	1	Anchor Post/Post
B01003B	1	Front Support Leg Kit
B01004A	1	Cable Guide Assembly Kit
B01004B	1	Sliding Panel
B01005A	1	End Panel Assembly Kit
B01005B	2	End Panel
B01006A	4	Post Terminal Mount
B01006B	1	Front Cable Anchor
B01007A	1	Post Piece
B01007B	2	Cable
B01008A	1	Post Mounting Hardware

ITEMS TO BE DETERMINED, DEPENDING ON BACKUP TYPE AND SYSTEM LENGTH, SEE MANUFACTURER'S PRODUCT MANUAL

**TAU-II (NARROW) SYSTEM LENGTHS**

BACKSTOP	TL-2	TL-3	70 mph
PCB	12'-7"	26'-10"	29'-7"
FLUSH MOUNT	13'-0"	27'-3"	30'-0"
COMPACT	14'-3"	28'-6"	31'-3"

NOTE: SYSTEM LENGTHS ARE 32"

**TRANSITION OPTIONS**

VERTICAL WALL
CONCRETE TRAFFIC BARRIERS
W-BEAM GUARDRAIL
TRIPLE BEAM GUARDRAIL

BACKUP AND TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS. (SEE ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES)

FOR BI-DIRECTIONAL TRANSITION PANEL AND PCB SHIP DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.

**FOUNDATION OPTIONS**

6" REINFORCED CONCRETE
8" UNREINFORCED CONCRETE
ASPHALT OVER CONCRETE WITH MINIMUM 6" EMBEDMENT IN CONCRETE
6" ASPHALT OVER 4" COMPACT SUBBASE
8" MINIMUM ASPHALT

FOR STEEL PLACEMENT OR CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

**BACKUP SUPPORT OPTIONS**

COMPACT, STAND ALONE
FLUSH MOUNT
PCB (CONCRETE-BARRIER)

Liberty Transportation Solutions  
 Department of Transportation  
**LTS-BARRIER SYSTEMS**  
**CRASH CUSHION**  
**(NARROW UNIT)**  
**TAU-II (N) - 16**

DATE: 04/11/2013	TIME: 10:16:13	USER: JLM
PROJECT: 6314-60-001	DATE: 04/11/2013	TIME: 10:16:13
PROJECT: 6314-60-001	DATE: 04/11/2013	TIME: 10:16:13
PROJECT: 6314-60-001	DATE: 04/11/2013	TIME: 10:16:13

PROJECT: 6314-60-001  
 DATE: 04/11/2013  
 TIME: 10:16:13  
 USER: JLM  
 PROJECT: 6314-60-001  
 DATE: 04/11/2013  
 TIME: 10:16:13  
 USER: JLM

- GENERAL NOTES**
- For specific information regarding installation and technical guidance of the system, contact: Highway Transportation Solutions - Barrier Systems, Inc. at 1703 314-6800, 110 River Road, Rio Vista, CA 94571
  - Refer to installation manual and identification sheet for specific system assembly and element orientation.
  - For unusual localities, the manufacturer's configuration sheet must be used. If the configuration sheet does not apply to your site, contact the manufacturer for a special design or design details. In some cases, contact the manufacturer for further information.
  - For bi-directional traffic, incorporate transition panels will be required.
  - Additional details for the backup support options, transition, options and foundation options will be shown in the manufacturer's shop drawings furnished to the Engineer.
  - Concrete shall be class "3" with a minimum compressive strength of 4,000 p.s.i.
  - Maximum permitted cross-slope is .6%.
  - The installation area should be free from curbs, elevated objects, or depressions.
  - The TAU-11 System should be approximately parallel with the barrier or edge of existing barrier.

**BILL OF MATERIAL**

PRODUCT CODE	QTY	DESCRIPTION
BO1004	1	FRONT SUPPORT
BO1005	1	MIDDLE SUPPORT
TBD	1	XL ROLLHEAD
TBD	1	XL BELLEHEAD
TBD	1	XLAL ROLLHEAD
TBD	1	XXAL ROLLHEAD
TBD	1	XXAL BELLEHEAD
TBD	1	BACKUP SUPPORT
TBD	1	FRONT CABLE ANCHOR
TBD	1	NOSE
BO1002	1	SLIDING PANEL
BO1009	1	FRONT PANEL
BO1003	1	SLIDER ASSEMBLY KIT
BO1002	1	ENERGY ABSORBING CARTRIDGE, TYPE A
BO1022	1	ENERGY ABSORBING CARTRIDGE, TYPE B
TBD	2	CABLE
BO1001	1	LATERAL SUPPORT KIT
BO1004	1	CABLE GUIDE KIT
BO1005	2	FRONT SUPPORT LEG KIT
TBD	1	ANCHORING PADSHOE
BO1013	1	NOSE ATTACHING HARDWARE

(TBD) = To Be Determined, depending on Backup Width, Backup Type and System length. Use manufacturer's product manual


Texas Department of Transportation  
Traffic Division  
Standard

**LTS-BARRIER SYSTEMS  
CRASH CUSHION  
(WIDE UNIT)**

**TAU-11 (W) -16**

DATE	REVISION	BY	CHKD
01/01/2011	1	JM	JM
01/01/2011	2	JM	JM
01/01/2011	3	JM	JM
01/01/2011	4	JM	JM
01/01/2011	5	JM	JM
01/01/2011	6	JM	JM
01/01/2011	7	JM	JM
01/01/2011	8	JM	JM
01/01/2011	9	JM	JM
01/01/2011	10	JM	JM

REUSABLE



FOR ATTACHMENT AND TRANSITIONS TO BARRIERS, HALLWAYS AND BI-DIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

**FOUNDATION OPTIONS**


6" REINFORCED CONCRETE
8" UNREINFORCED CONCRETE
ASPHALT OVER CONCRETE WITH MINIMUM 6" UNDERLAY ON CONCRETE

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

**TAU-11 (W) SYSTEM LENGTHS**

SYSTEM WIDTH	TL-2	TL-3	70 MPH
42"	14'-4"	28'-5"	31'-3"
48"	14'-4"	28'-5"	31'-3"
54"	14'-4"	28'-5"	31'-3"
60"	11'-5"	23'-7"	29'-5"
66"	11'-5"	23'-7"	29'-5"
72"	11'-5"	23'-7"	29'-5"
78"	11'-5"	23'-7"	29'-5"
84"	11'-5"	23'-7"	29'-5"
90"	11'-5"	23'-7"	29'-5"
96"	11'-5"	23'-7"	29'-5"
102"	11'-5"	23'-7"	29'-5"

NOTE: SYSTEM LENGTHS ARE 4'-2"




NOTE: NOSE PILE DELINEATION ORIENTATION, IS SHOWN ELSEWHERE ON THE PLANS.

**GENERAL NOTES:**

- For specific information regarding installation and technical outcomes of the system, contact Lindsay Transportation Solutions - Barrier Systems, Inc. at (707) 374-8800, 180 River Road, Rio Vista, CA 94571
- For bi-directional traffic, appropriate transition panels will be required.
- Additional details for the backup support options, transition options and foundation options will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class "S" with a minimum compressive strength of 4,000 psi.
- Maximum permissible cross-slope is 3%.
- The installation area should be free from curbs, elevated objects, or depressions.
- The TAU-11-R system should be spaced (and/or partially) with the barrier or center of merging barrier.
- Refer to universal TAU-11-R configuration chart for specific systems configuration number and location of each type of energy absorbing elements.
- 36" high (36") model shown, also available in 36-inch (36") configuration.


Attachments and transitions to various barrier types, barrier railings and bi-directional traffic flows are available.

(SEE MANUFACTURER'S PRODUCT MANUAL)




PLAN VIEW

TRAFFIC



ELEVATION VIEW



ENERGY ABSORBING ELEMENTS (EAE)

Backup Support Options	
Compact (Strand Alone)	
Flush Mount	
PGB (Concrete Barrier)	

TAU-11-R (Narrow) System Lengths	
BACKSTOP	7L-2, 7L-3, 70 mdy
PGB	27'-10", 36'-7"
Flush Mount	14'-0", 28'-3", 31'-0"
Compact	15'-3", 28'-6", 32'-3"

Backup and Transition types are shown elsewhere on the plans. I.e. Attachment location details or in the general notes.


Note: System lengths are 2'

Transition Options	
Vertical Wall	
Concrete Traffic Barriers	
W-Beam Quadrail	
Triple Beam Quadrail	

For bi-directional transition panel and end shoe details, see manufacturer's product manual.

Foundation Options	
6" Reinforced Concrete	
8" Unreinforced Concrete	
Asphalt over concrete with Minimum	
6" Embedment in Concrete	
6" Asphalt over 6" compact subbase	
8" Minimum Asphalt	

For steel placement in concrete foundations, see manufacturer's product manual.



SECTION A-A

PRODUCT CODE	QTY	DESCRIPTION
8030704	1	Front Support
8030703	180	W/D Support
TBD	1	Backstop Assembly (See Table)
TBD	1	Front Cable Anchor
TBD	1	Noise Assembly
8010302	180	Sliding Panel
8010303	2	End Panel
8010304	1	Slider Assembly Kit
851-102069-KT	TBD	TAU-11-R Slider Kit
851-110131-KT	TBD	TAU-11-R EAE Mounting Kit
851-102069-00	180	Energy Absorbing Element, Type 1
851-102070-00	180	Energy Absorbing Element, Type 2
851-102071-00	TBD	Energy Absorbing Element, Type 3
851-1110038-00	180	Energy Absorbing Element, Type 3A
TBD	180	Cable Assembly
8001004	180	Cable Guide Kit
8001005	2	Front Support Leg Kit
8010051	4	Pipe Panel Mount
TBD	1	Anchoring Package

(TBD) = To Be Determined, depending on Backup Type and System Length.

(See manufacturer's product manual for details)

**LTS-BARRIER SYSTEMS**  
**CRASH CUSHION**  
**(R-NARROW)**

**TAU-11-R (N) -16**


Division:  Division  
 Standard:  Standard

Rev:	10/11/14	Rev:	10/11/14	Rev:	10/11/14
System:	TAU-11-R	Rev:	10/11/14	Rev:	10/11/14
Drawn:	10/11/14	Rev:	10/11/14	Rev:	10/11/14
Checked:	10/11/14	Rev:	10/11/14	Rev:	10/11/14
Approved:	10/11/14	Rev:	10/11/14	Rev:	10/11/14


LOW MAINTENANCE

**GENERAL NOTES**

- For specific information regarding installation and technical conditions of the system, contact Lindsay Transportation Solutions - Barrier Systems, Inc. at (707) 214-8400, 180 River Road, Ste Vista, CA 94971.
- For bi-directional traffic, appropriate transition details will be required.
- Additional details for the backup support system transition detail and foundation options will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class 75 with a minimum compressive strength of 4,000 psi.
- Maximum permissible cross-slope is 3%.
- The installation area should be free from curbs, elevated objects, or ground depressions.
- The TAU-11-R system should be installed approximately parallel with the barrier or center of merging barrier.
- Refer to universal TAU-11-R configuration charts for system configuration numbers and location of each type of energy absorbing element.




At transitions and configurations, the various barrier shapes, barrier railings and bi-directional traffic flows are available.  
(See manufacturer's product manual)



TAU-11-R-WIDE SYSTEM LENGTHS		
SYSTEM WIDTH	TL-2	TL-3 TO mph
42"	15'-4"	29'-5"
48"	15'-4"	29'-5"
54"	15'-4"	29'-5"
60"	12'-5"	29'-5"
66"	12'-5"	29'-5"
72"	12'-5"	26'-7"
78"	12'-5"	26'-7"
84"	12'-5"	26'-7"
90"	12'-5"	26'-7"
96"	12'-5"	26'-7"
102"	12'-5"	26'-7"


Note: System lengths are +/-2"



ENERGY ABSORBING ELEMENTS (EAE)

FOUNDATION OPTIONS	TRANSITION OPTIONS
6" Reinforced Concrete	Vertical Wall
8" Unreinforced Concrete	Concrete Traffic Barriers
Asphalt over concrete with minimum 6" embedment in concrete	W-beam Guardrail
	Triple Beam Guardrail

For steel placement in concrete foundation, see manufacturer's product manual.  
For bi-directional transition detail, see manufacturer's product manual.



BACKUP SUPPORT OPTIONS
Wide Flange (I-Beam)
Backup and Transition types are shown elsewhere on the plans. See Attachment location details or in the general notes.

PRODUCT CODE	QTY	DESCRIPTION
B030704	1	Front Support
B030703	TBD	Mid Support
TBD	TBD	XL Backup Pad
TBD	TBD	XXL Backup Pad
TBD	1	Backup Assembly (See Table)
TBD	2	Front Corner Anchor
TBD	1	Rose Assembly
B010202	2	End Panel
B010203	1	Slider Assembly Kit
K001003	1	TAU-11-R S100R Kit
B51-1107131-KT	TBD	TAU-11-R EAE Mounting Kit
B51-102069-00	TBD	Energy Absorbing Element, Type 1
B51-102070-00	TBD	Energy Absorbing Element, Type 2
B51-102071-00	TBD	Energy Absorbing Element, Type 3
B51-110718-00	TBD	Energy Absorbing Element, Type 2S
B51-1110009-00	TBD	Energy Absorbing Element, Type 3H
TBD	TBD	Cable Assembly
X001031	TBD	Letteral Support Kit
X001034	TBD	Scalloped Guide Kit
X001035	2	Front Support Lab Kit
TBD	1	Mounting Package

(TBD) = To Be Determined, depending on Backup Type and System Length.  
(See manufacturer's product manual for details)


**LTS-BARRIER SYSTEMS**  
**CRASH CUSHION**  
**(R-WIDE)**  
**TAU-11-R (W) - 16**


THIS DRAWING IS THE PROPERTY OF Lindsay Transportation Solutions. It is to be used only for the project and location shown hereon. It is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Lindsay Transportation Solutions.

DATE: 04/07/2013  
PROJECT: 6314-60-001  
DRAWING NO: 16-001  
SCALE: 1/8" = 1'-0"

DESIGN: [ ]  
CHECKED: [ ]  
APPROVED: [ ]



LOW MAINTENANCE







DISCLAIMER: The use of this document for purposes other than those intended by the Texas Department of Transportation is prohibited. The Texas Department of Transportation is not responsible for any errors, omissions, or inaccuracies in this document. The user of this document shall be responsible for verifying the accuracy of the information contained herein. The Texas Department of Transportation is not responsible for any damages, losses, or liabilities resulting from the use of this document.



Speed (kph)	Speed (mph)	Minimum Setback (m)	Minimum Setback (ft)	Minimum Spacing (m)	Minimum Spacing (ft)	Suggested Buffer Spacing (m)	Suggested Buffer Spacing (ft)
30	18.5	1.50	4.92	1.50	4.92	3.00	9.84
35	21.7	2.00	6.56	2.00	6.56	4.00	13.12
40	24.9	2.50	8.20	2.50	8.20	5.00	16.40
45	27.9	3.00	9.84	3.00	9.84	6.00	19.68
50	31.1	3.50	11.48	3.50	11.48	7.00	22.96
55	34.2	4.00	13.12	4.00	13.12	8.00	26.24
60	37.3	4.50	14.76	4.50	14.76	9.00	29.52
65	40.4	5.00	16.40	5.00	16.40	10.00	32.80
70	43.5	5.50	18.04	5.50	18.04	11.00	36.08
75	46.6	6.00	19.68	6.00	19.68	12.00	39.36
80	49.7	6.50	21.32	6.50	21.32	13.00	42.64
85	52.8	7.00	22.96	7.00	22.96	14.00	45.92
90	55.9	7.50	24.60	7.50	24.60	15.00	49.20

- GENERAL NOTES**
- Flow of traffic to flow where shown are required.
  - All traffic control devices illustrated are required, except those omitted or otherwise indicated.
  - The device "ROAD WORK AHEAD" sign may be omitted if the following conditions are met:
    - 1. A sign is placed in advance of the work zone.
    - 2. The work zone is clearly marked with advance warning signs.
    - 3. The work zone is clearly marked with advance warning signs.
    - 4. The work zone is clearly marked with advance warning signs.
    - 5. The work zone is clearly marked with advance warning signs.
  - If this sign is used for a left lane closure, C90-31, LEFT LANE CLOSED sign shall be used and spacekeeping device shall be placed on the left side of the work zone. If used for a right lane closure, the arrow panel should be placed on the side of the affected lane.
  - Work vehicles shall be placed in the work zone in advance of the work zone. Work vehicles shall be placed in the work zone in advance of the work zone.
  - Work vehicles shall be placed in the work zone in advance of the work zone. Work vehicles shall be placed in the work zone in advance of the work zone.


Texas Department of Transportation  
Traffic Operations Division


### TRAFFIC CONTROL PLAN LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP (1-4) - 12

DATE	REVISED	BY
12/11/12	12/11/12	JAC-K

For construction or maintenance of a project, the project engineer shall submit a traffic control plan to the project engineer for review. The project engineer shall submit a traffic control plan to the project engineer for review. The project engineer shall submit a traffic control plan to the project engineer for review.





**LEGEND**

Symbol	Symbol	Symbol	Symbol
Class 3 Barricade	Truck Mounted Attenuator (TMA)	Flagger	Automated Flagging Device (AFAD)
Heavy Work Vehicle	Variable Message Sign (VMS)	Priority Flow	
Assistant Device (AFAD)			
Stop			
Flag			

Vehicle	Formula	Minimum Stopping Distance (ft)	Minimum Stopping Distance (ft)	Minimum Stopping Distance (ft)
30	$0.14V^2 + 1.47V$	130	180	50'
35	$0.14V^2 + 1.47V$	155	210	60'
40	$0.14V^2 + 1.47V$	180	240	70'
45	$0.14V^2 + 1.47V$	205	270	80'
50	$0.14V^2 + 1.47V$	230	300	90'
55	$0.14V^2 + 1.47V$	255	330	100'
60	$0.14V^2 + 1.47V$	280	360	110'
65	$0.14V^2 + 1.47V$	305	390	120'
70	$0.14V^2 + 1.47V$	330	420	130'
75	$0.14V^2 + 1.47V$	355	450	140'

**TYPICAL USAGE**

Vehicle	Short Duration	Short Term Stationary	Intermediate	Long Term Stationary
Motorcycle	✓			
Car	✓	✓		
Truck			✓	
Tractor				✓


- GENERAL NOTES**
- Flagger to signs where shown are REQUIRED.
  - In the direction of travel where there is the lack of approaching traffic.
  - Approach stopping sight distance must be provided to each AFAD location for approaching traffic.
  - Each AFAD shall be controlled by a qualified/unlicensed flagger. Flaggers operating AFAD shall not leave their stations while they are in use.
  - AFADs shall be located on the right side of the roadway, but an unobstructed view of both AFADs and of the approaching traffic in both directions.
  - When AFADs are used, a flagger controlling traffic shall be located on each side of the roadway.
  - All AFADs shall be equipped with one-way or two-way or fluorescent red-orange flag attached to the end of the work arm. The flag shall be a minimum of 18" square.
  - 100 feet in advance of the work zone, a sign shall be posted with the word "STOP" and the word "AHEAD" in both directions.
  - Other controlling devices may be substituted for the above vehicles and sign.
  - Additional safety vehicles may be used on the work zone.
  - Flagger should use two-way radios or other means of communication to control traffic.
  - Length of work zones should be based on the ability of flaggers to communicate.
  - AFADs should be used in advance of the work zone to maintain stopping sight distance to the AFAD.
  - Changeable message signs should be used in advance of the work zone to maintain stopping sight distance to the AFAD.
  - The "STOP" sign shall be posted on the AFAD in advance of the work zone.
  - The "STOP" sign shall be posted on the AFAD in advance of the work zone.

Texas Department of Transportation  
Traffic Operations Division

**TRAFFIC CONTROL PLAN**  
**AUTOMATED FLAGGER ASSISTANCE DEVICES (AFADs)**  
TCP (1-6) - 12

PROJECT: \_\_\_\_\_  
DATE: \_\_\_\_\_  
DRAWN BY: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_

DISCLAIMER: The use of this plan is limited to the project for which it was prepared. It is not to be used for any other project without the written consent of the Texas Department of Transportation. The Texas Department of Transportation is not responsible for any errors or omissions in this plan or for any consequences arising from its use.



**LEGEND**

Symbol	Item
[Cone]	Conventionalizing Devices
[Sign]	Truck Mounted
[Sign]	Trailer Mounted
[Sign]	Flashing Arrow Board
[Sign]	Sign
[Sign]	Flare

Speed Limit (mph)	Work Space (ft)	Sign Placement (ft)	Sign Size (ft)	Sign Spacing (ft)	Sign Color	Sign Text
10	30	30	30	30	Red	ROAD WORK AHEAD
15	45	45	30	30	Red	ROAD WORK AHEAD
20	60	60	30	30	Red	ROAD WORK AHEAD
25	75	75	30	30	Red	ROAD WORK AHEAD
30	90	90	30	30	Red	ROAD WORK AHEAD
35	105	105	30	30	Red	ROAD WORK AHEAD
40	120	120	30	30	Red	ROAD WORK AHEAD
45	135	135	30	30	Red	ROAD WORK AHEAD
50	150	150	30	30	Red	ROAD WORK AHEAD
55	165	165	30	30	Red	ROAD WORK AHEAD
60	180	180	30	30	Red	ROAD WORK AHEAD
65	195	195	30	30	Red	ROAD WORK AHEAD
70	210	210	30	30	Red	ROAD WORK AHEAD
75	225	225	30	30	Red	ROAD WORK AHEAD
80	240	240	30	30	Red	ROAD WORK AHEAD
85	255	255	30	30	Red	ROAD WORK AHEAD
90	270	270	30	30	Red	ROAD WORK AHEAD
95	285	285	30	30	Red	ROAD WORK AHEAD
100	300	300	30	30	Red	ROAD WORK AHEAD

**TYPICAL USAGE**

Equipment	Mobile	Stationary	Low New
Sign	✓	✓	✓
Truck Mounted	✓	✓	✓
Trailer Mounted	✓	✓	✓
Flashing Arrow Board	✓	✓	✓
Sign	✓	✓	✓
Flare	✓	✓	✓


**GENERAL NOTES**


1. All signs and cones shall be placed in accordance with the Texas Department of Transportation Manual of Traffic Control.
2. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
3. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
4. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
5. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
6. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
7. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
8. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
9. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.
10. Signs shall be placed in the work space or in the shoulder, as indicated on this plan.


Texas Department of Transportation  
Traffic Operations Division


TRAFFIC CONTROL PLAN  
CONVENTIONAL ROAD  
SHOULDER WORK


TCP (2-1) - 12











DISCLAIMER: The use of this standard is governed by the "Terms and Conditions of Use" of the standard. The user of this standard is responsible for its proper application. The user of this standard is responsible for its proper application. The user of this standard is responsible for its proper application.

DATE: \_\_\_\_\_  
FILED: \_\_\_\_\_

**TRAFFIC CONTROL PLAN  
 DIVERSIONS AND  
 NARROW BRIDGES**  
 TCP (2-7) - 12

Texas Department of Transportation  
 Traffic Operations Division

**BRIDGE WIDENING**

**ROADWAY DIVERSION**

**LEGEND**

Symbol	Description	Notes
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	
W W	Channelizing device	


**GENERAL NOTES**

- Plans attached to signs where shown are required.
- Where shown in the plans, or for routine maintenance work, when approved by the Engineer.
- Retardement systems shall be placed at 100 ft from centerline.
- Retardement systems shall be placed as shown on centerline.
- Retardement systems shall be placed as shown on centerline.
- Retardement systems shall be placed as shown on centerline.

**TABLE OF CONTENTS**

Sheet No.	Sheet Title	Quantity
...	...	...

**DISCLAIMER:**  
 The use of this drawing is limited to the project for which it was prepared. The Texas Department of Transportation and the Engineer assume no liability for the consequences of its use.



**LEGEND**

Symbol	Type 3 Borehole	Symbol	Drainage Ditch
Symbol	Sign	Symbol	Traffic Flow
Symbol	Flag	Symbol	Flower
Symbol	Revised Pavement Markers 5' 11"-A	Symbol	Temporary or Portable Traffic Signal

Speed	Minimum Lane Width	Minimum Sight Triangle	Minimum Sight Triangle	Minimum Sight Triangle
mph	ft	ft	ft	ft
10	10	100	100	100
15	10	150	150	150
20	10	200	200	200
25	10	250	250	250
30	10	300	300	300
35	10	350	350	350
40	10	400	400	400
45	10	450	450	450
50	10	500	500	500
55	10	550	550	550
60	10	600	600	600
65	10	650	650	650
70	10	700	700	700
75	10	750	750	750
80	10	800	800	800
85	10	850	850	850
90	10	900	900	900
95	10	950	950	950
100	10	1000	1000	1000

**TYPICAL USAGE**

1. Place on road to indicate a change in traffic flow. Use in conjunction with the 'Yield' sign. The 'Yield' sign should be placed 100 feet before the change in traffic flow.

2. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Stop' sign. The 'Stop' sign should be placed 100 feet before the change in traffic flow.

3. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Pass with Care' sign. The 'Pass with Care' sign should be placed 100 feet before the change in traffic flow.

4. Use on road to indicate a change in traffic flow. Use in conjunction with the 'One Lane Bridge' sign. The 'One Lane Bridge' sign should be placed 100 feet before the change in traffic flow.

5. Use on road to indicate a change in traffic flow. Use in conjunction with the 'One Lane Road Ahead' sign. The 'One Lane Road Ahead' sign should be placed 100 feet before the change in traffic flow.

6. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Do Not Pass' sign. The 'Do Not Pass' sign should be placed 100 feet before the change in traffic flow.

7. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Road Work Ahead' sign. The 'Road Work Ahead' sign should be placed 100 feet before the change in traffic flow.

**GENERAL NOTES**

1. Place on road to indicate a change in traffic flow. Use in conjunction with the 'Yield' sign. The 'Yield' sign should be placed 100 feet before the change in traffic flow.

2. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Stop' sign. The 'Stop' sign should be placed 100 feet before the change in traffic flow.

3. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Pass with Care' sign. The 'Pass with Care' sign should be placed 100 feet before the change in traffic flow.

4. Use on road to indicate a change in traffic flow. Use in conjunction with the 'One Lane Bridge' sign. The 'One Lane Bridge' sign should be placed 100 feet before the change in traffic flow.

5. Use on road to indicate a change in traffic flow. Use in conjunction with the 'One Lane Road Ahead' sign. The 'One Lane Road Ahead' sign should be placed 100 feet before the change in traffic flow.

6. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Do Not Pass' sign. The 'Do Not Pass' sign should be placed 100 feet before the change in traffic flow.

7. Use on road to indicate a change in traffic flow. Use in conjunction with the 'Road Work Ahead' sign. The 'Road Work Ahead' sign should be placed 100 feet before the change in traffic flow.

**TRAFFIC CONTROL PLAN**  
**LONG TERM ONE-LANE**  
**TWO-WAY CONTROL**

TCP (2-8)-12

Texas Department of Transportation  
Traffic Services Division

Project No.	6314-60-001
Sheet No.	108
Date	1-12-88
Scale	AS SHOWN
Author	...
Checker	...
Appr.	...

LEGEND	
* Trail Vehicle	ARROW BOARD DISPLAY
** Shadow Vehicle	
*** Work Vehicle	RIGHT DIRECTIONAL
*** Heavy Work Vehicle	LEFT DIRECTIONAL
*** Truck Mounted Attenuator (TMA)	Double Arrow
*** Traffic Flow	SHUTTLE (Alternating Downward or Upward Arrow)
TYPICAL CASES	
SHORT TRAIL VEHICLE	INTERMEDIATE TRAIL VEHICLE
STATIONARY TRAIL VEHICLE	LONG TRAIL VEHICLE
STATIONARY SHADOW VEHICLE	STATIONARY SHADOW VEHICLE

- GENERAL NOTES**
1. TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as specified. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD vehicle is required. All vehicles shall be equipped based on prevailing roadway conditions, traffic volume, and sign distance restrictions.
  2. The use of other high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights are permitted on the driver's side of the vehicle may be operated simultaneously with the same become or strobe lights.
  3. The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
  4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION DMS 8200, Type A.
  5. Flashing arrow boards shall be Type B or Type C as per the Barriore and Construction (BC) standards. The board shall be controlled from inside the vehicle.
  6. Each vehicle shall have two-way radio communication capability.
  7. When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to show the other convoy vehicles.
  8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and the TRAIL VEHICLE shall be determined by the WORK VEHICLE and LEAD VEHICLE vary according to terrain, work activity and other factors.
  9. "X VEHICLE CONVOY" (6221-1001) or "WORK CONVOY" (6221-1007) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option an "X 48" diamond shaped sign shall be used on TRAIL VEHICLES and SHADOW VEHICLES. Signs may be used where appropriate near the work area. The "X VEHICLE CONVOY" sign shall be used on the TRAIL VEHICLE. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE. If a TRAIL VEHICLE is used.
  10. On two-lane two-way roadways, the work and protection vehicles should still only periodically allow motor vehicle traffic to pass. If motorists are not allowed to pass the work convoy, a "DO NOT PASS" (64-11) sign should be placed on the back of the rear-most protection vehicles.

Texas Department of Transportation






**TRAFFIC CONTROL PLAN  
MOBILE OPERATIONS  
UNDIVIDED HIGHWAYS**

TCP (3-1)-13

DATE: 10/23/14  
DESIGN: December 1985  
BY: JRM  
CHECKED: JRM  
DATE: 1/19/15

Scale: 1" = 10'-0" (Horizontal) 1" = 10'-0" (Vertical)

**STRIPING FOR TMA**



DATE: 10/23/14  
DESIGN: December 1985  
BY: JRM  
CHECKED: JRM  
DATE: 1/19/15




TRAFFIC CONTROL PLAN  
MOBILE OPERATIONS  
UNDIVIDED HIGHWAYS

LEGEND	
* Trail Vehicle	Arrow Board Display
** Shadow Vehicle	Right Directional
*** Heavy Work Vehicle	Left Directional
□ Track Mounted Attenuator (TMA)	Beacon Arrow
◁ Traffic Flare	Stationary Intermediate Stationary
	Long Term Stationary

TYPICAL USAGE:	
TABLE:	SHORT TERM STATIONARY
	INTERMEDIATE STATIONARY
	LONG TERM STATIONARY

**GENERAL NOTES:**

1. ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the back of the Construction Job Order. The flashing arrow board shall be used in accordance with the instructions included in the job order. The arrow boards shall be operated from inside the vehicle.
2. For TCP(13-2b) the Engineer will determine if the TRAIL VEHICLE is restricted based on other vehicles shown for both TCP(13-2a) and TCP(13-2b) are required.
3. The use of amber high intensity rotating, flashing, oscillating, or strobe lighting on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights, when mounted on the driver's side of the vehicle may be operated simultaneously with the amber, beacon or strobe lights.
4. The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
5. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of MWS 8300, Type A.
6. Each vehicle shall have two-way radio communication capability.
7. When work convoys meet at a junction, the TRAIL VEHICLE should advance lanes first to shadow the other convoy vehicles.
8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance requirements. Motorists approaching the work convoy shall be able to see the TRAIL VEHICLE in time to slow down. The SHADOW VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
9. Standard 48" x 24" diamond shaped warning signs with the same message as those shown may be used where adequate mounting space exists.
10. The signs shown should be used on the Advance Warning Vehicle. An exception, a particular sign, shall be used on the Shadow Vehicle. Motorists approaching the work convoy shall be able to see the TRAIL VEHICLE in time to slow down. The SHADOW VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors. An appropriate directional arrow display, indicating the size and position of the flashing arrow board, must be used in the second phase of the Advance Warning Vehicle. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
11. Standard diamond shaped warning signs may be used on an option if their placement at a given station is not practical.
12. The principles on this sheet may be used to close lanes from the left side of the roadway, considering the number of lanes, shoulder width, sight distance, and ramp frequency.
13. Signs and flashing arrow boards shall be appropriately offset when implementing left lane closures or interior closures which close the left lanes.
14. The Advance Warning Vehicle may advance the edge line when shoulder width makes it necessary.



RIGHT LANE CLOSURE ON DIVIDED HIGHWAY - TCP(13-2c)

INTERIOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(13-2b)


RIGHT LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY - TCP(13-2b)


**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**DIVIDED HIGHWAYS**

TCP(13-2)-13

State Department of Transportation

Date: \_\_\_\_\_  
 Drawn by: \_\_\_\_\_  
 Checked by: \_\_\_\_\_  
 Approved by: \_\_\_\_\_





**LEGEND**





* Trail Vehicle	Arrow Board Display
** Shadow Vehicle	Right Directional
*** Work Vehicle	Left Directional
□ Heavy Work Vehicle	Double Arrow
▲ Truck Mounted Attenuator (TMA)	CAUTION (Intermittent) or 4 Corner Flash
◀ Traffic Flow	

**TYPICAL USAGE**

MARKER	WORK VEHICLE	SHADOW VEHICLE	TRAIL VEHICLE	ADVANCE WARNING VEHICLE
✓	✓	✓	✓	✓

**GENERAL NOTES**

1. TRAIL, shadow, and lead vehicles shall be equipped with arrow boards, as shown on the drawings. The arrow boards shall be used on the work vehicle in a manner consistent with the type of work being performed. The Engineer shall specify the type of work being performed. The Engineer shall specify the type of work being performed. The Engineer shall specify the type of work being performed.
2. The use of either high intensity reflecting, flashing, oscillating, or strobe lights on vehicles are required. The high intensity reflecting, flashing, oscillating, or strobe lights shall be used in accordance with the specifications of the vehicle manufacturer.
3. The use of truck-mounted attenuators (TMA) on the shadow vehicle, advance warning vehicle and other requirements of DEPARTMENTAL MATERIAL SPECIFICATION shall apply.
4. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION.
5. Flashing arrow boards shall be Type B or Type C as per the Bureau and Construction (BCE) standards. The board shall be controlled from inside the vehicle.
6. Trail vehicles shall have two-way radio communication capability.
7. When work convoys must change lanes, the TRAIL VEHICLE shall engage (arms) the arrow board on the TRAIL VEHICLE. The TRAIL VEHICLE will vary the spacing and direction of the TRAIL VEHICLE in time to slow down and/or change lanes or to approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE may vary according to terrain, work activity and other factors.
8. X VEHICLE CONVOY (X21-100T) or X VEHICLE CONVOY (X21-100T) shall be used on work convoys. The X VEHICLE CONVOY (X21-100T) shall be used on work convoys. The X VEHICLE CONVOY (X21-100T) shall be used on work convoys.
9. X VEHICLE CONVOY (X21-100T) or X VEHICLE CONVOY (X21-100T) shall be used on work convoys. The X VEHICLE CONVOY (X21-100T) shall be used on work convoys.
10. The use of a portable programmable message sign (PPMS) or truck-mounted attenuator (TMA) shall be used on the TRAIL VEHICLE. The TRAIL VEHICLE shall be used on the TRAIL VEHICLE.
11. A double arrow shall not be utilized on the arrow board on the advance warning vehicle.
12. Standard diamond shaped warning signs shall be used as shown on the drawings. The advance warning signs shall be used as shown on the drawings.
13. Standard diamond shaped warning signs shall be used as shown on the drawings.
14. In two-lane two-way roadways, the work and protection vehicles should pull over completely to allow motor vehicle traffic to pass. If motorists are not completely clear of the work area, the advance warning sign should be placed on the back of the rear-most protection vehicle.



Texas Department of Transportation  
Traffic Signs, Signals, and Markings Unit

**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS**  
**RAISED PAVEMENT MARKER INSTALLATION/REMOVAL**  
**TCP (3-3) - 14**

DATE	DESCRIPTION	BY
02/01/01	ISSUED	...
04/01/01	...	...
08/01/01	...	...
12/01/01	...	...

**LEGEND**

* Trail Vehicle	ARROW BOARD DISPLAY
** Shadow Vehicle	
*** Work Vehicle	RIGHT Directional
**** Heavy Work Vehicle	LEFT Directional
***** Truck Mounted Attenuator (TMA)	Double Arrow
***** Traffic Flow	Channelizing Devices

Position	Permit	Minimum Distance from Front of Vehicle	Minimum Spacing of Channelizing Devices	Minimum Spacing of Shadow Vehicle	Suggested Length of Spacing Buffer Zone
30	30'	150'	15'	30'	50'
35	35'	205'	235'	35'	120'
40	40'	265'	285'	40'	155'
45	45'	450'	495'	45'	200'
50	50'	500'	550'	50'	240'
55	55'	550'	605'	55'	285'
60	60'	600'	660'	60'	330'
65	65'	650'	715'	65'	375'
70	70'	700'	770'	70'	420'
75	75'	750'	825'	75'	465'

\* Conventional Road Only  
\*\* Tag Lengths have been rounded off.  
L=Length of Taper (FT) Width of Offset(FT); Subtotal Speed(DPH)

**TRAFFIC SIGNALS**

MOBILE	SHORT	STATIONARY	LONG
			STATIONARY

**GENERAL NOTES**

- This traffic control plan is for use on conventional roads, posted at 45 mph or less and is intended for mobile operations. The presence of a shadow vehicle is required for mobile operations. The vehicle should be continuously stopped up to approximately 15 minutes. The vehicle should be continuously stopped up to approximately 15 minutes. The vehicle should be continuously stopped up to approximately 15 minutes.
- Truck Mounted Attenuator (TMA) shall be used on Shadow Vehicle. The TMA shall be placed on the back panel of the truck mounted attenuator. The TMA shall be placed on the back panel of the truck mounted attenuator. The TMA shall be placed on the back panel of the truck mounted attenuator.
- All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (TMUD), latest edition.
- The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating flashing, oscillating or strobe lights shall be mounted on the drivers side of the vehicle. The flashing lights shall be used in conjunction with the other beacons or strobe lights.
- Flashing arrow board shall be used on Shadow Vehicle. Flashing arrow board shall be Type B or Type C or DC Strobe. The arrow board operation shall be controlled from inside the truck.





Texas Department of Transportation  
**TRAFFIC CONTROL PLAN**  
**MOBILE OPERATIONS FOR ISOLATED WORK AREAS UNDIVIDED HIGHWAYS**  
TCP (3-4) -13

DATE: 10-1-01  
BY: J. W. B. (JWB)


DATE: 10-1-01  
BY: J. W. B. (JWB)


DATE: 10-1-01  
BY: J. W. B. (JWB)


DATE: 10-1-01  
BY: J. W. B. (JWB)



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty or responsibility is assumed by the author for any errors or omissions. The user of this standard is advised to check for any amendments or updates. The user of this standard is advised to check for any amendments or updates.







**LEGEND**

Symbol	Description
W	Channelizing Devices
W	FRISK required
W	FRISK not required
W	Permissible Dimensions
W	Permissible Sign Text
W	Traffic Flow
W	Flag

Minimum Speed Limit (mi/h)	Minimum Speed Limit (km/h)	Sign Size (ft)	Sign Size (m)	Sign Spacing (ft)	Sign Spacing (m)
45	72	45" x 45"	14" x 14"	100'	30.5'
50	80	45" x 45"	14" x 14"	100'	30.5'
55	88	45" x 45"	14" x 14"	100'	30.5'
60	97	45" x 45"	14" x 14"	100'	30.5'
65	104	45" x 45"	14" x 14"	100'	30.5'
70	112	45" x 45"	14" x 14"	100'	30.5'
75	121	45" x 45"	14" x 14"	100'	30.5'
80	129	45" x 45"	14" x 14"	100'	30.5'
85	137	45" x 45"	14" x 14"	100'	30.5'
90	145	45" x 45"	14" x 14"	100'	30.5'
95	153	45" x 45"	14" x 14"	100'	30.5'
100	161	45" x 45"	14" x 14"	100'	30.5'

**GENERAL NOTES**

- ALL traffic control devices illustrated are required. Deviate or alter in the field.
- Between ramp and mainline can be seen from both roadways.
- See "Advance Notice Sign" on page 1 for recommended data.
- The 200' sign spacing may be reduced to 100' if the work area is less than 200' long.

**TYPICAL USAGE**

MOBILE	STATIONARY	NON-STATIONARY	STATIONARY
✓	✓	✓	✓

**GENERAL NOTES**

- ALL traffic control devices illustrated are required. Deviate or alter in the field.
- Between ramp and mainline can be seen from both roadways.
- See "Advance Notice Sign" on page 1 for recommended data.
- The 200' sign spacing may be reduced to 100' if the work area is less than 200' long.

Additional requirements for lane closures and vehicle signing shall be as shown on TCP 6-21 or as directed by the Engineer.

Traffic Department of Transportation  
Traffic Operations Division Station


**TRAFFIC CONTROL PLAN**  
**WORK AREA NEAR RAMP**


TCP (6-2) - 12


DATE	1/11/93	BY	WJL
SCALE	AS SHOWN	CHECKED	WJL
PROJECT	TRUCK STOP	DATE	1/11/93
NO.	12	SCALE	AS SHOWN

TCP (6-2b)  
ENTRANCE RAMP CLOSED

TCP (6-2a)  
ENTRANCE RAMP OPEN  
WORK WITHIN 500' OF RAMP







**LEGEND**

Symbol	Type	Description
[Symbol]	3	Channelizing Devices
[Symbol]	M	Truck Mounted Attenuator (TMA)
[Symbol]	5	Flashing Arrow Board
[Symbol]	5	Traffic Flow
[Symbol]	5	Flagger

Formula	Distance	Speed	Reaction Time	Stopping Distance	Subtractive Constant	Stopping Distance
$1.47 S T + \frac{S^2}{30}$	70	15	1.0	150	10	160
	50	10	1.0	75	10	85
	35	7	1.0	35	10	45
	20	4	1.0	15	10	25

1. Length of Taper (FT) = 100 \* (S - 15) / (S - 10)

2. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 50

3. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 100

4. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 150

5. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 200

6. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 250

7. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 300

8. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 350

9. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 400

10. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 450

11. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 500

12. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 550

13. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 600

14. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 650

15. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 700

16. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 750

17. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 800

18. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 850

19. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 900

20. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 950

21. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 1000

22. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 1050

23. Length of Taper (FT) = 100 \* (S - 15) / (S - 10) + 1100

**TYPICAL USAGE**

Symbol	Short Term Stationary	Intermediate Term Stationary	Long Term Stationary
[Symbol]	✓		
[Symbol]		✓	
[Symbol]			✓

**GENERAL NOTES**

- All traffic control devices illustrated are REQUIRED. Devices deviated from the triangle symbol may be omitted when signs elsewhere in the plan.
- See 86 standards for sign details.
- If an advance lane closure sign is used, it must be placed in the work zone and the taper. Consideration should be given to closing the ramp.

14. When vehicle equipped with a truck mounted attenuator is used in a lane closure situation, it must be placed in the work zone or area adjacent to the taper. Consideration should be given to closing the ramp.

Additional requirements for lane closures and advance stopping shall be as shown on TCP (6-1) or as directed by the Engineer.

Texas Department of Transportation  
Traffic Operation Design Manual

TRAFFIC CONTROL PLAN  
WORK AREA BEYOND EXIT RAMP


TCP (6-5)-12

DATE: 08-10-99  
DRAWN: J. S. JONES  
CHECKED: J. S. JONES  
SCALE: AS SHOWN

1-17 P-M  
1-17 P-M  
1-17 P-M

1-17 P-M

1-17 P-M



**LEGEND**

Type 3 Barricade	Channelizing Devices
Heavy Work Vehicle	Work Enclosure (TMA)
Roller Mounted	Portable Changeable Message Sign (PCMS)
Flashing Arrow Board	Traffic Flow
Flashing Arrow Board in Caution Mode	
Sign	

Rated Speed	Minimum	Maximum	Suggested Spacing
Feet	Feet	Feet	Feet
45	30'	31'	13'
50	30'	31'	13'
55	30'	31'	13'
60	30'	31'	13'
65	30'	31'	13'
70	30'	31'	13'
75	30'	31'	13'
80	30'	31'	13'
85	30'	31'	13'
90	30'	31'	13'
95	30'	31'	13'
100	30'	31'	13'
105	30'	31'	13'
110	30'	31'	13'
115	30'	31'	13'
120	30'	31'	13'
130	30'	31'	13'
140	30'	31'	13'
150	30'	31'	13'

\*XX taper lengths have been rounded off.  
L=L length of taper (T) x (width of offset) (FT) x (Posting Speed (mph))

**TYPICAL USAGE**

MOBILE	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY
✓	✓	✓	✓

**GENERAL NOTES**


- All traffic control devices illustrated are required. Before opening with the traffic signal may be waived when stated elsewhere in the plans.
- Phase 2 of the taper message should include appropriate information formatted as follows: "ROAD CLOSED", "LEFT LANE CLOSED", "ALL TRAFFIC MUST EXIT", and "LEFT LANE MUST EXIT".
- When used in an additional lane, additional signs should be used to warn approaching high speed traffic of the end of the taper, as directed by the sign.
- Temporary signs located from the advance warning area to the exit.
- The sign shall meet 1500-21 when it conflicts with 1500-22 signs already in place on the project.

If used in a lane with a posted speed limit of 55 mph or greater, the sign shall be used in advance of the taper. If used in a lane with a posted speed limit of 55 mph or less, the sign shall be used in advance of the taper. The sign shall be used in advance of the taper.

Additional requirements for lane closures and advance signing shall be as shown on TDP (6-1) or as directed by the Engineer.

Texas Department of Transportation  
Traffic Control Plan  
FREEWAY CLOSURE  
TCP (6-6)-12

DATE	PROJECT	LOCATION	SECTION
12/15/00	194	194	194
12/15/00	194	194	194
12/15/00	194	194	194
12/15/00	194	194	194





Texas Department of Transportation  
Traffic Control Plan

**TRAFFIC CONTROL PLAN**  
**SHORT DURATION FREEWAY**  
**CLOSURE SEQUENCE**

TCP (6-7)-12

DATE: 10/11/13  
SCALE: AS SHOWN  
PROJECT: 1393  
SHEET: 1102 OF 1102



**"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES**

A. Prior to the beginning of construction, all currently striped no-passing zones shall be aligned with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer.

B. At the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If necessary, the DO NOT PASS sign and a NEXT XX MILES sign may be used at the beginning of each zone. The DO NOT PASS sign and the NEXT XX MILES sign should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be aligned with a PASS WITH CARE sign and a NEXT XX MILES sign.

C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent congestion to vehicles and trucks. The DO NOT PASS sign and NEXT XX MILES sign should be used and repeated as often as necessary for this purpose. Where several no-passing zones are combined, the length of the no-passing zone should be indicated on the sign. The DO NOT PASS sign should be placed at the beginning and end of the no-passing zone. The length of each combined zone, regardless of whether the DO NOT PASS sign is placed at the beginning and end of the no-passing zone where the surfacing operation has stopped for the day.

D. R4-1 and R4-2 signs shall remain in place until standard pavement markings are installed.

**"NO CENTER LINE" SIGN (R8-12)**

A. Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.

B. At the time construction activity crosses the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (R8-12) sign should be placed at the beginning of the work area, or approximately 2 miles in rural areas and closer in urban areas, and other locations deemed necessary by the Engineer.

C. The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

**"LOOSE GRAVEL" SIGN (R8-7)**

A. When construction begins, a LOOSE GRAVEL (R8-7) sign should be placed at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.

B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

**PAVEMENT MARKINGS**

A. Temporary markings for surfacing projects shall be Temporary Flexible-reflective Reseal Coat. These markings shall be approved by the Engineer. These are to be installed to provide true alignment for air-laying crews or as directed by the Engineer. Tabs will be placed at the beginning and end of the work area, or approximately 2 miles in rural areas and closer in urban areas. The cover over the reflective strip shall be removed.

B. Tabs shall not be used to simulate edge lines.

C. Tab placement for overlay/mix operations shall be as shown on the existing standard sheet.

**COORDINATION OF SIGN LOCATIONS**

A. The location of warning signs at the beginning and end of a work area are to be coordinated with other advance signs shown on the Barricade and Construction Standards for project limits to ensure adequate sign spacing.

B. Where possible the road work shall include: LOOSE GRAVEL (R8-7), and NO CENTER LINE (R8-12) signs. These signs shall be placed at the beginning and end of the work area. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer.

Posted Speed Limit, mph	Minimum Sign Spacing, ft	Distance
30	120'	
35	140'	
40	160'	
45	180'	
50	200'	
55	220'	
60	240'	
65	260'	
70	280'	
75	300'	

\* Conventional Roads Only

**TYPICAL USAGE**

VEHICLE	SHORT TERM	INTERMEDIATE	LONG TERM
STATIONARY	✓		
STATIONARY		✓	
STATIONARY			✓

**GENERAL NOTES**

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where signs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- The devices shown on this sheet are to be used to supplement those required by the IC Standards or other required standards in the plans.
- Signs shall be erected as detailed on the IC Standards or the Companion Work Zone Traffic Control Devices List (CWTCD) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways and expressways, signs shall be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.
- Signs on divided highways, freeways and expressways shall be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.

Texas Department of Transportation

**TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS**

TCP (7-1)-13


DATE	10/27/09	NO. REV.	01	ON	10/27/09	BY	JK
DATE	10/27/09	NO. REV.	01	ON	10/27/09	BY	JK
DATE	10/27/09	NO. REV.	01	ON	10/27/09	BY	JK
DATE	10/27/09	NO. REV.	01	ON	10/27/09	BY	JK

449 2-13  
149 2-13

112131518191101112131415  
16171819202122232425262728  
2930313233343536373839404142434445464748495051525354555657585960616263646566676869707172737475767778798081828384858687888990919293949596979899100

**DISCLAIMER**  
The use of this standard is governed by the Texas Engineering Practice Act. No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion or this standard to other formats or for incorrect results or damages resulting from its use.

### EXAMPLES OF SIGN SUPPORTS




△ See the notes for the type of sign supports used on each standard sign support.  
△ The section shall be made of galvanized steel tubing. Round or oval shall not be used.  
△ Posts are required by engineer or as shown on plans.  
△ 1 Foot mounting height.



### NOTES WILL NOT BE ALLOWED.

Attachment to wooden supports will be by bolts and nuts. Manufacturer's recommended procedures for attaching sign supports to other type of sign supports.  
△ See the notes for the type of sign supports used on each standard sign support.

**SIGNS IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS**  
**MOVERS AHEAD SIGNS ARE USED FOR MOWING OPERATIONS.**  
**LITTER PICKUP AHEAD, ROAD WORK AHEAD AND WORKERS AHEAD SIGNS ARE USED IN MAINTENANCE OPERATIONS WHEN HIGHWAY SURFACE OFF.**



**ROLL-UP SIGNS CONFORMING TO DMS-8310 AND THE CWZTD ALLOWED**  
Refer dimensions and spacing to "CWZTD-SPECIAL" or the same as 833-10P



**TYPICAL LOCATION OF SIGNS AT HIGHWAY CROSSING**  
WORK AREA IS A MINIMUM OF 50 FEET WIDELY APPROXIMATE DIRECTED. SIGNS ARE TO BE PLACED IN PLACE ONLY DURING NIGHT HOURS. ROAD WORK AHEAD SIGNS SHOULD BE PLACED IN FRONT OF THE WORK AREA. SIGNS AT THE HIGHWAY ARE REQUIRED WHEN CROSSING IS FROM

**GENERAL NOTES FOR WORK ZONE SIGNS:**  
1. Contractor shall install and maintain signs in a straight and plain condition and/or as directed by the Engineer.  
2. Modern sign posts shall be defined white.  
3. Signs shall not be used to support other signs or other equipment.  
4. All signs shall be treated in accordance with the signs or as directed by the Engineer. Signs shall be used to regulate, warn, and inform the traveling public. Signs shall not be used to support other signs or other equipment.  
5. All signs shall be treated in accordance with the signs or as directed by the Engineer. Signs shall be used to regulate, warn, and inform the traveling public. Signs shall not be used to support other signs or other equipment.  
6. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
7. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
8. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
9. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
10. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
11. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
12. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
13. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
14. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".

**SIGN CONSTRAINTS**  
1. The Contractor shall ensure that the sign substrate is allowed for the type of sign support to be used. The CWZTD lists 300 "Type" materials are not an approved sign substrate.  
2. All wooden signposts shall be made of oak or select white pine. All metal signposts shall be galvanized steel.  
3. All signs shall be treated in accordance with the signs or as directed by the Engineer. Signs shall be used to regulate, warn, and inform the traveling public. Signs shall not be used to support other signs or other equipment.  
4. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".  
5. The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone". The Contractor shall furnish every sign support, sign, and sign board in the work zone in the "Standard Sign Shop" for "Work Zone".

**SIGN LETTERS**  
1. All sign letters and numbers shall be clear, and open rounded type uppercase outlined letters as approved by the Federal Highway Administration.  
2. Signs shall be viewed or completely covered when not working.  
3. Sign and support shall be treated with preservative.  
4. Sign and support shall be treated with preservative.

**WORKING WEIGHTS**  
1. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.  
2. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.  
3. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.  
4. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.  
5. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.  
6. The Contractor shall ensure that the weight of the sign support and the weight of the sign shall not exceed the design load.

**CONTRACTOR REQUIREMENTS FOR MAINTAINING PERMANENT SIGNS WITHIN THE PROJECT LIMITS**  
1. The Contractor shall ensure that the signs are maintained within the project limits.  
2. The Contractor shall ensure that the signs are maintained within the project limits.  
3. The Contractor shall ensure that the signs are maintained within the project limits.  
4. The Contractor shall ensure that the signs are maintained within the project limits.  
5. The Contractor shall ensure that the signs are maintained within the project limits.  
6. The Contractor shall ensure that the signs are maintained within the project limits.

Texas Department of Transportation  
Maintenance Division  
Standard Plans

ROADSIDE  
TRAFFIC CONTROL PLAN

SHEET 1 OF 1 RS-TCIP-05 NOT TO SCALE

DATE	REVISED	BY	DATE
10/1/2005	10/1/2005	10/1/2005	10/1/2005

**TRAFFIC CONTROL PLAN FOR WORK OFF OF THE PAVED SURFACE.**

Only prequalified products shall be used. A copy of the "Compliant Work Zone Traffic Control Manual List" (CWZTD-SPECIAL) shall be available to the Contractor at the project location. The Contractor shall ensure that the signs are maintained within the project limits.

TRAFFIC CONTROL DIVISION - 10  
Texas Department of Transportation  
100 East 11th Street  
Austin, Texas 78711-4093  
Phone (512) 416-2328  
Fax (512) 416-5239

Interpretation is to be made by the "SECTION" on "TRAFFIC CONTROL PLAN".

Start at "SECTION" on "TRAFFIC CONTROL PLAN".  
Click on "TRAFFIC CONTROL PLAN" and "TRAFFIC CONTROL PLAN" and "TRAFFIC CONTROL PLAN".  
Click on "TRAFFIC CONTROL PLAN" and "TRAFFIC CONTROL PLAN".

# EXHIBIT “B”

CRP

PRICING

Contract Description: MBGFR

Provider: TIEH

Item Number	Description	UOM	Current Price	Proposed Price	Counter offer
0450-5042	RAIL (TY PR 1)	LF	\$150.00	\$150.00	approved
0450-5099	REMOVE RAIL (METAL ELEMENTS)	LF	\$3.00	\$3.00	approved
0540-5001	MTL W-BEAM GD FEN (TM POST)	LF	\$21.00	\$21.00	approved
0540-5005	TERMINAL ANCHOR SECTION	EA	\$350.00	\$350.00	approved
0540-5010	MTL W-BEAM GD FEN ADJUSTMENT	LF	\$10.00	\$10.00	approved
0540-5006	MTL BEAM GD FEN TRANS (THRE-BEAM)	EA	\$1,250.00	\$1,800.00	\$1,500.00
0540-5016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA	\$1,000.00	\$1,200.00	approved
0540-5017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF	\$0.00	\$35.00	\$30.00
0542-5001	REMOVING METAL BEAM GUARD FENCE	LF	\$3.00	\$3.00	approved
0542-5002	REMOVING TERMINAL ANCHOR SECTION	EA	\$100.00	\$100.00	approved
0542-5004	RM MTL BM GD FEN TRANS (THRE BEAM)	EA	\$75.00	\$100.00	approved
0542-5005	RM MTL BM GD FEN TRANS (T101)	EA	\$450.00	\$450.00	approved
0544-5001	GUARD RAIL END TREATMENT (INSTALL)	EA	\$2,300.00	\$2,300.00	approved
0544-5003	GUARD RAIL END TREATMENT (REMOVE)	EA	\$300.00	\$300.00	approved
0545-5003	CRASH CUSHION ATTEN (MOVE & RESET)	EA	\$1,800.00	\$2,000.00	approved
0545-5005	CRASH CUSHION ATTEN (REMOVE)	EA	\$1,000.00	\$1,000.00	approved
0545-5024	CRASH CUSHION ATTEN (INSTALL) (TRACC)	EA	\$16,000.00	\$20,000.00	\$15,000.00
0545-5025	CRASH CUSHION ATTEN (INSTALL) (REACT(N))	EA	\$23,000.00	\$23,000.00	approved
0545-5026	CRASH CUSHION ATTEN (INSTALL) (QUAD)(N)	EA	\$17,500.00	\$20,000.00	approved
0545-5027	CRASH CUSHION ATTEN (INSTALL) (QUAD)(W)	EA	\$26,000.00	\$26,500.00	approved
0550-5001	CHAIN LINK FENCE (INSTALLATION)(6)	LF	\$9.50	\$10.00	approved
0550-5002	CHAIN LINK FENCE (REPAIR)(6)	LF	\$5.00	\$10.00	approved
0550-5007	CHAIN LINK FENCE (REPAIR)(4)	LF	\$9.50	\$10.00	approved
0770-5001	REPAIR RAIL ELEMENT (W - BEAM)	LF	\$11.00	\$12.00	approved
0770-5054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	LF	\$5.00	\$5.00	approved
0770-5010	REWRPL TMBER/STL POST W/O CONC FND	EA	\$40.00	\$40.00	approved
0770-5011	REWRPL TMBER/STL POST W/ CONC FND	EA	\$80.00	\$80.00	\$50.00
0770-5017	REALIGN POSTS	EA	\$15.00	\$15.00	approved
0770-5018	REMOVE AND REPLACE BLOCK CUT	EA		\$20.00	approved
0770-5027	REMOVE GORAIL END TRT/REPL WITH SGT	EA	\$2,350.00	\$2,500.00	approved
0770-5021	REPLACE SINGLE GORAIL TERMINAL RAIL	LF	\$15.00	\$15.00	approved
0770-5029	REPL SINGLE GORAIL TERM IMPACT HEAD	EA	\$900.00	\$900.00	approved
0770-5023	REPLACE SINGLE GORAIL TERMINAL POST	EA	\$42.00	\$45.00	approved
0770-5030	REPLACE SGT-CABLE ASSEMBLY	EA		\$200.00	\$75.00
0770-5031	REPLACE CABLE ANCHOR	EA		\$100.00	\$85.00
0770-5032	REPLACE SGT STRUT	EA		\$50.00	approved
0770-5033	REPLACE SGT OBJECT MARKER	EA		\$45.00	\$25.00
0770-5052	REPAIR STEEL POST WITH BASE PLATE	EA	\$200.00	\$300.00	approved
0770-5046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA	\$250.00	\$250.00	approved
0772-5001	POST AND CABLE FENCE (REMOVAL)	LF	\$3.00	\$3.00	approved
0772-5003	POST AND CABLE FENCE (NEW INSTALLATION)	LF	\$5.50	\$10.00	approved
0772-5004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA	\$50.00	\$175.00	\$100.00
0772-5005	POST AND CABLE FENCE (REMY/REPL POSTS)	EA	\$50.00	\$50.00	approved
0772-5006	POST AND CABLE FENCE (REMY/REPL CONC ANCHR)	EA	\$100.00	\$200.00	\$125.00
0774-5006	REPAIR (TRACC)	EA	\$2,600.00	\$2,600.00	approved
0774-5008	REPAIR (WIDE TRACC)	EA	\$2,600.00	\$2,600.00	approved
0774-5018	REPAIR (CATGR-FRONT SECTION)	EA	\$2,500.00	\$7,000.00	\$3,500.00
0774-5019	REPAIR (CATGR-END SECTION)	EA	\$1,500.00	\$2,500.00	approved
0774-5023	REPAIR REACT (N) (MISC HARDWARE)	EA		\$2,500.00	\$2,500.00
0774-5027	REPAIR REACT (N) (CYLINDERS)	EA		\$3,500.00	\$3,500.00
0774-5028	QUAD (N) (BAY) (REPAIR ONLY)	EA	\$750.00	\$1,600.00	\$1,500.00
0774-5083	QUAD (N) (BAY) CARTRIDGE	EA	\$1,200.00	\$1,300.00	approved
0774-5084	QUAD (N) (BAY) NOSE ASSEMBLY	EA	\$1,000.00	\$1,000.00	approved
0774-5029	QUAD (W) (BAY) (REPAIR ONLY)	EA	\$750.00	\$1,600.00	approved
0774-5086	QUAD (W) (BAY) CARTRIDGE	EA	\$1,200.00	\$1,200.00	approved
0774-5087	QUAD (W) (BAY) NOSE ASSEMBLY	EA	\$1,000.00	\$1,200.00	\$1,100.00
0774-5088	QUAD (M) (BAY) Diaphragm	EA	\$1,000.00	\$1,200.00	\$1,100.00
0543-5017	CABLE BARRIER TERMINAL SECTION (TL-3)	EA	\$2,700.00	\$2,500.00	\$2,800.00
0543-5022	REMOVE CABLE BARRIER TERMINAL SECTION	EA	\$1.00		\$500.00
0771-5001	REPLACE POSTS (TL 3)	EA	\$110.00	\$135.00	approved
0771-5005	REPAIR CONCRETE FOUNDATION (TL 3)	EA	\$225.00	\$2,500.00	\$250.00
0771-5009	REPLACE CABLE (TL 3)	LF	\$7.50	\$5.00	approved
7053-5001	CLEAN TRAFFIC ATTENUATORS (TRACC) (N)	EA	\$500.00	\$500.00	approved
7053-5002	CLEAN TRAFFIC ATTENUATORS (QUAD) (N)	EA	\$500.00	\$500.00	approved
7053-5003	CLEAN TRAFFIC ATTENUATORS (QUAD) (W)	EA	\$500.00	\$500.00	approved
7053-5004	CLEAN TRAFFIC ATTENUATORS (REACT 350)	EA	\$500.00	\$500.00	approved
7053-5005	RIGHT OF WAY MARKERS (LABOR ONLY)	EA	\$25.00	\$30.00	approved
7053-5008	TMA	DAY	\$400.00	\$410.00	approved
New Item	QUAD FENDER PANEL	EA		\$1,000.00	\$750.00
New Item	REACT CABLE 350 (6 BAY)	EA		\$1,500.00	\$1,200.00
New Item	REACT DECAL	EA		\$350.00	approved
New Item	REACT CABLE 350 (9 BAY)	EA		\$1,500.00	\$1,250.00
New Item	CABLE RELEASE POST	EA		\$500.00	approved
New Item	ANCHOR POST	EA		\$800.00	approved
New Item	REACT 350 CABLE HOLDERS	EA		\$350.00	approved
New Item	FAST TRACK CENTER PANELS	EA		\$1,200.00	approved

## TIBH APPROVED 2018 GUARD RAIL RATES / HIDALGO COUNTY

	ITEM CODE	DESCRIPTION	UNIT	UNIT \$
1	0450 6042	RAIL (TY PR1)	LF	\$ 150.00
2	0496 6099	REMOVE RAIL (METAL ELEMENTS)	LF	\$ 3.00
3	0540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	\$ 21.00
4	0540-6005	TERMINAL ANCHOR SECTION	EA	\$ 350.00
5	0540-6010	MTL W-BEAM GD FEN ADJUSTMENT	LF	\$ 10.00
7	0540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	\$ 1,500.00
8	0540-6016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA	\$ 1,200.00
9	0540-6017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF	\$ 30.00
10	0542 6001	REMOVING METAL BEAM GUARD FENCE	LF	\$ 3.00
11	0542 6002	REMOVING TERMINAL ANCHOR SECTION	EA	\$ 100.00
12	0542 6004	RM MTL BM GD FEN TRANS (THRIE BEAM)	EA	\$ 100.00
13	0542 6005	RM MTL BM GD FEN TRANS (T101)	EA	\$ 450.00
14	0544-6001	GUARD RAIL END TREATMENT (INSTALL)	EA	\$ 2,300.00
15	0544-6003	GUARD RAIL END TREATMENT (REMOVE)	EA	\$ 300.00
16	0545 6003	CRASH CUSHION ATTEN (MOVE & RESET)	EA	\$ 2,000.00
17	0545 6005	CRASH CUSHION ATTEN (REMOVE)	EA	\$ 1,000.00
18	0545 6024	CRASH CUSHION ATTEN (INSTALL) (TRACC)	EA	\$ 16,000.00
19	0545 6025	CRASH CUSHION ATTEN (INSTALL) (REACT)(N)	EA	\$ 23,000.00
20	0545 6026	CRASH CUSHION ATTEN (INSTALL) (QUAD)(N)	EA	\$ 20,000.00
21	0545 6027	CRASH CUSHION ATTEN (INSTALL) (QUAD)(W)	EA	\$ 26,500.00
22	0550-6001	CHAIN LINK FENCE (INSTALLATION)(6')	LF	\$ 10.00
23	0550-6002	CHAIN LINK FENCE (REPAIR)(6')	LF	\$ 10.00
24	0550-6007	CHAIN LINK FENCE (REPAIR)(4')	LF	\$ 10.00
25	0770-6001	REPAIR RAIL ELEMENT (W - BEAM)	LF	\$ 12.00
26	0770-6054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	EA	\$ 6.00
27	0770 6010	REM/REPL TIMBER/STL POST W/O CONC FND	EA	\$ 40.00
28	0770 6011	REM/REPL TIMBER/STL POST W/ CONC FND	EA	\$ 60.00
29	0770 6017	REALIGN POSTS	EA	\$ 15.00
30	0770-6019	REMOVE AND REPLACE BLOCK OUT	EA	\$ 20.00
31	0770 6027	REMOVE GDRAIL END TRT/REPL WITH SGT	EA	\$ 2,500.00
32	0770 6021	REPLACE SINGLE GDRAIL TERMINAL RAIL	LF	\$ 15.00
33	0770 6028	REPLACE SINGLE GDRAIL TERM IMPACT HEAD	EA	\$ 900.00
34	0770 6022	REPLACE SINGLE GDRAIL TERMINAL POST	EA	\$ 45.00
35	0770-6030	REPLACE SGT CABLE ASSEMBLY	EA	\$ 75.00
36	0770 6031	REPLACE CABLE ANCHOR	EA	\$ 85.00
37	0770-6032	REPLACE SGT STRUT	EA	\$ 60.00
38	0770-6033	REPLACE SGT OBJECT MARKER	EA	\$ 25.00
39	0770-6052	REPAIR STEEL POST WITH BASE PLATE	EA	\$ 200.00
40	0770-6046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA	\$ 250.00
41	0772-6001	POST AND CABLE FENCE (REMOVAL)	LF	\$ 3.00
42	0772-6003	POST AND CABLE FENCE (NEW INSTALLATION)	LF	\$ 10.00
43	0772-6004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA	\$ 100.00
44	0772-6005	POST AND CABLE FENCE (REMV/REPL POSTS)	EA	\$ 50.00
45	0772-6006	POST AND CABLE FENCE (REMOVE CONC ANCHOR)	EA	\$ 125.00
46	0774 6006	REPAIR (TRACC)	EA	\$ 2,600.00
47	0774 6008	REPAIR (WIDE TRACC)		

TIBH APPROVED 2018 GUARD RAIL RATES / HIDALGO COUNTY

ITEM CODE	DESCRIPTION	UNIT	UNIT \$
1	0450 6042	RAIL (TY PR1)	LF \$ 150.00
2	0496 6099	REMOVE RAIL (METAL ELEMENTS)	LF \$ 3.00
3	0540-6001	MTL W-BEAM GD FEN (TIM POST)	LF \$ 21.00
4	0540-6005	TERMINAL ANCHOR SECTION	EA \$ 350.00
5	0540-6010	MTL W-BEAM GD FEN ADJUSTMENT	LF \$ 10.00
7	0540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA \$ 1,500.00
8	0540-6016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA \$ 1,200.00
9	0540-6017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF \$ 30.00
10	0542 6001	REMOVING METAL BEAM GUARD FENCE	LF \$ 3.00
11	0542 6002	REMOVING TERMINAL ANCHOR SECTION	EA \$ 100.00
12	0542 6004	RM MTL BM GD FEN TRANS (THRIE BEAM)	EA \$ 100.00
13	0542 6005	RM MTL BM GD FEN TRANS (T101)	EA \$ 450.00
14	0544-6001	GUARD RAIL END TREATMENT (INSTALL)	EA \$ 2,300.00
15	0544-6003	GUARD RAIL END TREATMENT (REMOVE)	EA \$ 300.00
16	0545 6003	CRASH CUSHION ATTEN (MOVE & RESET)	EA \$ 2,000.00
17	0545 6005	CRASH CUSHION ATTEN (REMOVE)	EA \$ 1,000.00
18	0545 6024	CRASH CUSHION ATTEN (INSTALL) (TRACC)	EA \$ 16,000.00
19	0545 6025	CRASH CUSHION ATTEN (INSTALL) (REACT)(N)	EA \$ 23,000.00
20	0545 6026	CRASH CUSHION ATTEN (INSTALL) (QUAD)(N)	EA \$ 20,000.00
21	0545 6027	CRASH CUSHION ATTEN (INSTALL) (QUAD)(W)	EA \$ 26,500.00
22	0550-6001	CHAIN LINK FENCE (INSTALLATION)(6')	LF \$ 10.00
23	0550-6002	CHAIN LINK FENCE (REPAIR)(6')	LF \$ 10.00
24	0550-6007	CHAIN LINK FENCE (REPAIR)(4')	LF \$ 10.00
25	0770-6001	REPAIR RAIL ELEMENT (W - BEAM)	LF \$ 12.00
26	0770-6054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	EA \$ 6.00
27	0770 6010	REM/REPL TIMBER/STL POST W/O CONC FND	EA \$ 40.00
28	0770 6011	REM/REPL TIMBER/STL POST W/ CONC FND	EA \$ 60.00
29	0770 6017	REALIGN POSTS	EA \$ 15.00
30	0770-6019	REMOVE AND REPLACE BLOCK OUT	EA \$ 20.00
31	0770 6027	REMOVE GDRAIL END TRT/REPL WITH SGT	EA \$ 2,500.00
32	0770 6021	REPLACE SINGLE GDRAIL TERMINAL RAIL	LF \$ 15.00
33	0770 6028	REPLACE SINGLE GDRAIL TERM IMPACT HEAD	EA \$ 900.00
34	0770 6022	REPLACE SINGLE GDRAIL TERMINAL POST	EA \$ 45.00
35	0770-6030	REPLACE SGT CABLE ASSEMBLY	EA \$ 75.00
36	0770 6031	REPLACE CABLE ANCHOR	EA \$ 85.00
37	0770-6032	REPLACE SGT STRUT	EA \$ 60.00
38	0770-6033	REPLACE SGT OBJECT MARKER	EA \$ 25.00
39	0770-6052	REPAIR STEEL POST WITH BASE PLATE	EA \$ 200.00
40	0770-6046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA \$ 250.00
41	0772-6001	POST AND CABLE FENCE (REMOVAL)	LF \$ 3.00
42	0772-6003	POST AND CABLE FENCE (NEW INSTALLATION)	LF \$ 10.00
43	0772-6004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA \$ 100.00
44	0772-6005	POST AND CABLE FENCE (REMV/REPL POSTS)	EA \$ 50.00
45	0772-6006	POST AND CABLE FENCE (REMOVE CONC ANCHOR)	EA \$ 125.00
46	0774 6006	REPAIR (TRACC)	EA \$ 2,600.00
47	0774 6008	REPAIR (WIDE TRACC)	EA \$ 2,600.00
48	0774 6018	REPAIR (CATGR-FRONT SECTION)	EA \$ 3,500.00
49	0774 6019	REPAIR (CATGR-END SECTION)	EA \$ 2,500.00
50	0774 6023	REPAIR REACT (N) (MISC HARDWARE)	EA \$ 2,500.00
54	0774 6027	REPAIR REACT (N) (CYLINDERS)	EA \$ 3,500.00
55	0774 6028	QUAD (N) (BAY) (REPAIR ONLY)	EA \$ 1,600.00
56	0774 6083	QUAD (N) (BAY) CARTRIDGE	EA \$ 1,300.00
57	0774 6084	QUAD (N) (BAY) NOSE ASSEMBLY	EA \$ 1,000.00
58	0774 6029	QUAD (W) (BAY) (REPAIR ONLY)	EA \$ 1,600.00
59	0774 6086	QUAD (W) (BAY) CARTRIDGE	EA \$ 1,200.00
60	0774 6087	QUAD (W) (BAY) NOSE ASSEMBLY	EA \$ 1,200.00
61	0774 6088	QUAD (W) (BAY) DIAPHRAGM	EA \$ 1,200.00
62	0543-6017	CABLE BARRIER TERMINAL SECTION (TL-3)	EA \$ 2,800.00
63	0543-6022	REMOVE CABLE BARRIER TERMINAL SECTION	EA \$ 500.00
64	0771-6001	REPLACE POSTS (TL 3)	EA \$ 136.00
65	0771-6005	REPAIR CONCRETE FOUNDATION (TL 3)	EA \$ 250.00
66	0771-6009	REPLACE CABLE (TL 3)	LF \$ 5.00
67	7053-6001	CLEAN TRAFFIC ATTENUATORS (TRACC) (N)	EA \$ 500.00
68	7053-6002	CLEAN TRAFFIC ATTENUATORS (QUAD) (N)	EA \$ 500.00
69	7053-6003	CLEAN TRAFFIC ATTENUATORS (QUAD) (W)	EA \$ 500.00
70	7053-6004	CLEAN TRAFFIC ATTENUATORS (REACT 350)	EA \$ 500.00
71	7053-6005	RIGHT AWAY MARKERS (LABOR ONLY)	EA \$ 30.00
72	7053-6008	TMA	EA \$ 410.00
73	NEW ITEM	QUAD FENDER PANER	EA \$ 750.00
74	NEW ITEM	REACT CABLE 350 (6 BAY)	EA \$ 1,200.00
75	NEW ITEM	REACT DECAL	EA \$ 350.00
76	NEW ITEM	REACT CABLE 350 (9 BAY)	EA \$ 1,250.00
77	NEW ITEM	CABLE RELEASE POST	EA \$ 600.00
78	NEW ITEM	ANCHOR POST	EA \$ 800.00
79	NEW ITEM	REACT 350 CABLE HOLDERS	EA \$ 350.00
80	NEW ITEM	FAST TRACK CENTER PANELS	EA \$ 1,200.00



# EXHIBIT “C”

# CERTIFICATE OF INSURANCE





# CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)  
4/20/2018

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

**IMPORTANT:** If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER (956)787-4989 Crystal Jeannie Salinas James E. Capt & Associates LLC P. O. BOX 126 San Juan, TX 78589-0126	CONTACT NAME: LUCY OR JEANNIE PHONE (A/C No, Ext): (800)887-4989 Ext.	FAX (A/C No): (956)781-3380
	E-MAIL ADDRESS: lucy@captinsurance.com	
INSURER(S) AFFORDING COVERAGE		NAIC #
INSURED RGR INDUSTRIES, INC. 6700 N MILE 3 1/2 WEST WESLACO, TX 78596-0000	INSURER A: ADMIRAL INSURANCE COMPANY	
	INSURER B: HALLMARK COUNTY MUTUAL	
	INSURER C: TEXAS MUTUAL INSURANCE	
	INSURER D:	
	INSURER E:	

COVERAGES                      CERTIFICATE NUMBER:                      REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDITIONAL SUBR INSR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	GENERAL LIABILITY		CA00002573002	11/07/17	11/07/18	EACH OCCURRENCE \$ 1,000,000
	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY					DAMAGE TO RENTED PREMISES (Ex occurrences) \$ 100,000
	<input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR					MED EXP (Any one person) \$ 5,000
	GEN'L AGGREGATE LIMIT APPLIES PER:					
	<input type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOG					GENERAL AGGREGATE \$ 2,000,000
B	AUTOMOBILE LIABILITY		A42503271-04	05/15/17	05/15/18	COMBINED SINGLE LIMIT (Ex resident) \$ 1,000,000
	<input type="checkbox"/> ANY AUTO					BODILY INJURY (Per person) \$
	<input type="checkbox"/> ALL OWNED AUTOS	<input checked="" type="checkbox"/> SCHEDULED AUTOS				BODILY INJURY (Per accident) \$
	<input type="checkbox"/> HIRED AUTOS	<input type="checkbox"/> NON-OWNED AUTOS				PROPERTY DAMAGE (Per accident) \$
C	UMBRELLA LIAB		TSF-0001201928	06/10/17	06/10/18	EACH OCCURRENCE \$
	EXCESS LIAB	<input type="checkbox"/> OCCUR				AGGREGATE \$
	<input type="checkbox"/> DEQ <input type="checkbox"/> RETENTION \$	<input type="checkbox"/> CLAIMS-MADE				\$
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY	<input type="checkbox"/> Y/N				
	ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory In NH)	<input checked="" type="checkbox"/> N/A				E.L. EACH ACCIDENT \$ 1,000,000
	If yes, describe under DESCRIPTION OF OPERATIONS below					E.L. DISEASE - EA EMPLOYEE \$ 1,000,000
						E.L. DISEASE - POLICY LIMIT \$ 1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (Attach ACORD 101, Additional Remarks Schedule, if more space is required)

<b>CERTIFICATE HOLDER</b> COUNTY OF HIDALGO 2812 S BUSINESS HWY281 EDINBURG TX 78539	<b>CANCELLATION</b> SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE:
---	---

© 1988-2010 ACORD CORPORATION. All rights reserved.

