

CHANGE ORDER No. 5

PROJECT: 10th Street Extension Project

DATE OF ISSUANCE: 5/21/19

OWNER: Hidalgo County

**CONTRACTOR:
Texas Cordia Construction, LLC.
3149-A Center Pointe Dr.
Edinburg, Texas 78539**

**Engineer:
L&G Engineers**

**CONTRACT FOR:
Project: 10th Street Ext. Project
Contract: C-17-218-01-16
CSJ: 0921-02-300
Limits: from SH 107 to FM 1925 (Monte Christo Rd.)**

You are directed to make the following changes in the Contract Documents.

Description:

This CO is requesting the introduction of Item 450-9001 Rail (Ty PR1)(Spl), Item 529-6035 Conc Curb TY A, Item 5001-6001 GeoGrid Base Reinforcement, Item 9001-6001 Instl Rdsd Flsh Bcn Assm (Solar) (Mod) and Item 9002-6001 Elc Srv Ty T (Service Extension). Also, this CO is requesting quantity adjustments for Item 104-6013 Removing Conc (Foundation), Item 160-6005 Furnishing and Placing Topsoil, Item 260-6043 Lime (Hyd,Com, or Qk)(Slurry), Item 400-6006 Cut & Restore Pav, Item 496-6004 Remov Str (SET), Item 506-6031 Frnt End Loader Work (Ersn & Sed Cnt), Item 508-6001 Construct Detours, Item 529-6028 Conc Curb & Gutter (Ty B)(Mountable), and Item 530-6004 Driveways (Conc).

Purpose of Change Order:

Items being introduced are needed to address work not originally included in the plans and specifications. Item 450-9001 and Item 529-6035 are needed to address a slope concern adjacent to the proposed sidewalk. Item 5001-6001 is needed to address unstable areas encountered in the roadbed. Item 9001-6001 is needed to convert a school crossing flasher from electrical power to solar power and Item 9002-6001 is needed to pay for the extension of power line and poles to service the proposed flashing beacon on 10th and Russel Road.

The other items on this change order will require plan quantity adjustments to match additional quantities needed due to underestimation or adjust quantities to match final As-Built quantities. Please see TxDOT Form 2146-L for more details. TxDOT has reviewed this request and has concurred with cost associated with the changes.

Attachments: TxDOT Form 2146-L

CHANGE IN CONTRACT PRICE:	CHANGE IN CONTRACT TIME:
Original Contract Price <u>\$ 9,142,335.55</u>	Original Contract Time <u>480 Working days</u> days or date
Previous Change Orders No. <u> 1 </u> to No. <u> 4 </u> <u>\$ 192,448.31</u>	Net change from previous Change Orders <u>-0-</u> days
Contract Price prior to this Change Order <u>\$ 9,334,783.86</u>	Contract Time Prior to this Change Order <u>480 Working days</u> days or date
Net increase of this Change order <u>\$ 67,551.35</u>	Net Decrease of this Change Order <u>0 Working days</u> days
Contract Price with all approved Change Orders <u>\$ 9,402,335.21</u>	Contract Time with all approved Change Orders <u>480 Working days</u> days or date

Construction Contract Change Order Number: 5

1. Contractor: Texas Cordia Construction, LLC.
2. Change Order Work Limits: Sta. Proj Limits to Sta. Project Limits
3. Type of Change (on federal-aid nonexempt projects: Minor (Major/Minor)
4. Describe the change and the reason for the change order. When necessary include exceptions to this agreement.

CCSJ: 0921-02-300

Project: 10th Street Ext. Project

Highway: 10th Street

County: Hidalgo

District: Pharr

Contract Number: Bid # C 17-218-01-16

The following changes are being requested: Introduce Item 529-6035 Conc Curb TY A which is required for the placement of new Item 450-9001 Rail (TY PR1)(SPL) quantities (8 separate locations) needing to be added to address slope concerns adjacent to the recently constructed concrete sidewalk. Item 5001-6001 GeoGrid Base Reinforcement is being introduce to address soft spots encountered on treated roadbed. Additionally quantities for Item 260-6043 Lime is needed to provide extra lime for stabilization to area between Sta 223+00 to Sta 232+17. (See Additional Description on following page.)

5. New or revised plan sheet (s) are attached and numbered:
 Each signatory hereby warrants that each has the authority to execute this Change Order.

By signing this change order, the contractor agrees to waive any and all claims for additional compensation due to any and all other expenses; additional changes for time, overhead and profit, or loss of compensation as a result of this change. Further, the contractor agrees that this agreement is made in accordance with item 4 and the Contract. Exception should be noted in the response for #5 above.

The following information must be provided

Time Ext #. N/A Days added to this C.O.:

Amt. added by this change order: \$ 67,551.35

For TxDOT use only:

Days participating _____

Amount Participating \$67,551.35

Signature _____ Date _____

Name/Title _____

THE CONTRACTOR Date 5-16-19

By [Signature]

Type/Print Name _____

CEO

Type/Print Title _____

Recommended for Execution:

[Signature] Proj. Mgr 5/16/19

Name/Title David Calapez Date _____

Name/Title _____ Date _____

Name/Title _____ Date _____

CHRISTOPHER RODRIGUEZ Project Engineer

Name/Title _____ Date _____

Engineer's Seal



_____ Name/Title	_____ Date	_____ Approved	_____ Request Approval
_____ Name/Title	_____ Date	_____ Approved	_____ Request Approval
_____ Name/Title	_____ Date	_____ Approved	_____ Request Approval
_____ Name/Title	_____ Date	_____ Approved	_____ Request Approval

Construction Contract Change Order Number: 5

4. (Continued) Describe the change and the reason for the change order. When necessary include exceptions to this agreement.

Quantities for Item 529-6028 Conc Curb & Gutter (TY B) and Item 530-6004 Driveways (Conc) are being increased due to original quantities being under estimated. Additionally, Item 9001-6001 and Item 9002-6002 are being introduced. Item 9001-6001 Instl RDSB Flsh Bcn Assm (Solar)(Mod) is needed to modify the newly installed flashing beacon signs by converting the power supply from electrical to Solar. Item 9002-6001 Elc Srv TY T (Service Extension) is needed to compensate the Contractor for extending power service (additional poles and line) for the Russel Road flashing beacon. Also quantities for the following items are being adjusted to as built quantities: Item 104-6013 Removing Conc (Foundation), Item 160-6005 Furnishing and Placing Topsoil, Item 400-6006 Cut & Restore Pav, Item 496-6004 Remov Str (SET), Item 506-6031 Front End Loader Work, and Item 508-6001 Construct Detours.