



Purchase Order COUNTY OF HIDALGO

PO# 796778

DATE: 04/12/19

PAGE NO: 1 Of 2

PO TYPE:

VENDOR: 4537

REQ: 00391707

PHONE: (956) 968-0515

EMAIL:

SHIP TO: HIDALGO CO. PCT 2

300 WEST HALL ACRES, SUITE G
PHARR TX 78577

BURTON AUTO SUPPLY, INC.

PO BOX 297

WESLACO TX 78599

CONTACT: R. GONZALEZ

(956) 787-1891

SITE: COMMISSIONER, PRECINCT 2

CONTRACT NO: BUYBOARD #577-18

SPECIAL INSTRUCTIONS:

VENDOR NOTES

1. Do not add to, or alter this Purchase Order. This Order is not renewable.
2. TAX EXEMPTION: This Purchase Order may be accepted in lieu of Exemption Certificate.
3. This Order is also placed F.O.B. Destination. Vendor must repay all shipping costs.
4. Invoice each Purchase Order singly. Original invoices are required customer copy may be accepted. Out number must appear on all invoices, bills of lading, and packages.
5. Payment will be made only for bona fide and full completed orders, unless otherwise attached.

QTY	UOM	DESCRIPTION	UNIT PRICE	AMOUNT
1.00	EACH	<p>DO NOT DUPLICATE ORDER</p> <p>BUYBOARD #577-18 EXPIRES 11/30/2021 PCT 2 ROAD MAINTENANCE - STATIONARY EMERGENCY DIESEL GENERATOR SET FOR THE PCT 2 FIELD OPERATIONS FACILITY @ 4011 S VETERANS BLVD, SAN JUAN, TX</p> <p>CO ASSET# 77330 #350REOZJB-280-1 GENERATOR SYSTEM INCLUDES EQUIPMENT & INSTALLATION AS FOLLOWS: KOHLER POWER SYSTEMS OUTDOOR STATIONARY EMERGENCY DIESEL GENERATOR SET RATED 280 KW EPA EMISSIONS-ENGINE IS CERTIFIED TO MEET CURRENT EPA EMISSION REQUIREMENTS WHEN USED IN EMERGENCY STATIONARY APPLICATION PER ICE DEFINITIONS. NOT UL 2200 LISTED STANDBY RATED, 120/240V, SINGLE PHASE, 60 HZ ELECTRONIC ISOCHRONOUS GOVERNOR 50c/122f UNIT MOUNTED RADIATOR PMG ALTERNATOR, MODEL 5M4027 CONTROLLER, APM402 MICROPROCESSOR BASED * REMOTE ANNUNCIATOR PANEL-NFPA 110 * 2 INPUT / 5 OUTPUT MODULE FOR REMOTE INDICATION (PROGRAMMABLE) * RUN RELAY FOR REMOTE INDICATION * MODBUS TO ETHERNET CONVERTER 1200 AMP MAIN LINE CIRCUIT BREAKER, 100% RATED SOUND-ATTENUATED ENCLOSURE WITH INTERNAL SILENCER 24 HOUR/774 GALLON UL142 LISTED SUBBASE DIESEL TANK ENGINE JACKET WATER HEATER - 120VAC2500w STARTING BATTERIES, CABLES, AND FLOAT-EQUALIZE CHARGER - 12V,10AMP WITH ALARMS STARTUP AND ON-SITE TEST WITH FULL LOAD FACTORY .8 POWER FACTOR TEST FIVE YEAR SYSTEM WARRANTY AGAINST ANY MANUFACTURE'S DEFECTS.</p> <p>ATC3CFX21200WSU, 1200 AMP AUTOMATIC TRANSFER SWICTH 2 POLE, SOLID NEUTRAL, 240VAC,SINGLE PHASE NEMA I ENCLOSURE - IN-PHASE MONITOR - PROGRAMMABLE TIME DELAYS</p> <p>INCLUDES TURNKEY INSTALLATION INSTALL ELECTRICAL FOR GENERATOR, INCLUDING SET GENERATOR ON CONCRETE PAD. NOTE: CUSTOMER WILL INSTALL THE CONCRETE PAD. WE WILL RUN CONDUIT AND WIRE FROM ATS TO GENERATOR, TRANSFER MAIN FEED FROM PANEL TO ATS, INSTALL JUNCTION BOX AND MAKE SPLICE TO MAKE FEEDER, RUN CONDUIT, WIRE AND INSTALL REMOTE ANNUNCIATOR, SET UP POWER FOR CRITICAL LOADS DURING POWER CHANGE OVER.</p> <p>*CUTOVER WORK SHALL BE PERFORMED ON A WEEKEND, TURN MAIN POWER</p>	147,970.0000	147,970.00

Authorized by:

Martha Salazar

