



2802 S. Bus. Hwy 281
Edinburg, Texas 78539
Phone: (956) 318-2626
Fax: (956) 318-2629
www.co.hidalgo.tx.us/purchasing

November 22, 2019

Workquest
Bidder's name
Attn: Rosa Valdez
1011 E. 53rd 1/2 Street
Address
Austin, TX 78751
City, State, Zip Code

email: rvaldez@workquest.com

**Re: HB Form 1295 Required/Renewal/Extension Notice
Contract/Renewal# C-18-082-04-24-Hidalgo County – "Purchase of Guardrail Materials and/or Turnkey Solutions"**

Dear Ms. Valdez,

Be advised, that in order to proceed with the County's option to extend/renew its **second and final of two (2) one (1) year option, under the same rates, terms and conditions as provided in the current contract** with **Workquest**, for the referenced project, the County is required, as of **January 1, 2016**, to comply with the **Texas Government Code, §2252.908**, and the rules issued by the **Texas Ethics Commission** found in Title 1, Section 46.1, 46.3 and 46.5 of the Texas Administrative Code. In accordance with these requirements for the type of contract being considered, a business must submit a completed **Certificate of Interested Parties Form 1295**, to the County before the County may enter into a contract with the business entity.

In order for County staff to process the above referenced extension/renewal; you must complete Form 1295 and file Form 1295 with the Texas Ethics Commission. You can find the 1295 Form through the Texas Ethics Commission at the following website:

https://www.ethics.state.tx.us/whatsnew/elf_info_form1295.htm

In box 3 of **Form 1295**, provide **Reference No. E-20-022** Once completed and filed, "*unsworn declaration*" Form 1295 must be printed, signed and submitted to our office by the deadline stated below.

In order to proceed with approval of **Renewal/Extension** for referenced project by **Commissioners Court on January 28, 2020**, the signed notarized "**HB Form 1295**" and "**Extension Notice**" must be received in our office completed **by no later than January 06, 2020 or sooner if possible**. Hidalgo County cannot enter into a contract until Form 1295 is submitted, therefore, failure to timely submit Form 1295 signed, and notarized may result in delay of award.

In, addition, please include your "**Updated Certificate of Insurance**" with acknowledgment of receipt to this notice by signing below and returning to the Hidalgo County Purchasing Department, via email: tanya.delira@co.hidalgo.tx.us by no later than date reflected above.

By:



Date: 12/03/19

Hidalgo County Purchasing Department welcomes and appreciates your participation in the contract process. If any further assistance is required, please do not hesitate to call the Purchasing Department (956)318-2626.

Sincerely,

Martha L. Salazar

Martha L. Salazar, CPPB
Hidalgo County Purchasing Agent

MLS/tdl
Enclosures

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

WorkQuest
Austin, TX United States

Certificate Number:
2019-565722

Date Filed:
12/02/2019

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

Date Acknowledged:

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C18-082-04-24
Purchase of Guardrails - Material and/or Labor Turnkey Solution

4	Name of Interested Party	City, State, Country (place of business)	Nature of Interest (check applicable)	
			Controlling	Intermediary
	DuTerroil, Gibson	Austin, TX United States	X	
	Weber, Jr., Fred	Austin, TX United States	X	
	Foreman, Peggy	Austin, TX United States	X	
	Luna, John	Austin, TX United States	X	
	Miller, Brian	Austin, TX United States	X	
	Nash, Jack	Austin, TX United States	X	
	Williams, Donnie	Austin, TX United States	X	

5 Check only if there is NO Interested Party.

6 UNSWORN DECLARATION

My name is Fred M. Weber, Jr., and my date of birth is November 23, 1959.

My address is 1011 East 53rd 1/2 Street, Austin, Texas, 78751, USA.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in Travis County, State of Texas, on the 2nd day of December, 2019.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

4/24/2019

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Higginbotham Insurance Agency, Inc. William Gammon Insurance 1615 Guadalupe Austin TX 78701	CONTACT NAME: Michele Lane PHONE (A/C, No, Ext): 817-728-2374 E-MAIL ADDRESS: mlane@higginbotham.net	FAX (A/C, No): 817-347-6981
	INSURER(S) AFFORDING COVERAGE	
INSURED WorkQuest 1011 E. 53rd 1/2 St Austin TX 78751	INSURER A : Travelers Casualty & Surety Co	
	INSURER B : Great American Assurance Company	
	INSURER C : Great American Alliance Ins. Co.	
	INSURER D : Technology Insurance Company	
	INSURER E :	
	INSURER F :	

COVERAGES

CERTIFICATE NUMBER: 973344510

REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.


INSR LTR	TYPE OF INSURANCE	ADDL SUBR INSD WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
B	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input checked="" type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:		PAC429587104	4/25/2019	4/25/2020	EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 100,000 MED EXP (Any one person) \$ 5,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 Emp. Ben. \$ 1,000,000
	AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> HIRED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> NON-OWNED AUTOS					COMBINED SINGLE LIMIT (Ea accident) \$ BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
C	<input checked="" type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> DED <input checked="" type="checkbox"/> RETENTION \$ 0		UMB4295872	4/25/2019	4/25/2020	EACH OCCURRENCE \$ 9,000,000 AGGREGATE \$ 9,000,000 \$
D	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below	Y/N N N/A	TWC3783191	4/25/2019	4/25/2020	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000
A	Crime		106911495	4/25/2019	4/25/2020	Limit \$2,000,000 Deductible \$25,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

The General Liability policy includes a blanket automatic additional insured endorsement that provides additional insured status and General Liability and Workers' Compensation policy includes a blanket waiver of subrogation endorsement to the certificate holder only when there is a written contract between the named insured and the certificate holder that requires such status.

The General Liability policy has a blanket Primary & Non Contributory endorsement that affords that coverage to certificate holders only where there is a written contract between the Named Insured and the certificate holder that requires such status.

See Attached...

CERTIFICATE HOLDER Hidalgo County 711 El Cibolo Rd Edinburg TX 78541	CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.
	AUTHORIZED REPRESENTATIVE 

© 1988-2014 ACORD CORPORATION. All rights reserved.



E-19-054-04-09

2802 S. Bus. Hwy 281
Edinburg, Texas 78539
Phone: (956) 318-2626
Fax: (956) 318-2629
www.co.hidalgo.tx.us/purchasing

March 15, 2019

Workquest
Bidder's name
Attn: Rosa Valdez
1011 E. 53rd 1/2 Street
Address
Austin, TX 78751
City, State, Zip Code

email: rvaldez@tibh.org

Term: 05/01/2019 thru 04/30/2020

**Re: HB Form 1295 Required/Renewal/Extension Notice
Contract/Renewal# C-18-082-04-24-Hidalgo County – "Purchase of Guardrail Materials and/or Turnkey Solutions"**

Dear Ms. Valdez,

Be advised, that in order to proceed with the County's option to extend/renew its **first (1st) of two (2) one (1) year option, under the same rates, terms and conditions as provided in the current contract** with **Workquest**, for the referenced project, the County is required, as of **January 1, 2016**, to comply with the **Texas Government Code, §2252.908**, and the rules issued by the **Texas Ethics Commission** found in Title 1, Section 46.1, 46.3 and 46.5 of the Texas Administrative Code. In accordance with these requirements for the type of contract being considered, a business must submit a completed **Certificate of Interested Parties Form 1295**, to the County before the County may enter into a contract with the business entity.

In order for County staff to process the above referenced extension/renewal; you must complete Form 1295 and file Form 1295 with the Texas Ethics Commission. You can find the 1295 Form through the Texas Ethics Commission at the following website:

https://www.ethics.state.tx.us/whatsnew/elf_info_form1295.htm

In box 3 of **Form 1295**, provide **Reference No. E-19-054** Once completed and filed, "*unsworn declaration*" Form 1295 must be printed, signed and submitted to our office by the deadline stated below.

In order to proceed with approval of **Renewal/Extension** for referenced project by **Commissioners Court on March 26, 2019**, the signed notarized "**HB Form 1295**" and "**Extension Notice**" must be received in our office completed **by no later than Tuesday, March 19, 2019 or sooner if possible**. Hidalgo County cannot enter into a contract until Form 1295 is submitted, therefore, failure to timely submit Form 1295 signed, and notarized may result in delay of award.

In, addition, please include your "**Updated Certificate of Insurance**" with acknowledgment of receipt to this notice by signing below and returning to the Hidalgo County Purchasing Department, via email: yolanda.velasquez@co.hidalgo.tx.us by no later than date reflected above.

By:



Date: 03/18/19

Hidalgo County Purchasing Department welcomes and appreciates your participation in the contract process. If any further assistance is required, please do not hesitate to call the Purchasing Department (956)318-2626.

Sincerely,

Martha L. Salazar

Martha L. Salazar, CPPB
Hidalgo County Purchasing Agent

MLS/yzv
Enclosures



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

3/21/2019

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an **ADDITIONAL INSURED**, the policy(ies) must be endorsed. If **SUBROGATION IS WAIVED**, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER Higginbotham Insurance Agency, Inc. William Gammon Insurance 1615 Guadalupe Austin TX 78701	CONTACT NAME: Michele Lane PHONE (A/C, No, Ext): 817-728-2374 E-MAIL ADDRESS: mlane@higginbotham.net	FAX (A/C, No): 817-347-6981
	INSURER(S) AFFORDING COVERAGE	
INSURED WorkQuest 1011 E. 53rd 1/2 St Austin TX 78751	INSURER A : Travelers Casualty & Surety Co	
	INSURER B : Great American Assurance Company	
	INSURER C : Great American Alliance Ins. Co.	
	INSURER D : Technology Insurance Company	
	INSURER E :	
	INSURER F :	

COVERAGES

CERTIFICATE NUMBER: 2093737276

REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
B	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input checked="" type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:			PAC429587103	4/25/2018	4/25/2019	EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 100,000 MED EXP (Any one person) \$ 5,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 Emp. Ben. \$ 1,000,000
	AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> ALL OWNED AUTOS <input type="checkbox"/> HIRED AUTOS <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> NON-OWNED AUTOS						COMBINED SINGLE LIMIT (Ea accident) \$ BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
C	<input checked="" type="checkbox"/> UMBRELLA LIAB <input checked="" type="checkbox"/> OCCUR <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> DED <input checked="" type="checkbox"/> RETENTION \$ 0			UMB429587203	4/25/2018	4/25/2019	EACH OCCURRENCE \$ 9,000,000 AGGREGATE \$ 9,000,000 \$
D	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below		Y/N N/A	TWC3624438	4/25/2018	4/25/2019	<input checked="" type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ 1,000,000 E.L. DISEASE - POLICY LIMIT \$ 1,000,000
A	Crime			106911495	4/25/2018	4/25/2019	Limit \$2,000,000 Deductible \$25,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

Named Insured: TIBH Industries, Inc., Horizons of New Mexico, TIBH Central Store, Disabled Recyclers of TX, Inc., DRT, Inc.

The General Liability policy includes a blanket automatic additional insured endorsement that provides additional insured status and General Liability and Workers' Compensation policy includes a blanket waiver of subrogation endorsement to the certificate holder only when there is a written contract between the named insured and the certificate holder that requires such status.

The General Liability policy has a blanket Primary & Non Contributory endorsement that affords that coverage to certificate holders only where there is a written contract between the Named Insured and the certificate holder that requires such status.
See Attached...

CERTIFICATE HOLDER**CANCELLATION**

Hidalgo County Courthouse
 100 North Clossner
 Edinburg TX 78539

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

© 1988-2014 ACORD CORPORATION. All rights reserved.



ADDITIONAL REMARKS SCHEDULE

AGENCY Higginbotham Insurance Agency, Inc.		NAMED INSURED WorkQuest 1011 E. 53rd 1/2 St Austin TX 78751	
POLICY NUMBER		EFFECTIVE DATE:	
CARRIER	NAIC CODE		

ADDITIONAL REMARKS

THIS ADDITIONAL REMARKS FORM IS A SCHEDULE TO ACORD FORM,
FORM NUMBER: 25 **FORM TITLE:** CERTIFICATE OF LIABILITY INSURANCE

The General Liability policy includes a blanket notice of cancellation to certificate holders endorsement, providing for 30 days' advance notice if the policy is canceled by the company other than for nonpayment of premium, 10 days' notice after the policy is canceled for nonpayment of premium. Notice is sent to certificate holders with mailing addresses on file with the agent or the company.

Umbrella Liability is follow form

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

**OFFICE USE ONLY
CERTIFICATION OF FILING**

Certificate Number:
2019-465838

Date Filed:
03/20/2019

Date Acknowledged:
03/29/2019

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.
WorkQuest
Austin, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.
Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.
E-19-054
Guard Rail Contract

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	DuTerroil, Gibson	Austin, TX United States	X	
	Weber, Jr., Fred M.	Austin, TX United States	X	
	Crowe, Tommy	Austin, TX United States	X	
	Foreman, Peggy	Austin, TX United States	X	
	Luna, John	Austin, TX United States	X	
	Miller, Brian	Austin, TX United States	X	
	Nash, Jack	Austin, TX United States	X	
	Williams, Donnie	Austin, TX United States	X	

5 Check only if there is NO Interested Party.

6 UNSWORN DECLARATION

My name is _____, and my date of birth is _____.

My address is _____, _____, _____, _____, _____.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in _____ County, State of _____, on the ____ day of _____, 20____.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:
2019-465838

Date Filed:
03/20/2019

Date Acknowledged:

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

WorkQuest
Austin, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

E-19-054
Guard Rail Contract

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	DuTerroil, Gibson	Austin, TX United States	X	
	Weber, Jr., Fred M.	Austin, TX United States	X	
	Crowe, Tommy	Austin, TX United States	X	
	Foreman, Peggy	Austin, TX United States	X	
	Luna, John	Austin, TX United States	X	
	Miller, Brian	Austin, TX United States	X	
	Nash, Jack	Austin, TX United States	X	
	Williams, Donnie	Austin, TX United States	X	

5 Check only if there is NO Interested Party.


6 UNSWORN DECLARATION

My name is Fred M. Weber, Jr., and my date of birth is November 23, 1959.


My address is 1011 East 53rd 1/2 Street, Austin, Texas, 78751, USA.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in Travis County, State of Texas, on the 20th day of March, 2019.
(month) (year)


Signature of authorized agent of contracting business entity
(Declarant)

STATE OF TEXAS §
 §
COUNTY OF HIDALGO §



**FIRST AMENDMENT TO SERVICE CONTRACT
(C-18-082-04-24)**

This **AMENDMENT** to Service Contract for “**Purchase Guardrail Materials and/or Turnkey Solutions**” for **Hidalgo County**” and **Workquest** is made this **04th** day of **December, 2018**, between the parties, as follows:

WHEREAS, on April 24, 2018, Hidalgo (“County”) entered into Service Contract with TIBH Industries, Inc. (“Company”), in which County would use the service of purchase of guardrails materials and/or turnkey solutions as described in the contract.

WHEREAS, Company, has notified County of the recent change of name of Company to Workquest, a certificate of name change recorded in the Office of the Secretary of State under Document Number 834218300002 and;

WHEREAS, the parties desire to amend the Contract as hereinafter provided.

NOW THEREFORE, for and in consideration of the terms and provisions set forth herein, for other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, County and Company hereby agree to the following amendment to the Contract:

1. **Workquest** shall be the name of the company and the name of **Workquest** shall be substituted throughout the Contract in lieu of the name of TIBH Industries, Inc. wherever the name of TIBH Industries, Inc. appears in the Contract.
2. Except as modified herein, all terms and conditions of the Contract, as amended, remain in full force and effect and Company and County ratify and confirm the terms and provisions of the Contract as amended.

EXECUTED IN DUPLICATE ORIGINALS and effective as of the day and year first written above.

Workquest


By: Rosa M Valdez
Printed Name: Rosa M Valdez
Title: Regional Mktg Manager

HIDALGO COUNTY, TEXAS

By: Ramon Garcia
Ramon Garcia, County Judge

ATTEST:

By: Arturo Guajardo
Arturo Guajardo, Jr., County Clerk



APPROVED BY
COMMISSIONERS' COURT
ON: 12/4/18 me

APPROVED AS TO FORM:
Hidalgo County Office of District Attorney
Ricardo Rodriguez, Jr.

By: VM Garza
Victor M. Garza
Assistant District Attorney

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

**OFFICE USE ONLY
CERTIFICATION OF FILING**

Certificate Number:
2018-422991

Date Filed:
11/06/2018

Date Acknowledged:

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.
WorkQuest
Austin, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.
Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.
C-18-082
Purchase guardrail materials and/or turnkey solutions

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	DuTerroil, Gibson	Austin, TX United States	X	
	Weber, Jr., Fred M.	Austin, TX United States	X	
	Crowe, Tommy	Austin, TX United States	X	
	Foreman, Peggy	Austin, TX United States	X	
	Luna, John	Austin, TX United States	X	
	Miller, Brian	Austin, TX United States	X	
	Nash, Jack	Austin, TX United States	X	
	Williams, Donnie	Austin, TX United States	X	

5 Check only if there is NO Interested Party.


6 UNSWORN DECLARATION

My name is Fred M. Weber, Jr., and my date of birth is 11/23/1959.

My address is 1011 East 53rd 1/2 Street, Austin, Texas, 78751, USA.
(street) (city) (state) (zip code) (country)


I declare under penalty of perjury that the foregoing is true and correct.

Executed in Travis County, State of Texas, on the 6th day of November 2018.
(month) (year)


 Signature of authorized agent of contracting business entity
(Declarant)

THE STATE OF TEXAS §
§
COUNTY OF HIDALGO §

SERVICE CONTRACT
C-18-082-04-24



THIS CONTRACT is made and entered into this 24th day of April 2018 by and between the **County of Hidalgo, Texas** ("County"), and TIBH Industries, Inc. ("Company") acting by and through **CRP, RGR Industries, Inc.**, ("Provider"); and

WHEREAS, the Texas Human Resources Code, Section 122.017, authorizes the State to Purchase services and products produced by persons with disabilities under the provisions of Chapter 122 Tex. Human Res. Code and establishes procedures for such purchases (hereinafter referred to as the State Use Program); and

WHEREAS, the Texas Workforce Commission has promulgated rules for the State Use Program at Title 40, Texas Administrative Code, Chapter 806; and

WHEREAS, Hidalgo County desires to "**Purchase Guardrail Materials and/or Turnkey Solutions**", as more particularly described in the attached Exhibit "A" (the "Services"); and

WHEREAS, TIBH and the Texas Workforce Commission acting through Provider shall provide services in accordance with the specifications attached as Exhibits "A" and "B" ("CRP Pricing") respectively, and incorporated herein for all purposes; and

WHEREAS, in recognition of and in consideration of Company and Provider's agreement to perform the Services in accordance with specifications, the Commissioners Court of County awarded the project to Company.

NOW, THEREFORE, in mutual consideration of the foregoing and the further consideration of the following, the parties hereto agree as follows:

1. County, Company and Provider hereby agree that this Contract is entered into in

order to provide the Services to **Hidalgo County**. This Contract does not extend to any third parties any duties or benefits conferred in any manner hereunder or otherwise.

2. Company and Provider hereby promise and agree to render and provide, during the term of this Contract, and shall be obligated to render and provide the Services in accordance with the RFB Packet within **Hidalgo County** following a request for Services by the **County** or its designated agent. Company and Provider agree in performing the Services that it will use proper professional standards, comply with any and all appropriate laws and regulations in providing the Services, and devote such time as is necessary to safely and efficiently provide the Services.

3. This Contract shall be for a period of One (1) year, **(on an as needed basis)**, commencing on May 01, 2018 (or upon Commissioner's Court Approval and fully executed document), and expiring on April 30, 2019, and may be extended at the sole discretion of the County for an additional two (2) one (1) year term under the same rates, terms and conditions. Hidalgo County also reserves the right to continue this sealed bid for an additional sixty (60) day grace period at the end of the contract term for unforeseen delay of award for the next term and contingent upon cost remaining unchanged.

4. As a condition of this Contract, Company and Provider shall hold and maintain throughout the term of this Contract all licenses and permits required, or which may be required by any authority during the term hereof to provide the Services. If such license or permit is suspended or revoked, this Agreement shall automatically be terminated and Company and Provider shall immediately notify the County.

5. All trucks or vehicles operated by the Company/Provider to perform the Services shall contain all equipment required by any authority to operate on streets and roads and all persons in the employ of Company/Provider who operate such trucks or vehicles shall have the required licenses, qualifications, skill and expertise to perform such Services and shall comply with all laws, rules and regulations prescribed by any agency or authority having jurisdiction with regard to the operation of such trucks or vehicles in providing the Services.

6. As consideration for rendering the Services provided for in this Contract, the County agrees to pay Company the amounts specified in Exhibit "B" attached hereto payable against written invoice submitted by Company in accordance with the Texas Prompt Payment Act, Tex. Govt. Code Ch. 2251.

7. Company/Provider shall provide insurance in force on all its vehicles and all persons connected with providing services under this Contract naming County as an additional insured (with the coverages and in the amounts described in Exhibit "C" attached hereto and incorporated herein at this point for all purposes), and shall furnish to County certificates of such insurance coverage.

8. Company/Provider shall provide a sufficient number of trucks, vehicles, personnel, and equipment available to safely and efficiently provide the Services.

9. **Company/Provider shall indemnify and hold harmless County, its elected officials, employees and agents from any and all claims, damages, losses, and expenses including attorney's fees for the defense of any action against County arising out of, resulting from, or connected with the provision of the Service by Company/Provider under this Contract. Said indemnity shall cover any act or failure to act by the Company/Provider, its agents or employees.**

10. This Contract shall not be assignable in whole or in part by either party without the prior written consent of the other party.

11. It is expressly agreed that this Contract and the performance by the parties hereunder does not create any agency relationship or master-servant relationship that County has no supervision of the performance of the Services provided by Company/Provider, and that Company/Provider is an independent contractor under this Contract.

12. Any notice required or permitted to be given hereunder shall be in writing and shall be delivered personally or sent by certified mail, postage prepaid, as set forth below:

If to County: **The County of Hidalgo**
 Attn: County Judge
 100 E. Cano
 Edinburg, Texas 78539

If to Company: **TIBH INDUSTRIES, INC.**
 Attn: Rosa M. Valdez
 1011 E 53 ½ Street
 Austin, TX 78751

13. In case any one or more of the provisions contained in this Agreement shall for any reason be held to be invalid, illegal or unenforceable in any respect, such invalidity, illegality, or unenforceability shall not affect any other provision thereof and this Agreement shall be construed as if such invalid, illegal, or unenforceable provision had never been contained herein.

14. This Agreement may be terminated by County without cause upon thirty (30) days written notice.

15. This Agreement shall be binding upon and inure to the benefit of and be enforceable by the parties hereto and their respective heirs, executors, administrators, legal representatives, successors, and assigns where permitted by this Agreement.

16. This Agreement shall be governed by and construed in accordance with the laws of the State of Texas and shall be performable in Hidalgo County.

17. In the event that, during any term hereof, the Commissioners Court does not appropriate sufficient funds to meet the obligations of County under this Agreement, County may terminate this Agreement upon ninety (90) days written notice to Provider and Company. County agrees, however, to use reasonable efforts to secure funds necessary for the continued performance of this Agreement. The parties intend this provision to be a continuing right to terminate this Agreement at the expiration of each budget period of County.

18. This Agreement contains the entire contract between the parties hereto, and each party acknowledges that neither has made (either directly or through any agent or representative) any representation or agreement in connection with this Agreement not specifically set forth herein. This Agreement may be modified or amended only by an agreement in writing executed by the parties hereto, and not otherwise.

19. Nothing in this Agreement is intended to and County does not hereby waive, release or relinquish any right to assert any of the defenses County enjoys by virtue of the state or federal constitution, laws, rules or regulations, and any sovereign, official or qualified immunity available to County as to any claim or action of any person, entity, or individual against County.

20. Company/Provider, including subcontractors, assignees and successors in interest, ensures that no person shall on the grounds of race, religion, color, national origin, sex, age, disability, or any other protected class under law, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination or retaliation under any federally or non-federally funded program or activity when providing any services described herein under this contract/agreement.

21. The parties hereto covenant and agree that they will execute each such other and further instruments and documents as are or may become necessary or convenient to effectuate and carry out the terms of this contract/agreement.

EXECUTED and effective as of the day and year first written above.

COUNTY OF HIDALGO

Ramon Marcia
Ramon Garcia, County Judge

APPROVED BY
COMMISSIONERS' COURT
ON: 4/24/18 mrs

ATTEST

Arturo Guajardo
Arturo Guajardo, County Clerk



Note: Need signature for the Provider as well.

Company: TIBH Industries, Inc.

By: Rosa M. Valdez

Printed Name: Rosa M. Valdez /

Title: Regional Marketing Manager / CEO

Provider: RGR Industries, Inc.

By: [Signature]

Printed Name: Ricardo Guerra

Title: President

Approved By Commissioners Court On: _____

APPROVED AS TO FORM:
Hidalgo County Office of District Attorney
Ricardo Rodriguez, Jr.

By: [Signature]
Victor M. Garza
Assistant District Attorney

EXHIBIT “A”

SPECIFICATIONS

#

ATTACHMENT A SCOPE OF WORK

HARDWARE:

Perform "Metal Beam Guard Fence and Elements Repair".

GENERAL

Prior to beginning operations, a conference between representatives of the County and the Community Rehabilitation Program (CRP) will be arranged. In this meeting, the CRP will outline the proposed method of accomplishing this work.

The CRP is to visit the site to make its own examination of the work areas. The CRP will carefully examine these specifications and secure from the Department any additional information that may be essential for a clear and full understanding of the work.

Scheduled work that falls on a National Holiday will be performed on the following work day. National Holidays as defined in the "Texas Standard Specification 2014" are January 1, the last Monday in May, July 4, the first Monday in September, the fourth Thursday in November, December 24 and December 25.

The CRP is responsible for damage to County equipment, plants, shrubs, and County employee vehicles caused by its maintenance activities.

All lost and found items will be turned over to the County Representative.

The CRP is responsible for its employees reporting daily any needed repairs. This information will be reported to the County's representative.

All personal protective equipment (PPE) will be provided by the CRP.

Clear and remove from all work sites, surplus and waste materials and leave the site in a neat and aesthetically pleasing condition.

Work is on an as-needed basis and as directed by the County.

Perform work Monday through Friday during daylight hours unless otherwise approved. Close no more than one (1) lane at a time

If closing a lane is necessary, closure time will be Monday through Thursday, 9:00 A.M. to 3:00 P.M. and Friday, 9:00 A.M. to 12:00 P.M. (noon).

The CRP keeps all unusable salvaged material. Material that is deemed usable by the County shall be returned to Hidalgo County.

EQUIPMENT AND LABOR

The CRP will not be allowed to begin work until all equipment has been inspected, and found to be in good working condition, and deemed safe by the County.

BARRICADES, SIGNS, AND TRAFFIC HANDLING

The CRP will furnish and install all signs, barricades and other incidentals necessary for proper traffic control, in accordance with the 2011 "Texas Manual on Uniform Traffic Control Devices and as directed. All warning signs will be factory made and in satisfactory condition.

#

ITEM 502 BARRICADES, SIGNS, AND TRAFFIC HANDLING

The CRP shall provide to the Engineer a letter certifying that all truck-mounted attenuators (TMA) used on the contract that were purchased on or after October 1, 1998, have been found to be crashworthy using the criteria outlined in the National Cooperative Highway Research Program (NCHRP) Report 350. If the TMA was purchased prior to October 1, 1998, a letter certifying crashworthiness using the criteria outlined in either (NCHRP) reports 230 or 350 shall be provided to the Engineer.

Provide flagmen properly attired in a white hard hat, approved safety vest and stop/slow paddle. Provide two-way radios in areas where flagmen do not have visual contact with one another or cannot communicate with one another.

Provide shadow vehicles equipped with Truck Mounted Attenuators (TMA) when performing work on the expressway as shown on Traffic Control Plan (TCP) standards (2 series).

Limit lane closures to a maximum of three (3) miles. If more than one (1) lane closure location is desired, provide a minimum of a 2 mile passing zone between locations. Provide a separate sign set up for each location.

Ensure equipment and materials are a minimum of 30 feet from the edge of the travel lane during non-working hours.

Erect signs in locations not obstructing the traveling public's view of the normal roadway signing or necessary sight distance at intersections and curves.

All signs will conform to the Roadside Traffic Control Plan (RS-TCP-05) (see attached).

ITEM 544 "Guardrail End Treatments"

Label "end treatment type" on backside of unit at time of installation.

ITEM 545 CRASH CUSHION ATTENUATORS

Damaged crash cushion attenuators beyond repair will be replaced with the same attenuator model or similar. Exemptions to the similar model replacements will be determined by the Engineer to satisfy crash test levels (TL-2 for roadways 45 mph or less and TL-3 for roadways greater than 50 mph).

Crash cushions needing to be moved and reset will be paid under Item 545-6003 regardless of attenuator model. Foundations, materials, incidentals, etc. is subsidiary to this item. Crash cushions needing to be removed will be paid under Item 545-6005 regardless of attenuator model. Removing, materials, hauling, incidentals, etc. is subsidiary to this item.

The CRP will have 24 hours to respond via e-mail, phone, fax, etc. confirming the request by the County to repair damaged facility. The CRP will have 24 hours to contact and advise Hidalgo County of timeline or schedule for work to be completed/performed This includes delivery of materials.

The CRP is to return any used materials to the County. Any material deemed salvageable by the State will also be returned.

The CRP is to avoid damaging utilities during guard fence operations by contacting utility companies and locating all underground lines in the vicinity of the work.

The CRP will furnish crew(s) and equipment capable of maintaining work in a continuous manner for the completion of the work on schedule, as approved.

The CRP will use care to avoid disturbing pavement surfaces. Any damaged caused by the normal operation outside the work area will be paid by the CRP.

#

Furnish and place topsoil to repair areas disturbed by construction operations, as approved. The topsoil and placement will not be paid for directly, but will be considered subsidiary to the various bid items. (?)

ITEM 7650 CLEAN TRAFIC ATTENUATORS

Remove debris at locations shown on the plans, or as directed by the Engineer. Dispose of debris off the right of way. (?)

MEASUREMENT

The unit of measurement for "Purchase Guardrail Materials and/or Turnkey Solutions" will be based upon the various Items of work as specified on Attachment B.

PAYMENT

Work performed as prescribed by this specification, measured as provided under "Measurement" will be paid for at the contract unit price, which will be full compensation for furnishing all labor, equipment, materials and incidentals necessary to complete the work. Payment will be made once each month after satisfactory completion of work.

POINT OF CONTACT (?)

	Contact	Telephone No
H. C. Precinct 1		
H. C. Precinct 2		
H. C. Precinct 3		
H. C. Precinct 4		



Item 540 Metal Beam Guard Fence

1. DESCRIPTION

Furnish, install, replace, or adjust metal beam guard fence consisting of metal beam rail elements, hardware, blocks, and support posts.

2. MATERIALS

Provide samples of metal beam rail elements, terminal sections, bolts, and nuts for compliance testing according to Tex- 708-I and Tex-713-I to verify physical and chemical properties meet AASHTO M 180 when directed.

Obtain materials at the locations shown on the plans when the plans designate that the Department will furnish materials.

- 2.1. **Metal Beam Rail Elements.** Furnish new metal beam rail elements, transitions, anchor sections, and terminals that meet the requirements of Table 1 and are from a manufacturer on the Department's MPL of rail element manufacturers.

Type I or II is required, unless otherwise shown on the plans. Base metal for metal beam rail elements must not contain more than 0.04% phosphorous or more than 0.05% sulfur.

Warped or deformed rail elements will be rejected.

**Table 1
Rail Element Requirements**

Specification	AASHTO M 180
Class	A— Base metal nominal thickness 0.105 in. B— Base metal nominal thickness 0.135 in.
Type	I— Zinc-coated 1.80 oz. per square foot minimum single-spot. II— Zinc-coated 3.60 oz. per square foot minimum single-spot. IV— Weathering Steel (required when shown on the plans).
Shape	W-Beam Thrie Beam W-Beam to Thrie Beam Transition
Markings	Permanently mark each metal beam rail element with the information required in AASHTO M 180. In addition, permanently mark all curved sections of metal beam rail element with the radius of the curved section in the format "R=XX ft." Markings must be on the back of the metal beam rail section away from traffic and visible after erection.

- 2.2. **Posts.** Furnish new round timber, rectangular timber, or rolled steel section posts in accordance with details shown on the plans and the following requirements:

- 2.2.1. **Timber Posts.** Meet the requirements of DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.

- 2.2.2. **Steel Posts.** Provide rolled sections conforming to the material requirements of ASTM A36. Drill or punch posts for standard rail attachment as shown on the plans. Galvanize according to Item 445, "Galvanizing." Low-fill culvert posts may be fabricated as galvanized "blanks" with the rail hole and the final height field
- fabricated. Treat all exposed post surfaces caused by the field fabrication in accordance with Section 445.3.5., "Repairs."
- 2.3. **Blocks.** Furnish new rectangular timber or composite blocks in accordance with details shown on the plans and the following requirements:
- 2.3.1. **Timber.** Meet the requirements of DMS-7200 "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.
- 2.3.2. **Composite.** Meet the requirements of DMS-7210 "Composite Material Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer on the Department's MPL of composite material blocks and posts.
- 2.4. **Fittings.** Furnish new fittings (bolts, nuts, and washers) according to the details shown on the plans and galvanized according to Item 445, "Galvanizing."
- 2.5. **Terminal Connectors.** Furnish new terminal connectors, where required, meeting the material and galvanizing requirements specified for metal beam rail elements.
- 2.6. **Concrete.** Furnish concrete for terminal anchor posts meeting the requirements for Class A concrete as required in Item 421, "Hydraulic Cement Concrete."
- 2.7. **Curb.** If indicated in the details, furnish the curb shown with metal beam guard fence transition as required by Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- 2.8. **Terminal Anchor Posts.** Furnish new terminal anchor posts from steel conforming to the material requirements of ASTM A36. Fabricate posts according to Item 441, "Steel Structures." Galvanize terminal anchor posts after fabrication according to Item 445, "Galvanizing."
- 2.9. **Driveway Terminal Anchor Posts.** Furnish new terminal anchor posts from steel conforming to the material requirements of ASTM A36. Fabricate posts according to Item 441, "Steel Structures." Galvanize terminal anchor posts after fabrication according to Item 445, "Galvanizing."
- 2.10. **Downstream Anchor Posts.** Furnish new terminal anchor posts consisting of new rectangular timber and new steel foundation tubes according to details shown on the plans.
- 2.11. **Downstream Anchor Hardware.** Furnish new hardware (brackets, plates, struts, cable, etc.) according to the details shown on the plans and galvanized according to Item 445, "Galvanizing."
- 2.12. **Controlled Released Terminal (CRT) Posts.** Furnish new CRT posts according to the details shown on the plans and conforming to the requirements of DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence." Purchase from a manufacturer or supplier on the Department's MPL of timber treating plants and suppliers.

3. CONSTRUCTION

Install posts and rail elements according to details shown on the plans.

- 3.1. **Posts.** Install posts by either drilling or driving.
- 3.1.1. **Drilling.** Drill holes and set posts plumb and firm to the line and grade shown. Backfill posts by thoroughly compacting material to the density of adjacent undisturbed material.

- 3.1.2. **Driving.** Drive posts plumb with approved power hammers (steam, compressed air, vibratory, or diesel) or gravity hammers to the line and grade shown while preventing damage to the post. Use pilot holes when required and approved. Determine the size and depth of pilot holes based on results of the first few posts
- driven. Thoroughly tamp loosened soil around the post, fill voids with suitable material, and thoroughly compact to the density of adjacent undisturbed material.
- 3.2. **Rail Elements.** Erect metal beam rail elements to produce a smooth, continuous rail paralleling the line and grade of the roadway surface or as shown on the plans. Bolt rail elements end-to-end and lap splices in the direction of traffic. Field-drill or punch holes in rail elements for special details, only when approved.
- 3.3. **Short Radius.** Special rail fabrication with a required radius must be as shown on the plans.
- 3.4. **Terminal Anchor Posts.** Embed terminal anchor posts in concrete, unless otherwise shown on the plans.
- 3.5. **Galvanizing Repair.** Repair all parts of galvanized steel posts, washers, bolts, and rail elements after erection where galvanizing has become scratched, chipped, or otherwise damaged. Repair in accordance with Section 445.3.5., "Repairs."
- 3.6. **Guardrail Adjustment.** Work includes vertical adjustment, horizontal shift, and overlap of the rail element to meet the detail shown on the plans.
- 3.7. **Curb.** If indicated in the details, construct the curb shown with metal beam guard fence transition as required by Item 529, "Concrete Curb, Gutter, and Combined Curb and Gutter."
- 3.8. **Driveway Terminal Anchor Posts.** Embed terminal anchor posts in concrete, unless otherwise shown on the plans.
-

4. MEASUREMENT

- 4.1. **Guard Fence.** Measurement will be by the foot of fence. Fence will be measured on the face of the rail in place, from center-to-center of end splice locations.
- 4.2. **Terminal Anchor Sections.** Measurement will be by each section, complete in place, consisting of a terminal anchor post and one 25-ft. section of rail element.
- 4.3. **Transitions.** Transitions for rail connection will be measured by each transition.
- 4.4. **Short Radius.** Measurement will be by the foot to the nearest whole foot along the face of the rail in place, from beginning of radius (first CRT post) to the end of radius.
- 4.5. **Driveway Terminal Anchor Section.** Measurement will be by each section, complete in place, consisting of a driveway terminal anchor post and one 6-ft. section of rail element.
- 4.6. **Downstream Anchor Terminal.** Measurement will be by each section, complete in place, consisting of one W-Beam end section, 2 downstream anchor posts, and one rail section.
- 4.7. **Long Span System.** Measurement will be by the foot of fence. Fence will be measured on the face of the rail, in place, between the first CRT and last CRT posts in the system.

5. **PAYMENT**

The work performed and material furnished in accordance with this Item and measured as provided under "Measurement" will be paid at the unit price bid for "Metal W-Beam Guard Fence" of the post type specified; "Metal Thrie Beam Guard Fence" of the post type specified; "Terminal Anchor Section"; "Metal Beam Guard Fence Transition" of the type specified; "Metal W-Beam Guard Fence Adjustment"; "Metal Thrie Beam Guard Fence Adjustment"; "Terminal Anchor Section Adjustment"; "Transition Adjustment"; "Short Radius"; "Driveway Terminal Anchor Section"; "Downstream Anchor Terminal"; or "Metal Beam Guard Fence (Long Span System)." When weathering steel is required, Type IV will be specified.

Samples furnished to the Department for testing purposes, special backfill materials, and concrete curbs will not be paid directly but are subsidiary to this Item.

- 5.1. **Guard Fence.** The price bid for "Metal W-Beam Guard Fence" or "Metal Thrie Beam Guard Fence" is full compensation for materials, hauling, erection, setting posts in concrete, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.
- 5.2. **Terminal Anchor Section.** When a separate bid item is specified, the price bid for "Terminal Anchor Section" is full compensation for furnishing the rail element, anchor assembly, terminal anchor post, and foundations; installing the rail element anchor assembly and the terminal anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.3. **Transition.** The price bid for "Metal Beam Guard Fence Transition" is full compensation for furnishing nested sections of Thrie Beam; nested sections of W-Beam; Thrie Beam to W-Beam transitional rail piece, posts, concrete, curb, and connections to W-Beam guard fence and bridge rails; Thrie Beam terminal connectors; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.4. **Guardrail Adjustment.** The price bid for "Metal W-Beam Guard Fence Adjustment," "Metal Thrie Beam Guard Fence Adjustment," "Terminal Anchor Section Adjustment," and "Transition Adjustment" is full compensation for furnishing materials not supplied by the Department, drilling holes in posts, hauling, erection, blocks, excavation, backfill, cleaning, salvaging materials, setting rail element anchor assembly and terminal anchor post, removal of rail element, concrete, curb, equipment, labor, tools, and incidentals.
- 5.5. **Short Radius.** The price bid for "Short Radius" is full compensation for furnishing special rail fabricated metal beam guard fence, CRT posts, steel posts, sand barrels, end terminal, cable anchor, materials, hauling, erection, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.
- 5.6. **Driveway Terminal Anchor Section.** The price bid for "Driveway Terminal Anchor Section" is full compensation for furnishing the rail element, driveway anchor assembly, driveway terminal anchor post, and foundations; installing the rail element anchor assembly and the driveway terminal anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.7. **Downstream Anchor Terminal.** The price bid for "Downstream Anchor Terminal" is full compensation for furnishing the rail element, W-Beam end section, guardrail anchor bracket, shelf angle bracket, channel strut, downstream anchor posts, breakaway cable terminal (BCT) cable anchor assembly, and foundations; installing the BCT cable anchor assembly and the downstream anchor post and foundations; excavation and backfilling; and equipment, labor, tools, and incidentals.
- 5.8. **Long Span System.** The price bid for "Metal Beam Guard Fence (Long Span System)" is full compensation for furnishing the rail element, CRT posts, materials, hauling, erection, blocks, driving posts, excavating, backfilling, equipment, labor, tools, and incidentals.



Item 542

Removing Metal Beam Guard Fence

1. DESCRIPTION

Remove existing metal beam guard fence and store at locations shown on the plans or as directed.

2. CONSTRUCTION

Remove rail elements in original lengths. Remove fittings from the posts and the metal rail and then pull the posts. Do not mar or damage salvageable materials during removal.

Completely remove posts and any concrete surrounding the posts. Furnish backfill material and backfill the hole with material equal in composition and density to the surrounding soil unless otherwise directed.

Cut off or bend down deadman eyebolts to an elevation at least 1 ft. below the new subgrade elevation and leave in place along with the deadman.

Neatly stack salvaged materials to be retained by the Department at designated sites shown on the plans. Properly dispose of unsalvageable materials in accordance with federal, state, and local regulations. Repair or replace Contractor-damaged salvageable material at the Contractor's expense.

3. MEASUREMENT

This Item will be measured by the foot for "Remove Metal Beam Guard Fence" in its original position. Measurement will be made along the face of the rail, in place, including metal beam guard fence transitions, from center-to-center of end posts and from terminal points shown on the plans.

When "Remove Terminal Anchor Section" is specified as a separate bid item, measurement will be made for each removed section. A terminal anchor section consists of one post, one 25-ft. rail element, and associated hardware.

When "Remove Downstream Anchor Terminal" is specified as a separate bid item, measurement will be made for each removed section. Downstream anchor terminal consists of 2 posts, 1 section, and associated hardware.

4. PAYMENT

The work performed and measured as provided under "Measurement" will be paid at the unit price bid for "Remove Metal Beam Guard Fence," "Remove Terminal Anchor Section," and "Remove Downstream Anchor Terminal." This price will be full compensation for removing materials; loading, hauling, unloading, and storing or disposal; furnishing backfill material; backfilling postholes; and equipment, labor, tools, and incidentals.

Removal of curb associated with the metal beam guard fence transitions will not be paid directly but will be subsidiary to this Item.



Item 543

Cable Barrier System

1. DESCRIPTION

Furnish and install a cable barrier system and cable barrier terminal sections at the locations shown on the plans.

2. MATERIALS

Furnish a new cable barrier system and cable barrier terminal sections in accordance with the details shown on the plans and on the manufacturer's shop drawings, or equal as approved. Cable barrier systems approved for use have passed NCHRP Report 350 or MASH of the test level specified (TL-3, TL-4, etc.) with a maximum deflection of 8 ft.

Furnish pre-stretched cable.

Furnish Class A concrete in accordance with Item 421, "Hydraulic Cement Concrete."

Furnish delineators as shown on the plans and in accordance with Item 658, "Delineator and Object Marker Assemblies."

3. CONSTRUCTION

Install cable barrier system in accordance with the details, dimensions, and requirements shown on the plans and manufacturer's recommendations. Install cable barrier terminal sections in accordance with the details shown on the plans and manufacturer's recommendations.

Place posts into steel sleeves in a concrete foundation unless otherwise shown on the plans. Locate terminal sections at locations as shown on the plans. Repair or replace damaged parts immediately. Provide an installation and repair manual specific to the cable barrier system and cable barrier terminal sections.

Locate barrier delineators at a maximum spacing of 100 ft. and according to TMUTCD or as shown on the plans. Install barrier delineators in accordance with manufacturer's recommendations.

3.1. **Training.** Provide training as specified by the Department.

4. MEASUREMENT

This Item will be measured by the foot of cable barrier system and by each cable barrier terminal section installed.

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.), "Cable Barrier System" of the test level specified (TL-3, TL-4, etc.) and post spacing specified, and "Cable Barrier Terminal Section" of the test level specified (TL-3, TL-4, etc.). This price is full compensation for furnishing cable barrier system, cable barrier terminal section, concrete, delineators, equipment, labor, tools, and incidentals. Delineators will not be measured or paid for directly but will be considered subsidiary to this Item



Item 544

Guardrail End Treatments

1. DESCRIPTION

Furnish and install, move, or remove guardrail end treatments.

2. MATERIALS

Furnish new materials from the Department's MPL of rail element manufacturers. Obtain materials at the location shown on the plans when furnished by the Department.

3. CONSTRUCTION

Install guardrail end treatments in accordance with manufacturer's assembly and installation requirements and the details shown on the plans. Provide the Engineer with manufacturer's installation and repair manuals specific to the guardrail end treatment.

Move or remove guardrail end treatments in accordance with the plans and as directed. Deliver salvageable materials in accordance with the plans or as directed. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.

4. MEASUREMENT

This Item will be measured by each guardrail end treatment.

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided for under "Measurement" will be paid for at the unit price bid for "Guardrail End Treatment (Install)" of the post and type specified where applicable, "Guardrail End Treatment (Move and Reset)," or "Guardrail End Treatment (Remove)." This price is full compensation for foundations, materials, stockpiling, disposal of unsalvageable materials, equipment, labor, tools, and incidentals.

Payment for "Guardrail End Treatment (Move and Reset)" will include each guardrail end treatment removed from a stockpile or from an existing location and reset in a new location as detailed on the plans or as directed.

Payment for "Guardrail End Treatment (Remove)" will include each guardrail end treatment removed from an existing location and stockpiled at the location designated on the plans, disposed, or as otherwise directed.



Item 545

Crash Cushion Attenuators

1. DESCRIPTION

Furnish and install, move and reset, or remove crash cushion attenuators.

2. MATERIALS

2.1. **Crash Cushion Attenuators.** Furnish new crash cushion attenuators in accordance with the details shown on the plans and on the manufacturer's shop drawings. Obtain crash cushion attenuators at the location shown on the plans when furnished by the Department.

2.2. **Concrete.** Furnish Class S concrete for pads that meets Item 421, "Hydraulic Cement Concrete."

3. CONSTRUCTION

Perform the following as shown on the plans:

- 3.1. **Installation.** Assemble and install crash cushion attenuators in accordance with the details shown on the plans and manufacturer recommendations. Obtain assembly and installation information for the crash cushion attenuators from the manufacturer and provide the Engineer with an installation and repair manual specific to the crash cushion attenuators.
- 3.2. **Moving and Resetting.** Remove crash cushion attenuators from a stockpile or from an existing location and reset in a new location as shown on the plans or as directed. Install crash cushion attenuators in accordance with pertinent standards and manufacturer recommendations. Provide additional materials to complete the installation as needed. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.
- 3.3. **Removal.** Remove crash cushion attenuators from an existing location and stockpile in the area designated on the plans, as directed, or dispose. Clean and repair salvageable units before inspection and return them to the Department. Dispose of unsalvageable materials in accordance with federal, state, and local regulations.
-

4. MEASUREMENT

This Item will be measured by each crash cushion attenuator.

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided for under "Measurement" will be paid for at the unit price bid for "Crash Cushion Attenuator (Furnish and Install, Designated Source, Move and Reset, Stockpile, or Remove)" of the category, width (N or W), and test level. This price is full compensation for foundations; materials, stockpiling, moving and removing, hauling, installing and resetting, disposal of unsalvageable materials, equipment, labor, tools, and incidentals.

- 5.1. **Furnish and Install.** This price is full compensation for furnishing and installing crash cushion attenuator.
- 5.2. **Designated Source.** This price is full compensation for delivering and installing Department-furnished crash cushion attenuator from a designated source.

- 5.3. **Move and Reset.** This price is full compensation for moving crash cushion attenuator installations on the project from one location to another (including disassembly and reassembly costs), moving crash cushion attenuator from an installation on the project to a temporary storage area (including disassembly costs), and moving crash cushion attenuator from a temporary storage area to an installation site on the project (including assembly costs).
- 5.4. **Stockpile.** This price is full compensation for removing crash cushion attenuator from the project and delivering to the Department stockpile area shown on the plans or as directed.
- 5.5. **Remove.** This price is full compensation for removing crash cushion attenuator from the project and retained by the Contractor.



Item 550

Chain Link Fence

1. DESCRIPTION

Furnish, install, remove, repair, or replace chain link fence and gates.

2. MATERIALS

Furnish certification from the chain link fence materials manufacturer stating that all fencing materials comply with the requirements of this Item before installation of the fence. Use only new materials.

2.1. General. Furnish materials in accordance with the following:

- Item 421, "Hydraulic Cement Concrete," Class B
- Item 445, "Galvanizing"

2.2. Wire Fabric. Provide wire fabric with:

- 9 gauge (0.148 in. diameter) steel wire with a minimum breaking strength of 1,290 lb. meeting ASTM A392 Class I or ASTM A491;
- mesh size of 2 in. \pm 1/8 in. between parallel wires with at least 7 meshes in a vertical dimension of 23 in. along the diagonals of the openings; and
- knuckled selvages at the top and bottom edge of the fabric, unless otherwise shown on the plans.

2.3. Posts. Provide posts of the size and weight shown on the plans. Do not provide rerolled or open-seam posts. Use material for all posts meeting ASTM F1043 Group 1A Regular Grade or Group 1C High Strength.

2.4. Post Caps. Provide malleable iron post caps designed to exclude all moisture. Furnish barbed wire support arms integral with the post caps if barbed wire is shown on the plans. Furnish post caps with an opening for the top rail if top rail is shown on the plans. Post caps must have a 2-in. skirt.

2.5. Gates. Provide gates fabricated from round sections of pipe of the size and weight shown on the plans. Use material for all gate pipes meeting ASTM F1043 Group 1A Regular Grade or Group 1C High Strength. For each gate, include:

- corner and tee fittings of malleable iron or pressed steel with means for attaching diagonal bracing members;
- hinges of malleable iron allowing a full 180° swing, easily operated by one person;
- ball-and-socket-type bottom hinges that do not twist or turn from the action of the gate and prevent the closed gate from being lifted off the hinges;
- a positive stop that prevents any portion of the gate from swinging over an adjacent traffic lane;
- malleable iron pulley systems for roll type gate (only when required);
- diagonal braces consisting of 3/8-in. diameter cable with turnbuckles, 2 to each gate frame, and, for vehicle gates, a vertical pipe brace of the size and weight shown on the plans at the center of each gate leaf;
- latches of malleable iron or steel for single gates with a single-fork latch and padlock eye that will keep the gate closed;
- 2 fork latches mounted on a center plunger rod with a padlock eye for double-leaf gates;
- holdbacks for each leaf of vehicular gates, with a semi-automatic holdback catch anchored at least 12 in. into a 12-in. diameter by 24-in. deep concrete footing; and

- a malleable iron center rest, designed to receive the plunger rod anchored as shown on the plans for all double-leaf gates.
- 2.6. **Top Rail.** Use material meeting ASTM F1043 Group 1A or 1C for all top rail pipes. Provide 1.660 in. OD top rail manufactured from Group 1A standard weight (Schedule 40) steel pipe weighing 2.27 lb. per foot or from Group 1C high-strength pipe weighing 1.84 lb. per foot when shown on the plans. Provide pipe in sections at least 18 ft. long joined with outside steel sleeve couplings at least 6 in. long with a minimum wall thickness of 0.70 in. Use couplings designed to allow for expansion of the top rail.
- 2.7. **Tension Wire.** Use 7 gauge (0.177-in.) carbon steel wire with a minimum breaking strength of 1,950 lb. for the bottom edge of all fence fabric, and for the top edge of fence fabric when a top rail is not specified.
- 2.8. **Truss Bracing.** Provide truss bracing as shown on the plans.
- 2.9. **Cables.** Provide 7-wire strand cables manufactured of galvanized annealed steel at least 3/8 in. in diameter.
- 2.10. **Barbed Wire.** Provide 3 strands of twisted 12.5 gauge barbed wire with 2-point, 14 gauge barbs spaced approximately 5 in. apart conforming to ASTM A121 or ASTM A585 when specified on the plans.
- 2.11. **Barbed Wire Support Arms.** Provide support arms at an angle of 45° from vertical, with clips for attaching 3 strands of barbed wire to each support arm and sufficient strength to support a 200-lb. weight applied at the outer strand when barbed wire is specified on the plans.
- 2.12. **Stretcher Bars.** Provide stretcher bars made of flat steel at least 3/16 × 3/4 in. and not more than 2 in. shorter than the fabric height. Provide one stretcher bar for each gate and end post and 2 stretcher bars for each corner and pull post.
- 2.13. **Grounds.** Provide copper-clad steel rods 8 ft. long with a minimum diameter of 5/8 in., or other UL-listed ground rods.
- 2.14. **Miscellaneous Fittings and Fasteners.** Furnish enough fittings and fasteners to erect all fencing materials in a proper manner. Furnish fittings for posts from pressed or rolled steel, forged steel, malleable iron or wrought iron of good commercial quality spaced as shown on the plans.
- 2.15. **Coatings.** Hot-dip galvanize all materials unless specified otherwise in this Item or on the plans. Fabric, tension wire, and barbed wire may be aluminum-coated or alloy-coated if approved. Additionally coat all material except bolts, nuts, washers, and pipe material with thermally fused polyvinyl chloride (PVC) in accordance with ASTM F668, Class 2b, meeting the specified color when shown on the plans.
 - 2.15.1. **Fabric.**
 - 2.15.1.1. **Galvanizing.** Hot-dip galvanize in accordance with ASTM A392, Class I.
 - 2.15.1.2. **Aluminum Coating.** Aluminum-coat in accordance with ASTM A491.
 - 2.15.1.3. **Alloy Coating.** Coat with zinc-5% aluminum-mischmetal alloy (Zn-5Al-MM) in accordance with ASTM F1345, Class I.
 - 2.15.2. **Posts, Braces, and Gates.**
 - 2.15.2.1. **Standard Weight (Schedule 40) Pipe.** Hot-dip galvanize inside and outside according to ASTM F1043 (1.8 oz./sq. ft. galvanized zinc weight).
 - 2.15.2.2. **High Strength Pipe.** Hot-dip galvanize before or after forming pipe according to ASTM F1043 Group 1C and as follows:
 - Outside—minimum 0.9 oz./sq. ft. galvanized zinc weight with a verifiable polymer overcoat.

- Inside—minimum 0.9 oz./sq. ft. galvanized zinc weight before forming, or minimum 0.3 mils zinc-based coating after forming containing a minimum 90% zinc dust, by weight.

- 2.15.2.3. **Optional Additional Coating.** Additionally coat all pipe material with 10 mils minimum thermally fused PVC according to ASTM F1043, meeting the specified color when shown on the plans.
- 2.15.3. **Fittings, Bolts, and Other Miscellaneous Hardware.** Galvanize all fittings, bolts, and miscellaneous hardware in conformance with Item 445, "Galvanizing."
- 2.15.4. **Tension Wire.** Zinc-coat tension wire with a minimum coating of 0.80 oz./sq. ft. or aluminum-coat with a minimum coating of 0.30 oz./sq. ft.
- 2.15.5. **Barbed Wire.** Zinc-coat barbed wire in accordance with ASTM A121 (0.80 oz./sq. ft.) or aluminum-coat in accordance with ASTM A585 (0.30 oz./sq. ft.).
- 2.15.6. **Pull Cable.** Zinc-coat pull cable with a minimum coating of 0.80 oz./sq. ft. of individual-wire surface when tested in conformance with ASTM A116.

3. CONSTRUCTION

Erect the chain link fence to the lines and grades established on the plans. Overall height of the fence when erected is the height above the grade shown.

Repair or replace damaged fence or gates. Remove and replace the post and foundation if posts cannot be repaired by straightening. Return all salvageable material to the location shown on the plans when a fence installation is to be removed in its entirety and not replaced. Backfill all postholes with suitable material. Return the salvaged fence fabric in secured rolls not more than 50 ft. long. Dispose of unsalvageable material.

- 3.1. **Clearing and Grading.** Clear all brush, rocks, and debris necessary for the installation of this fencing.

Stake the locations for corner posts and terminal posts unless otherwise shown on the plans. Follow the finished ground elevations for fencing panels between corner and terminal posts. Level off minor irregularities in the path of the fencing.
- 3.2. **Erection of Posts.** Install posts as shown on the plans. Plumb and permanently position posts with anchorages firmly set before fabric is placed. Brace corner and pull posts as shown on the plans.
- 3.2.1. **Post Spacing.** Space posts as shown in Table 1.

**Table 1
Post Spacing and Placement**

Post Type	Required Spacing or Placement
Line posts	no more than 10 ft. apart
Pull posts	no more than 500 ft. apart and at each change in direction exceeding 20° vertically
Corner posts	at each horizontal angle point

Install cables on all terminal posts and extend to adjacent posts. Install cables on each side of corner and pull posts with a 3/8-in. drop-forged eye-and-eye or eye-and-clevis turnbuckle unless otherwise shown on the plans.

- 3.2.2. **Postholes.** Drill holes for concrete footings for all posts to provide footings of the dimensions shown on the plans.

Penetrate solid rock by at least 12 in. (18 in. for end, corner, gate, and pull posts) or to plan depth where the rock is encountered before reaching plan depth. Drill holes in the solid rock with a diameter at least 1 in. greater than the outside diameter of the post.

Fill the hole in the solid rock with grout consisting of 1 part hydraulic cement and 3 parts clean, well-graded sand after the posts are set and plumbed. If desired, other grouting materials may be used only if approved. Thoroughly work the grout into the hole, leaving no voids. Construct concrete footings from the solid rock to the top of the ground.

- 3.2.3. **Gate Posts.** Align the tops of all gate frames with the fencing top tension wire or top rail. Provide vehicular gates that are greater in overall height than the adjacent fencing by the height necessary to extend to within 2 in. of the pavement between the curbs if curbs are shown on the plans.
- 3.2.4. **Concrete Footings.** Center posts in their footings. Place concrete and compact by tamping or other approved methods. Machine mix all batches of concrete over 1/2 cu. yd. Hand mixing concrete is allowed on batches under 1/2 cu. yd.
- Use forms for footings where the ground cannot be satisfactorily excavated to neat lines. Crown the concrete or grout (for solid rock) to carry water from the post. Keep the forms in place for at least 24 hr. Backfill the footing with moistened material as soon as each form is removed, and thoroughly tamp. Cover concrete with at least 4 in. of loose moist material, free of clods and gravel, immediately after placing concrete. No other curing is required.
- Spread all excess excavated and loose material used for curing neatly and uniformly. Remove excess concrete and other construction debris from the site.
- 3.3. **Erection of Fabric.** Place the fabric with the cables drawn taut with the turnbuckles after all posts have been permanently positioned and anchorages firmly set. Secure one end and apply enough tension to the other end to remove all slack before making attachments. Cut the fabric and independently attach each span at all corner posts and pull posts unless otherwise shown on the plans.
- Follow the finished contour of the site with the bottom edge of fabric located approximately 2 in. above the grade. Grade uneven areas so the maximum distance between the bottom of fabric and ground is 6 in. or less.
- Fasten fabric at 12 in. intervals to the top and bottom tension wires between posts. Fasten the fabric in the same manner when top rail is shown on the plans. Fasten the fabric on gate frames to the top and bottom of the frame at 12 in. intervals. Use steel wire fabric ties of 9 gauge steel or larger. Fasten fabric to terminal posts by steel stretcher bars and stretcher bar bands fitted with carriage bolts and nuts of the size and spacing shown on the plans. Use stretcher bars to fasten end posts, pull posts, corner posts, and gateposts with stretcher bar bands at intervals of no more than 15 in. Attach stretcher bars to terminal posts with 1 x 1/8 in. flat steel bands with 3/8-in. carriage bolts at intervals up to 15 in.
- 3.4. **Electrical Grounds.** Provide at least one electrical ground for each 1,000 ft. of fence, located near the center of the run. Provide additional grounds directly under the point where power lines pass over the fence.
- Vertically drive or drill in the grounding rod until the top of the rod is approximately 6 in. below the top of the ground. Connect a No. 6 solid copper conductor to the rod and to the fence by a UL-listed method so that each element of the fence is grounded.
- 3.5. **Repair of Coatings.** Repair damaged zinc coating in accordance with Section 445.3.5., "Repairs."

4. MEASUREMENT

Chain link fence will be measured by the foot of fence installed, repaired, replaced, or removed, measured at the bottom of the fabric along the centerline of the fence from center to center of posts, excluding gates.

Gates will be measured as each gate installed, repaired, replaced, or removed.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Chain Link Fence (Install)" or "Chain Link Fence (Repair)" of the height specified or "Chain Link Fence (Remove)" and "Gate (Install)" or "Gate (Repair)" of the type, height, and width of opening specified or "Gate (Remove)." Clearing and grading for fencing and gates will not be paid for directly but is subsidiary to this Item.

- 5.1. **Chain Link Fence (Install).** This price is full compensation for furnishing and installing fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus material; and equipment, labor, tools, and incidentals.
- 5.2. **Chain Link Fence (Repair).** This price is full compensation for furnishing materials; repairing or replacing fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus or damaged material; and equipment, labor, tools, and incidentals.
- 5.3. **Chain Link Fence (Remove).** This price is full compensation for removing all fencing, except gates; cleaning, grading, and backfilling; removing and disposing of surplus material; and equipment, labor, tools, and incidentals.
- 5.4. **Gate (Install).** This price is full compensation for installing gate and for providing materials, center anchorages, equipment, labor, tools, and incidentals.
- 5.5. **Gate (Repair).** This price is full compensation for repairing or replacing gate and for furnishing materials; removing and disposing of damaged materials; and equipment, labor, tools, and incidentals.
- 5.6. **Gate (Remove).** This price is full compensation for removing gate and for materials, equipment, labor, tools, and incidentals.



Item 770

Guard Fence Repair

1. DESCRIPTION

Repair guard fence elements, posts, terminal anchor sections, single guard fence terminals, and other appurtenances.

2. MATERIALS

Furnish the following materials, unless otherwise shown on the plans:

- rail elements, posts, blockouts, fittings, and anchor concrete meeting Item 540, "Metal Beam Guard Fence";
- single guardrail terminal (SGT), in accordance with Item 544, "Guardrail End Treatments";
- steel posts with base plates or terminal anchor posts to match original design, meeting ASTM A36 or better;
- paint as required;
- concrete for structural repair, in accordance with Item 429, "Concrete Structure Repair";
- grout meeting the requirements of Item 421, "Hydraulic Cement Concrete"; and
- backfill material as approved.

Pick up materials furnished by the Department at the locations shown on the plans. Load and deliver furnished material to the project location. Pick up Department-furnished materials during normal business hours.

3. WORK METHODS

Replace guard fence, including thrie beam, curb, and transitions, in accordance with Item 540, "Metal Beam Guard Fence," and as shown on the plans or as directed. Work requests are made on a callout basis. Begin physical work within 72 hr. of notification, unless otherwise shown on the plans. Replace end treatments in accordance with Item 544, "Guardrail End Treatments," and as shown on the plans or as directed. Weld in accordance with Item 448, "Structural Field Welding." Repair concrete in accordance with Item 429, "Concrete Structure Repair." Remove guard fence in accordance with Item 542, "Removing Metal Beam Guard Fence." Replace rail and posts removed during the same workday, unless otherwise approved.

- Protect traffic from exposure to unattached rail elements left overnight, as approved.
- Cover or fill postholes at the end of each day.
- Place rail to a smooth line and grade, with posts plumb to the correct height, in accordance with the plans.
- Remove salvageable rail elements in original lengths. Remove fittings from posts and rail elements. Deliver salvageable materials to a designated stockpile site and neatly stack as directed. Reuse salvageable materials in the repair as approved.
- Dispose of debris and damaged components in accordance with all federal, state, and local regulations.

- 3.1. **Repair of Rail Element.** Remove and replace rail elements as directed. Bolt rail elements end to end and lap in the direction of traffic in the lane adjacent to the guard fence. Provide prefabricated curved rail when needed. Field-drill,

punch, or use other approved methods to create holes for special details. Tighten nuts. Replace bridge end connection when required, in accordance with Item 540, "Metal Beam Guard Fence."

- 3.2. **Removal and Replacement of Timber or Steel Post.** Replace posts as directed. Dispose of any concrete removed. Drill new post holes as needed. Clean postholes free of loose dirt and debris, and thoroughly compact bottom of hole to the correct elevation for placement of post. Place post to the correct alignment, elevation, and plumb. Backfill with select material by thoroughly compacting material to the density of adjacent undisturbed material. Replace concrete foundations only as directed. Use grout to fill space between riprap and posts when replacing posts.
- 3.3. **Realignment of Posts.** Realign existing posts to a smooth line and grade.
- 3.4. **Repair of Terminal Anchor Post.** Repair the steel anchor post by straightening or welding to the existing post above the concrete foundation.
- 3.5. **Replacing Terminal Anchor Posts.** Remove and replace damaged anchor posts with foundation or install new anchor posts with foundation. Remove anchor and clean existing holes or drill new holes, as approved.
- 3.6. **Removal of Guardrail End Treatment and Replacement with SGT.** Remove damaged guard fence end treatment and replace with complete new SGT.
- 3.7. **Repair of SGT.** Remove damaged SGT components and replace with new components. Salvage and reuse components as approved.
- 3.8. **Repair of Steel Post with Base Plate.** Replace damaged steel posts with base plates. Drill anchor holes and install new bolts or weld new anchor bolts to existing bolts as directed. Field-weld in accordance with Item 448, "Structural Field Welding," or shop-weld in accordance with Item 441, "Steel Structures." Repair damaged galvanized coating in accordance with Section 445.3.5., "Repairs."
- 3.9. **Raise Rail Element.** Raise rail as shown on the plans.
- 3.10. **Repair of Blockouts.** Remove and replace damaged or deteriorated blockouts with new blockouts when shown on the plans or as directed.

4. MEASUREMENT

This Item will be measured as follows:

- 4.1. **Repair of Rail Element (W-Beam, Thrie-Beam, or Thrie-Beam Transition to W-Beam).** By the foot along the face of the rail from center to center of the slotted hole at each end of the rail elements repaired, including the terminal anchor section and the rail with any bolt hole spacing, but excluding the first 2 rail elements of the SGT section.
- 4.2. **Removal and Replacement of Timber or Steel Posts without Concrete Foundation.** By each post replaced.
- 4.3. **Removal and Replacement of Timber or Steel Posts with Concrete Foundation.** By each post replaced.
- 4.4. **Realignment of Posts.** By each post realigned.
- 4.5. **Repair of Terminal Anchor Post.** By each post repaired.
- 4.6. **Replacement of Terminal Anchor Posts.** By each post replaced.
- 4.7. **Removal of Guardrail End Treatment and Replacement with SGT.** By each SGT.

- 4.8. **Replacement of SGT Impact Head.** By each head.
- 4.9. **Replacement of SGT Rail.** By the foot from center to center of posts, 2 rails.
- 4.10. **Replacement of SGT Post.** By each post replaced, includes metal sleeves.
- 4.11. **Remove and Replace Blockouts.** By each blockout replaced.
- 4.12. **Repair of Steel Post with Base Plate.** By each post repaired. Includes top or side mount posts.
- 4.13. **Remove and Reset SGT Impact Head.** By each head reset.
- 4.14. **Replace SGT Object Marker.** By each marker replaced, as directed, including the removal and disposal of the existing rubber bumpers.
- 4.15. **Replace SGT Cable Anchor.** By each cable anchor replaced.
- 4.16. **Replace SGT Cable Assembly.** By each cable assembly replaced.
- 4.17. **Replace SGT Strut.** By each strut replaced.
- 4.18. **Raise Rail.** By the foot along the face of the rail from center to center of the slotted hole at each end of the rail element raised.

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid at the unit price bid for: "Repair Rail Element of the type specified," "Raise Rail of the type specified," "Remove Post of the type specified," "Replace Post of the type specified," "Repair Post of the type specified," "Realign Posts of the type specified," "Remove Guardrail End Treatment and Replace with SGT," "Replace SGT Impact Head," "Remove and Reset SGT Impact Head," "Remove and Replace Blockouts," "Replace SGT Object Marker," "Replace SGT Cable Anchor," "Replace SGT Cable Assembly," and "Replace SGT Strut."

This price is full compensation for repairing rail and furnishing equipment, materials, labor, tools, and incidentals. Realignment of existing rail without removing will not be paid for directly but considered subsidiary to realigning posts. Replacement of concrete riprap around posts, removal and replacement of curbs, and bridge end connection will not be paid for directly but considered subsidiary to the various bid items. Replacement of SGT components not mentioned above will not be paid for directly but considered subsidiary to the various bid items. Concrete repair will be paid for in accordance with pertinent Items. Payment for repair of steel posts with base plate includes work performed above the concrete foundation. Any rail removed and replaced to remove/replace posts will not be paid for directly but considered subsidiary to various bid items.

Coring new holes and furnishing new bolts and epoxy for the repair or replacement of posts with base plate will be considered subsidiary to various bid items.



Item 772 Post and Cable Fence

1. DESCRIPTION

Install, repair, or remove post and cable fence.

2. MATERIALS

Furnish materials as follows, unless otherwise shown on the plans.

- 2.1. **Posts.** Furnish timber posts meeting DMS-7200, "Timber Posts and Blocks for Metal Beam Guard Fence."
- 2.2. **Cable.** Furnish wire cable meeting ASTM A475 and the following requirements:
 - 3/8 in. nominal strand diameter,
 - 7-wire strand, common grade,
 - minimum breaking strength of 4,000 lb., and
 - 0.30 oz. per square foot minimum weight of zinc coating.
- 2.3. **Fittings and Anchors.** Furnish fittings and anchors galvanized in accordance with ASTM A153.
- 2.4. **Concrete.** Furnish concrete meeting Item 421, "Hydraulic Cement Concrete," of the class shown on the plans.
- 2.5. **Reflectors.** Furnish reflectors as shown on the plans.
- 2.6. **Backfill.** Furnish backfill material as approved.
- 2.7. **Gate.** Furnish gates as shown on the plans.

3. WORK METHODS

Install, repair, or remove post and cable fence, including reflectors and related items as shown on the plans.

- 3.1. **Removal.** Remove concrete anchors, posts, and cable. Backfill and thoroughly compact post and anchor holes. Accept ownership of removed materials, unless otherwise shown on the plans. Dispose of removed materials in accordance with federal, state, and local regulations.
- 3.2. **Installation.** Place new anchors, posts, and cable as shown on the plans. Set posts on firm foundation and plumb to the required lines and grades. Thoroughly compact backfill in 4-in. layers. Space pull posts as shown on the plans. Lengthen or shorten one pull post space per continuous section if necessary to accommodate site conditions. Cover or fill open holes at the end of each workday.

Maintain current pull post spacing of existing installations if approved. Straighten undamaged posts that are more than 1 in. out of plumb. Stretch cable to remove sag between posts. One cable splice will be allowed between posts, adjacent to the post, but no more than 2 splices in any 100 ft. of cable. Painting is not required, unless otherwise shown on the plans.

- 3.3. **Repair.** Plumb and realign post in a vertical and horizontal position. Stretch cable to remove sag between posts. One cable splice will be allowed between posts, adjacent to the post, but no more than 2 splices in any 100 ft. of cable. Removal and replacement of posts, anchors, or cable will be paid with the appropriate bid item.
-

4. MEASUREMENT

This Item will be measured as follows:

- 4.1. **Post and Cable Fence Removal.** By the foot from center to center of pull posts.
- 4.2. **Concrete Anchor Removal.** By each anchor removed.
- 4.3. **New Installation of Post and Cable Fence.** By the foot of fence from center to center of pull posts for each continuous section installed.
- 4.4. **New Concrete Anchor.** By each anchor installed.
- 4.5. **Removal and Replacement of Posts.** By each post removed and replaced.
- 4.6. **Removal and Replacement of Concrete Anchors.** By each anchor removed and replaced.
- 4.7. **Removal and Replacement of Cable.** By the foot of cable removed and replaced.
- 4.8. **New Installation of Post and Cable Fence (Gate).** By each gate installed.
- 4.9. **Repair.** By the foot of fence from center to center of pull posts for each repair.
-

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Post and Cable Fence (Removal)," "Post and Cable Fence (Remove Concrete Anchor)," "Post and Cable Fence (New Installation)," "Post and Cable Fence (New Concrete Anchor)," "Post and Cable Fence (Remove and Replace Posts)," "Post and Cable Fence (Remove and Replace Concrete Anchors)," or "Post and Cable Fence (Remove and Replace Cable)," "Post and Cable Fence (Gate) (New Installation)," or "Post and Cable Fence (Repair)." This price is full compensation for cable splices, straightening posts, realignments of posts, tightening cable, backfilling posts and anchor holes, installation of reflectors, bollards, foundations, backfilling, gate and hardware, paint, materials, equipment, labor, tools, and incidentals.



Item 774 Attenuator Repair

1. DESCRIPTION

Repair or replace damaged attenuators or crash cushions.

2. MATERIALS

Furnish materials in accordance with details shown on the plans.

3. WORK METHODS

Repair or replace attenuators as approved. Begin physical repair for Contracts with callout work within 72 hr. of notification, unless otherwise shown on the plans. Repair damaged components, such as foundation, concrete, anchors, and pavement, as necessary to ensure the final installation functions as designed. Sweep and clean area around attenuator. Dispose of debris and damaged components in accordance with federal, state, and local regulations. Weld in accordance with Item 448, "Structural Field Welding," as directed or approved. Salvage materials as directed.

3.1. **Removal and Replacement.** Remove existing attenuator and replace with a system shown on the plans or as directed.

3.2. **Repair.** Remove and replace damaged elements of attenuators and repair to meet the installation requirements of the system shown on the plans and the specifications that pertain to that appropriate system.

4. MEASUREMENT

4.1. **Removal and Replacement.** When replacing a complete unit, measurement will be by each unit.

4.2. **Repair.** Repair will be measured by the each for the component specified or by the foot.

5. PAYMENT

The work performed and the materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Remove and Replace" or "Repair" of the type or component specified. This price is full compensation for repairing or replacing attenuators; furnishing materials; salvage and disposal; and equipment, labor, tools, and incidentals.



Item 776

Metal Rail Repair

1. DESCRIPTION

Repair metal traffic or pedestrian rail. Replace metal traffic or pedestrian rail if beyond repair as determined by the Engineer.

2. MATERIALS

Furnish materials in accordance with Item 450, "Railing," and details shown on the plans.

3. WORK METHODS

Remove damaged steel or aluminum rail and repair to match the original or details shown on the plans. Replace steel or aluminum rail to match the original or details shown on the plans if the damaged rail is beyond repair as determined by the Engineer. Begin physical repair for Contracts with callout work within 72 hr. of notification, unless otherwise shown on the plans. Repair damaged components, anchors, etc., as necessary to ensure the final installation functions as originally constructed. Drill anchor holes and install new bolts or weld new anchor bolts to existing bolts as directed. Weld in accordance with Item 441, "Steel Structures," or Item 448, "Structural Field Welding." Repair damaged galvanized coating in accordance with Section 445.3.5, "Repairs." Paint repaired areas of painted rail to match existing color, in accordance with Item 446, "Field Cleaning and Painting Steel." Repair railing removed for repair during the same workday unless otherwise approved. Deliver salvageable materials to a designated stockpile site and dispose of debris and damaged components in accordance with federal, state, and local regulations.

4. MEASUREMENT

Rail repair will be measured by the foot between centers of the first undamaged post on each side of the repair or to the end of the rail. Repairing metal post with base plate will be measured by each post repaired. Rail replacement will be measured by the foot between centers of the first undamaged post on each side of the replacement or to the end of the rail.

5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" will be paid for at the unit price bid for "Repair" of the type specified, "Repair Metal Post with Base Plate" of the type specified, and "Replacement" of the type specified. This price is full compensation for removing and repairing rail; salvage and disposal; and materials, tools, equipment, labor, and incidentals. Concrete repair will be paid for in accordance with Item 429, "Concrete Structure Repair."

INDEX OF SHEETS

SHEET NO.	DESCRIPTION	SHEET NO.	DESCRIPTION
<u>ATTACHMENT SHEETS</u>			
9-14	ATTACHMENT A	68	TAU-II-R(N)- 16
15	ATTACHMENT B	69	TAU-II-R(W)- 16
 <u>DETAIL SHEETS</u>			
40	GF (31)-14		
41	GF (31)DAT-14		
42	GF (31)LS-14		
43	GF (31)TR-14		
44	GF (31)TL2-11		
45	GF (31)T101-13		
46	GF (31)MS-11	70-75	<u>TRAFFIC CONTROL PLAN</u> TCP (1-1)-12 THRU (1-6)-12
47	SGT (8)31-14	76-83	TCP (2-1)-12 THRU (2-8)-12
48	SGT (8S)31-14	84-85	TCP (3-1)-13 THRU (3-2)-13
49	SGT (9S)31-14	86	TCP (3-3)-14
50	SGT (10S)31-16	87	TCP (3-4)-13
51	CATGR(2)- 17	88	TCP (5-1)-12
52	CATGR(2)- 17	89-95	TCP (6-1)-12 THRU (6-7)-12
53	CATCB(1)- 17	96	TCP (7-1)-13
54	CATCB(1)- 17	97	RS-TCP-05
55	BED-14		
56	REACT(N)- 16		
57	REACT(W)- 16		
58	PCF-05		
59	QUAD(N)- 17		
60	QUAD(W)- 17		
61	QGELITE(N)- 17		
62	QGELITE(W)- 17		
63	TRACC(N)- 16		
64	TRACC(W)- 16		
65	SSCC- 16		
66	TAU-II(N)- 16		
67	TAU-II(W)- 16		

The Standard Sheets specifically identified above have been selected by me or under my responsible supervision as being applicable to this project.

Isaac Garza, P.E.
Transportation Engineer

Date

GENERAL NOTES

- The detail shown is the minimum length of head (LCH) for a DAT connected to a concrete rail.
- The rail section at the end post is supported by the steel angle bracket, the rail element is not attached to the end post.
- The foundation tubes shall not project more than 3/4" above the finished grade.
- All hardware for DAT shall be ASTM A307 unless otherwise shown.
- Refer to GF (31) sheet for terminal connection details.

LOW STRIP INSTALLATION

If a low strip is required with the DAT installation, the low-out end around the steel foundation tubes and the two channel struts may be omitted. This will require a full pour of the foundation tubes.


#	(DAT) PARTS LIST	QTY
1	Steel Foundation Tube	2
2	DAT Terminal Post	2
3	Channel Strut	2
4	Terminal Rail Element	1
5	Steel Angle Bracket	1
6	BCT Bearing Plate	1
7	BCT Post Sleeve	1
8	Quadrant Anchor Bracket	1
9	Roundoff-Beam End Section	1
10	BCT Cable Anchor	1
11	Recessed Nut, Duralroll	20
12	1 1/2" Button Head Bolt	4
13	10" Button Head Bolt	2
14	3/4" x 2" Hex Head Bolt	8
15	1/2" x 8" Hex Head Bolt	4
16	1/2" x 10" Hex Head Bolt	2
17	3/4" Flat Washer	16

Texas Department of Transportation
Design Standard

METAL BEAM GUARD FENCE
(Downstream Anchor Terminal)

GF (31) DAT - 14

DATE	DESCRIPTION	BY	CHKD	APP'D
01/15/00	DESIGN




DOWNSTREAM ANCHOR TERMINAL (DAT)
Only for downstream use, when located outside the horizontal clearance area of opposing traffic.


GENERAL NOTES

- The type of line post (round wood post, extensior wood post, or steel post) will be as shown in the plans. The exact position of the transitions shall be as shown according with Item 14, "Sizing".
- Post element shall meet all requirements of Item 540, "Metal Beam Guard Fence". The contractor may furnish full details of 1 1/2" x 3" or 25 foot nominal lengths.
- Post spacing shall be 3' - 1 1/2" from standard guardrail to accommodate the transition spacing.
- Each end post shall be of sufficient length to extend through the full thickness of the post (ASTM A36) and no more than 3" beyond it. Rivon head splice bolts (ASTM A307) or 3/4" x 1 1/2" with a 3/8" double threaded end shall be used for transition. The transition shall be in accordance with Item 540, "Metal Beam Guard Fence". The transition shall be in accordance with Item 540, "Metal Beam Guard Fence".
- Where solid rock is encountered or where shown on the plans, the diameter of the holes shall be approximately 1/2" inches, the boring filling shall be with a cohesionless material, and maximum depth shall be 1' - 0" or more as directed by the Engineer.
- Refer to GF(31) Standard Sheet for additional details.


NOTE: Field drilled holes shall be realized in accordance with Item 445, "Sizing".
Punch cutting of holes in guardrail shall not be permitted.



**Rectangular CRT Post
(6" x 6" x 5' Long)**
(5) CRT Posts
See Elevation Detail for locations.




Standard Line Post Installation




**METAL BEAM GUARD FENCE
(Long Span)**
GF(31)LS-14

DATE	DESCRIPTION	BY	CHECKED
10/22/20	REVISED
08/28/20
08/28/20
08/28/20

Florida Department of Transportation
Tallahassee District Office






GENERAL NOTES

- For additional information contact Interstate Steel Inc. (823) 283-3728
- The type of set unit will be specified elsewhere in the plans. The numbers in the circles indicate the material to be used. The type of set unit shown is a maintenance consideration and does not affect the system performance.
- Use the following materials:
 - Steel: A36
 - Welds: E70
 - Posts: 1/2" Dia. x 18" (SKT-31)
 - Plate: 1/2" Thick
 - Angle: L4 x 3
 - Channel: C4
 - Structural Bolt: 1/2" Dia. x 3" (Type III)
 - Structural Nut: 1/2" (Type III)
 - Structural Washer: 1/2" (Type III)
 - Structural Gasket: 1/2" (Type III)
- 50T's placed within the "spine" 150 ft. radius, shall be installed straight. Standard rail elements may be installed within the radius, without special justification.
- All bolts, nuts, coils, assemblies, coils, anchors, steel tubes & bearing plates shall be galvanized.
- 50T's shall be driven over the steel 30 ft. of the station to be placed. The standard needs from accompanying this station. The 50T's may be checked or "blasted" for identification, if directed by the Engineer.
- The steel tubes shall not protrude more than 4 inches above ground. Site grading may be necessary to meet this requirement.
- The steel tubes may be driven with an approved driving head. They shall not be driven with the use of a hammer or other method. The driving head shall be in certified holes. The bearing material must be satisfactorily compacted to prevent tube settlement.
- Installation pullback.
- The manufacturer's installation manual for the proper installation of the bearing plate.
- The bearing plate assembly must be true. A leveling device (like a spirit or dumpy level) should be used to prevent the coils from "wobbling" when tightening the nuts.
- The wood blocks shall be "pre-notched" to the resistor wood posts to prevent them from toppling when the wood arrives. The bearing plate on the front post shall also be "pre-notched" to prevent toppling.
- For the instructions, the rail tubes and posts shall be installed on the proper ground elevation and the set unit shall be installed on the proper post. The set unit shall be installed on the proper post height above the rail. The set unit shall be installed on the proper post height above the rail. The set unit shall be installed on the proper post height above the rail.
- The set unit shall be installed on the proper post height above the rail. The set unit shall be installed on the proper post height above the rail. The set unit shall be installed on the proper post height above the rail.

POST & SET OPTIONS		BILL OF MATERIAL	
Item No.	Type	Quantity	Description
1	1	1	SKT-31 (1/2" DIA. x 18" L)
2	1	1	SKT-31 (1/2" DIA. x 18" L)
3	1	1	SKT-31 (1/2" DIA. x 18" L)
4	1	1	SKT-31 (1/2" DIA. x 18" L)
5	1	1	SKT-31 (1/2" DIA. x 18" L)
6	1	1	SKT-31 (1/2" DIA. x 18" L)
7	1	1	SKT-31 (1/2" DIA. x 18" L)
8	1	1	SKT-31 (1/2" DIA. x 18" L)
9	1	1	SKT-31 (1/2" DIA. x 18" L)
10	1	1	SKT-31 (1/2" DIA. x 18" L)
11	1	1	SKT-31 (1/2" DIA. x 18" L)
12	1	1	SKT-31 (1/2" DIA. x 18" L)
13	1	1	SKT-31 (1/2" DIA. x 18" L)
14	1	1	SKT-31 (1/2" DIA. x 18" L)
15	1	1	SKT-31 (1/2" DIA. x 18" L)
16	1	1	SKT-31 (1/2" DIA. x 18" L)
17	1	1	SKT-31 (1/2" DIA. x 18" L)
18	1	1	SKT-31 (1/2" DIA. x 18" L)
19	1	1	SKT-31 (1/2" DIA. x 18" L)
20	1	1	SKT-31 (1/2" DIA. x 18" L)
21	1	1	SKT-31 (1/2" DIA. x 18" L)
22	1	1	SKT-31 (1/2" DIA. x 18" L)
23	1	1	SKT-31 (1/2" DIA. x 18" L)
24	1	1	SKT-31 (1/2" DIA. x 18" L)
25	1	1	SKT-31 (1/2" DIA. x 18" L)
26	1	1	SKT-31 (1/2" DIA. x 18" L)
27	1	1	SKT-31 (1/2" DIA. x 18" L)
28	1	1	SKT-31 (1/2" DIA. x 18" L)
29	1	1	SKT-31 (1/2" DIA. x 18" L)
30	1	1	SKT-31 (1/2" DIA. x 18" L)
31	1	1	SKT-31 (1/2" DIA. x 18" L)
32	1	1	SKT-31 (1/2" DIA. x 18" L)
33	1	1	SKT-31 (1/2" DIA. x 18" L)
34	1	1	SKT-31 (1/2" DIA. x 18" L)
35	1	1	SKT-31 (1/2" DIA. x 18" L)
36	1	1	SKT-31 (1/2" DIA. x 18" L)
37	1	1	SKT-31 (1/2" DIA. x 18" L)
38	1	1	SKT-31 (1/2" DIA. x 18" L)
39	1	1	SKT-31 (1/2" DIA. x 18" L)
40	1	1	SKT-31 (1/2" DIA. x 18" L)
41	1	1	SKT-31 (1/2" DIA. x 18" L)
42	1	1	SKT-31 (1/2" DIA. x 18" L)
43	1	1	SKT-31 (1/2" DIA. x 18" L)
44	1	1	SKT-31 (1/2" DIA. x 18" L)
45	1	1	SKT-31 (1/2" DIA. x 18" L)
46	1	1	SKT-31 (1/2" DIA. x 18" L)
47	1	1	SKT-31 (1/2" DIA. x 18" L)
48	1	1	SKT-31 (1/2" DIA. x 18" L)
49	1	1	SKT-31 (1/2" DIA. x 18" L)
50	1	1	SKT-31 (1/2" DIA. x 18" L)
51	1	1	SKT-31 (1/2" DIA. x 18" L)
52	1	1	SKT-31 (1/2" DIA. x 18" L)
53	1	1	SKT-31 (1/2" DIA. x 18" L)
54	1	1	SKT-31 (1/2" DIA. x 18" L)
55	1	1	SKT-31 (1/2" DIA. x 18" L)
56	1	1	SKT-31 (1/2" DIA. x 18" L)
57	1	1	SKT-31 (1/2" DIA. x 18" L)
58	1	1	SKT-31 (1/2" DIA. x 18" L)
59	1	1	SKT-31 (1/2" DIA. x 18" L)
60	1	1	SKT-31 (1/2" DIA. x 18" L)
61	1	1	SKT-31 (1/2" DIA. x 18" L)
62	1	1	SKT-31 (1/2" DIA. x 18" L)
63	1	1	SKT-31 (1/2" DIA. x 18" L)
64	1	1	SKT-31 (1/2" DIA. x 18" L)
65	1	1	SKT-31 (1/2" DIA. x 18" L)
66	1	1	SKT-31 (1/2" DIA. x 18" L)
67	1	1	SKT-31 (1/2" DIA. x 18" L)
68	1	1	SKT-31 (1/2" DIA. x 18" L)
69	1	1	SKT-31 (1/2" DIA. x 18" L)
70	1	1	SKT-31 (1/2" DIA. x 18" L)
71	1	1	SKT-31 (1/2" DIA. x 18" L)
72	1	1	SKT-31 (1/2" DIA. x 18" L)
73	1	1	SKT-31 (1/2" DIA. x 18" L)
74	1	1	SKT-31 (1/2" DIA. x 18" L)
75	1	1	SKT-31 (1/2" DIA. x 18" L)
76	1	1	SKT-31 (1/2" DIA. x 18" L)
77	1	1	SKT-31 (1/2" DIA. x 18" L)
78	1	1	SKT-31 (1/2" DIA. x 18" L)
79	1	1	SKT-31 (1/2" DIA. x 18" L)
80	1	1	SKT-31 (1/2" DIA. x 18" L)
81	1	1	SKT-31 (1/2" DIA. x 18" L)
82	1	1	SKT-31 (1/2" DIA. x 18" L)
83	1	1	SKT-31 (1/2" DIA. x 18" L)
84	1	1	SKT-31 (1/2" DIA. x 18" L)
85	1	1	SKT-31 (1/2" DIA. x 18" L)
86	1	1	SKT-31 (1/2" DIA. x 18" L)
87	1	1	SKT-31 (1/2" DIA. x 18" L)
88	1	1	SKT-31 (1/2" DIA. x 18" L)
89	1	1	SKT-31 (1/2" DIA. x 18" L)
90	1	1	SKT-31 (1/2" DIA. x 18" L)
91	1	1	SKT-31 (1/2" DIA. x 18" L)
92	1	1	SKT-31 (1/2" DIA. x 18" L)
93	1	1	SKT-31 (1/2" DIA. x 18" L)
94	1	1	SKT-31 (1/2" DIA. x 18" L)
95	1	1	SKT-31 (1/2" DIA. x 18" L)
96	1	1	SKT-31 (1/2" DIA. x 18" L)
97	1	1	SKT-31 (1/2" DIA. x 18" L)
98	1	1	SKT-31 (1/2" DIA. x 18" L)
99	1	1	SKT-31 (1/2" DIA. x 18" L)
100	1	1	SKT-31 (1/2" DIA. x 18" L)

THE ENGINEERING COMPANY
Department of Transportation
SINGLE GUARDRAIL TERMINAL
(SKT-31)
(WOOD POST)
SGT (8) 31 - 14

DATE: 10/15/80
DRAWN BY: [Name]
CHECKED BY: [Name]
DATE: 10/15/80
SCALE: AS SHOWN




GENERAL NOTES

- For additional information contact: Linway Transportation Solutions - Beam Systems, 180 River Road, 160 Tins, CA 94711, (970) 374-8800
- All dimensions are shown in inches, except as otherwise indicated.
- All cable attachment, cable anchors, ground wires, wire pieces, impact heads, nuts, bolts and all steel components shall be galvanized unless otherwise noted.
- X-LITE placed within the minimum 500 ft. radius will be installed straight. Standard rail treatments may be installed within the radius without special notification.
- A flag pole of 37.5 ft may be used over the first 50 ft. of this system to prevent the terminal head from encroaching on the shoulder. The flag pole may be attached or attached for specific installations, or as directed by the engineer.
- At each location the post shall be bolted at two proper areas of elevation behind the post. The post will be secured with a self-drilling post. The post shall be secured to the post connection bolt to maintain the proper height of the rail above the gutter. The excess post length above the rail will be removed as directed by the engineer.
- If rock excavation is encountered, the soil poles may be modified if approved by the project engineer.
- When site conditions permit, post may be driven. If poles are placed in a drilled hole, the bottom material must be satisfactorily compacted to prevent settlement.
- An object marker shall be installed on the impact head as detailed on CH04(VIA)
- The X-LITE for steel post (SCT) shall be suitable for locations calling for wood post or (When used with wood post guardrail system, post 7 from 9 may be replaced with CRT post).

Minimum length of MBGF shown. See current guard fence standards for further information.
The rail-to-rail cable assembly must be tested. A locking device (knee-plate or channel lock-plate) should be used to prevent the cable from twisting when tightening the nut.

ITEM	PART NO.	DESCRIPTION	QTY
1	MB-G1000-00	X-LITE SHIMMED POST-FRONT ONLY	1
2	MB-G1000-00	X-LITE SHIMMED POST-REAR ONLY	1
3	MB-G1000-00	X-LITE SHIMMED POST	1
4	MB-G1000-00	X-LITE SHIMMED POST	1
5	MB-G1000-00	X-LITE SHIMMED POST	1
6	MB-G1000-00	X-LITE SHIMMED POST	1
7	MB-G1000-00	X-LITE SHIMMED POST	1
8	MB-G1000-00	X-LITE SHIMMED POST	1
9	MB-G1000-00	X-LITE SHIMMED POST	1
10	MB-G1000-00	X-LITE SHIMMED POST	1
11	MB-G1000-00	X-LITE SHIMMED POST	1
12	MB-G1000-00	X-LITE SHIMMED POST	1
13	MB-G1000-00	X-LITE SHIMMED POST	1
14	MB-G1000-00	X-LITE SHIMMED POST	1
15	MB-G1000-00	X-LITE SHIMMED POST	1
16	MB-G1000-00	X-LITE SHIMMED POST	1
17	MB-G1000-00	X-LITE SHIMMED POST	1
18	MB-G1000-00	X-LITE SHIMMED POST	1
19	MB-G1000-00	X-LITE SHIMMED POST	1
20	MB-G1000-00	X-LITE SHIMMED POST	1
21	MB-G1000-00	X-LITE SHIMMED POST	1
22	MB-G1000-00	X-LITE SHIMMED POST	1




Linway Department of Transportation
Single Guardrail Terminal (X-LITE) STEEL POST SGT(9S)31-14

DATE: 01/20/2014	TIME: 10:00 AM	USER: JACOB
PROJECT: 6314-60-001	DATE: 01/20/2014	TIME: 10:00 AM
USER: JACOB	DATE: 01/20/2014	TIME: 10:00 AM




1. SEE SPECIFIC INFORMATION REGARDING INSTALLATION AND TECHNICAL COLLAPSE FOR THIS PROJECT. SEE DRAWING 6287-93-001.
2. FOR INSTALLATION, REPAIR AND MAINTENANCE, REFER TO THE SOFTWARE BIDDING MANUAL, PRODUCT DESCRIPTION ASSEMBLY MANUAL, PH 6287-93-001.
3. APPLY WITH EXTREME CARE AND PRECISION TO THE POINT OF CONTACT WITH THE SURFACE. DO NOT OVER-TIGHTEN. THE POINT OF CONTACT SHALL BE THE POINT OF CONTACT WITH THE SURFACE. DO NOT OVER-TIGHTEN.
4. PER POST CLEARANCE, INSTALLATION AND CLEARANCE SEE TABLE LATEST DRAWING AND SHOP DRAWING.
5. HARDWARE SHALL BE AS SPECIFIED IN ACCORDANCE WITH THE DRAWING. HARDWARE SHALL BE SUBSTITUTED TO THE FULL LEVEL.
6. ALL COMPONENTS SHALL BE INSTALLED IN ACCORDANCE WITH THE DRAWING. HARDWARE SHALL BE SUBSTITUTED TO THE FULL LEVEL.
7. IF AVOID OVER IS ENCOUNTERED FOR THE SUBASSEMBLY'S INSTALLATION, REFER TO THE DRAWING FOR THE LATEST REVISION AND CLEARANCE FOR INSTALLATION CLEARANCE.
8. POSTS SHALL NOT BE SET IN CONCRETE.
9. DO NOT ATTEMPT TO INSTALL THE SOFTWARE SYSTEM DIRECTLY TO A RAIL CARREL.
10. UNDER NO CIRCUMSTANCES SHALL THE SOFTWARE SYSTEM BE INSTALLED TO A RAIL CARREL.
11. IF AVOID OVER IS ENCOUNTERED FOR THE SUBASSEMBLY'S INSTALLATION, REFER TO THE DRAWING FOR THE LATEST REVISION AND CLEARANCE FOR INSTALLATION CLEARANCE.
12. THE INSTALLATION HEIGHT OF FULLY ASSEMBLED ANCHOR POST WILL VARY FROM 8'-0" MIN. TO 4' MAX. ABOVE FINISHED GRADE.

PART	QTY	DESCRIPTION
42200	1	ANCHOR POST ASSEMBLY (SEE DRAWING)
42201	1	ANCHOR POST (SEE DRAWING)
42202	1	ANCHOR PLATE (SEE DRAWING)
42203	1	ANCHOR WELDER (SEE DRAWING)
42204	1	ANCHOR WELDER (SEE DRAWING)
42205	1	ANCHOR WELDER (SEE DRAWING)
42206	1	ANCHOR WELDER (SEE DRAWING)
42207	1	ANCHOR WELDER (SEE DRAWING)
42208	1	ANCHOR WELDER (SEE DRAWING)
42209	1	ANCHOR WELDER (SEE DRAWING)
42210	1	ANCHOR WELDER (SEE DRAWING)
42211	1	ANCHOR WELDER (SEE DRAWING)
42212	1	ANCHOR WELDER (SEE DRAWING)
42213	1	ANCHOR WELDER (SEE DRAWING)
42214	1	ANCHOR WELDER (SEE DRAWING)
42215	1	ANCHOR WELDER (SEE DRAWING)
42216	1	ANCHOR WELDER (SEE DRAWING)
42217	1	ANCHOR WELDER (SEE DRAWING)
42218	1	ANCHOR WELDER (SEE DRAWING)
42219	1	ANCHOR WELDER (SEE DRAWING)
42220	1	ANCHOR WELDER (SEE DRAWING)
42221	1	ANCHOR WELDER (SEE DRAWING)
42222	1	ANCHOR WELDER (SEE DRAWING)
42223	1	ANCHOR WELDER (SEE DRAWING)
42224	1	ANCHOR WELDER (SEE DRAWING)
42225	1	ANCHOR WELDER (SEE DRAWING)
42226	1	ANCHOR WELDER (SEE DRAWING)
42227	1	ANCHOR WELDER (SEE DRAWING)
42228	1	ANCHOR WELDER (SEE DRAWING)
42229	1	ANCHOR WELDER (SEE DRAWING)
42230	1	ANCHOR WELDER (SEE DRAWING)
42231	1	ANCHOR WELDER (SEE DRAWING)
42232	1	ANCHOR WELDER (SEE DRAWING)
42233	1	ANCHOR WELDER (SEE DRAWING)
42234	1	ANCHOR WELDER (SEE DRAWING)
42235	1	ANCHOR WELDER (SEE DRAWING)
42236	1	ANCHOR WELDER (SEE DRAWING)
42237	1	ANCHOR WELDER (SEE DRAWING)
42238	1	ANCHOR WELDER (SEE DRAWING)
42239	1	ANCHOR WELDER (SEE DRAWING)
42240	1	ANCHOR WELDER (SEE DRAWING)
42241	1	ANCHOR WELDER (SEE DRAWING)
42242	1	ANCHOR WELDER (SEE DRAWING)
42243	1	ANCHOR WELDER (SEE DRAWING)
42244	1	ANCHOR WELDER (SEE DRAWING)
42245	1	ANCHOR WELDER (SEE DRAWING)
42246	1	ANCHOR WELDER (SEE DRAWING)
42247	1	ANCHOR WELDER (SEE DRAWING)
42248	1	ANCHOR WELDER (SEE DRAWING)
42249	1	ANCHOR WELDER (SEE DRAWING)
42250	1	ANCHOR WELDER (SEE DRAWING)



DATE	BY	CHKD	APP'D	SCALE
10/20/00	JM	JM	JM	1/8" = 1'-0"


Trinity Highway
SOFTSTOP END TERMINAL
MASH - TL-3
SGT(105)31-16



SHEET 1 OF 2

	TRINITY HIGHWAY ENERGY ABSORPTION CRASH CUSHION (GUARDRAIL)	
	CATGR (2) - 17	
DATE: 08/11/09 DRAWN BY: JMM CHECKED BY: JMM DESIGNED BY: JMM	DATE: 08/11/09 DATE: 08/11/09 DATE: 08/11/09	DATE: 08/11/09 DATE: 08/11/09 DATE: 08/11/09

Disclaimers: This drawing is provided by the Texas Department of Transportation. It is intended for informational purposes only. It is not intended to be used for any other purpose. The user of this drawing assumes all responsibility for the construction of the project. The user of this drawing is advised to check for any updates or changes to this drawing.



SHEET 1 OF 2

Texas Department of Transportation
**TRINITY HIGHWAY
 ENERGY ABSORPTION
 CRASH CUSHION
 (CONCRETE BARRIER)**
 CATCB(1) - 17


DATE	BY	CHKD	APP'D
10/1/00	J. B. BROWN	J. B. BROWN	J. B. BROWN
10/1/00	J. B. BROWN	J. B. BROWN	J. B. BROWN
10/1/00	J. B. BROWN	J. B. BROWN	J. B. BROWN

DESIGNED BY: J. B. BROWN
 CHECKED BY: J. B. BROWN
 APPROVED BY: J. B. BROWN

GENERAL NOTES

1. For specific information regarding installation and technical guidance of this system, contact Trinity Highway at (1888)323-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60602
2. Crown will be widened to accommodate the CAT system. The crown should extend at least 3 feet beyond the inside face of rail. The ground line at posts should be an extension of the roadway surface crown.
3. All bolts, nuts, washers, cable assemblies, cable anchors, post caps, endcap brackets and wall plates shall be galvanized.
4. The exposed end segment of the End Section should be evaluated as a potential obstacle in the determination of the need of MBF for the opposing direction of traffic.
5. For placement at curb sections, the height from gutter edge to post bolt will be 27", and the front section shall be fixed (See Detail 2).
6. The wood blockouts shall be "stepped" to the rectangular post posts to prevent them from floating when the wood blockouts. Either 6" x 6" or 5 1/2" x 7 1/2" wood blocks may be used of posts. If a 6" x 6" is used, it shall be supported by the manufacturer.
7. If a "single sided" transition section is required for the attachment to a rigid concrete rail, see the MBF transition standards for the proper installation.
8. Object markers shall be installed on the front of the terminal as detailed on the BLOWUP.

SHEET 2 OF 2


TRINITY HIGHWAY ENERGY ABSORPTION CRASH CUSHION (CONCRETE BARRIER) CATCB(1) -17
 DESIGN STANDARD
 THIS DRAWING IS THE PROPERTY OF THE TEXAS DEPARTMENT OF TRANSPORTATION. IT IS TO BE USED ONLY FOR THE PROJECT AND LOCATION SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE TEXAS DEPARTMENT OF TRANSPORTATION.

SACRIFICIAL

CATCB TRANSITION SECTION (POSTS 9 THRU END SHOT)

REF. QTY	DESCRIPTION
3140	4 1/2" x 1/2" x 1/2" Gal
3141	2 1/2" x 1/2" x 1/2" Gal
3142	2 1/2" x 1/2" x 1/2" Gal
3143	2 1/2" x 1/2" x 1/2" Gal
3144	2 1/2" x 1/2" x 1/2" Gal
3145	2 1/2" x 1/2" x 1/2" Gal
3146	2 1/2" x 1/2" x 1/2" Gal
3147	2 1/2" x 1/2" x 1/2" Gal
3148	2 1/2" x 1/2" x 1/2" Gal
3149	2 1/2" x 1/2" x 1/2" Gal
3150	2 1/2" x 1/2" x 1/2" Gal
3151	2 1/2" x 1/2" x 1/2" Gal
3152	2 1/2" x 1/2" x 1/2" Gal
3153	2 1/2" x 1/2" x 1/2" Gal
3154	2 1/2" x 1/2" x 1/2" Gal
3155	2 1/2" x 1/2" x 1/2" Gal
3156	2 1/2" x 1/2" x 1/2" Gal
3157	2 1/2" x 1/2" x 1/2" Gal
3158	2 1/2" x 1/2" x 1/2" Gal
3159	2 1/2" x 1/2" x 1/2" Gal
3160	2 1/2" x 1/2" x 1/2" Gal
3161	2 1/2" x 1/2" x 1/2" Gal
3162	2 1/2" x 1/2" x 1/2" Gal
3163	2 1/2" x 1/2" x 1/2" Gal
3164	2 1/2" x 1/2" x 1/2" Gal
3165	2 1/2" x 1/2" x 1/2" Gal
3166	2 1/2" x 1/2" x 1/2" Gal
3167	2 1/2" x 1/2" x 1/2" Gal
3168	2 1/2" x 1/2" x 1/2" Gal
3169	2 1/2" x 1/2" x 1/2" Gal
3170	2 1/2" x 1/2" x 1/2" Gal
3171	2 1/2" x 1/2" x 1/2" Gal
3172	2 1/2" x 1/2" x 1/2" Gal
3173	2 1/2" x 1/2" x 1/2" Gal
3174	2 1/2" x 1/2" x 1/2" Gal
3175	2 1/2" x 1/2" x 1/2" Gal
3176	2 1/2" x 1/2" x 1/2" Gal
3177	2 1/2" x 1/2" x 1/2" Gal
3178	2 1/2" x 1/2" x 1/2" Gal
3179	2 1/2" x 1/2" x 1/2" Gal
3180	2 1/2" x 1/2" x 1/2" Gal
3181	2 1/2" x 1/2" x 1/2" Gal
3182	2 1/2" x 1/2" x 1/2" Gal
3183	2 1/2" x 1/2" x 1/2" Gal
3184	2 1/2" x 1/2" x 1/2" Gal
3185	2 1/2" x 1/2" x 1/2" Gal
3186	2 1/2" x 1/2" x 1/2" Gal
3187	2 1/2" x 1/2" x 1/2" Gal
3188	2 1/2" x 1/2" x 1/2" Gal
3189	2 1/2" x 1/2" x 1/2" Gal
3190	2 1/2" x 1/2" x 1/2" Gal
3191	2 1/2" x 1/2" x 1/2" Gal
3192	2 1/2" x 1/2" x 1/2" Gal
3193	2 1/2" x 1/2" x 1/2" Gal
3194	2 1/2" x 1/2" x 1/2" Gal
3195	2 1/2" x 1/2" x 1/2" Gal
3196	2 1/2" x 1/2" x 1/2" Gal
3197	2 1/2" x 1/2" x 1/2" Gal
3198	2 1/2" x 1/2" x 1/2" Gal
3199	2 1/2" x 1/2" x 1/2" Gal
3200	2 1/2" x 1/2" x 1/2" Gal


CATCB CHAIRRAIL TERMINAL END SECTION (POSTS 7 & 8)

REF. QTY	DESCRIPTION
3201	2 1/2" x 1/2" x 1/2" Gal
3202	2 1/2" x 1/2" x 1/2" Gal
3203	2 1/2" x 1/2" x 1/2" Gal
3204	2 1/2" x 1/2" x 1/2" Gal
3205	2 1/2" x 1/2" x 1/2" Gal
3206	2 1/2" x 1/2" x 1/2" Gal
3207	2 1/2" x 1/2" x 1/2" Gal
3208	2 1/2" x 1/2" x 1/2" Gal
3209	2 1/2" x 1/2" x 1/2" Gal
3210	2 1/2" x 1/2" x 1/2" Gal
3211	2 1/2" x 1/2" x 1/2" Gal
3212	2 1/2" x 1/2" x 1/2" Gal
3213	2 1/2" x 1/2" x 1/2" Gal
3214	2 1/2" x 1/2" x 1/2" Gal
3215	2 1/2" x 1/2" x 1/2" Gal
3216	2 1/2" x 1/2" x 1/2" Gal
3217	2 1/2" x 1/2" x 1/2" Gal
3218	2 1/2" x 1/2" x 1/2" Gal
3219	2 1/2" x 1/2" x 1/2" Gal
3220	2 1/2" x 1/2" x 1/2" Gal
3221	2 1/2" x 1/2" x 1/2" Gal
3222	2 1/2" x 1/2" x 1/2" Gal
3223	2 1/2" x 1/2" x 1/2" Gal
3224	2 1/2" x 1/2" x 1/2" Gal
3225	2 1/2" x 1/2" x 1/2" Gal
3226	2 1/2" x 1/2" x 1/2" Gal
3227	2 1/2" x 1/2" x 1/2" Gal
3228	2 1/2" x 1/2" x 1/2" Gal
3229	2 1/2" x 1/2" x 1/2" Gal
3230	2 1/2" x 1/2" x 1/2" Gal
3231	2 1/2" x 1/2" x 1/2" Gal
3232	2 1/2" x 1/2" x 1/2" Gal
3233	2 1/2" x 1/2" x 1/2" Gal
3234	2 1/2" x 1/2" x 1/2" Gal
3235	2 1/2" x 1/2" x 1/2" Gal
3236	2 1/2" x 1/2" x 1/2" Gal
3237	2 1/2" x 1/2" x 1/2" Gal
3238	2 1/2" x 1/2" x 1/2" Gal
3239	2 1/2" x 1/2" x 1/2" Gal
3240	2 1/2" x 1/2" x 1/2" Gal
3241	2 1/2" x 1/2" x 1/2" Gal
3242	2 1/2" x 1/2" x 1/2" Gal
3243	2 1/2" x 1/2" x 1/2" Gal
3244	2 1/2" x 1/2" x 1/2" Gal
3245	2 1/2" x 1/2" x 1/2" Gal
3246	2 1/2" x 1/2" x 1/2" Gal
3247	2 1/2" x 1/2" x 1/2" Gal
3248	2 1/2" x 1/2" x 1/2" Gal
3249	2 1/2" x 1/2" x 1/2" Gal
3250	2 1/2" x 1/2" x 1/2" Gal

CATCH FRONT SECTION (POSTS 1 THRU 6)

REF. QTY	DESCRIPTION
3251	2 1/2" x 1/2" x 1/2" Gal
3252	2 1/2" x 1/2" x 1/2" Gal
3253	2 1/2" x 1/2" x 1/2" Gal
3254	2 1/2" x 1/2" x 1/2" Gal
3255	2 1/2" x 1/2" x 1/2" Gal
3256	2 1/2" x 1/2" x 1/2" Gal
3257	2 1/2" x 1/2" x 1/2" Gal
3258	2 1/2" x 1/2" x 1/2" Gal
3259	2 1/2" x 1/2" x 1/2" Gal
3260	2 1/2" x 1/2" x 1/2" Gal
3261	2 1/2" x 1/2" x 1/2" Gal
3262	2 1/2" x 1/2" x 1/2" Gal
3263	2 1/2" x 1/2" x 1/2" Gal
3264	2 1/2" x 1/2" x 1/2" Gal
3265	2 1/2" x 1/2" x 1/2" Gal
3266	2 1/2" x 1/2" x 1/2" Gal
3267	2 1/2" x 1/2" x 1/2" Gal
3268	2 1/2" x 1/2" x 1/2" Gal
3269	2 1/2" x 1/2" x 1/2" Gal
3270	2 1/2" x 1/2" x 1/2" Gal
3271	2 1/2" x 1/2" x 1/2" Gal
3272	2 1/2" x 1/2" x 1/2" Gal
3273	2 1/2" x 1/2" x 1/2" Gal
3274	2 1/2" x 1/2" x 1/2" Gal
3275	2 1/2" x 1/2" x 1/2" Gal
3276	2 1/2" x 1/2" x 1/2" Gal
3277	2 1/2" x 1/2" x 1/2" Gal
3278	2 1/2" x 1/2" x 1/2" Gal
3279	2 1/2" x 1/2" x 1/2" Gal
3280	2 1/2" x 1/2" x 1/2" Gal
3281	2 1/2" x 1/2" x 1/2" Gal
3282	2 1/2" x 1/2" x 1/2" Gal
3283	2 1/2" x 1/2" x 1/2" Gal
3284	2 1/2" x 1/2" x 1/2" Gal
3285	2 1/2" x 1/2" x 1/2" Gal
3286	2 1/2" x 1/2" x 1/2" Gal
3287	2 1/2" x 1/2" x 1/2" Gal
3288	2 1/2" x 1/2" x 1/2" Gal
3289	2 1/2" x 1/2" x 1/2" Gal
3290	2 1/2" x 1/2" x 1/2" Gal
3291	2 1/2" x 1/2" x 1/2" Gal
3292	2 1/2" x 1/2" x 1/2" Gal
3293	2 1/2" x 1/2" x 1/2" Gal
3294	2 1/2" x 1/2" x 1/2" Gal
3295	2 1/2" x 1/2" x 1/2" Gal
3296	2 1/2" x 1/2" x 1/2" Gal
3297	2 1/2" x 1/2" x 1/2" Gal
3298	2 1/2" x 1/2" x 1/2" Gal
3299	2 1/2" x 1/2" x 1/2" Gal
3300	2 1/2" x 1/2" x 1/2" Gal






* Dimension or through bolts may be used with optional bracket installation.



DISCLAIMER: This drawing is prepared by the Texas Engineering Experiment Station (TEXES) for the Texas Department of Transportation (TxDOT) and is not to be used for any purpose other than that for which it was prepared. The user of this drawing is responsible for the accuracy of the information contained herein and for the proper interpretation and application of the drawing. The user of this drawing is also responsible for the accuracy of the information contained herein and for the proper interpretation and application of the drawing.

GENERAL NOTES

- For more details see OF (31), SOT (31), OF (31)TR, and OF (31)TL2 standard sheets.
- Quantities of cast-in-place beam guard fence (MBGF) at individual bridge ends are as shown in the plans.
- Use straight taper (SOT) for the approach near to determine MBGF length of need in accordance with the roadway design unless otherwise specified. Where significant traffic volume growth is anticipated on low volume (0-100 ADT) highways, use length determinations for the higher volume category.
- MBGF may not be required to shield departure end of bridge unless other methods within the horizontal clearance limits or opposing traffic indicate a MBGF consideration.
- Downstream anchor terminals (DAT) are only for downstream and enclosure use, outside the horizontal clearance area of opposing traffic.
- Direct connection of MBGF to concrete rails are only for downstream rail connections outside the horizontal clearance area of opposing traffic. Connections shall be a minimum of three standard line posts plus the DAT terminal. See Detail A.
- The crown shall be viewed to accommodate MBGF. Typically the "front slope" shall be viewed to accommodate MBGF. The MBGF shall be properly transitioned to be viewed to increase roadway width. This does not apply to ramp-connection work where existing roadway crown width is to be retained. Use typical cross section at MBGF.
- For restrictive bridge widths, the MBGF should be properly transitioned to be viewed to increase roadway width. This does not apply to ramp-connection work where existing roadway crown width is to be retained. Use typical cross section at MBGF.
- Standard metal beam guard fence on these bridges (concrete) shall be located the terminal end at the 2 1/4" "maximum" offset from the shoulder edge in the approach direction.
- Transition length and post spacing will vary depending on the transition type. Transition type will be shown elsewhere in the plans.
- A minimum 25' length of MBGF will be required.



BRIDGE END DETAILS
(METAL BEAM GUARD FENCE APPLICATIONS TO RIGID RAILS)


BED-14

DATE	BY	CHKD	APP'D

THOS Department of Transportation


TYPICAL PLAN VIEW

MODEL B (Self contained Steel BackUp)




TYPICAL ELEVATION VIEW

MODEL B (Self contained Steel BackUp)




TYPICAL PLAN VIEW

MODEL C (Concrete Backup with Side Mount Anchors)



TYPICAL ELEVATION VIEW

MODEL C (Concrete Backup with Side Mount Anchors)




GENERAL NOTES


1. For specific information regarding installation and technical guidance of the system, contact Trinity Highway Energy Absorption at 11881323-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60682.
2. The ribs of the REACT 350 shall be spaced with a plastic wrap with standard reflection on both sides of the unit. See site plan view for marker and plastic wrap color orientation.
3. All steel components to be hot dipped galvanized (except stakes); drive spikes, treated bolts in basins and, and wedge fittings on cables.
4. The installation area should be free from curbs, elevated collectors, or depressions. If the REACT system is to span expansion joints contact the manufacturer.
5. The REACT system should be approximately parallel with the centerline or E. of merging barriers. The maximum permissible cross-slope is 12.5%.
6. REACT 350 II has laminated concrete. In cylinders 1, 5, 6 & 8.

TYPE	REACT 350	REACT 350 II	REACT 350 II
Test Level	TL-2	TL-2	TL-3
OVERALL LENGTH	19'-3"	19'-3"	19'-5"

FOUNDATION TYPE	MINIMUM THICKNESS	ANCHORAGE
A CONCRETE PAD OR ROADWAY	6"	WP-3 WITH 1" STUDS 15-3" EMBEDMENT PLUS ASPHALT THICKNESS
B ASPHALT OVER CONCRETE PAVEMENT	6" CONCRETE PAVEMENT	AS ABOVE
C ASPHALT OVER BASE	8" BASE	WP-3 WITH 1" STUDS 15-3" EMBEDMENT
D ASPHALT ONLY	8"	WP-3 WITH 1" STUDS 15-3" EMBEDMENT



Trinity Highway Energy Absorption
TRINITY HIGHWAY ENERGY ABSORPTION (REACT 350 NARROW) (REACT 350 II NARROW) REACT(N)-16
 TEXAS DEPARTMENT OF TRANSPORTATION
 TRINITY HIGHWAY ENERGY ABSORPTION (REACT 350 NARROW) (REACT 350 II NARROW) REACT(N)-16
 DRAWN BY: [] CHECKED BY: [] DATE: []
 PROJECT NO. [] SHEET NO. []



DISCLAIMER: The use of this standard is governed by the Texas Engineering Practice Act, the terms of any bond or agreement for professional services, and the terms of any contract for engineering services. The user assumes no responsibility for the preparation of this document or for the accuracy of the information contained therein. The user assumes no responsibility for the preparation of this document or for the accuracy of the information contained therein.





- GENERAL NOTES**
1. For specific information regarding installation and technical details for this system, contact Trinity Highway - Energy Absorption at 11881-33-63-42, 70 N. Madison St., Suite 2300, Chicago, IL 60602.
 2. The back-up of the REACT 350 shall be clad with a plastic wrap which is to be attached to the back-up and the REACT 350. See the plan view for markers and plastic wrap color orientation.
 3. For bi-directional traffic, appropriate transition details will be as shown on the manufacturer's shop drawings.
 4. Details of components for the REACT(W) and back-up and reinforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
 5. If the cross-slope varies more than 2% over the length of the system, the concrete pad will require leveling. Maximum permissible cross-slope is 2%.
 6. The installation area should be free from curbs, elevated objects, or depressions.
 7. The REACT(W) system should be approximately parallel with the barrier or E of curbing barriers.
 8. All steel components to be hot-dipped galvanized, except spikes, anchor plates, threaded bolts in backup unit, and wedge fittings on casters.

WIDE REACT SYSTEMS			
SYSTEM TYPE	BACKUP WIDTH	TEST SYSTEM LENGTH	EFFECTIVE LENGTH
W60	60"	18'-10"	16'-3"
W66	66"	20'-10"	17'-8"
W72	72"	23'-10"	20'-2"

See the manufacturer's shop drawings for additional details.

ANCHOR SYSTEM TYPE
W60* requires reinforcing system with 1.5" spine, 5.5' element

FOUNDATION TYPES
Minimum 8" reinforced concrete pad required for concrete pad. Minimum 6" non-reinforced concrete pad required. Minimum 8" non-reinforced concrete pad required. Minimum 7" concrete stock structure, 3rd Minimum 5" reinforced concrete roadway




MONORAIL ASSEMBLY DETAIL
See the manufacturer's shop drawings for monorail hardware details.

TRINITY HIGHWAY
ENERGY ABSORPTION
CRASH CUSHION
(REACT 350 WIDE)
REACT(W) -16

TRINITY HIGHWAY
ENERGY ABSORPTION
CRASH CUSHION
(REACT 350 WIDE)
REACT(W) -16

LOW MAINTENANCE



- GENERAL NOTES:**
1. Refer to all drawings for materials and quantities. All materials shall be of the highest quality available and shall conform to the specifications of the American Institute of Steel Construction, Inc. (AISC).
 2. All steel shall be galvanized steel.
 3. All steel shall be painted with a minimum of two coats of a high quality, rust-inhibiting paint.
 4. All steel shall be galvanized steel.
 5. All steel shall be painted with a minimum of two coats of a high quality, rust-inhibiting paint.
 6. All steel shall be galvanized steel.
 7. All steel shall be painted with a minimum of two coats of a high quality, rust-inhibiting paint.


PROJECT NAME		POST & CABLE FENCE
PROJECT NUMBER		P.C.F.-05
DRAWING SCALE		1/4" = 1'-0"
DATE		
DRAWN BY		
CHECKED BY		
APPROVED BY		

GENERAL NOTES

1. For specific information regarding installation and technical details, refer to the system manufacturer's literature - Energy Absorption of (NSA) 325-874, 70th Edition, 5th Series 2550, Chicago, IL 60602.
2. For all directions, install, appropriate transition panels will be required.
3. Details of components for the road and backstop, and reinforcing furnished to the fabricator.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. If the cross-slope water ways show 2% over the length of the system, the concrete pad will require leveling. Minimum permeable cross-slope is .8%.
6. The installation area should be free from curbs, elevated objects, or obstructions.
7. The road system should be approximately parallel with the barrier or C of existing barriers.
8. Unit width selected would be adequate to protect an errant vehicle, traveling at 15 degrees to the roadway from the face or corner of the fixed object.
9. For the permanent steel backup (Type A), the distance between the back of backup and the barrier wall should not exceed 7 inches in any case.

Typ#	NO. OF BAYS	EFFECTIVE LENGTH	ROAD WIDTH	BACK STOP WIDTH
TL-2	2	8'-0"	9'-0"	4'-6"
TL-3	5	17'-0"	18'-0"	17'-0"

Additional base may be added if special applications exist and if the manufacturer's literature is consulted. All units are available in 24" increments. All units are available in 24" increments. All units are available in 24" increments.





TYPE A TENSION STRUT BACKUP

TENSION STRUT consists of diagonal struts, connected to the concrete pad at the rear of the DAD unit. Typical application is for DAD units attached to concrete curb. The front portion of the concrete pad, except where the DAD unit is to be placed on or bridge deck, will require concrete pavement or non-reinforced concrete pavement (minimum, 4,000 p.s.i.).


Anchor requirements are as follows:

WITH FOUNDATION TYPE	ANCHOR WITH
MINIMUM six inch diameter concrete pad	Embedment with 7" studs, 5.5" embedment
MINIMUM three inch diameter concrete over minimum three inch diameter concrete pad	Spiky anchoring system with 18" studs, 16.5" embedment
MINIMUM six inch diameter concrete over minimum six inch diameter concrete pad	Spiky anchoring system with 18" studs, 16.5" embedment
MINIMUM eight inch diameter concrete	Spiky anchoring system with 18" studs, 16.5" embedment

If the unit is anchored to asphaltic concrete, it should be rebarbed to the concrete with 18" studs. To ensure adequate future performance, a zero clearance between the back of barrier wall is recommended in no case should this distance exceed 7 inches.



QUADGUARD II SYSTEM DETAIL



MONORAIL ASSEMBLY DETAIL

See other manufacturer's shop drawings for monorail hardware installation.

TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD II) (NARROW)

QUAD (N) - 17

Scale: 1/4" = 1'-0"

DATE: 1/19/88

DESIGNED BY: [Name]

CHECKED BY: [Name]

APPROVED BY: [Name]


REUSABLE

GENERAL NOTES

1. For specifications regarding installation and technical details of the QUAD, consult the Energy Absorption at 148881323-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60602.
2. For bidirectional traffic, appropriate transition details will be required.
3. Details of components for the QUAD and baseplate and reinforcing steel for the manufacturer's shop drawings are furnished to the Engineer.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. If the cross-slope varies more than 2% over the length of the system, the address pad will require leveling, maximum accessible cross-slope is 2%.
6. The installation area should be free from curbs, elevated sections, or depressions.
7. The QUAD system should be approximately parallel with the barrier or line of marking barriers.
8. Unit width selected should be adequate to protect an entire vehicle traveling at 15 degrees to the roadway from the face or corner of the fixed object.

QUADGUARD II WIDEBAY SYSTEM			
Level	NO. OF BAYS	UNIT LENGTH	UNIT TYPE
TL-2	3	11'-0"	TYPE A
TL-3	5	17'-0"	TYPE B

Additional bays may be added if special conditions warrant and site conditions will accommodate additional length. QUAD II units are available in 8' and 10' unit widths. Number of bays, and backup type shall be specified elsewhere in the plans.




TYPE A TENSION STRUT BACKUP


TENSION STRUT: Consists of diagonal struts, end anchor bolts, and a concrete pad. The manufacturer, located on the rear of the unit, is attached to the concrete pad. The front portion of the concrete pad, except for anchor bolts, shall be provided beneath the QUAD unit. It is to be placed on a non-reinforced concrete pavement or on a minimum 4,000 p.s.i. reinforced concrete pavement.

TYPE B CONCRETE WALL BACKUP


CAST-IN-PLACE CONCRETE WALL BACKUP: If cast-in-place structures such as bridge abutments, columns, or special walls are used as backup structures, when immediately adjacent to the QUAD unit, the QUAD unit shall be reinforced with a steel backup. A cast-in-place concrete wall backup shall be placed on the standard barrier section to the standard backup section. Details for the intermediate walls, cast-in-place concrete walls, and concrete walls backup may be placed on continuously reinforced concrete pavement or bridge deck (minimum 4,000 p.s.i. for non-reinforced concrete pavement). The backup shall be placed on existing decks or placed and placed prior to pouring proposed decks as approved by the Engineer.




PLAN VIEW



ELEVATION VIEW



PLAN VIEW



ELEVATION VIEW

THESE DRAWINGS ARE THE PROPERTY OF THE ENGINEER. THE USER OF THIS DRAWING IS OBLIGATED TO PROTECT IT FROM UNAUTHORIZED REPRODUCTION. THE USER OF THIS DRAWING IS OBLIGATED TO PROTECT IT FROM UNAUTHORIZED REPRODUCTION. THE USER OF THIS DRAWING IS OBLIGATED TO PROTECT IT FROM UNAUTHORIZED REPRODUCTION.


Illinois Department of Transportation
TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD II) (WIDE)
QUAD (W) - 17

DATE: FEBRUARY 1987	DESIGNER: []	CHECKER: []	INCHES: []	FOOTING: []
PROJECT NO. 6314-60-001	SHEET NO. 17	TOTAL SHEETS: 17	SCALE: []	DATE: []

REUSABLE


GENERAL NOTES:

1. For specific information regarding installation and technical details, refer to the manufacturer's literature. Energy Absorption of 11,000 ft-lb (1500 J) for 50 mph impact. Concrete shall be 4,000 p.s.i. with a minimum compressive strength of 4,000 p.s.i.
2. After each impact, measurements should be taken of the shortest distance on the concrete pad from the original 32" to 20" diameter hole to the center of the hole. If the hole diameter is more than 20" in diameter, all the impact cylinders will need to be replaced, including the nose cylinder. If the hole diameter is less than 20" in diameter, only the hole cylinder will be replaced.
3. For bi-directional traffic, appropriate transition details will be required.
4. Details of components for the GCELLITE and backups and reinforcing details will be shown on the manufacturer's shop drawings furnished to the Engineer.
5. Concrete shall be class "3" with a minimum compressive strength of 4,000 p.s.i.
6. If the cross-section varies more than 2% over the length of the system, the concrete pad will require reinforcing. Minimum permissible cross-section is 36".
7. The installation area should be free from bumps, elevated objects, or depressions.
8. The GCELLITE system should be approximately parallel with the barrier 3'-6" of leading barriers.
9. All width setbacks should be adequate to protect an impact on the barrier. The setback should be 2'-0" from the face of the barrier to the face of the GCELLITE unit.



TENSION STRUT:
Consists of diagonal struts, connections, and accessories, as shown in the manufacturer's literature, located at the rear of the GCELLITE unit.


Typical Application:
GCELLITE units attached to 18" diameter Guard-Rails. When used a 4'-0" x 4'-0" x 3'-0" concrete for anchor block shall be provided beneath the front portion of the concrete pad, except where the GCELLITE units is to be placed on continuously reinforced concrete pavement or bridge deck (minimum 4,000 psi) or non-reinforced concrete pavement (minimum 4,000 psi).



QUADGUARD ELITE SYSTEM DETAIL

Concrete tie anchor block required, unless noted on shop drawings, or in front of concrete barrier.

Concrete tie anchor block required, unless noted on shop drawings, or in front of concrete barrier.



MONORAIL ASSEMBLY DETAIL

Concrete tie anchor block required, unless noted on shop drawings, or in front of concrete barrier.

Notes: Monorail & Backup assembly must be installed within one-half inch.

QUADGUARD ELITE (NARROW) SYSTEM			
Test Level	No. of Spacing Bars	UNIT SYSTEM EFFECTIVE LENGTH	OBSTACLE WIDTH
TL-2	5	17'-3"	12'-0"
TL-3	8	25'-11"	24" to 36"

SEE MANUFACTURER'S SHOP DRAWINGS FOR TYPE A BACKUP INFORMATION.

ANCHORAGE REQUIREMENTS ARE AS FOLLOWS:

WITH FOUNDATION TYPE:	ANCHOR WITH:
Minimum 8" post-tensioned concrete	Epoxy anchoring system with 7" studs and 5.5" embedment
8" post-tensioned concrete pad	

Trinity Highway Energy Absorption (QUADGUARD ELITE) (NARROW) GCELLITE (N) - 17

Trinity Highway Energy Absorption (QUADGUARD ELITE) (NARROW) GCELLITE (N) - 17


DATE: 08/15/2011
DRAWN BY: [Name]
CHECKED BY: [Name]
APPROVED BY: [Name]

LOW MAINTENANCE

DISCLAIMER: This set of drawings is provided by the Texas Engineering Experiment Station (TEXES) for the use of the user. TEXES does not assume any responsibility for the accuracy or completeness of the information provided. The user is responsible for the accuracy and completeness of the information provided. The user is responsible for the accuracy and completeness of the information provided.

GENERAL NOTES

- For specific information regarding installation and technical guidance of the system, contact Trinity Highway Energy Absorption at (488) 325-6374, 70 W. Madison St., Suite 2350, Chicago, IL 60602.
- After each impact, measurements should be taken at the shortest outside diameter of the last cylinder (closest to the backup), when the cylinder is reduced from its original diameter. The measurements should be taken at the same location, including the case of impact. The measurements will need to be repeated, including the case of impact, as required.
- For bi-directional traffic, appropriate transition details will be required.
- Details of components for the QCELTIE and backup and reinforcing details will be shown on the manufacturer's shop drawings.
- Concrete shall be class "5" with a minimum compressive strength of 4,000 psi.
- The vertical bars shall be spaced at the length of the system, the concrete and will require a maximum maximum permeable cross-section is 3".
- The installation area should be free from curbs, streets, collectors, or obstructions.
- The QCELTIE system should be approximately parallel with the barrier or E of merging barriers.
- Unit width selected should be adequate to protect on impact vehicle travelling at 15 degrees to the roadway from the face of corner of the fixed object.



TENSION STRUTS:
Details of diagonal struts, connections, and connector, to be detailed by the manufacturer, located on the face of the QCELTIE unit.

Typical application:
QCELTIE units attached to ECUATE-Fuse Guard-Rail, J When used a 4'-0" x 4'-0" x 3'-0" concrete box and/or block shall be provided beneath the top portion of the concrete and secured by rebar. The concrete or bridge deck (7" minimum, 4,000 psi) or concrete reinforced concrete pavement (8" minimum, 4,000 psi)



Test Level	NO. OF DAYS	QUADGUARD ELITE (WIDE) SYSTEM			UNSTABLE WIDTH	
		UNIT LENGTH	PAD LENGTH	RAIL LENGTH		
TL-2	7	17'-11"	17'-3"	14'-0"	12'-0"	69" to 90"
TL-3	8	26'-7"	25'-11"	27'-11"	21'-0"	

SEE MANUFACTURER'S SHOP DRAWINGS FOR TYPE A BACKUP INFORMATION.

WITH FOUNDATION TYPES: ANCHOR WITH Epoxy anchor into existing with 75# stirrup and 3/8" embedment

ANCHORAGE REQUIREMENTS ARE AS FOLLOWS:

Concrete use epoxy: black, red, or white, unless used on crack bridge deck or in front of concrete barrier.



TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD ELITE) (WIDE) QCELTIE (W) - 17


TRINITY HIGHWAY ENERGY ABSORPTION (QUADGUARD ELITE) (WIDE) QCELTIE (W) - 17

DATE: 10/15/11
DRAWN BY: [Name]
CHECKED BY: [Name]
APPROVED BY: [Name]


LOW MAINTENANCE

GENERAL NOTES:

1. For assistance information regarding installation and technical assistance of the system, contact: Trinity Highway at 1(888)323-6374, 2825 W. Stemmons Freeway, Dallas, TX 75207
2. For bleed-traction traffic, appropriate traction panels will be required.
3. Details of components for the TRACC and backstop and reinforcing details will be shown on the manufacturer's shop drawing furnished to the Engineer.
4. Concrete shall be class "B" with a minimum compressive strength of 4,000 p.s.i.
5. The connections shall be made with a minimum lap length of 24" over the length of the reinforcement. The reinforcement shall be lap spliced at a minimum lap length of 24".
6. The installation area should be free from curbs, elevated objects, or obstructions.
7. The TRACC system should be approximately parallel with the barrier or edge of merging barrier.



Attachment shown is to ensure with the TRACC system into modified concrete Traffic Barriers. Traffic flow is uni-directional.



Attachments are responsible to cover exposed barrier railings and all structural traffic flows are available. (See manufacturer's product manual)

TYPE (NARROW)	TEST LEVEL	SYSTEM LENGTH	EFFECTIVE LENGTH	PAD LENGTHS
FASTRACC (1 Stage System)	70'	26'	27'-0"	26'-0"
TRACC (2 STAGE System)	71'-3"	21'-3"	23'-0"	22'-0" 23'-0" 24'-0"
SHORTRACC (2 STAGE System)	71'-2"	14'-3"	14'-0"	13'-0" 18'-0" 17'-0"

The Stage System refers to number of replaceable steel sections that could be replaced independently. Concrete pad length on TRACC & SHORTRACC depends on backup type.

FOUNDATION OPTIONS:

6" Reinforced concrete
8" Unreinforced concrete
3" Min. Asphalt over 3" Min. Concrete
6" Asphalt over 3" Compact Subbase
8" Minimum Asphalt

For steel placement in concrete foundations. (See manufacturer's product manual)


BACKUP SUPPORT OPTIONS:

Square Concrete Backup
Concrete Barrier (CBB) Backup
Single Slope Concrete Barrier (SSCB)
Quadrant Backup (Beehive Post)
Quadrant Backup (Drum Post)

TRANSITION OPTIONS:

Vertical Wall
Modified (CBB) to Vertical Wall
Concrete Barrier (CBB)
Quadrant (Drum Post)
Quadrant (Beehive)

For Uni-directional transition panel details (See manufacturer's product manual)
Backup and transition types are shown elsewhere on the plans, i.e. Attenuator location details etc. in the General Notes.



BELL OF MATERIAL

TRACC #	QTY	DESCRIPTION
24938A	1	FASTRACC UNIT ASSEMBLY
24938B	1	TRACC UNIT ASSEMBLY
24939A	1	SHORTRACC UNIT ASSEMBLY
33100	4	4 1/2" Dia x 6" Section Epoxy Anchor
44510	4	4 1/2" Dia x 6" Section Epoxy Anchor
65210	1	1 Plastic Staples
66500	4	4 Reflective Sheet Ing
* ANCHOR HARDWARE (CONCRETE BASE)		
32040	22	22 1/2" Dia x 7 1/2" x 1/2" Stud Rod
33100	32	32 1/2" x 1/2" Lockwasher
33610	32	32 1/2" x 1/2" Hex Nut
33000	32	32 1/2" Flat Washer
32000	3	3 TRACC ANCHORS W/ 1/2" DIA x 1/2"
* ANCHOR HARDWARE (ASPHALT BASE)		
63000	32	32 1/2" Dia x 7 1/2" x 1/2" Stud Rod
33100	32	32 1/2" x 1/2" Lockwasher
33610	32	32 1/2" x 1/2" Hex Nut
33000	32	32 1/2" Flat Washer
32000	3	3 TRACC ANCHORS W/ 1/2" DIA x 1/2"

* See manufacturer's product manual








Trinity Highway
Crash Cushion (Narrow)
TRACC (N) - 16

Texas Department of Transportation
Design Division Standard

FILE NUMBER	PROJECT	DATE	SCALE
DATE	BY	CHECKED	DATE

REUSABLE

DISCLAIMER
The use of this standard is intended to provide a uniform basis for the construction of this project and does not constitute an endorsement or approval by the State of Texas of the products or services mentioned herein. The contractor shall be responsible for the design and construction of the project and shall be responsible for the safety of the project.



- GENERAL NOTES**
1. See specific information regarding installation for each component of the system. Road Systems, Inc., at 13301 146th St., Houston, Texas 77040.
 2. Due to the SSSC's design, the SSSC is not recommended for use at locations where median locations where bases to absorb the direction of travel are likely.
 3. All bolts, nuts, washers, cables, cables, bearings, rollers, spacers, posts, impact heads, and other steel components shall be galvanized, unless otherwise noted.
 4. The bracket cable assembly must be installed in a location where it will not be subjected to any other stress or strain.
 5. When the cable assembly is installed, the lower section of the cable shall be secured to the upper section of the cable with a splice.
 6. If rock excavation is encountered, see manufacturer's installation booklet for installation recommendations.
 7. Post shall not be set full depth in concrete.
 8. The appropriate connection at the SSSC to the rail body's field structure is indicated in the system to insure proper performance of the system. The length of the rail body used to attach the system to the field structure will vary with the wall thickness and will need to be determined in the field.
 9. The compression area in front of the SSSC and the area within the system itself shall be free of high or water.
 10. Unless otherwise shown in the plans, SSSC will be placed in the vicinity of curves shall be placed on so that the face of the SSSC is located directly in front of the curve. The SSSC shall be installed on the ground surface, make the gutter run or roadway surface, curve located along or in front of the SSSC system shall not be greater than 4 inches in height.
 11. An object marker shall be installed on the front of the impact head as detailed on P. 4, 20/21/22.

ITEM NO.	DESCRIPTION
1	Steel Plate, Impact Head
2	Steel Plate, Impact Head
3	Steel Plate, Impact Head
4	Steel Plate, Impact Head
5	Steel Plate, Impact Head
6	Steel Plate, Impact Head
7	Steel Plate, Impact Head
8	Steel Plate, Impact Head
9	Steel Plate, Impact Head
10	Steel Plate, Impact Head
11	Steel Plate, Impact Head
12	Steel Plate, Impact Head
13	Steel Plate, Impact Head
14	Steel Plate, Impact Head
15	Steel Plate, Impact Head
16	Steel Plate, Impact Head
17	Steel Plate, Impact Head
18	Steel Plate, Impact Head
19	Steel Plate, Impact Head
20	Steel Plate, Impact Head
21	Steel Plate, Impact Head
22	Steel Plate, Impact Head
23	Steel Plate, Impact Head
24	Steel Plate, Impact Head
25	Steel Plate, Impact Head
26	Steel Plate, Impact Head
27	Steel Plate, Impact Head
28	Steel Plate, Impact Head
29	Steel Plate, Impact Head
30	Steel Plate, Impact Head
31	Steel Plate, Impact Head
32	Steel Plate, Impact Head
33	Steel Plate, Impact Head
34	Steel Plate, Impact Head
35	Steel Plate, Impact Head
36	Steel Plate, Impact Head
37	Steel Plate, Impact Head
38	Steel Plate, Impact Head
39	Steel Plate, Impact Head
40	Steel Plate, Impact Head
41	Steel Plate, Impact Head
42	Steel Plate, Impact Head
43	Steel Plate, Impact Head
44	Steel Plate, Impact Head
45	Steel Plate, Impact Head
46	Steel Plate, Impact Head
47	Steel Plate, Impact Head
48	Steel Plate, Impact Head
49	Steel Plate, Impact Head
50	Steel Plate, Impact Head

Texas Department of Transportation
Design Division
Standard

ROAD SYSTEMS INC
CRASH CUSHION
(BEAT)

SSCC-16

DATE: 10/11/01
DRAWN: J. H. HARRIS
CHECKED: J. H. HARRIS

THE USE OF THIS STANDARD IS SOLELY FOR THE PURPOSE OF IDENTIFYING THE PRODUCTS AND SERVICES TO BE USED IN THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SELECTION OF THE PRODUCTS AND SERVICES TO BE USED IN THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SELECTION OF THE PRODUCTS AND SERVICES TO BE USED IN THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SELECTION OF THE PRODUCTS AND SERVICES TO BE USED IN THE PROJECT.

GENERAL NOTES

- For specific information regarding the installation and technical guidance of the system, contact: Liberty Transportation Solutions - Barrier Systems, Inc., or (707) 374-9600, 180 River Road, Rio Vista, CA 94071
- Refer to the installation manual and configuration chart for system assembly and element orientation. For bi-directional traffic, appropriate transition details will be required.
- Additional details for the backup support system, installation and foundation details will be shown on the manufacturer's and drawings furnished to the engineer.
- Concrete shall be class "5" with a minimum compressive strength of 4,000 p.s.i.
- Maximum permissible cross-slope is 2%.
- The installation area should be free from other elevated objects, or depressions.
- The TAU-II system should be approximately parallel with the barrier or center line of merging barriers.
- 30-inch (30") model shown, also available in 36-inch (36") configuration.

BILL OF MATERIAL

PRODUCT CODE	QTY	DESCRIPTION
B03070A	1	Front Support
B03070B	1	Middle Support Diaphragm
B03070C	1	Backup Support Diaphragm
B01002	1	Energy Absorbing Cartridge Type A
B01072	1	Energy Absorbing Cartridge Type B
B01008	1	Anchor Post/Kit
B01004	1	Cable Guide Assembly Kit
B01005	1	5/16" Galv. Steel
B01006	1	End Plate
B01007	1	End Plate
B01008	1	End Plate
B01009	1	End Plate
B01010	1	End Plate
B01011	1	End Plate
B01012	1	End Plate
B01013	1	End Plate
B01014	1	End Plate
B01015	1	End Plate
B01016	1	End Plate
B01017	1	End Plate
B01018	1	End Plate
B01019	1	End Plate
B01020	1	End Plate
B01021	1	End Plate
B01022	1	End Plate
B01023	1	End Plate
B01024	1	End Plate
B01025	1	End Plate
B01026	1	End Plate
B01027	1	End Plate
B01028	1	End Plate
B01029	1	End Plate
B01030	1	End Plate
B01031	1	End Plate
B01032	1	End Plate
B01033	1	End Plate
B01034	1	End Plate
B01035	1	End Plate
B01036	1	End Plate
B01037	1	End Plate
B01038	1	End Plate
B01039	1	End Plate
B01040	1	End Plate
B01041	1	End Plate
B01042	1	End Plate
B01043	1	End Plate
B01044	1	End Plate
B01045	1	End Plate
B01046	1	End Plate
B01047	1	End Plate
B01048	1	End Plate
B01049	1	End Plate
B01050	1	End Plate
B01051	1	End Plate
B01052	1	End Plate
B01053	1	End Plate
B01054	1	End Plate
B01055	1	End Plate
B01056	1	End Plate
B01057	1	End Plate
B01058	1	End Plate
B01059	1	End Plate
B01060	1	End Plate
B01061	1	End Plate
B01062	1	End Plate
B01063	1	End Plate
B01064	1	End Plate
B01065	1	End Plate
B01066	1	End Plate
B01067	1	End Plate
B01068	1	End Plate
B01069	1	End Plate
B01070	1	End Plate
B01071	1	End Plate
B01072	1	End Plate
B01073	1	End Plate
B01074	1	End Plate
B01075	1	End Plate
B01076	1	End Plate
B01077	1	End Plate
B01078	1	End Plate
B01079	1	End Plate
B01080	1	End Plate
B01081	1	End Plate
B01082	1	End Plate
B01083	1	End Plate
B01084	1	End Plate
B01085	1	End Plate
B01086	1	End Plate
B01087	1	End Plate
B01088	1	End Plate
B01089	1	End Plate
B01090	1	End Plate
B01091	1	End Plate
B01092	1	End Plate
B01093	1	End Plate
B01094	1	End Plate
B01095	1	End Plate
B01096	1	End Plate
B01097	1	End Plate
B01098	1	End Plate
B01099	1	End Plate
B01100	1	End Plate
B01101	1	End Plate
B01102	1	End Plate
B01103	1	End Plate
B01104	1	End Plate
B01105	1	End Plate
B01106	1	End Plate
B01107	1	End Plate
B01108	1	End Plate
B01109	1	End Plate
B01110	1	End Plate
B01111	1	End Plate
B01112	1	End Plate
B01113	1	End Plate
B01114	1	End Plate
B01115	1	End Plate
B01116	1	End Plate
B01117	1	End Plate
B01118	1	End Plate
B01119	1	End Plate
B01120	1	End Plate
B01121	1	End Plate
B01122	1	End Plate
B01123	1	End Plate
B01124	1	End Plate
B01125	1	End Plate
B01126	1	End Plate
B01127	1	End Plate
B01128	1	End Plate
B01129	1	End Plate
B01130	1	End Plate
B01131	1	End Plate
B01132	1	End Plate
B01133	1	End Plate
B01134	1	End Plate
B01135	1	End Plate
B01136	1	End Plate
B01137	1	End Plate
B01138	1	End Plate
B01139	1	End Plate
B01140	1	End Plate
B01141	1	End Plate
B01142	1	End Plate
B01143	1	End Plate
B01144	1	End Plate
B01145	1	End Plate
B01146	1	End Plate
B01147	1	End Plate
B01148	1	End Plate
B01149	1	End Plate
B01150	1	End Plate
B01151	1	End Plate
B01152	1	End Plate
B01153	1	End Plate
B01154	1	End Plate
B01155	1	End Plate
B01156	1	End Plate
B01157	1	End Plate
B01158	1	End Plate
B01159	1	End Plate
B01160	1	End Plate
B01161	1	End Plate
B01162	1	End Plate
B01163	1	End Plate
B01164	1	End Plate
B01165	1	End Plate
B01166	1	End Plate
B01167	1	End Plate
B01168	1	End Plate
B01169	1	End Plate
B01170	1	End Plate
B01171	1	End Plate
B01172	1	End Plate
B01173	1	End Plate
B01174	1	End Plate
B01175	1	End Plate
B01176	1	End Plate
B01177	1	End Plate
B01178	1	End Plate
B01179	1	End Plate
B01180	1	End Plate
B01181	1	End Plate
B01182	1	End Plate
B01183	1	End Plate
B01184	1	End Plate
B01185	1	End Plate
B01186	1	End Plate
B01187	1	End Plate
B01188	1	End Plate
B01189	1	End Plate
B01190	1	End Plate
B01191	1	End Plate
B01192	1	End Plate
B01193	1	End Plate
B01194	1	End Plate
B01195	1	End Plate
B01196	1	End Plate
B01197	1	End Plate
B01198	1	End Plate
B01199	1	End Plate
B01200	1	End Plate

TRANSITION OPTIONS

- VERTICAL WALL
- CONCRETE TRAFFIC BARRIERS
- W-BEAM GUARDRAIL
- TRIPLE BEAM GUARDRAIL

BACKUP AND TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS. (SEE ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES.)

FOR BI-DIRECTIONAL TRANSITION PANEL AND PCB SHIELD DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.

FOUNDATION OPTIONS

- 6" REINFORCED CONCRETE
- 8" UNREINFORCED CONCRETE
- ASPHALT OVER CONCRETE WITH MINIMUM 6" EMBEDMENT IN CONCRETE
- 6" ASPHALT OVER 4" COMPACT SUBBASE
- 8" MINIMUM ASPHALT

FOR STEEL PLACEMENT OR CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

TAU-II (NARROW) SYSTEM LENGTHS

BACKSTOP	TL-2	TL-3	70 mph
PCB	12'-7"	26'-10"	29'-7"
FLUSH MOUNT	13'-0"	27'-3"	30'-0"
COMPACT	14'-3"	28'-6"	31'-3"

NOTE: SYSTEM LENGTHS ARE 32"

TAU-II (NARROW) SYSTEM LENGTHS

BACKSTOP	TL-2	TL-3	70 mph
PCB	12'-7"	26'-10"	29'-7"
FLUSH MOUNT	13'-0"	27'-3"	30'-0"
COMPACT	14'-3"	28'-6"	31'-3"

NOTE: SYSTEM LENGTHS ARE 32"

BACKUP SUPPORT OPTIONS

- COMPACT, STAND ALONE
- FLUSH MOUNT
- PCB (CONCRETE-BARRIER)

SECTION A-A

Notes: Piece of Inset or Attachment is shown elsewhere on the plans.

PLAN VIEW

TRAFFIC FLOW

ATTACHMENTS AND TRANSITIONS TO USE FOR BARRIER OPTIONS. BARRIER ATTACHMENTS AND BI-DIRECTIONAL TRAFFIC FLOW ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

ELEVATION VIEW

TRAFFIC FLOW

ROAD LENGTH (VARIES)

ROAD LENGTH FOR TAU-II SYSTEMS DEPENDS ON DESIGN SPEED AND BACKUP TYPE

SECTION A-A

Notes: Piece of Inset or Attachment is shown elsewhere on the plans.

Liberty Transportation Solutions
 Traffic Department of Transportation
LTS-BARRIER SYSTEMS
CRASH CUSHION
(NARROW UNIT)
TAU-II (N) - 16

FILE NO. _____
 DRAWING NO. _____
 DATE: _____
 SCALE: _____
 SHEET NO. _____

- GENERAL NOTES**
1. For specific information regarding installation and technical guidance of the system, contact: Highway Transportation Solutions - Barrier Systems, Inc. at 1703 314-6800, 110 River Road, Rio Vista, CA 94571
 2. Refer to installation manual and identification sheet for specific system assembly and element orientation.
 3. For unusual localities, the manufacturer's configuration sheet must be used. If the configuration sheet does not apply to your site, contact the manufacturer for a special design or design details. In some cases, contact the manufacturer for further information.
 4. For bi-directional traffic, incorporate transition panels will be required.
 5. Additional details for the backup support options, transition, and foundation options will be shown in the manufacturer's shop drawings furnished to the Engineer.
 6. Concrete shall be class "3" with a minimum compressive strength of 4,000 p.s.i.
 7. Maximum permitted cross-slope is .6%.
 8. The installation area should be free from curbs, elevated objects, or depressions.
 9. The TAU-II System should be approximately parallel with the barrier or axis of merging barrier.

BILL OF MATERIAL

PRODUCT CODE	QTY	DESCRIPTION
BO1004	1	FRONT SUPPORT
BO1005	1	MIDDLE SUPPORT
TBD	1	XL ROLLHEAD
TBD	1	XL BELLEHEAD
TBD	1	XLAL ROLLHEAD
TBD	1	XXAL ROLLHEAD
TBD	1	BACKUP SUPPORT
TBD	1	FRONT CABLE ANCHOR
TBD	1	NOSE
BO1002	1	SLIDING PANEL
BO1009	1	FRONT PANEL
BO1003	1	SLIDER ASSEMBLY KIT
BO1002	1	ENERGY ABSORBING CARTRIDGE, TYPE A
BO1022	1	ENERGY ABSORBING CARTRIDGE, TYPE B
TBD	2	CABLE
BO1001	1	LATERAL SUPPORT KIT
BO1004	1	CABLE GUIDE KIT
BO1005	2	FRONT SUPPORT LEG KIT
TBD	1	ANCHORING PADSHOE
BO1013	1	NOSE ATTACHING HARDWARE

(TBD) = To Be Determined, depending on Backup Width, Backup Type and System length. Use manufacturer's product manual


Texas Department of Transportation
Traffic Division
Standard

**LTS-BARRIER SYSTEMS
CRASH CUSHION
(WIDE UNIT)**

TAU-II (W) -16

DATE	REVISION	BY	CHKD
01/10/10	1	JM	JM
02/10/10	2	JM	JM
03/10/10	3	JM	JM
04/10/10	4	JM	JM
05/10/10	5	JM	JM

REUSABLE



FOR ATTACHMENT AND TRANSITIONS TO BARRIERS, HALLWAYS AND BI-DIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE. (SEE MANUFACTURER'S PRODUCT MANUAL)

FOUNDATION OPTIONS


6" REINFORCED CONCRETE
8" UNREINFORCED CONCRETE
ASPHALT OVER CONCRETE WITH MINIMUM 6" UNDERLAY ON CONCRETE

FOR STEEL PLACEMENT IN CONCRETE FOUNDATIONS, SEE MANUFACTURER'S PRODUCT MANUAL.

TAU-II (W) WIDE SYSTEM LENGTHS

SYSTEM WIDTH	TL-2	TL-3	70 MPH
42"	14'-4"	28'-5"	31'-3"
48"	14'-4"	28'-5"	31'-3"
54"	14'-4"	28'-5"	31'-3"
60"	11'-5"	23'-7"	29'-5"
66"	11'-5"	23'-7"	29'-5"
72"	11'-5"	23'-7"	29'-5"
78"	11'-5"	23'-7"	29'-5"
84"	11'-5"	23'-7"	29'-5"
90"	11'-5"	23'-7"	29'-5"
96"	11'-5"	23'-7"	29'-5"
102"	11'-5"	23'-7"	29'-5"

NOTE: SYSTEM LENGTHS ARE 4'-2"



NOTE: NOSE PILE DELINEATION ORIENTATION, IS SHOWN ELSEWHERE ON THE PLANS.


- BACKUP SUPPORT
 - WIDE-FLANGE BACKUP (STAND-ALONE)
 - TRANSITION OPTIONS
 - VERTICAL WALL
 - CONCRETE TRAFFIC BARRIER
 - W-BEAM GUARDRAIL
 - TURF BEAM GUARDRAIL
- TRANSITION TYPES ARE SHOWN ELSEWHERE ON THE PLANS, I.E. ATTENUATOR LOCATION DETAILS OR IN THE GENERAL NOTES.
- FOR BI-DIRECTIONAL TRANSITION PANEL AND END SHOE DETAILS, SEE MANUFACTURER'S PRODUCT MANUAL.

GENERAL NOTES:


- For specific information regarding installation and technical outcomes of the system, contact Lindsay Transportation Solutions - Barrier Systems, Inc. at (707) 374-8800, 180 River Road, Rio Vista, CA 94571
- For bi-directional traffic, appropriate transition panels will be required.
- Additional details for the backup support options, transition options and foundation options will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class "C" with a minimum compressive strength of 4,000 psi.
- Maximum permissible cross-slope is 3%.
- The installation area should be free from curbs, elevated objects, or depressions.
- The TAU-11-R system should be spaced (and/or partially) with the barrier or center of merging barrier.
- Refer to universal TAU-11-R configuration chart for specific systems configuration number and location of each type of energy absorbing element.
- 36" high (36") model shown, also available in 36-inch (36") configuration.

Attachments and transitions to various barrier types, barrier railings and bi-directional traffic flows are available.


(SEE MANUFACTURER'S PRODUCT MANUAL)



PLAN VIEW



ELEVATION VIEW



SECTION A-A

Note: Please see Inset for foundation details and end shoe details. Use Minimum Asphalt.

TRANSITION OPTIONS:

- Vertical Wall
- Concrete Traffic Barriers
- W-Beam Guardrail
- Triple Beam Guardrail

For bi-directional transition panel and end shoe details, see manufacturer's product manual.

FOUNDATION OPTIONS:

- 6" Reinforced Concrete
- 8" Unreinforced Concrete
- Asphalt over concrete with Minimum
- 6" Embedment in Concrete
- 6" Asphalt over 6" compact subbase
- 8" Minimum Asphalt

For steel placement in concrete foundation, see manufacturer's product manual.

ENERGY ABSORBING ELEMENTS (EAE)

Backup Support Options:

- Compact (Strand Alone)
- Flush Mount
- PGB (Concrete Barrier)

TAU-11-R (Narrow) System Lengths	Backstop	PGB	Flush Mount	Compact
JL-2	7'-0"	7'-0"	7'-0"	7'-0"
JL-3	7'-0"	7'-0"	7'-0"	7'-0"
27'-10"	36'-7"	36'-7"	36'-7"	36'-7"
28'-6"	36'-7"	36'-7"	36'-7"	36'-7"
28'-6"	36'-7"	36'-7"	36'-7"	36'-7"

Backup and Transition types are shown elsewhere on the plans. I.e. Attachment location details or in the general notes.

Note: System lengths are 2'

BILL OF MATERIAL

PRODUCT CODE	QTY	DESCRIPTION
8030704	1	Front Support
8030703	1	W/D Support
TBD	1	Backstop Assembly (See Table)
TBD	1	Front Cable Anchor
TBD	1	Noise Assembly
8010302	1	Sliding Panel
8010303	2	End Panel
8010304	1	Slider Assembly Kit
851-102069-KT	TBD	TAU-11-R EAE Kit
851-110131-KT	TBD	TAU-11-R EAE Mounting Kit
851-102069-00	TBD	Energy Absorbing Element, Type 1
851-102070-00	TBD	Energy Absorbing Element, Type 2
851-102071-00	TBD	Energy Absorbing Element, Type 3
851-1110038-00	TBD	Energy Absorbing Element, Type 3A
TBD	TBD	Cable Assembly
8001004	1	Cable Guide Kit
8001005	2	Front Support Leg Kit
8001006	4	Pipe Panel Mount
TBD	1	Anchoring Package

(TBD) = To Be Determined, depending on Backup Type and System Length.

(See manufacturer's product manual for details)

LTS-BARRIER SYSTEMS
CRASH CUSHION
(R-NARROW)
TAU-11-R (N) -16


Product Division Standard
Texas Department of Transportation

DATE: 10/11/2016	PROJECT: 1601	REV: 1	SCALE:
SYSTEM: 1601	DATE: 10/11/2016	BY: JBT	CHK: JBT
DESIGNER: JBT	CHECKER: JBT	DATE: 10/11/2016	SCALE: 1/8"=1'-0"


LOW MAINTENANCE

GENERAL NOTES

- For specific information regarding installation and technical conditions of the system, contact Lindsay Transportation Barrier Systems, Inc. at (707) 214-8400, 180 River Road, Ste Vista, CA 94971.
- For bi-directional traffic, appropriate transition details will be required.
- Additional details for the backup support system transition detail and foundation options will be shown on the manufacturer's shop drawings furnished to the Engineer.
- Concrete shall be class 75 with a minimum compressive strength of 4,000 psi.
- Maximum permissible cross-slope is 3%.
- The installation area should be free from curbs, elevated objects, or ground depressions.
- The TAU-11-R system should be installed approximately parallel with the barrier or center of merging barrier.
- Refer to universal TAU-11-R configuration charts for system configuration numbers and location of each type of energy absorbing element.




At intersections and transitions, the various barrier shapes, barrier railings and bi-directional traffic flows are available.
(See manufacturer's product manual)



TAU-11-R-WIDE SYSTEM LENGTHS		
SYSTEM WIDTH	TL-2	TL-3 TO mph
42"	15'-4"	29'-5"
48"	15'-4"	29'-5"
54"	15'-4"	29'-5"
60"	12'-5"	29'-5"
66"	12'-5"	29'-5"
72"	12'-5"	26'-7"
78"	12'-5"	26'-7"
84"	12'-5"	26'-7"
90"	12'-5"	26'-7"
96"	12'-5"	26'-7"
102"	12'-5"	26'-7"

Note: System lengths are +/-2"



ENERGY ABSORBING ELEMENTS (EAE)

(TBD) = To Be Determined, depending on Backup Type and System Length.
(S) = manufacturer's product manual for details

PRODUCT CODE	QTY.	DESCRIPTION
B030704	1	Front Support
B030703	TBD	Mid Support
TBD	TBD	XL Backup Pad
TBD	TBD	XXL Backup Pad
TBD	1	Backup Assembly (See Table)
TBD	2	Front Corner Anchor
TBD	1	Rose Assembly
B010202	2	End Panel
B010203	2	End Panel
K001003	1	Sliding Trolley
B51-120200E-KT	1	Sliding Trolley Kit
B51-1107131-KT	TBD	TAU-11-R EAE Mounting Kit
B51-1012069-00	TBD	Energy Absorbing Element, Type 1
B51-1012070-00	TBD	Energy Absorbing Element, Type 2
B51-1012071-00	TBD	Energy Absorbing Element, Type 3
B51-1109142-00	TBD	Energy Absorbing Element, Type 3S
B51-1107118-00	TBD	Energy Absorbing Element, Type 2S
B51-11110009-00	TBD	Energy Absorbing Element, Type 3H
TBD	TBD	Cable Assembly
X001031	TBD	Letteral Support kit
X001034	TBD	Letteral Guide Kit
X001035	2	Front Support Leg Kit
TBD	1	Mounting Package

LTS-BARRIER SYSTEMS
CRASH CUSHION
(R-WIDE)
TAU-11-R (W) -16

16000 River Road, Ste Vista, CA 94971
Tel: (707) 214-8400
Fax: (707) 214-8401
www.lts-barrier.com

DATE: 01/07/2013
REV: 01/07/2013
PROJECT: 6314-60-001

DESIGN: []
CHECK: []
DATE: []
BY: []

FOUNDATION OPTIONS

- 8" Reinforced Concrete
- 8" Unreinforced Concrete
- Asphalt over concrete with minimum 6" embedment in concrete

TRANSITION OPTIONS


- Vertical Wall
- Concrete Traffic Barriers
- W-beam Guardrail
- Triple Beam Guardrail

BACKUP SUPPORT OPTIONS

- Wide Flange (stand alone)

Note: Backup and Transition types are shown elsewhere on the plans. I.E. Attachment location details or in the general notes.

Note: Steel placement in concrete foundation. (See manufacturer's product manual)



LEGEND

Symbol	Type 3 Barricade	Flagger	Channelizing Devices
[Symbol]	Heavy Work Vehicle	Flagger	Flagger
[Symbol]	Flagger Arrow Board	Flagger	Flagger
[Symbol]	Sign	Flagger	Flagger
[Symbol]	Flagger	Flagger	Flagger

Speed (mph)	Work Zone Length (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)	Advance Warning (ft)
30	150	150	150	150	150	150	150	150	150
35	180	180	180	180	180	180	180	180	180
40	210	210	210	210	210	210	210	210	210
45	240	240	240	240	240	240	240	240	240
50	270	270	270	270	270	270	270	270	270
55	300	300	300	300	300	300	300	300	300
60	330	330	330	330	330	330	330	330	330
65	360	360	360	360	360	360	360	360	360
70	390	390	390	390	390	390	390	390	390
75	420	420	420	420	420	420	420	420	420

TYPICAL USAGE

Mobile	Short	Long	Intermediate	Long Term
✓	✓	✓	✓	✓

GENERAL NOTES


1. All traffic control devices shall be installed in accordance with the Manual on Uniform Traffic Control Devices (MUTCD), except those devices specified in the notes.
2. All traffic control devices shall be installed in the blocks, or for varying lengths, as indicated in the notes.
3. The sign shall be placed to stop or to yield as indicated in the notes.
4. The sign shall be placed to stop or to yield as indicated in the notes.
5. In advance of the work, if workers are no longer present but road or work conditions require the sign to be placed, it shall be placed in the advance of the work.
6. Additional signs shall be placed in the advance of the work as indicated in the notes.
7. Signs shall be placed in the advance of the work as indicated in the notes.
8. Signs shall be placed in the advance of the work as indicated in the notes.
9. Signs shall be placed in the advance of the work as indicated in the notes.
10. Signs shall be placed in the advance of the work as indicated in the notes.
11. Signs shall be placed in the advance of the work as indicated in the notes.
12. Signs shall be placed in the advance of the work as indicated in the notes.
13. Signs shall be placed in the advance of the work as indicated in the notes.

Texas Department of Transportation
Traffic Operations Division

TRAFFIC CONTROL PLAN
ONE-LANE TWO-WAY
TRAFFIC CONTROL

TCP (1-2) - 12

DATE	12/15/00	DESIGNED BY	12/15/00
SCALE	AS SHOWN	CHECKED BY	12/15/00
PROJECT	12/15/00	APPROVED BY	12/15/00



LEGEND

Symbol	Description
[Symbol]	Type 3 Barricade
[Symbol]	Channelizing Devices
[Symbol]	Truck Mounted Attenuator (TMA)
[Symbol]	Portable Bannable
[Symbol]	Flagger (SEE 1001 USES)
[Symbol]	5100
[Symbol]	5100
[Symbol]	Flagger

Speed (mi/h)	Minimum Spacing (ft)	Minimum Spacing (ft) - 100 ft	Minimum Spacing (ft) - 150 ft	Minimum Spacing (ft) - 200 ft	Minimum Spacing (ft) - 250 ft	Minimum Spacing (ft) - 300 ft	Minimum Spacing (ft) - 350 ft	Minimum Spacing (ft) - 400 ft	Minimum Spacing (ft) - 450 ft	Minimum Spacing (ft) - 500 ft
10	150	150	150	150	150	150	150	150	150	150
20	150	150	150	150	150	150	150	150	150	150
30	150	150	150	150	150	150	150	150	150	150
40	150	150	150	150	150	150	150	150	150	150
50	150	150	150	150	150	150	150	150	150	150
60	150	150	150	150	150	150	150	150	150	150
70	150	150	150	150	150	150	150	150	150	150
80	150	150	150	150	150	150	150	150	150	150
90	150	150	150	150	150	150	150	150	150	150
100	150	150	150	150	150	150	150	150	150	150

Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing
Minimum Spacing

TYPICAL USAGE

Signals	Short Station	Intermediate Station	Long Term Station
[Symbol]	[Symbol]	[Symbol]	[Symbol]


- GENERAL NOTES**
1. All traffic control signs should be placed in advance of the work zone in the direction of travel.
 2. Flagger control should not be used unless specifically authorized by the contract.
 3. Flagger control should not be used unless specifically authorized by the contract.
 4. All workers should wear high visibility safety vests.
 5. When the work zone is less than 1/2 mile in length, all workers should wear high visibility safety vests.
 6. All workers should wear high visibility safety vests.
 7. All workers should wear high visibility safety vests.
 8. All workers should wear high visibility safety vests.
 9. All workers should wear high visibility safety vests.
 10. All workers should wear high visibility safety vests.


Texas Department of Transportation
Traffic Operations Division

**TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO LANE ROADS**

TCP (1-3)-12

DATE	2-17
BY	[Name]
CHECKED	[Name]
DATE	2-17
BY	[Name]
CHECKED	[Name]
DATE	2-17
BY	[Name]





DISCLAIMER: The use of this plan is for informational purposes only. It is not intended to be used as a legal document. The user assumes all responsibility for the use of this plan. The user agrees to hold the provider harmless for any and all damages, including consequential damages, arising from the use of this plan. The provider makes no warranty, express or implied, regarding the accuracy or completeness of the information contained herein. The provider is not liable for any errors or omissions in this plan. The provider is not responsible for any delays or interruptions in the service provided by this plan. The provider is not responsible for any loss of data or information resulting from the use of this plan. The provider is not responsible for any unauthorized access to or disclosure of any information contained in this plan. The provider is not responsible for any use of this plan in violation of applicable laws or regulations. The provider is not responsible for any use of this plan in violation of applicable policies or procedures. The provider is not responsible for any use of this plan in violation of applicable standards or practices. The provider is not responsible for any use of this plan in violation of applicable codes or standards. The provider is not responsible for any use of this plan in violation of applicable laws, regulations, policies, procedures, standards, or practices.

LEGEND

Symbol	Symbol	Symbol	Symbol
Channelizing Device	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Heavy Work Vehicle	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Trailing Vehicle	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Fishing Arrow Board	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Sign	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)
Flag	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)	Truck Mounted Attenuator (TMA)

Proposed Number of Lanes	Minimum Spacing of Channelizing Devices (ft)	Minimum Spacing of Channelizing Devices (ft)	Minimum Spacing of Channelizing Devices (ft)	Minimum Spacing of Channelizing Devices (ft)	Minimum Spacing of Channelizing Devices (ft)
30	135'	180'	30'	60'	120'
35	135'	225'	35'	70'	150'
40	135'	270'	40'	80'	180'
45	135'	315'	45'	90'	210'
50	135'	360'	50'	100'	240'
55	135'	405'	55'	110'	270'
60	135'	450'	60'	120'	300'
65	135'	495'	65'	130'	330'
70	135'	540'	70'	140'	360'
75	135'	585'	75'	150'	390'
80	135'	630'	80'	160'	420'
85	135'	675'	85'	170'	450'
90	135'	720'	90'	180'	480'
95	135'	765'	95'	190'	510'
100	135'	810'	100'	200'	540'

TYPICAL USAGE

Vehicle	Short Term	Intermediate	Long Term
Mobile	✓	✓	✓
Stationary	✓	✓	✓
Stationary	✓	✓	✓

- GENERAL NOTES**
- Plan of road to show where cones are located.
 - All traffic control devices illustrated are required, except those omitted or otherwise indicated.
 - The "ROAD WORK AHEAD" sign may be replaced by the "ROAD WORK" sign.
 - A stability of the work zone is less than 1000 feet. It can be maintained for a period of 30 to 100 feet in advance of the work zone.
 - When a vehicle is stopped in a work zone, the driver should be notified of the work zone.
 - When a vehicle is stopped in a work zone, the driver should be notified of the work zone.

Texas Department of Transportation
Traffic Control Devices Division


TRAFFIC CONTROL PLAN


LANE CLOSURES ON MULTILANE CONVENTIONAL ROADS

TCP (1-4) - 12


Project No.	193	Sheet No.	12
Date	2-12	Scale	AS SHOWN
Drawn by	...	Checked by	...
Approved by

For construction or maintenance of a road, the contractor shall be responsible for providing the traffic control devices and signs required for the work zone. The contractor shall be responsible for the placement and maintenance of the traffic control devices and signs. The contractor shall be responsible for the removal of the traffic control devices and signs when the work is completed. The contractor shall be responsible for the cost of the traffic control devices and signs. The contractor shall be responsible for the cost of the traffic control devices and signs.





DISCLAIMER: The use of this plan is limited to the project for which it was prepared. It is not to be used for any other project without the written consent of the Texas Department of Transportation. The Texas Department of Transportation is not responsible for any errors or omissions in this plan or for any consequences arising from its use.



LEGEND

Symbol	Item
[Symbol]	Truck Mounted Flashing Arrow Board
[Symbol]	Truck Mounted Message Sign (TMS)
[Symbol]	Flashing Arrow Board
[Symbol]	Sign
[Symbol]	Flare

Speed Limit (mph)	Minimum Length (ft)	Minimum Length (ft) - 100 mph	Minimum Length (ft) - 85 mph	Minimum Length (ft) - 70 mph	Minimum Length (ft) - 55 mph	Minimum Length (ft) - 40 mph
100	317	317	317	317	317	317
85	250	250	250	250	250	250
70	183	183	183	183	183	183
55	116	116	116	116	116	116
40	50	50	50	50	50	50

TYPICAL USAGE

Mobile	Stationary	Low New
[Symbol]	[Symbol]	[Symbol]
[Symbol]	[Symbol]	[Symbol]
[Symbol]	[Symbol]	[Symbol]
[Symbol]	[Symbol]	[Symbol]

GENERAL NOTES


1. All signs and devices shall be maintained in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
2. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
3. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
4. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
5. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
6. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
7. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
8. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
9. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).
10. Signs shall be placed in accordance with the Texas Department of Transportation Manual of Uniform Traffic Control Devices (MUTCD).


Texas Department of Transportation
Traffic Operations Division

**TRAFFIC CONTROL PLAN
CONVENTIONAL ROAD
SHOULDER WORK**

TCP (2-1) - 12

DATE	1/13/93
BY	1/13/93
CHECKED	1/13/93
APPROVED	1/13/93





LEGEND

Type 3 Barricade	W 8	Channelizing Device
Heavy Work Vehicle	W 10	Top Mount Barricade
Trailer Mounted Flashing Arrow Board	W 11	Relined Pavement Markings by 11-AA
Sign	W 12	Traffic Flow
Flare	W 13	

Typical Usage

Vehicle	Duration	Short Term Stationary	Intermediate Term Stationary	Long Term Stationary
W 8	15'	15'	15'	15'
W 10	15'	15'	15'	15'
W 11	15'	15'	15'	15'
W 12	15'	15'	15'	15'
W 13	15'	15'	15'	15'

GENERAL NOTES

1. Flare chains to a tow, wear chains, etc. REQUIRED.
2. All traffic control devices illustrated are required, except those denoted as optional.
3. When work zones will be in place, leading vehicles shall be used to separate traffic.
4. Flagger control should not be used unless roadway conditions or heavy traffic require it.
5. The R4-1, W1-1, W2-1, W3-1, W4-1, W5-1, W6-1, W7-1, W8-1, W9-1, W10-1, W11-1, W12-1, W13-1, W14-1, W15-1, W16-1, W17-1, W18-1, W19-1, W20-1, W21-1, W22-1, W23-1, W24-1, W25-1, W26-1, W27-1, W28-1, W29-1, W30-1, W31-1, W32-1, W33-1, W34-1, W35-1, W36-1, W37-1, W38-1, W39-1, W40-1, W41-1, W42-1, W43-1, W44-1, W45-1, W46-1, W47-1, W48-1, W49-1, W50-1, W51-1, W52-1, W53-1, W54-1, W55-1, W56-1, W57-1, W58-1, W59-1, W60-1, W61-1, W62-1, W63-1, W64-1, W65-1, W66-1, W67-1, W68-1, W69-1, W70-1, W71-1, W72-1, W73-1, W74-1, W75-1, W76-1, W77-1, W78-1, W79-1, W80-1, W81-1, W82-1, W83-1, W84-1, W85-1, W86-1, W87-1, W88-1, W89-1, W90-1, W91-1, W92-1, W93-1, W94-1, W95-1, W96-1, W97-1, W98-1, W99-1, W100-1.

TYPICAL USAGE

W 8: Channelizing Device
W 10: Top Mount Barricade
W 11: Relined Pavement Markings by 11-AA
W 12: Traffic Flow
W 13: Flare


CONTRACTOR'S RESPONSIBILITIES

For construction contract work, specific traffic control devices shall be used in the work zone. This traffic control plan is intended for the area of the confining workline, not the entire work zone.

TRAFFIC CONTROL PLAN
TRAFFIC SHIFTS ON
TWO-LANE ROADS

TCP (2-3)-12

Texas Department of Transportation
Traffic Operations Division



LEGEND

Type	Symbol	Description
Demarcating devices	—	Truck Mounted Attenuator (TMA)
Heavy Work Vehicle	☑	Truck Mounted Attenuator (TMA)
Flashing Arrow Board	(A)	Flashing Arrow Board
Flashing Arrow Board	(M)	Flashing Arrow Board
Flashing Arrow Board	(B)	Flashing Arrow Board
Flashing Arrow Board	(C)	Flashing Arrow Board
Flashing Arrow Board	(D)	Flashing Arrow Board
Flashing Arrow Board	(E)	Flashing Arrow Board
Flashing Arrow Board	(F)	Flashing Arrow Board
Flashing Arrow Board	(G)	Flashing Arrow Board
Flashing Arrow Board	(H)	Flashing Arrow Board
Flashing Arrow Board	(I)	Flashing Arrow Board
Flashing Arrow Board	(J)	Flashing Arrow Board
Flashing Arrow Board	(K)	Flashing Arrow Board
Flashing Arrow Board	(L)	Flashing Arrow Board
Flashing Arrow Board	(M)	Flashing Arrow Board
Flashing Arrow Board	(N)	Flashing Arrow Board
Flashing Arrow Board	(O)	Flashing Arrow Board
Flashing Arrow Board	(P)	Flashing Arrow Board
Flashing Arrow Board	(Q)	Flashing Arrow Board
Flashing Arrow Board	(R)	Flashing Arrow Board
Flashing Arrow Board	(S)	Flashing Arrow Board
Flashing Arrow Board	(T)	Flashing Arrow Board
Flashing Arrow Board	(U)	Flashing Arrow Board
Flashing Arrow Board	(V)	Flashing Arrow Board
Flashing Arrow Board	(W)	Flashing Arrow Board
Flashing Arrow Board	(X)	Flashing Arrow Board
Flashing Arrow Board	(Y)	Flashing Arrow Board
Flashing Arrow Board	(Z)	Flashing Arrow Board

TYPICAL USAGE

MOBILE	SHORT STATION	INTERMEDIATE	LONG TERM STATIONARY
✓	✓	✓	✓

GENERAL NOTES

- Flow arrows to signs shown, are required.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.
- Signs shall be used in accordance with the Manual on Uniform Traffic Control Devices, 4th Edition, as amended.

Texas Department of Transportation
Traffic Services Division

TRAFFIC CONTROL PLAN
LONG TERM LANE CLOSURES
MULTILANE CONVENTIONAL RDS.

TCP (2-5) - 12

PROJECT: _____ DATE: _____

DESIGNED BY: _____

CHECKED BY: _____

DATE: _____

SCALE: _____

PROJECT NO: _____


DATE: _____

SCALE: _____

PROJECT NO: _____

DATE: _____

SCALE: _____



LEGEND

□	Channelizing devices
→	Traffic Flow
○	Flower
▲	Temporary or Portable Traffic Signal

Speed	Width	Distance	Sign	Sign Size	Sign Spacing	Sign Color
30	10'	10'	11-1	36" X 48"	120'	Red
35	10'	15'	11-2	36" X 48"	120'	Red
40	10'	20'	11-3	36" X 48"	120'	Red
45	10'	25'	11-4	36" X 48"	120'	Red
50	10'	30'	11-5	36" X 48"	120'	Red
55	10'	35'	11-6	36" X 48"	120'	Red
60	10'	40'	11-7	36" X 48"	120'	Red
65	10'	45'	11-8	36" X 48"	120'	Red
70	10'	50'	11-9	36" X 48"	120'	Red
75	10'	55'	11-10	36" X 48"	120'	Red
80	10'	60'	11-11	36" X 48"	120'	Red
85	10'	65'	11-12	36" X 48"	120'	Red
90	10'	70'	11-13	36" X 48"	120'	Red
95	10'	75'	11-14	36" X 48"	120'	Red
100	10'	80'	11-15	36" X 48"	120'	Red

TYPICAL USAGE

ROAD TYPE	STATIONARY	INTERMEDIATE	LONG TERM
URBAN	✓	✓	✓
SUBURBAN	✓	✓	✓
RURAL	✓	✓	✓

GENERAL NOTES

- Flare off signs shall be used where shown on a location.
- 48" x 48" "ONE LANE BRIDGE" signs shall be used in lieu of the 36" x 48" "ONE LANE BRIDGE" signs. The 36" x 48" "ONE LANE BRIDGE" signs shall be used in lieu of the 36" x 48" "ONE LANE BRIDGE" signs.
- Do not place signs and stop or flag lines.
- Do not place signs and stop or flag lines.

TCP (2-8B)

TCP (2-8G)

TRAFFIC CONTROL PLAN
LONG TERM ONE-LANE
TWO-WAY CONTROL

TCP (2-8)-12

Texas Department of Transportation
Traffic Services Division










DATE	1-12
BY	1-12
CHKD BY	1-12
APP'D BY	1-12

LEGEND	
* Trail Vehicle	ARROW BOARD DISPLAY
** Shadow Vehicle	
*** Work Vehicle	RIGHT Directional
**** Heavy Work Vehicle	LEFT Directional
***** Truck Mounted Attenuator (TMA)	Double Arrow
***** Traffic Flow	SHOULDER Alternating (Downward or Upward Arrow)






TYPICAL CASES	
SHORT TRAIL VEHICLE	INTERMEDIATE TRAIL VEHICLE
STATIONARY TRAIL VEHICLE	LONG TRAIL VEHICLE
STATIONARY TRAIL VEHICLE	STATIONARY TRAIL VEHICLE

GENERAL NOTES

- TRAIL, SHADOW, and LEAD vehicles shall be equipped with arrow boards as specified. When a LEAD vehicle is not used the WORK vehicle must be equipped with an arrow board. The Engineer will determine if the LEAD vehicle is required. All vehicles shall be equipped with flashing roadway conditions, traffic volume, and sign distance restrictions.
- The use of other high intensity rotating, flashing, oscillating, or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights are required on the driver's side of the vehicle may be operated simultaneously with the case become or strobe lights.
- The use of truck mounted attenuators (TMA) on the SHADOW VEHICLE and TRAIL VEHICLE are required.
- Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of DEPARTMENTAL MATERIAL SPECIFICATION (MS 820), Type A.
- Flashing arrow boards shall be Type B or Type C as per the Barriore and Construction (BC) standards. The board shall be controlled from inside the vehicle.
- Each vehicle shall have two-way radio communication capability.
- When work convoys must change lanes, the TRAIL VEHICLE should change lanes first to show the other convoy vehicles.
- Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the TRAIL VEHICLE in time to slow down and/or change lanes as they approach the TRAIL VEHICLE. Vehicle spacing between the WORK VEHICLE and the TRAIL VEHICLE shall be determined by the WORK VEHICLE and LEAD VEHICLE varying according to terrain, work activity and other factors.
- "X VEHICLE CONVOY" (MS-1007) or "WORK CONVOY" (MS-1007) signs shall be used on TRAIL VEHICLES and SHADOW VEHICLES as shown. As an option an "X 48" diamond shaped sign shall be used. A VEHICLE CONVOY sign shall be used on the TRAIL VEHICLE. The number of the convoy vehicles displayed on the sign in the number and/or "X" location. The "X VEHICLE CONVOY" sign shall not be used on the SHADOW VEHICLE. If a TRAIL VEHICLE is used.
- On two-lane two-way roadways, the work and protection vehicles should still only periodically to allow motor vehicle traffic to pass. If motorists on the back of the pass the work convoy, a "DO NOT PASS" (M-11) sign should be placed on the back of the rear-most protection vehicles.






TRAFFIC CONTROL PLAN	
MOBILE OPERATIONS	
UNDIVIDED HIGHWAYS	
TCP (3-1)-13	
DATE: 10/11/11	BY: [Signature]
PROJECT: [Project Name]	LOCATION: [Location]
SCALE: 1/4" = 1'-0"	DATE: [Date]
REVISED: [Date]	BY: [Signature]
DATE: [Date]	BY: [Signature]
DATE: [Date]	BY: [Signature]
DATE: [Date]	BY: [Signature]



LEGEND	
* Trail Vehicle	Arrow Board Display
** Shadow Vehicle	Right-of-Way Sign
*** Heavy Mark Vehicle	Left-of-Way Sign
□ Track Mounted Attenuator (TMA)	Beacon Arrow
◁ Traffic Flare	Stationary Intermediate Stationary

TYPICAL USAGE:	
SHIELD	SHORT TERM
✓	INTERMEDIATE
	LONG TERM

- GENERAL NOTES:**
1. ADVANCE WARNING, TRAIL and SHADOW vehicles shall be equipped with Type B or Type C flashing arrow boards as per the back of the Construction Job Order. The flashing arrow board shall be used in accordance with the instructions included in the job order. The arrow boards shall be operated from inside the vehicle.
 2. For TCP(13-2b) the Engineer will determine if the TRAIL VEHICLE is restricted based on other vehicles shown for both TCP(13-2a) and TCP(13-2b) are required.
 3. The use of amber high intensity rotating, flashing, oscillating, or strobe lighting on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights, when mounted on the driver's side of the vehicle may be operated simultaneously with the amber, beacon or strobe lights.
 4. The use of truck mounted attenuators (TMA) on the ADVANCE WARNING, SHADOW, and TRAIL vehicles are required.
 5. Reflective sheeting on the rear of the TMA shall meet or exceed the reflectivity and color requirements of MVA 8300, Type A.
 6. Each vehicle shall have two-way radio communication capability.
 7. When work convoys meet at a junction, the TRAIL VEHICLE should advance lanes first to shadow the other convoy vehicles.
 8. Vehicle spacing between the TRAIL VEHICLE and the SHADOW VEHICLE will vary depending on sight distance requirements. Motorists approaching the work convoy shall be able to see the TRAIL VEHICLE in time to slow down. The TRAIL VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors.
 9. Standard 48" x 24" diamond shaped warning signs with the same message as those signs may be used where adequate mounting space exists.
 10. The signs shown should be used on the Advance Warning Vehicle. An exception, a particular sign, shall be used on the Shadow Vehicle. Motorists approaching the work convoy shall be able to see the TRAIL VEHICLE in time to slow down. The TRAIL VEHICLE and SHADOW VEHICLE may vary according to terrain, work activity and other factors. An appropriate directional arrow display, indicating the size and position of the flashing arrow board, must be used in the second phase of the Advance Warning Vehicle. When this is done, the arrow board will not be required on the Advance Warning Vehicle.
 11. Standard diamond shaped warning signs may be used on an option if their placement at a sign station are not available.
 12. The principles on this sheet may be used to close lanes from the left side of the roadway, considering the number of lanes, shoulder width, sight distance, and ramp frequency.
 13. Signs and flashing arrow boards shall be appropriately oriented when implementing left lane closures or interior closures which close the left lanes.
 14. The Advance Warning Vehicle may advance the edge line when shoulder width makes it necessary.




TRAFFIC CONTROL PLAN
MOBILE OPERATIONS
DIVIDED HIGHWAYS

TCP (13-2) - 13

State Department of Transportation

Date: _____
 Drawn by: _____
 Checked by: _____
 Approved by: _____

Sheet No. _____ of _____



LEGEND

* Trail Vehicle	ARROW BOARD DISPLAY
** Shadow Vehicle	RIGHT Directional
*** Work Vehicle	LEFT Directional
Truck Mounted Attenuator (TMA)	Double Arrow
Traffic Flow	Channelizing Devices

Position	Minimum Distance from Front of Work Area	Minimum Spacing of Channeled Traffic	Minimum Spacing of Channelizing Devices	Minimum Spacing of Traffic Signs	Minimum Spacing of Traffic Signs
30	150'	185'	180'	30'	120'
35	205'	235'	245'	35'	160'
40	265'	295'	320'	40'	200'
45	450'	495'	540'	45'	320'
50	500'	550'	600'	50'	400'
55	550'	605'	660'	55'	500'
60	600'	660'	720'	60'	600'
65	650'	715'	780'	65'	700'
70	700'	770'	840'	70'	800'
75	750'	825'	900'	75'	900'

* Conventional Roads Only
** Layer lengths have been rounded off.
L=Length of Layer (FT) Width of Offset(FT); Subtotal Speed(MPH)

MOBILE	SHORT	STATIONARY	LONG TERM
✓	✓	✓	✓

GENERAL NOTES

- This traffic control plan is for use on conventional roads, posted at 45 mph or less and is intended for mobile operations. The continuous or intermittent stopping up to approximately 15 minutes such as short-line striping and in-lane rumble striping. Traffic control plan should be used for short-term stationary traffic control.
- Truck Mounted Attenuator shall be used on Shadow Vehicles. Striping on the back panel of all truck mounted attenuators shall be red and white reflective sheeting placed in an inverted "V" design. The reflective sheeting shall meet or exceed the reflectivity and color requirements of departmental, superior specification DS-3500, Type A.
- All traffic control devices shall be in accordance with the "Texas Manual on Uniform Traffic Control Devices" (MUTCD), latest edition.
- The use of yellow rotating beacons or strobe lights on vehicles are required. Blue high intensity rotating, flashing, oscillating or strobe lights when mounted on the driver's side of the vehicle may be operated simultaneously with the other beacons or strobe lights.
- Flashing arrow board shall be used on Shadow Vehicles. Flashing arrow board shall be Type B or Type C or Type BC. Standard. The arrow board operation shall be controlled from inside the truck.

HEIGHT OF TMA
2'4"


WIDTH OF TMA
48"

STRIPING FOR TMA

TRAFFIC OPERATIONS FOR ISOLATED WORK AREAS UNDIVIDED HIGHWAYS
TCP (3-4) - 13

Texas Department of Transportation
Traffic Operations Standard

DATE: 10-1-00
BY: JAC
DATE: 07/20/01
BY: JAC



DATE FILED
The use of this product is governed by the Texas Engineering Practice Act, to the extent of any conflict with the provisions of this Act. The user of this product shall be responsible for the accuracy of the information and for the proper use of the product. The user of this product shall be responsible for the accuracy of the information and for the proper use of the product.

LEGEND

Channelizing devices	Channelizing devices
FLUKE mounted retro-reflective (FRM) message sign (FRMS)	FLUKE mounted retro-reflective (FRM) message sign (FRMS)
Flashing arrow board	Flashing arrow board
Sign	Traffic flow
Flare	Flare

Sign Size	Year	Lettering	Color	Material	Notes
45"	4500'	455"	540"	45"	195"
50"	5000'	505"	600"	50"	240"
55"	5500'	555"	660"	55"	295"
60"	6000'	605"	720"	60"	350"
65"	6500'	655"	780"	65"	405"
70"	7000'	705"	840"	70"	460"
75"	7500'	755"	900"	75"	515"
80"	8000'	805"	960"	80"	570"

TYPICAL USAGE

MOBILE	STATIONARY	INTERMEDIATE	LONG TERM STATIONARY
✓	✓	✓	✓

GENERAL NOTES

- All signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- All construction signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- The sign shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Static message boards or portable message signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- In cases of the above notes, the sign shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Other specific markings, signs, and equipment shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.
- Signs shall be placed in accordance with the Texas Manual on Uniform Traffic Control Devices (TMUTCD) and the Texas Department of Transportation (TxDOT) Standard Specifications for Road and Bridge Construction.

Texas Department of Transportation
Traffic Control Plan
FREEWAY LANE CLOSURES

TCP (6-1) - 12

DATE FILED

PROJECT NO. 6314-60-001

DATE 12/15/2001


SCALE 1" = 40'


DATE 12/15/2001

SCALE 1" = 40'

DATE 12/15/2001


SCALE 1" = 40'





Texas Department of Transportation
Traffic Operations Division
TRAFFIC CONTROL PLAN
FREEWAY CLOSURE
TCP (6-6)-12

DATE	PROJECT	NO.	NO.	NO.	NO.	NO.	NO.	NO.	NO.
12/15/00	6314-60-001	12	12	12	12	12	12	12	12
12/15/00	6314-60-001	12	12	12	12	12	12	12	12
12/15/00	6314-60-001	12	12	12	12	12	12	12	12



LEGEND

⊕	Characterizing Devices	⊕	Control Position (CP)
⊙	Portable Changeable Message Sign (PCMS)	⊙	Barrier Vehicle with Truck Mounted Attenuator
⊖	Low Intensity LED	⊖	Traffic Flow
⊗	Officer's Vehicle (OV)		

TYPICAL USAGE

MOBILE	SHORT STATION	INTERMEDIATE STATION	LONG TERM STATIONARY
✓	✓	✓	✓

GENERAL NOTES:

- All traffic control devices shall conform with the latest edition of the Manual on Uniform Traffic Control Devices and be located in the work area.
- When the roadway is clear for traffic, the LEOS should proceed forward from the left shoulder followed by the barrier vehicles, from left to right, as shown alphabetically in the plan view.
- The LEOS or LEOS on the right shoulder may remain on the shoulder until satisfied that traffic is moving satisfactorily before merging or proceeding.
- LEOS and barrier vehicles should re-group at their respective starting positions if necessary.

GENERAL NOTES:

- The roadway closure should be during off-peak hours, as shown in the plan, or as directed by the Engineer.
- Work should be limited to approximately 15 minutes maximum operation unless the work is not complete within 15 minutes or 15 minutes of the traffic queue.
- When the roadway is clear for traffic, the LEOS should proceed forward from the left shoulder followed by the barrier vehicles, from left to right, as shown alphabetically in the plan view.
- The LEOS or LEOS on the right shoulder may remain on the shoulder until satisfied that traffic is moving satisfactorily before merging or proceeding.
- LEOS and barrier vehicles should re-group at their respective starting positions if necessary.

GENERAL NOTES:

- The roadway closure should be during off-peak hours, as shown in the plan, or as directed by the Engineer.
- Work should be limited to approximately 15 minutes maximum operation unless the work is not complete within 15 minutes or 15 minutes of the traffic queue.
- When the roadway is clear for traffic, the LEOS should proceed forward from the left shoulder followed by the barrier vehicles, from left to right, as shown alphabetically in the plan view.
- The LEOS or LEOS on the right shoulder may remain on the shoulder until satisfied that traffic is moving satisfactorily before merging or proceeding.
- LEOS and barrier vehicles should re-group at their respective starting positions if necessary.

GENERAL NOTES:



- The roadway closure should be during off-peak hours, as shown in the plan, or as directed by the Engineer.
- Work should be limited to approximately 15 minutes maximum operation unless the work is not complete within 15 minutes or 15 minutes of the traffic queue.
- When the roadway is clear for traffic, the LEOS should proceed forward from the left shoulder followed by the barrier vehicles, from left to right, as shown alphabetically in the plan view.
- The LEOS or LEOS on the right shoulder may remain on the shoulder until satisfied that traffic is moving satisfactorily before merging or proceeding.
- LEOS and barrier vehicles should re-group at their respective starting positions if necessary.

Texas Department of Transportation
Traffic Control Plan

TRAFFIC CONTROL PLAN
SHORT DURATION FREEWAY
CLOSURE SEQUENCE

TCP (6-7) - 12

DATE: 10/15/93
BY: [Signature]
CHECKED BY: [Signature]
SCALE: AS SHOWN
SHEET NO. 101 OF 101



"DO NOT PASS" SIGN (R4-1) and NO-PASSING ZONES

A. Prior to the beginning of construction, all currently striped no-passing zones shall be aligned with the DO NOT PASS (R4-1) signs and PASS WITH CARE (R4-2) signs placed at the beginning and end of each zone. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer.

B. In the discretion of the Engineer, in areas of numerous no-passing zones, several zones may be combined as a single zone. If necessary, the DO NOT PASS (R4-1) signs and the NEXT XX MILES (R4-4) signs may be used at the beginning of each zone. The DO NOT PASS sign and the NEXT XX MILES sign should be repeated every mile to the end of the no-passing zone. In areas where there is considerable distance between no-passing zones, the end of the no-passing zone may be aligned with a PASS WITH CARE sign and a NEXT XX MILES sign.

C. Depending on traffic volumes and length of sections, it may be desirable to prohibit passing throughout the project to prevent congestion to vehicles and trucks. The DO NOT PASS sign and NEXT XX MILES signs should be used and repeated as often as necessary for this purpose. Where several no-passing zones are combined, the length of the no-passing zone should be indicated on the sign. The DO NOT PASS sign should be placed at the beginning of the no-passing zone. The length of each combined zone, regardless of whether the no-passing zone is placed at the beginning and end of the no-passing zone where the surfacing operation has stopped for the day.

D. R4-1 and R4-2 signs shall remain in place until standard pavement markings are installed.

"NO CENTER LINE" SIGN (R4-2)

A. Center line markings are yellow pavement markings that delineate the separation of travel lanes that have opposite directions of travel on a roadway. Divided highways do not typically have center line markings.

B. At the time construction activity crosses the existing center line markings (low volume roads may not have an existing centerline), a NO CENTER LINE (R4-2) sign should be placed at the beginning of the work area, or approximately 2 miles in rural areas and closer in urban areas, and other locations deemed necessary by the Engineer.

C. The NO CENTER LINE signs are to remain in place until standard pavement markings are installed.

"LOOSE GRAVEL" SIGN (R4-3)

A. When construction begins, a LOOSE GRAVEL (R4-3) sign should be placed at each end of the work area and repeated at intervals of approximately 2 miles in rural areas and closer in urban areas.

B. The LOOSE GRAVEL signs are to remain in place until the condition no longer exists.

PAVEMENT MARKINGS

A. Temporary markings for surfacing projects shall be Temporary Flexible-Reflective Resin. Temporary markings shall be approved by the Engineer. Temporary markings shall be installed to provide true alignment for air-laying crews or as directed by the Engineer. Tabs will be placed at the beginning and end of the work area. The length of the marking shall be as specified. After the surfacing is rolled and swept, the cover over the reflective strip shall be removed.

B. Tabs shall not be used to simulate edge lines.

C. Tab placement for overlay/mix operations shall be as shown on the existing standard sheet.

COORDINATION OF SIGN LOCATIONS

A. The location of warning signs at the beginning and end of a work area are to be coordinated with other advance signs shown on the Barrier and Construction Standards for project limits to ensure adequate sign spacing.

B. Where possible the road work shall include: LOOSE GRAVEL (R4-3), NO CENTER LINE (R4-2) signs and the NEXT XX MILES (R4-4) signs. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer. The location of the signs shall be determined by the Engineer.

Posted Speed Limit, mph	Minimum Sign Spacing, ft	Distance
30	120'	
35	140'	
40	160'	
45	180'	
50	200'	
55	220'	
60	240'	
65	260'	
70	280'	
75	300'	

* Conventional Roads Only

TYPICAL USAGE

VEHICLE	SHORT TERM STATIONARY	INTERMEDIATE STATIONARY	LONG TERM STATIONARY
VEHICLE			

GENERAL NOTES

- The traffic control devices detailed on this sheet will be furnished and erected as directed by the Engineer on sections of roadway where signs must be placed prior to the surfacing operation which will cover or obliterate the existing pavement markings.
- Signs shown on this sheet are to be used to supplement those required by the IC Standards or other required standards in the plans.
- Signs shall be erected as detailed on the IC Standards or the Companion Work Zone Traffic Control Devices List (CWTCDL) on supports approved for Long-Term / Intermediate-Term Work Zone Sign Supports.
- When surfacing operations take place on divided highways, freeways and expressways signs will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.
- Signs on divided highways, freeways and expressways will be placed on both right and left sides of the roadway based on roadway conditions as directed by the Engineer.

Texas Department of Transportation

TRAFFIC CONTROL DETAILS FOR SURFACING OPERATIONS

TCP (7-1)-13

DATE	10/27/09	BY	W. J. B. / J. B. / J. B.
DATE	10/27/09	BY	W. J. B. / J. B. / J. B.
DATE	10/27/09	BY	W. J. B. / J. B. / J. B.
DATE	10/27/09	BY	W. J. B. / J. B. / J. B.

449 2-13
149 2-13

EXHIBIT “B”

CRP

PRICING

Contract Description: MBGFR

Provider: TIEH

Item Number	Description	UOM	Current Price	Proposed Price	Counter offer
0450-5042	RAIL (TY PR 1)	LF	\$150.00	\$150.00	approved
0450-5099	REMOVE RAIL (METAL ELEMENTS)	LF	\$3.00	\$3.00	approved
0540-5001	MTL W-BEAM GD FEN (TM POST)	LF	\$21.00	\$21.00	approved
0540-5005	TERMINAL ANCHOR SECTION	EA	\$350.00	\$350.00	approved
0540-5010	MTL W-BEAM GD FEN ADJUSTMENT	LF	\$10.00	\$10.00	approved
0540-5006	MTL BEAM GD FEN TRANS (THRE-BEAM)	EA	\$1,250.00	\$1,300.00	\$1,500.00
0540-5016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA	\$1,000.00	\$1,200.00	approved
0540-5017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF	\$0.00	\$35.00	\$30.00
0542-5001	REMOVING METAL BEAM GUARD FENCE	LF	\$3.00	\$3.00	approved
0542-5002	REMOVING TERMINAL ANCHOR SECTION	EA	\$100.00	\$100.00	approved
0542-5004	RM MTL BM GD FEN TRANS (THRE BEAM)	EA	\$75.00	\$100.00	approved
0542-5005	RM MTL BM GD FEN TRANS (T101)	EA	\$450.00	\$450.00	approved
0544-5001	GUARD RAIL END TREATMENT (INSTALL)	EA	\$2,300.00	\$2,300.00	approved
0544-5003	GUARD RAIL END TREATMENT (REMOVE)	EA	\$300.00	\$300.00	approved
0545-5003	CRASH CUSHION ATTN (MOVE & RESET)	EA	\$1,500.00	\$2,000.00	approved
0545-5005	CRASH CUSHION ATTN (REMOVE)	EA	\$1,000.00	\$1,000.00	approved
0545-5024	CRASH CUSHION ATTN (INSTALL) (TRACC)	EA	\$16,000.00	\$20,000.00	\$15,000.00
0545-5025	CRASH CUSHION ATTN (INSTALL) (REACT(N))	EA	\$23,000.00	\$23,000.00	approved
0545-5026	CRASH CUSHION ATTN (INSTALL) (QUAD)(N)	EA	\$17,500.00	\$20,000.00	approved
0545-5027	CRASH CUSHION ATTN (INSTALL) (QUAD)(W)	EA	\$26,000.00	\$26,500.00	approved
0550-5001	CHAIN LINK FENCE (INSTALLATION)(6)	LF	\$9.50	\$10.00	approved
0550-5002	CHAIN LINK FENCE (REPAIR)(6)	LF	\$5.00	\$10.00	approved
0550-5007	CHAIN LINK FENCE (REPAIR)(4)	LF	\$9.50	\$10.00	approved
0770-5001	REPAIR RAIL ELEMENT (W - BEAM)	LF	\$11.00	\$12.00	approved
0770-5054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	LF	\$5.00	\$5.00	approved
0770-5010	REWREPL TIMBER/STL POST W/O CONC FND	EA	\$40.00	\$40.00	approved
0770-5011	REWREPL TIMBER/STL POST W/ CONC FND	EA	\$80.00	\$80.00	\$50.00
0770-5017	REALIGN POSTS	EA	\$15.00	\$15.00	approved
0770-5018	REMOVE AND REPLACE BLOCK CUT	EA		\$20.00	approved
0770-5027	REMOVE GORAIL END TRT/REPL WITH SGT	EA	\$2,350.00	\$2,500.00	approved
0770-5021	REPLACE SINGLE GORAIL TERMINAL RAIL	LF	\$15.00	\$15.00	approved
0770-5029	REPL SINGLE GORAIL TERM IMPACT HEAD	EA	\$900.00	\$900.00	approved
0770-5022	REPLACE SINGLE GORAIL TERMINAL POST	EA	\$42.00	\$45.00	approved
0770-5030	REPLACE SGT-CABLE ASSEMBLY	EA		\$200.00	\$75.00
0770-5031	REPLACE CABLE ANCHOR	EA		\$100.00	\$85.00
0770-5032	REPLACE SGT STRUT	EA		\$50.00	approved
0770-5033	REPLACE SGT OBJECT MARKER	EA		\$45.00	\$25.00
0770-5052	REPAIR STEEL POST WITH BASE PLATE	EA	\$200.00	\$300.00	approved
0770-5046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA	\$250.00	\$250.00	approved
0772-5001	POST AND CABLE FENCE (REMOVAL)	LF	\$3.00	\$3.00	approved
0772-5003	POST AND CABLE FENCE (NEW INSTALLATION)	LF	\$5.50	\$10.00	approved
0772-5004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA	\$50.00	\$175.00	\$100.00
0772-5005	POST AND CABLE FENCE (REMV/REPL POSTS)	EA	\$50.00	\$50.00	approved
0772-5006	POST AND CABLE FENCE (REMV/REPL CONC ANCHR)	EA	\$100.00	\$200.00	\$125.00
0774-5005	REPAIR (TRACC)	EA	\$2,600.00	\$2,600.00	approved
0774-5008	REPAIR (WIDE TRACC)	EA	\$2,600.00	\$2,600.00	approved
0774-5018	REPAIR (CATGR-FRONT SECTION)	EA	\$2,500.00	\$7,000.00	\$3,500.00
0774-5019	REPAIR (CATGR-END SECTION)	EA	\$1,500.00	\$2,500.00	approved
0774-5023	REPAIR REACT (N) (MISC HARDWARE)	EA		\$2,500.00	\$2,500.00
0774-5027	REPAIR REACT (N) (CYLINDERS)	EA		\$3,500.00	\$3,500.00
0774-5028	QUAD (N) (BAY) (REPAIR ONLY)	EA	\$750.00	\$1,600.00	\$1,500.00
0774-5083	QUAD (N) (BAY) CARTRIDGE	EA	\$1,200.00	\$1,300.00	approved
0774-5084	QUAD (N) (BAY) NOSE ASSEMBLY	EA	\$1,000.00	\$1,000.00	approved
0774-5029	QUAD (W) (BAY) (REPAIR ONLY)	EA	\$750.00	\$1,600.00	approved
0774-5086	QUAD (W) (BAY) CARTRIDGE	EA	\$1,200.00	\$1,200.00	approved
0774-5087	QUAD (W) (BAY) NOSE ASSEMBLY	EA	\$1,000.00	\$1,200.00	\$1,100.00
0774-5088	QUAD (W) (BAY) Diaphragm	EA	\$1,000.00	\$1,200.00	\$1,100.00
0543-5017	CABLE BARRIER TERMINAL SECTION (TL-3)	EA	\$2,700.00	\$2,500.00	\$2,800.00
0543-5022	REMOVE CABLE BARRIER TERMINAL SECTION	EA	\$1.00		\$500.00
0771-5001	REPLACE POSTS (TL 3)	EA	\$110.00	\$135.00	approved
0771-5005	REPAIR CONCRETE FOUNDATION (TL 3)	EA	\$225.00	\$2,500.00	\$250.00
0771-5009	REPLACE CABLE (TL 3)	LF	\$7.50	\$5.00	approved
7053-5001	CLEAN TRAFFIC ATTENUATORS (TRACC) (N)	EA	\$500.00	\$500.00	approved
7053-5002	CLEAN TRAFFIC ATTENUATORS (QUAD) (N)	EA	\$500.00	\$500.00	approved
7053-5003	CLEAN TRAFFIC ATTENUATORS (QUAD) (W)	EA	\$500.00	\$500.00	approved
7053-5004	CLEAN TRAFFIC ATTENUATORS (REACT 350)	EA	\$500.00	\$500.00	approved
7053-5005	RIGHT OF WAY MARKERS (LABOR ONLY)	EA	\$25.00	\$30.00	approved
7053-5008	TMA	DAY	\$400.00	\$410.00	approved
New Item	QUAD FENDER PANEL	EA		\$1,000.00	\$750.00
New Item	REACT CABLE 350 (6 BAY)	EA		\$1,500.00	\$1,200.00
New Item	REACT DECAL	EA		\$350.00	approved
New Item	REACT CABLE 350 (9 BAY)	EA		\$1,500.00	\$1,250.00
New Item	CABLE RELEASE POST	EA		\$500.00	approved
New Item	ANCHOR POST	EA		\$800.00	approved
New Item	REACT 350 CABLE HOLDERS	EA		\$350.00	approved
New Item	FAST TRACK CENTER PANELS	EA		\$1,200.00	approved

TIBH APPROVED 2018 GUARD RAIL RATES / HIDALGO COUNTY

	ITEM CODE	DESCRIPTION	UNIT	UNIT \$
1	0450 6042	RAIL (TY PR1)	LF	\$ 150.00
2	0496 6099	REMOVE RAIL (METAL ELEMENTS)	LF	\$ 3.00
3	0540-6001	MTL W-BEAM GD FEN (TIM POST)	LF	\$ 21.00
4	0540-6005	TERMINAL ANCHOR SECTION	EA	\$ 350.00
5	0540-6010	MTL W-BEAM GD FEN ADJUSTMENT	LF	\$ 10.00
7	0540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA	\$ 1,500.00
8	0540-6016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA	\$ 1,200.00
9	0540-6017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF	\$ 30.00
10	0542 6001	REMOVING METAL BEAM GUARD FENCE	LF	\$ 3.00
11	0542 6002	REMOVING TERMINAL ANCHOR SECTION	EA	\$ 100.00
12	0542 6004	RM MTL BM GD FEN TRANS (THRIE BEAM)	EA	\$ 100.00
13	0542 6005	RM MTL BM GD FEN TRANS (T101)	EA	\$ 450.00
14	0544-6001	GUARD RAIL END TREATMENT (INSTALL)	EA	\$ 2,300.00
15	0544-6003	GUARD RAIL END TREATMENT (REMOVE)	EA	\$ 300.00
16	0545 6003	CRASH CUSHION ATTEN (MOVE & RESET)	EA	\$ 2,000.00
17	0545 6005	CRASH CUSHION ATTEN (REMOVE)	EA	\$ 1,000.00
18	0545 6024	CRASH CUSHION ATTEN (INSTALL) (TRACC)	EA	\$ 16,000.00
19	0545 6025	CRASH CUSHION ATTEN (INSTALL) (REACT)(N)	EA	\$ 23,000.00
20	0545 6026	CRASH CUSHION ATTEN (INSTALL) (QUAD)(N)	EA	\$ 20,000.00
21	0545 6027	CRASH CUSHION ATTEN (INSTALL) (QUAD)(W)	EA	\$ 26,500.00
22	0550-6001	CHAIN LINK FENCE (INSTALLATION)(6')	LF	\$ 10.00
23	0550-6002	CHAIN LINK FENCE (REPAIR)(6')	LF	\$ 10.00
24	0550-6007	CHAIN LINK FENCE (REPAIR)(4')	LF	\$ 10.00
25	0770-6001	REPAIR RAIL ELEMENT (W - BEAM)	LF	\$ 12.00
26	0770-6054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	EA	\$ 6.00
27	0770 6010	REM/REPL TIMBER/STL POST W/O CONC FND	EA	\$ 40.00
28	0770 6011	REM/REPL TIMBER/STL POST W/ CONC FND	EA	\$ 60.00
29	0770 6017	REALIGN POSTS	EA	\$ 15.00
30	0770-6019	REMOVE AND REPLACE BLOCK OUT	EA	\$ 20.00
31	0770 6027	REMOVE GDRAIL END TRT/REPL WITH SGT	EA	\$ 2,500.00
32	0770 6021	REPLACE SINGLE GDRAIL TERMINAL RAIL	LF	\$ 15.00
33	0770 6028	REPLACE SINGLE GDRAIL TERM IMPACT HEAD	EA	\$ 900.00
34	0770 6022	REPLACE SINGLE GDRAIL TERMINAL POST	EA	\$ 45.00
35	0770-6030	REPLACE SGT CABLE ASSEMBLY	EA	\$ 75.00
36	0770 6031	REPLACE CABLE ANCHOR	EA	\$ 85.00
37	0770-6032	REPLACE SGT STRUT	EA	\$ 60.00
38	0770-6033	REPLACE SGT OBJECT MARKER	EA	\$ 25.00
39	0770-6052	REPAIR STEEL POST WITH BASE PLATE	EA	\$ 200.00
40	0770-6046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA	\$ 250.00
41	0772-6001	POST AND CABLE FENCE (REMOVAL)	LF	\$ 3.00
42	0772-6003	POST AND CABLE FENCE (NEW INSTALLATION)	LF	\$ 10.00
43	0772-6004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA	\$ 100.00
44	0772-6005	POST AND CABLE FENCE (REMV/REPL POSTS)	EA	\$ 50.00
45	0772-6006	POST AND CABLE FENCE (REMOVE CONC ANCHOR)	EA	\$ 125.00
46	0774 6006	REPAIR (TRACC)	EA	\$ 2,600.00
47	0774 6008	REPAIR (WIDE TRACC)		

TIBH APPROVED 2018 GUARD RAIL RATES / HIDALGO COUNTY

ITEM CODE	DESCRIPTION	UNIT	UNIT \$
1	0450 6042	RAIL (TY PR1)	LF \$ 150.00
2	0496 6099	REMOVE RAIL (METAL ELEMENTS)	LF \$ 3.00
3	0540-6001	MTL W-BEAM GD FEN (TIM POST)	LF \$ 21.00
4	0540-6005	TERMINAL ANCHOR SECTION	EA \$ 350.00
5	0540-6010	MTL W-BEAM GD FEN ADJUSTMENT	LF \$ 10.00
7	0540-6006	MTL BEAM GD FEN TRANS (THRIE-BEAM)	EA \$ 1,500.00
8	0540-6016	DOWNSTREAM ANCHOR TERMINAL (DAT) SECTION	EA \$ 1,200.00
9	0540-6017	METAL BEAM GUARD FENCE (LONG SPAN SYSTEM)	LF \$ 30.00
10	0542 6001	REMOVING METAL BEAM GUARD FENCE	LF \$ 3.00
11	0542 6002	REMOVING TERMINAL ANCHOR SECTION	EA \$ 100.00
12	0542 6004	RM MTL BM GD FEN TRANS (THRIE BEAM)	EA \$ 100.00
13	0542 6005	RM MTL BM GD FEN TRANS (T101)	EA \$ 450.00
14	0544-6001	GUARD RAIL END TREATMENT (INSTALL)	EA \$ 2,300.00
15	0544-6003	GUARD RAIL END TREATMENT (REMOVE)	EA \$ 300.00
16	0545 6003	CRASH CUSHION ATTEN (MOVE & RESET)	EA \$ 2,000.00
17	0545 6005	CRASH CUSHION ATTEN (REMOVE)	EA \$ 1,000.00
18	0545 6024	CRASH CUSHION ATTEN (INSTALL) (TRACC)	EA \$ 16,000.00
19	0545 6025	CRASH CUSHION ATTEN (INSTALL) (REACT)(N)	EA \$ 23,000.00
20	0545 6026	CRASH CUSHION ATTEN (INSTALL) (QUAD)(N)	EA \$ 20,000.00
21	0545 6027	CRASH CUSHION ATTEN (INSTALL) (QUAD)(W)	EA \$ 26,500.00
22	0550-6001	CHAIN LINK FENCE (INSTALLATION)(6')	LF \$ 10.00
23	0550-6002	CHAIN LINK FENCE (REPAIR)(6')	LF \$ 10.00
24	0550-6007	CHAIN LINK FENCE (REPAIR)(4')	LF \$ 10.00
25	0770-6001	REPAIR RAIL ELEMENT (W - BEAM)	LF \$ 12.00
26	0770-6054	REPAIR RAIL ELEMENT (W - BEAM) (LABOR)	EA \$ 6.00
27	0770 6010	REM/REPL TIMBER/STL POST W/O CONC FND	EA \$ 40.00
28	0770 6011	REM/REPL TIMBER/STL POST W/ CONC FND	EA \$ 60.00
29	0770 6017	REALIGN POSTS	EA \$ 15.00
30	0770-6019	REMOVE AND REPLACE BLOCK OUT	EA \$ 20.00
31	0770 6027	REMOVE GDRAIL END TRT/REPL WITH SGT	EA \$ 2,500.00
32	0770 6021	REPLACE SINGLE GDRAIL TERMINAL RAIL	LF \$ 15.00
33	0770 6028	REPLACE SINGLE GDRAIL TERM IMPACT HEAD	EA \$ 900.00
34	0770 6022	REPLACE SINGLE GDRAIL TERMINAL POST	EA \$ 45.00
35	0770-6030	REPLACE SGT CABLE ASSEMBLY	EA \$ 75.00
36	0770 6031	REPLACE CABLE ANCHOR	EA \$ 85.00
37	0770-6032	REPLACE SGT STRUT	EA \$ 60.00
38	0770-6033	REPLACE SGT OBJECT MARKER	EA \$ 25.00
39	0770-6052	REPAIR STEEL POST WITH BASE PLATE	EA \$ 200.00
40	0770-6046	REMOVE AND RESET SGT IMPACT HEAD (FURNISHED)	EA \$ 250.00
41	0772-6001	POST AND CABLE FENCE (REMOVAL)	LF \$ 3.00
42	0772-6003	POST AND CABLE FENCE (NEW INSTALLATION)	LF \$ 10.00
43	0772-6004	POST AND CABLE FENCE (NEW CONC ANCHOR)	EA \$ 100.00
44	0772-6005	POST AND CABLE FENCE (REMV/REPL POSTS)	EA \$ 50.00
45	0772-6006	POST AND CABLE FENCE (REMOVE CONC ANCHOR)	EA \$ 125.00
46	0774 6006	REPAIR (TRACC)	EA \$ 2,600.00
47	0774 6008	REPAIR (WIDE TRACC)	EA \$ 2,600.00
48	0774 6018	REPAIR (CATGR-FRONT SECTION)	EA \$ 3,500.00
49	0774 6019	REPAIR (CATGR-END SECTION)	EA \$ 2,500.00
50	0774 6023	REPAIR REACT (N) (MISC HARDWARE)	EA \$ 2,500.00
54	0774 6027	REPAIR REACT (N) (CYLINDERS)	EA \$ 3,500.00
55	0774 6028	QUAD (N) (BAY) (REPAIR ONLY)	EA \$ 1,600.00
56	0774 6083	QUAD (N) (BAY) CARTRIDGE	EA \$ 1,300.00
57	0774 6084	QUAD (N) (BAY) NOSE ASSEMBLY	EA \$ 1,000.00
58	0774 6029	QUAD (W) (BAY) (REPAIR ONLY)	EA \$ 1,600.00
59	0774 6086	QUAD (W) (BAY) CARTRIDGE	EA \$ 1,200.00
60	0774 6087	QUAD (W) (BAY) NOSE ASSEMBLY	EA \$ 1,200.00
61	0774 6088	QUAD (W) (BAY) DIAPHRAGM	EA \$ 1,200.00
62	0543-6017	CABLE BARRIER TERMINAL SECTION (TL-3)	EA \$ 2,800.00
63	0543-6022	REMOVE CABLE BARRIER TERMINAL SECTION	EA \$ 500.00
64	0771-6001	REPLACE POSTS (TL 3)	EA \$ 136.00
65	0771-6005	REPAIR CONCRETE FOUNDATION (TL 3)	EA \$ 250.00
66	0771-6009	REPLACE CABLE (TL 3)	LF \$ 5.00
67	7053-6001	CLEAN TRAFFIC ATTENUATORS (TRACC) (N)	EA \$ 500.00
68	7053-6002	CLEAN TRAFFIC ATTENUATORS (QUAD) (N)	EA \$ 500.00
69	7053-6003	CLEAN TRAFFIC ATTENUATORS (QUAD) (W)	EA \$ 500.00
70	7053-6004	CLEAN TRAFFIC ATTENUATORS (REACT 350)	EA \$ 500.00
71	7053-6005	RIGHT AWAY MARKERS (LABOR ONLY)	EA \$ 30.00
72	7053-6008	TMA	EA \$ 410.00
73	NEW ITEM	QUAD FENDER PANER	EA \$ 750.00
74	NEW ITEM	REACT CABLE 350 (6 BAY)	EA \$ 1,200.00
75	NEW ITEM	REACT DECAL	EA \$ 350.00
76	NEW ITEM	REACT CABLE 350 (9 BAY)	EA \$ 1,250.00
77	NEW ITEM	CABLE RELEASE POST	EA \$ 600.00
78	NEW ITEM	ANCHOR POST	EA \$ 800.00
79	NEW ITEM	REACT 350 CABLE HOLDERS	EA \$ 350.00
80	NEW ITEM	FAST TRACK CENTER PANELS	EA \$ 1,200.00

EXHIBIT “C”

CERTIFICATE OF INSURANCE



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
4/20/2018

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER (956)787-4989 Crystal Jeannie Salinas James E. Capt & Associates LLC P. O. BOX 126 San Juan, TX 78589-0126	CONTACT NAME: LUCY OR JEANNIE PHONE (A/C No, Ext): (800)887-4989 Ext.	FAX (A/C No): (956)781-3380
	E-MAIL ADDRESS: lucy@captinsurance.com	
INSURER(S) AFFORDING COVERAGE		NAIC #
INSURED RGR INDUSTRIES, INC. 6700 N MILE 3 1/2 WEST WESLACO, TX 78596-0000	INSURER A: ADMIRAL INSURANCE COMPANY	
	INSURER B: HALLMARK COUNTY MUTUAL	
	INSURER C: TEXAS MUTUAL INSURANCE	
	INSURER D:	
	INSURER E:	

COVERAGES CERTIFICATE NUMBER: REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDITIONAL SUBR INSR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	GENERAL LIABILITY		CA00002573002	11/07/17	11/07/18	EACH OCCURRENCE \$ 1,000,000
	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY					DAMAGE TO RENTED PREMISES (Ex occurrences) \$ 100,000
	<input type="checkbox"/> CLAIMS-MADE <input checked="" type="checkbox"/> OCCUR					MED EXP (Any one person) \$ 5,000
	GEN'L AGGREGATE LIMIT APPLIES PER:					
	<input type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOG					GENERAL AGGREGATE \$ 2,000,000
B	AUTOMOBILE LIABILITY		A42503271-04	05/15/17	05/15/18	COMBINED SINGLE LIMIT (Ex resident) \$ 1,000,000
	<input type="checkbox"/> ANY AUTO					BODILY INJURY (Per person) \$
	<input type="checkbox"/> ALL OWNED AUTOS	<input checked="" type="checkbox"/> SCHEDULED AUTOS				BODILY INJURY (Per accident) \$
	<input type="checkbox"/> HIRED AUTOS	<input type="checkbox"/> NON-OWNED AUTOS				PROPERTY DAMAGE (Per accident) \$
C	UMBRELLA LIAB		TSF-0001201928	06/10/17	06/10/18	EACH OCCURRENCE \$
	EXCESS LIAB	<input type="checkbox"/> OCCUR				AGGREGATE \$
	<input type="checkbox"/> DEQ <input type="checkbox"/> RETENTION \$	<input type="checkbox"/> CLAIMS-MADE				\$
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY	<input type="checkbox"/> Y/N				
	ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory In NH)	<input checked="" type="checkbox"/> N/A				E.L. EACH ACCIDENT \$ 1,000,000
	If yes, describe under DESCRIPTION OF OPERATIONS below					E.L. DISEASE - EA EMPLOYEE \$ 1,000,000
						E.L. DISEASE - POLICY LIMIT \$ 1,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (Attach ACORD 101, Additional Remarks Schedule, if more space is required)

CERTIFICATE HOLDER

COUNTY OF HIDALGO
2812 S BUSINESS HWY281
EDINBURG TX 78539

CANCELLATION

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

© 1988-2010 ACORD CORPORATION. All rights reserved.

