



2812 S. Bus. Hwy 2811
Edinburg, Texas 78539
Phone: (956) 318-2626
Fax: (956) 318-2629
www.co.hidalgo.tx.us/purchasing

TRANSMITTAL FORM

Today's Date: 08/05/2020 Department: 110 - County Judge
Contract No.: C-13-336-12-10 Effective Date: 12/10/2013
Description of Project: SA#2 to WA#1
Awarded Vendor: L & G
CC Approval on 08/04/2020 AI- 76693

Routing of documents:

- _____ 1. Executive Office – Attn: Monica Salinas
- _____ 2. District Attorney's Office – Attn: Select ADA
- _____ 3. County Judge's Office – Attn: Richard F. Cortez
- _____ 4. County Clerk's Office – Attn: Arturo Guajardo, Jr.
- _____ 5. Purchasing Department – Attn: Heidi Ortiz ext. 4877

ATTENTION COUNTY CLERK'S OFFICE:

Please do not attach the following to the minutes of this agenda due to the confidential nature of the information contained herein:

- ☐ Contract/Agreement
- ☐ Exhibit A – RFB Procurement Packet
- ☐ Exhibit B – Fee Schedule/Bid Page (Pgs. _____ to _____)
- ☐ Exhibit C – Certificate of Liability Insurance
- ☐ Other: _____

OK B.

Pct. 1

- ✓ 1. AI-76578 Acceptance and approval of a consulting and other related services contract (#070602) between awarded vendor, Absolute Business Consulting Group and Hidalgo County Precinct No. 1 through Hidalgo County's membership/participation in Region 8 Education Service Center Cooperative Purchasing Program TIPS with authority to execute agreement.
- p 4/2

OK C.

Pct. 2

1. ✓ AI-76698 Approval to exercise the sixty (60) day grace period extension as provided in the following contract E-19-116-08-06 with Southern Star Transport for Hidalgo County Precinct No. 2 - "Hauling Services of All Road Materials" under the same rates, terms and conditions so as to have no lapse in service while procurement process is completed and awarded.
- p 1/4
2. ✓ AI-76687 A. ✓ Authorization and approval to purchase through the State of Texas Federal Surplus Program under Chapter 2175.001 of the Texas Local Government Code and Sec 262.024 (9)(C): Two (2) LMTV Cargo Trucks in the amount of \$15,000.00 through Requisition No. 418825;
- p 1/4
- B. ✓ Authorization for the Purchasing Department to issue a purchase order and the County Treasurer to issue a check payable to Texas Facilities Commissioner after review, audit, and processing procedures have been completed by the County Auditor.
- p 2/4

OK D.


Pct. 4

1. ✓ AI-76605 Requesting approval of First Amendment to Professional Service Contract for construction management services between Hidalgo County Precinct No. 4 and SDI Engineering, LLC, contract C-19-207-09-03, to extend the termination date to December 31, 2020.
2. ✓ AI-76693 Requesting approval of Supplemental Agreement No. 2 to Work Authorization No.1 for the FM1925 project East to Sharp Road to update Exhibit D-1 - Estimated Man-Hour Breakdown of previously approved WA to reallocate funds to address upcoming necessary public involvement required to complete the environmental process with no net change in the amount as it remains the same and subject to compliance with HB1295.
3. ✓ AI-76606 Requesting approval of First Amendment to Professional Service Contract for construction management services between Hidalgo County Precinct No. 4 and Broaddus & Associates, contract C-19-208-08-27, to extend the termination date to December 31, 2020.
- p 4/1
4. ✓ AI-76663 Requesting approval of Second Amendment to Service Contract for Professional Engineering Services for Construction Material & Geotechnical Testing Services between Hidalgo County Precinct No. 4 and MEG Engineers, contract C-19-210-09-03, to extend the termination date to December 31, 2020.
- p 1/4

OK E.

Constable Pct. #2:

EXHIBIT "F"
Supplemental Agreement Form



THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

**SUPPLEMENTAL AGREEMENT NO. 2
TO WORK AUTHORIZATION NO. 1
TO AGREEMENT FOR PROFESSIONAL SERVICES
C-13-336-12-10**

This **SUPPLEMENTAL AGREEMENT** is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between **HIDALGO COUNTY**, hereinafter called the "**Owner**", and **L&G ENGINEERING**, professional engineers of Mercedes, Texas, hereinafter called the "**Engineer**".

WITNESSETH

WHEREAS, the **Owner** and the **Engineer** executed the Main Contract Agreement on the 10 the day of December, 2013 concerning professional engineering services for the "**FM 1925 (from FM 907 (Alamo Road) East to East of SH 68 (Uresti Street)**", (for preparation of the Environmental Assessment, Public Involvement, Schematic and Hydrologic Design) hereinafter referred to as the "**Project**"; and,

WHEREAS, it has become necessary to amend "*Exhibit B, Scope of Services to be provided by the Engineer*" of Work Authorization No. 1 for the following reasons:

- 1) Reallocate Funds:
 - FC 12070 – Archeological and Historical Research (\$14,846.00)
- 2) Add Funds:
 - FC 12001 – Additional work associated with Affording an Opportunity for Public Hearing \$14,846.00

WHEREAS, it has become necessary to amend "*Exhibit D-1 – Estimated Man-Hour Breakdown*" of Work Authorization No. 1 to separate the costs associated with Engineering Services for Public Hearing and,

WHEREAS, the Estimated Cost from the original Work Authorization No. 1 will not increase or decrease; therefore the amount of Supplemental No. 2 remains \$549,575.00

Hidalgo County / L&G Engineering
Hidalgo County (C-13-336-12-10)
Supplemental Agreement No. 2 to Work Authorization No. 1
Page 1 of 2

A. AGREEMENT

NOW THEREFORE, premises considered, the **Owner** and the **Engineer** agree that said **Agreement** is amended as follows:

1. Sections of the Agreement, EXHIBIT "B" – SERVICES TO BE PROVIDED BY THE ENGINEER and EXHIBIT "D-1" – PROJECT ESTIMATED FEE SCHEDULE, are revised to reflect the above listed modifications of this Supplement

All other provisions are unchanged and remain in full force and effect.

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the 4th day of August, 2020.

**THE ENGINEER:
ENGINEER**

BY: [Signature]
Jacinto Garza, P.E., President

**THE OWNER:
HIDALGO COUNTY**

BY: [Signature]
Richard Cortez, County Judge

APPROVED BY
COMMISSIONERS' COURT
ON: 8-4-20 MM

LIST OF EXHIBITS:

LOCATION MAP

EXHIBIT A – "Services to be provided by County"

EXHIBIT B – "Services to be provided by Engineer"

EXHIBIT C – "Work Schedule"

EXHIBIT D-1 – "Estimated Project Fee Schedule (w/man-hour breakdown)"

BY: [Signature]
Arturo Guajardo, Jr., County Clerk

REVISED EXHIBIT D-1
ESTIMATED MAN-HOUR BREAKDOWN

FM 1925 (SEGMENT II) PROJECT
 from FM 907 (Alamo Rd) to Sharp Rd including Sharp Rd Realignment (from FM 1925 N 0.5 mi.)

	MANHOURS														TOTAL HOURS	Sub-Contract Amounts / ROW COST	TOTAL LINE ITEM COST	ROUNDED TOTAL LINE ITEM COST
	Senior Project Manager	Senior Engineer	Senior Environmental Scientist /Specialist	Project Engineer	Design Engineer	ROW Administrator	EIT	Senior Engineer Tech	Environmental Scientist /Specialist	Engineer Tech	CADD Operator / GIS Analyst	Admin / Clerical	Biologist					
CONTRACT RATE	215.40	167.89	135.21	123.54	114.04	107.70	82.36	79.19	79.19	76.02	66.52	57.02	50.68					
WORK AUTHORIZATION NO. 1																		
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN																		
1 Environmental Assessment with TxDOT	60		250						200		245	100	201	1058		\$ 95,000.58	\$ 95,000.00	
2 Public Involvement for Environmental Assessment and 1 Public Meeting	30		35	39		10			28.25		41.25	17	36	238.5		\$ 25,000.66	\$ 25,000.00	
3 Archeological and Historical Research			2						0.5					2.5	\$ 29,692.00	\$ 312.02	\$ 312.00	
4 Engineering Technical Support at Public Meetings with Layouts, etc.	25		44	31		30				44.75	24	24	222.75			\$ 24,000.55	\$ 24,000.00	
5 Schematic for FM 1925	28	30		70	120		79	75.25		100	1496	15	13	2027.25		\$ 154,575.24	\$ 154,575.00	
6 Hydrological Map	14	24	8	65	32		37.75		10	81	163.75	8	6	455.5		\$ 42,000.66	\$ 42,000.00	
7 Schematic for intersecting streets (Sharp Rd)	9	8		8	8		8	9		10	479	10	5	554		\$ 40,000.83	\$ 40,000.00	
8 Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	10	10		30	49		30.25			20	49	7	4	209.25		\$ 21,000.19	\$ 21,000.00	
9 Preliminary Compensable Utility Management Identification on Schematic	10	18		18	19	9	18.25	20		26	34	5	2	177.25		\$ 18,000.25	\$ 18,000.00	
10 Update Schematic based on comments as provided by TxDOT/FHWA	24	24		36	60		44	17		60	101	29	12	407		\$ 39,000.33	\$ 39,000.00	
11 Engineering Technical Support at Public Hearing with Layouts, etc.	24	20	24	36		33	45		32	42	47	31	37	371		\$ 35,000.32	\$ 35,000.00	
12 Public involvement for 1 Public Hearing	21	17	18	18		19	18.25		22	29	37	32	23	254.25		\$ 25,000.65	\$ 25,000.00	
SUB-TOTAL	255	151	381	349	288	101	280.5	122.25	298.75	368	2737.75	278	365	5975.25	\$ 29,692.00	\$ 519,892.30	\$ 519,887.00	
Subtotal Manhour Fee with Sub-Consultant Costs:														\$ 549,584.30				
SUPPLEMENTAL #2 to WORK AUTHORIZATION NO. 1																		
3 Archeological and Historical Research														0	\$ (14,846.00)	\$ -	\$ -	
12 Afford Opportunity for Public Hearing	14		30	20		20				19	14	20.86	137.86			\$ 14,846.04	\$ 14,846.00	
Subtotal Manhour Fee with Sub-Consultant Costs:														\$ 0.04				
* Total Project Fee:														\$ 549,575.00				

*Rounded Figure

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:
2020-652763

Date Filed:
08/04/2020

Date Acknowledged:
08/05/2020

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

L&G Consulting Engineers, Inc.
Mercedes, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County Precinct No. 4

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10
FM 1925 (from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street))

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval, P.E., Armando	Mercedes, TX United States		X
	Garza, P.E., Jacinto	Mercedes, TX United States	X	

5 Check only if there is NO Interested Party.

☐

6 UNSWORN DECLARATION

My name is _____, and my date of birth is _____.

My address is _____, _____, _____, _____, _____.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in _____ County, State of _____, on the _____ day of _____, 20____.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:
2020-652763

Date Filed:
08/04/2020

Date Acknowledged:

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

L&G Consulting Engineers, Inc.
Mercedes, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County Precinct No. 4

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10
FM 1925 (from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street))

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval, P.E., Armando	Mercedes, TX United States		X
	Garza, P.E., Jacinto	Mercedes, TX United States	X	

5 Check only if there is NO Interested Party.

☐

6 UNSWORN DECLARATION

My name is Jacinto Garza, and my date of birth is 10/23/1961.

My address is 2100 W. Expressway 83, Mercedes, TX, 78570, USA.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in Hidalgo County, State of TX, on the 4th day of August, 20 20.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)



Purchase Order

COUNTY OF HIDALGO

PO# 819552

DATE: 08/04/20

PAGE NO: 1 OF 1

PO TYPE:

VENDOR: 486167

REQ: 00416027

PHONE: (844) 273-7658

EMAIL: marlabiles@crisistrack.com

SHIP TO: COUNTY JUDGE

100 E. CANO STREET
2ND FLOOR
EDINBURG TX 78539

CRISIS TRACK
GEOPLIANT, LLC
2831 SUMMERFIELD RD.
FALLS CHURCH VA 22042

CONTACT: M. HINOJOSA

(956) 318-2615

SITE: BUDGET AND MANAGEMENT

CONTRACT NO: EXEMPT

SPECIAL INSTRUCTIONS: 110-018

VENDOR NOTES

1. Do not add to, or alter this Purchase Order. This Order is not renewable.
2. TAX EXEMPTION: This Purchase Order may be accepted in lieu of Exemption Certificate.
3. This Order is also placed F.O.B. Destination. Vendor must repay all shipping costs.
4. Invoice each Purchase Order singly. Original invoices are required customer copy may be accepted. Out number must appear on all invoices, bills of lading, and packages.
5. Payment will be made only for bona fide and full completed orders, unless otherwise attached.

QTY	UOM	DESCRIPTION	UNIT PRICE	AMOUNT
		DO NOT DUPLICATE ORDER		
		CC APPROVAL 07/21/20 AI#76346 LGC 262.024 (2)		
1.00	YEAR	EX CTDM16 CRISIS TRACK DISASTER MANAGEMENT IS AN ANNUAL SUBSCRIPTION BASED ON THE POPULATION OF YOUR JURISDICTION. THE SUBSCRIPTION PROVIDES YOU WITH AN UNLIMITED NUMBER OF USERS TO COLLECT AND VIEW DISASTER MANAGEMENT DATA WITHIN YOUR JURISDICTION'S BOUNDARY. YOUR SUBSCRIPTION INCLUDES TECHNICAL SUPPORT VIA EMAIL MONDAY THROUGH FRIDAY 8:00 A.M. TO 5:00 P.M.	10,100.0000	10,100.00
1.00	EACH	EX CTRAIN02 CRISIS TRACK SYSTEM SETUP AND ONSITE TRAINING WILL INITIAZLIE THE CRISIS TRACK SYSTEM AND PROVIDE UP TO SIZE HOURS OF TRAINING. INITIALIZING THE CRISIS TRACK SYSTEM INCLUDES ONE UPLOAD OF YOUR JURISDICTIONS GIS AND/OR TAX DATA, EMPLOYEE LISTS AND EQUIPMENT LISTS. THE ONSITE TRAINING WILL CONSIST OF THREE TWO-HOUR TRAINING SESSIONS AT YOUR FACILITIES: ONE FOR ROAD/DEBRIS ASSESSMENTS, ONE FOR BUILDING ASSESSMENTS, ONE FOR BUILDING ASSESSMENTS, AND ONE FOR ADMINISTRATORS ON SETTING UP THE CRISIS TRACK SYSTEM.	3,200.0000	3,200.00
		TOTAL:		13,300.00
		REPORT ROAD HAZARDS 1-866-HCR-SAFE OR 1-866-427-7233		
		***** For Hidalgo County use only 0-1287-441-42-115-096-0-336		13,300.00

Authorized by:

Martha L Salazar

C. , AI-67883 1. Requesting approval of Supplemental Agreement No. 1 for services under Work Authorization No. 2, FM 1925 Project, Contract No. C-13-336-12-10 for L&G Consulting Engineers, Inc., resulting in a reduction in scope of services reducing the Work Authorization amount by \$70,686.52.

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 1, DAVID FUENTES, the Court made a UNANIMOUS vote of approval.

Vote: 3 - 0 - Unanimously

2. Requesting approval of Supplemental No. 3 to amend Agreement for Professional Services, FM 1925 Project, Contract No. C-13-336-12-10 for L&G Consulting Engineers, Inc., resulting in an extension of Agreement termination date from December 09, 2018 to December 09, 2020.

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 1, DAVID FUENTES, the Court made a UNANIMOUS vote of approval.

Vote: 3 - 0 - Unanimously

Attachments:

FM 1925 (907 to Sharp) Suppl. No. 3 to Agreement

FM 1925 - Suppl. 1 to WA 2

- B. *OK* AI-67817 Approval to accept from the WIC State Office a 2019 Ford Escape as part of the Hidalgo County WIC Program Inventory with authority for Executive Officer and/or WIC Director to sign documents. *Subj to final legal review*

18. Planning Department: *T.G.*

- OK* AI-67795 1. Pipeline and Utility Permit
 a. Applicant: North Alamo Water Supply Corporation
 Legal Description: Lots 13 and 14 Block 65 Alamo Land & Sugar Co. (Pct. 4) (Curve Road & Tower Road)
 Location of Pipeline or Utilities: South of Curve Road.
 Proposed Right-of-Way Improvement: 1-3/4" water service line extension south of Curve Road.

19. Precinct #1 - Comm. Fuentes: *Mayor Suarez*

- OK* A. AI-67865 Pct. 1 is requesting approval to accept the counter offer to purchase a tract of land known as Parcel No. 41 associated with the Mile 6 W Road Improvement Project (CSJ# 0921-02-356) with authority for the County Judge to sign the Administrative Evaluation and Approval Form.
- B. AI-67807 Pct. 1 is requesting approval to accept the counter offer to purchase a tract of land known as Parcel No. 65 associated with the Mile 6 W Road Improvement Project (CSJ# 0921-02-356) with authority for the County Judge to sign the Administrative Evaluation and Approval Form.

20. Precinct #2 - Comm. Cantu: *Mando*

- OK* A. AI-67703 1. Requesting approval to rescind the action taken by Commissioners' Court on November 6, 2018 AI#67533, for approval to enter into a license agreement.
 2. Requesting approval to enter into a License Agreement between the County of Hidalgo and Pharr San Juan Alamo Independent School District to allow the County to modify and utilize an existing parking facility on PSJA ISD property by general public users of the Pct 2 Regional Linear Park-Phase I.

21. Precinct #3 - Comm. Flores: *Victor*

- OK* A. AI-67872 Requesting approval of a "Possession and Use Agreement For Transportation Purposes with Additional Payment of Independent Consideration" between Texas Department of Transportation and The County of Hidalgo for the purpose of constructing a portion of Highway No. FM 494. *for Parcel 13/14*

Precinct #4 - Comm. Palacios: *Lizbeth*

- OK* A. AI-67899 Resolution Honoring South Texas Preparatory Academy Lady Spartans.
- B. AI-67952 Authorization for court members to sign resolutions on behalf of Commissioner Palacios *for Pct 4 employees*

- OK* C. AI-67883 1. Requesting approval of Supplemental Agreement No. 1 for services under Work Authorization No. 2, FM 1925 Project, Contract No. C-13-336-12-10 for L&G

- Consulting Engineers, Inc., resulting in a reduction in scope of services reducing the Work Authorization amount by \$70,686.52.
2. Requesting approval of Supplemental No. 3 to amend Agreement for Professional Services, FM 1925 Project, Contract No. C-13-336-12-10 for L&G Consulting Engineers, Inc., resulting in an extension of Agreement termination date from December 09, 2018 to December 09, 2020.

23.

Budget & Management:

A. AI-67931

Discussion, consideration and approval of TCDRS plan provisions for Plan Year 2019.

B. AI-67875

Texas VINE Grant (1283):

Approval to submit the FY19 Texas Vine Grant reimbursement maintenance invoice in the amount of \$7,136.69 (1st Quarter) and the Texas Statewide Automated Victim Notification Service (SAVNS) County Verification of Continuing Production Record with the authority for the County Judge to sign the required documents.

C.

Budget Appropriations:

1. AI-67934

Pursuant to Texas Local Government Code 111.070, approval of emergency appropriation from the General Fund - Fund Balance in the amount of \$600,000.00 for emergency related expenditures

24.

Purchasing Department - Notes:

A. FOR ANY CONTRACT(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FORWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

A. AI-67855

Requesting approval to purchase promotional items under "Public Purpose", pursuant to the Tx. Constitution, Art. 3, Sec. 52, to include, but not limited to a shadow box, frames and accessories for display so as to document and inform taxpayers and general public [visiting the Purchasing Dept.] of the concerted County efforts in the design and construction of a New Count Courthouse with all acquisitions to be procured through the requisition and purchase order protocols.

B.


Hidalgo County

1. AI-67849

A. Requesting exemption from competitive bidding requirements under Texas Local Government Code 262.024 (a)(7)...an item that can be obtained from only one source' and approval of a Sole Source Declaration for "PALM VALLEY ANIMAL CENTER" for the provision of: impoundment and the Quarantine of Small Animals in Hidalgo County;

APPROVED

B. Requesting approval of Contract # C-18-289-12-04 with Palm Valley Animal Center Sole Source vendor (approved by HCCC in 02/2011) for "Hidalgo County - Impoundment and Quarantine of Small Animals" effective January 01, 2019 through



L&G Engineering

Transportation Consultants

November 27, 2018

The Honorable Joseph Palacios
Commissioner, Hidalgo County Pct. No. 4
1051 N. Doolittle
Edinburg, Texas 78539

RE: FM 1925 Project (C-13-336-12-10)
Limits: from FM 907 (Alamo Road) East to Sharp Road (including the re-alignment of Sharp Rd.)
Supplemental No. 3 to Agreement for Professional Services

Dear Commissioner Palacios:

Attached for your review and consideration is Supplemental No. 3 to the FM 1925 Project Agreement for Professional Services. This Supplemental is needed to extend the termination date of said Agreement for an additional two years. This would allow time to complete the engineering services as approved on Work Authorization No. 3 of this Agreement and as outlined in Exhibit C – Work Schedule. We are enclosing the supplemental in duplicate for your review and further processing.

Attached you will find the following:

- 1.) Two signed originals of Supplemental No. 3 to the Agreement with the following attachments:
 - Exhibit C "Project Work Schedule"
 - Form 1295

Should you have any questions regarding this submittal, do not hesitate to call me at (956) 565-9813.

Sincerely,

L&G ENGINEERING

Robert Macheska, P.E.
Project Manager

Attachments

EXHIBIT "F"

Supplemental Agreement Form

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

SUPPLEMENTAL AGREEMENT NO. 3

TO AGREEMENT FOR PROFESSIONAL SERVICES

C-13-336-12-10

This **SUPPLEMENTAL AGREEMENT** is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between **HIDALGO COUNTY**, acting herein by and through the **Commissioner's Court**, hereinafter called the "**Owner**", and L&G Consulting Engineers, Inc. d/b/a **L&G Engineering**, Professional Engineers of, **Mercedes, Texas**, hereinafter called "**Engineer**".

WITNESSETH

WHEREAS, the **Owner** and the **Engineer** executed the **Agreement** on the 10th day of December, 2013 concerning professional engineering services required for the FM 1925 project from FM 907 (Alamo Road) East to Sharp Road (including the Re-Alignment of Sharp Road) for Hidalgo County Precinct No. 4 hereinafter referred to as the project; and,

WHEREAS, Article 3, Section 3.1 of the **Agreement**, Period of Service, Termination Date, establishes the termination date of this agreement; and,

WHEREAS, it has become necessary to amend the Agreement in order to extend the termination date and allow time to complete all tasks as outlined in Exhibit "C" – Work Schedule.

A. AGREEMENT

NOW THEREFORE, premises considered, the **Owner** and the **Engineer** agree that said **Agreement** is amended as follows:

- I. Section of the Agreement, Article 3. Period of Service, 3.1 Termination Date of the Agreement is amended as follows:

*Agreement is hereby amended to extend the termination date from **December 9, 2018** to **December 9, 2020** in order to complete the engineering services identified in Exhibit B – Services to be provide by the Engineer and Exhibit C – Work Schedule of the Agreement.*

All other provisions are unchanged and remain in full force and effect.

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the _____ day of _____, 2018.

THE ENGINEER:

ENGINEER

BY: *A. J. [Signature], PE*

THE OWNER:

HIDALGO COUNTY

BY: *[Signature]*

~~Ramon Garcia, County Judge~~
David Fuentes, County
Commissioner

APPROVED BY
COMMISSIONERS' COURT
ON: *12/4/18* *[Signature]*

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

**OFFICE USE ONLY
CERTIFICATION OF FILING**

Certificate Number:
2018-427063

Date Filed:
11/20/2018

Date Acknowledged:
03/22/2019

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

L&G Consulting Engineers, Inc.
Mercedes , TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10

FM 1925 from FM 907 to Sharp Rd (including the Realignment of Sharp Road) Suppl. No. 3 to Main Agreement - Time Extension

4	Name of Interested Party	City, State, Country (place of business)	Nature of Interest (check applicable)	
			Controlling	Intermediary
	Garza , Jacinto	Mercedes , TX United States	X	
	Sandoval , Armando	Mercedes, TX United States		X

5 Check only if there is NO Interested Party.

☐**6 UNSWORN DECLARATION**

My name is _____, and my date of birth is _____.

My address is _____, _____, _____, _____, _____.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in _____ County, State of _____, on the _____ day of _____, 20____.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.
L&G Consulting Engineers, Inc.
Mercedes, TX United States

Certificate Number:
2018-427063

Date Filed:
11/20/2018

Date Acknowledged:

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.
Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.
C-13-336-12-10
FM 1925 from FM 907 to Sharp Rd (including the Realignment of Sharp Road) Suppl. No. 3 to Main Agreement - Time Extension

4	Name of Interested Party	City, State, Country (place of business)	Nature of Interest (check applicable)	
			Controlling	Intermediary
	Garza, Jacinto	Mercedes, TX United States	X	
	Sandoval, Armando	Mercedes, TX United States		X

5 Check only if there is NO Interested Party. ☐

6 UNSWORN DECLARATION

My name is Jacinto Garza, and my date of birth is 10/23/1961.

My address is 2100 W. Expressway 83, Mercedes, TX, 78570, USA.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in Hidalgo County, State of Texas, on the 27th day of November, 20 18.
(month) (year)



Signature of authorized agent of contracting business entity
(Declarant)

EXHIBIT "F"

Supplemental Agreement Form

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

SUPPLEMENTAL AGREEMENT NO. 2

TO AGREEMENT FOR PROFESSIONAL SERVICES

C-13-336-12-10

This SUPPLEMENTAL AGREEMENT is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between HIDALGO COUNTY, acting herein by and through the Commissioner's Court, hereinafter called the "Owner", and L&G Consulting Engineers, Inc. d/b/a L&G Engineering, Professional Engineers of, Mercedes, Texas, hereinafter called "Engineer".

WITNESSETH

WHEREAS, the Owner and the Engineer executed the Agreement on the 10th day of December, 2013 concerning professional engineering services required for the FM 1925 project from FM 907 (Alamo Road) East to Sharp Road (including the Re-Alignment of Sharp Road) for Hidalgo County Precinct No. 4 hereinafter referred to as the project; and,

WHEREAS, Article 3, Section 3.1 of the Agreement, Period of Service, Termination Date, establishes the termination date of this agreement; and,

WHEREAS, it has become necessary to amend the Agreement in order to extend the termination date and allow time to complete all tasks as outlined in Exhibit "C" – Work Schedule.

A. AGREEMENT

NOW THEREFORE, premises considered, the Owner and the Engineer agree that said Agreement is amended as follows:

- I. Section of the Agreement, Article 3. Period of Service, 3.1 Termination Date of the Agreement is amended as follows:

Agreement is hereby amended to extend the termination date from December 9, 2016 to December 9, 2018 in order to complete the engineering services identified in Exhibit B – Services to be provide by the Engineer and Exhibit C – Work Schedule of the Agreement.

All other provisions are unchanged and remain in full force and effect.

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the 13th day of December, 2016.

THE ENGINEER:

ENGINEER

BY: _____

THE OWNER:

HIDALGO COUNTY

BY: Ramon Garcia_____

Ramon Garcia, County Judge

APPROVED BY
COMMISSIONERS' COURT
ON: 12/13/16 

L&G ENGINEERING TASK
TxDOT TASK
COUNTY TASK

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

Certificate Number:
2016-144472

Date Filed:
12/08/2016

Date Acknowledged:

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

L&G Consulting Engineers, Inc.
Mercedes, TX United States

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.


C-13-336-12-10
FM 1925 (from FM 907 to Sharp Road) Professional Engineering Services - Time Extension

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval, Armando	Mercedes, TX United States		X
	Garza, Jacinto	Mercedes, TX United States	X	

5 Check only if there is NO Interested Party. ☐

6 AFFIDAVIT

I swear, or affirm, under penalty of perjury, that the above disclosure is true and correct.



AFFIX NOTARY STAMP / SEAL ABOVE

Signature of authorized agent of contracting business entity

Sworn to and subscribed before me, by the said Jacinto Garza, this the 6th day of Dec. 2016, to certify which, witness my hand and seal of office.

Marie C. Bustamante
Signature of officer administering oath

Marie C. Bustamante
Printed name of officer administering oath

Exec. Admin
Title of officer administering oath

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

**OFFICE USE ONLY
CERTIFICATION OF FILING****1 Name of business entity filing form, and the city, state and country of the business entity's place of business.**

L&G Consulting Engineers, Inc.
Mercedes , TX United States

Certificate Number:
2016-144472

Date Filed:
12/08/2016

Date Acknowledged:
12/09/2016

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10
FM 1925 (from FM 907 to Sharp Road) Professional Engineering Services - Time Extension

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval , Armando	Mercedes, TX United States		X
	Garza , Jacinto	Mercedes , TX United States	X	

5 Check only if there is NO Interested Party.☐**6 AFFIDAVIT**

I swear, or affirm, under penalty of perjury, that the above disclosure is true and correct.

Signature of authorized agent of contracting business entity


AFFIX NOTARY STAMP / SEAL ABOVE

Sworn to and subscribed before me, by the said _____, this the _____ day of _____,
20_____, to certify which, witness my hand and seal of office.

Signature of officer administering oath

Printed name of officer administering oath

Title of officer administering oath



L&G Engineering

Transportation Consultants

December 6, 2016

The Honorable Joseph Palacios
Commissioner, Hidalgo County Pct. No. 4
Attn: Maria Lucio
1051 N. Doolittle
Edinburg, Texas 78539

RE: FM 1925 Project (C-13-336-12-10)
Limits: from FM 907 (Alamo Road) East to Sharp Road (including the re-alignment of Sharp Rd.)
Supplemental No. 2 to Agreement for Professional Services

Dear Commissioner Palacios:


Attached for your review and consideration is Supplemental No. 2 to the FM 1925 Project Agreement for Professional Services. This Supplemental is needed to extend the termination date of said Agreement for an additional two years. This would allow time to complete the PS&E, ROW Map, Right-of-Way Acquisition, Compensable Utility Management Oversight as approved on Work Authorization No. 2 of this Agreement and as outlined in Exhibit C – Work Schedule. We are enclosing the supplemental in duplicate for your review and further processing.

Attached you will find the following:

- 1.) Two signed originals of Supplemental No. 2 to the Agreement with the following attachments:
 - Exhibit C "Project Work Schedule"
 - Form 1295

Should you have any questions regarding this submittal, do not hesitate to call me at (956) 565-9813.

Sincerely,
L&G ENGINEERING


Jacinto Garza, P.E.
CEO/President

Attachments

SPECIAL MEETING - December 13, 2016

BE IT REMEMBERED, that on this 13th day of December A.D., 2016, there was begun and held a **SPECIAL MEETING** of the Honorable Commissioners' Court of Hidalgo County, Texas, wherein the following members thereof were present, to-wit:

HONORABLE RAMON GARCIA

HIDALGO COUNTY JUDGE

HONORABLE A.C. CUELLAR, JR.

COMMISSIONER, PRECINCT NO. 1

HONORABLE EDUARDO "EDDIE" CANTU

COMMISSIONER, PRECINCT NO. 2

HONORABLE JOE M. FLORES

COMMISSIONER, PRECINCT NO. 3

HONORABLE JOSEPH PALACIOS

COMMISSIONER, PRECINCT NO. 4

and **ARTURO GUAJARDO, JR., COUNTY CLERK & EX-OFFICIO CLERK OF THE COMMISSIONERS' COURT** of Hidalgo County, Texas, wherein the following proceedings were had, to-wit:



AGENDA
CC REGULAR CONSENT
COMMISSIONERS' COURT
December 13, 2016
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a **SPECIAL MEETING** of the Commissioners' Court will be held at the Edinburg Council Chambers 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

NOTICE TO THE PUBLIC
CONSENT AGENDA

The following items are of a routine or administrative nature. The Commissioners' Court has been furnished with background and support on each item, and/or it has been discussed at a previous meeting. All items will be acted upon by one vote without being discussed separately unless requested by a Court Commissioner, in which event the item or items will immediately be withdrawn for individual consideration in its normal sequence after the items not requiring separate discussion have been acted upon. The remaining items will be adopted by one vote.

On motion by COMMISSIONER PCT. 1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a **UNANIMOUS** vote of approval for the exception of Item.11.B.3. to be further discuss.

Vote: 5 - 0 - Unanimously

1. **AI-57786 Approval of check register and payment of claims and bills -**
(Payments from Juvenile Probation, Adult Probation, LEOSE Fund, DA Motor Vehicle Theft Fund, DA Check Fraud Fund, DA Forfeiture Fund, Sheriff Forfeiture Funds, Constable Forfeiture Funds, HIDTA Forfeiture Funds and VIT Interest Fund are presented for recording purposes only.)
2. **Auditor's Office:**
 - A. **AI-57788** Presentation of Fund Information Report
3. **2016 Intradepartmental transfers:**
 - A. **AI-57782** 2016 - Executive Office (1100)
 - B. **AI-57760** 2016 - Sheriff's Office (1100)
 - C. **AI-57761** 2016 - Tax Office (1100)
 - D. **AI-57753** 2016 - I. T. Department (1100)
 - E. **AI-57741** 2016 - Pct. 1 Parks (1100)

- B. **AI-57659** Approval of Monthly Special Services Report: November
- C. **AI-57658** Approval of Monthly Texas Department of Agriculture Meals/Snacks Report: November
- D. **AI-57657** Approval of Monthly Children's Applications Report for Program Year 2016-2017

10. Budget & Management:

- A. **AI-57754** Approval of medical coverage effective date correction as per revised report received from ETC for the employees listed below previously approved on CC 11/15/16 AI-57271.
 - 1. E#211060 effective 11/1/16
 - 2. E#212300 effective 2/1/17

- B. **AI-57639** 1. Approval of reimbursement in the amount of \$765,113.13 to Blue Cross Blue Shield Insurance Company for claims paid on behalf of Hidalgo County from 11/19/16 to 12/02/16.

11/19-25/16	\$296,863.71
11/26-30/16	\$221,737.92
12/01-02/16	\$246,511.50
TOTAL	\$765,113.13

- 2. Approval of wire transfer to cover claims paid.

C. Interfund transfers:

- 1. **AI-57772** Pct. 1 Rd. Maint (1200):
Approval of 2016 interfund transfer from Co. Wide Adm.-Contingency (1100) to Pct. 1 Rd. Maint (1200) in the amount of \$145,000.00 to fund general supplies & gasoline year-end expenses.
- 2. **AI-57713** TXDOT-Pct 1 (1315):
Approval of 2016 interfund transfer from CO2016-Pct 1 (1350) to various TXDOT-Pct 1 projects (1315) in the amount of \$22,743.00 to fund recent Change Order #5 for the Mile 2 West Project and Advance Funding Agreement (AFA) for the Charles Green (CR342) Bridge Rehabilitation Project.

11.

Purchasing Dept:

Notes:

A. FOR ANY CONTRACTS(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FOWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING

**PROCEDURES INCLUDING AUTHORITY FOR COUNTY
TREASURER TO ISSUE PAYMENT(S)/CHECK(S).**

- A. AI-57779** Acceptance and approval of Supplemental Agreement No. 2 to *increase the "term" expiring, December 9, 2018* for agreement #C-13-336-12-10 with and as submitted by L&G ENGINEERING for ongoing project: (FM 1925) from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street) within Hidalgo County Precinct No. 4.
- APPROVED**

- B. AI-57728**
1. Authority to exercise the Sixth (6th) Year of the additional nine (9) one (1) year option to extend/renew under the current lease agreement #E-16-037-01-05 (C-11-026-03-21) with O.E. INVESTMENTS, LTD.- "LEASE OF TOWER SPACE" for the Sheriff's Office,(under the same rates, terms and conditions), effective, 03/01/17.
 2. Authority to exercise the Second (2nd) Year of the additional three (3) one (1) year option to extend/renew under the current agreement #E-16-038-01-05 (C-14-001-02-11) with SOUTH TEXAS COMMUNICATIONS, INC. for the "Repairs, Installation and Removal of Communications Radio and Tower Miscellaneous Equipment (on an as needed basis)" for the Sheriff's Office, (under the same rates, terms and conditions), effective, 03/01/17.
 3. Requesting authority to exercise the second (2nd) year of the additional two (2) one (1) year option to extend/renew under the current contract #E-16-039-01-05 with MAO WESTWOOD PHARMACY d/b/a WESTWOOD PHARMACY for:"LEGEND and NON-LEGEND PHARMACEUTICALS"(on as needed basis) for the Sheriff's Office, (under the same rates, terms and conditions), effective 01/17/17.

Mr. Guerra informed that the form 1295 was not attached with regards to Item.11.B.3. Therefore, the auditor's office couldn't determine compliance. Guerra requested for the court to take action subject to compliance of form 1295.

On motion by COMMISSIONER PCT. 3, JOE M. FLORES, seconded by COMMISSIONER PCT. 1, A.C. CUELLAR, JR., the Court made a UNANIMOUS vote of approval subject to compliance of form 1295.

Vote: 5 - 0 - Unanimously

Guerra stated that this is in compliance with Sec. 2252.908 of gov. code.

- C. AI-57724** Acceptance and approval of Request for Payment-Application No. 1 in the amount of \$26,876.70 Herrcon, LLC, awarded contractor for the Autopsy Facility Space Pressure Control, and as certified for payment by project engineer, Halff Associates, Inc.

EXHIBIT "F"
Supplemental Agreement Form

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

**SUPPLEMENTAL AGREEMENT NO. 1
TO AGREEMENT FOR PROFESSIONAL SERVICES
C-13-336-12-10**

This **SUPPLEMENTAL AGREEMENT** is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between **HIDALGO COUNTY**, hereinafter called the "**Owner**", and **L&G ENGINEERING**, professional engineers of Mercedes, Texas, hereinafter called the "**Engineer**".

WITNESSETH

WHEREAS, the **Owner** and the **Engineer** executed the Main Contract Agreement on the 10 the day of December, 2013 concerning professional engineering services for the "**FM 1925 (from FM 907 (Alamo Road) East to East of SH 68 (Uresti Street)**", (for preparation of the Environmental Assessment, Public Involvement, Schematic and Hydrologic Design) hereinafter referred to as the "**Project**"; and,

WHEREAS, it has become necessary to amend Article 2, Section 2.1, Scope of Work, "*Exhibit A – Services to be provided by the Owner*" and "*Exhibit B – Services to be provided by the Engineer*" of the Agreement as identified below:

- (1) Revise the project limits as requested by the Texas Department of Transportation to end at Sharp Road including the Re-alignment of Sharp Road (from FM 1925 North approximately 0.5 miles) as identified on the attached *Location Map*; and,

WHEREAS, it has become necessary to amend Article 2, Section 2.3, Work Schedule, "*Exhibit C – Work Schedule*" of the Agreement, to reflect the revised project limits; and,

WHEREAS, it has become necessary to amend Article 3, Section 3.1, Termination Date of the Agreement, to extend the termination date of December 9, 2014 to December 9, 2016 in order to complete the engineering services identified in the scope of work and as outlined in *Exhibit C – Work Schedule*; and,

WHEREAS, it has become necessary to amend Article 5, Section 5.1, Basic Services, "Exhibit D-1 – Estimated Project Fee Schedule (w/man-hour breakdown)" of the Agreement, to reflect the revised project limits. Cost does not decrease or increase; therefore, the cost for this project remains the same.

A. AGREEMENT

NOW THEREFORE, premises considered, the **Owner** and the **Engineer** agree that said **Agreement** is amended as follows:

- I. Sections of the Agreement, LOCATION MAP, EXHIBIT "A" – SERVICES TO BE PROVIDED BY THE OWNER, EXHIBIT "B" – SERVICES TO BE PROVIDED BY THE ENGINEER, EXHIBIT "C" – WORK SCHEDULE, EXHIBIT "D-1" – ESTIMATED PROJECT FEE SCHEDULE are revised to reflect the above listed modifications of this Supplemental.

All other provisions are unchanged and remain in full force and effect.

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the 28th day of October, 2014.

THE ENGINEER:
ENGINEER

BY: Jacinto Garza
Jacinto Garza, P.E., President

THE OWNER:
HIDALGO COUNTY

BY: Ramon Garcia
Ramon Garcia, County Judge

LIST OF EXHIBITS:

LOCATION MAP

EXHIBIT A – "Services to be provided by County"

EXHIBIT B – "Services to be provided by Engineer"

EXHIBIT C – "Work Schedule"

EXHIBIT D-1 – "Estimated Fee Schedule"

Approved by Commissioners' Court
on 10/28/14 RO




EXHIBIT "A"
Services to be provided by the County

1. The County will issue work authorization to initiate all required services and designate the authorized representative of the coordination of each work authorization.
2. The County will provide copies of all subdivision plats of record and/or in the subdivision process.
3. The County will provide the Engineer with on-going guidance, timely reviews, and decisions necessary to complete services required by the work authorization in order to permit the Engineer to maintain an agreed upon project schedule.
4. The County will provide a Purchase Order and process all acceptable requests for payment in a timely manner.
5. The Work Authorization will identify the Notice to Proceed date.

PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: _____

PROJECT/DESCRIPTION: Professional Engineering Services

LENGTH: VARIABLE

HIGHWAY: FM 1925

LIMITS: from FM 907 (Alamo Rd) to Sharp Rd. including
Sharp Rd. Realignment (from FM 1925 North 0.5 Miles)

EXISTING FACILITY

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☐ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

NOTES

NOTE:

**NO REVISIONS WERE MADE TO EXHIBIT "B" BEYOND THIS POINT.
PAGES 1-1, 3-1 THRU C-3 REMAIN THE SAME IN THE CONTRACT.**

EXHIBIT "D-1"

ESTIMATED PROJECT FEE SCHEDULE

FM 1925 PROJECT (SEGMENT II)

(Limits: from FM 907 (Alamo Road) to Sharp Road
including the Sharp Road Realignment (from FM 1925 North 0.5 Miles)

ROADWAY PROJECT:	FM 1925	
LIMITS:	from FM 907 (Alamo Rd) to Sharp Rd including the Sharp Rd. Realignment (from FM 1925 North 0.5 mi.)	
EXISTING ROADWAY SECTION:	40-ft Rural	
EXISTING ROW WIDTH:	80-Feet	
PROPOSED ROADWAY SECTION:	4-lane divided urban	
PROPOSED ROW WIDTH:	120FT	
ESTIMATED CONSTRUCTION COST:	\$10,305,000.00	
LENGTH FOR 4-LANE ROADWAY	2.3 Miles	
ESTIMATED PROJECT COSTS	STATE/MPO	* LPA
WORK AUTHORIZATION NO. 1		
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN		
Environmental Assessment with TxDOT	\$ -	\$ 95,000.00
Public Involvement for the project with stakeholders and 1 Public Meeting	\$ -	\$ 25,000.00
Archeological and Historical Research	\$ -	\$ 30,000.00
Engineering Technical Support at Public Mtgs with Layouts etc	\$ -	\$ 24,000.00
Schematic for FM 1925	\$ -	\$ 154,575.00
Hydrological Map	\$ -	\$ 42,000.00
Schematic for Intersecting streets (Sharp to 3rd Street)	\$ -	\$ 40,000.00
Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	\$ -	\$ 21,000.00
Preliminary Compensable Utilities Identification on Schematic for Approval by TxDOT/FHWA	\$ -	\$ 18,000.00
Update Schematic based on comments as provide by TxDOT/County for schematic and EA update w/ FHWA	\$ -	\$ 39,000.00
Engineering Technical Support at Public Hearing with Layouts etc	\$ -	\$ 36,000.00
Public Involvement and 1 Public Hearing	\$ -	\$ 25,000.00
SUB-TOTAL	\$ -	\$ 549,575.00
WORK AUTHORIZATION NO. 2		
PHASE II- PS&E and CONSTRUCTION OVERSIGHT		
Complete ROW Map (Estimated 12 Parcels)		\$ 48,000.00
Outfall Identification Preliminary Property Ownership and Hydraulics	\$ -	\$ 36,000.00
PS&E Development (7.5% Engineering Fee)		\$ 772,875.00
Engineering Fee to Create sets of Plans and Submit through TxDot and Austin Letting		\$ 135,000.00
PS&E Development for OUTFALL(S)		\$ 162,000.00
Field Surveys for Design and Construction		\$ 110,000.00
Permitted Utilities Coordination to adjust	\$ -	\$ 90,000.00
ROADWAY CONSTRUCTION COST	\$ 10,305,000.00	
TxDOT Construction Inspection (11%)	\$ 1,133,550.00	
Eng Consultant Construction Management (18 Months)		\$ 162,000.00
SUB-TOTAL	\$ 11,438,550.00	\$ 1,515,875.00
WORK AUTHORIZATION NO. 3		
PHASE III - ROW Acquisition		
Right-of-Way Costs - Acq. Services @ (est. 12 Parcels @ \$13,800/Parcel Avg.)		\$ 165,600.00
Estimated County Attorney Costs for Condemnation (\$15,000/Parcel based on 20% total of parcels)		\$ 36,000.00
Estimated Compensable Utility Mgmt for Acq. of Property Rights and Compensate for Utility Adjust(s) (2) High Pressure Gas lines and One Parallel Irrigation Line and one Parallel Gas Line		\$ 189,000.00
Estimated Roadway Right-of-Way Costs (422,400 sq/ft @ \$4.5/ sq ft) (80/20)	\$ 1,881,792.00	\$ 19,008.00
COMPENSABLE UTILITY COSTS (Est 2-Pipeline Crossings at \$130,000 ea to lower and encase and 1 Parallel Pipeline and 1 Parallel Irrigation Line both at 150,000 each)	\$ 504,000.00	\$ 56,000.00
SUB-TOTAL	\$ 2,385,792.00	\$ 465,608.00
TOTAL	\$ 13,824,342.00	\$ 2,531,058.00

Work Authorization No. 1 Phase I	FY 13	\$ 549,575.00
Work Authorization No. 2 Phase II	FY 14	\$ 1,515,875.00
Work Authorization No. 3 Phase III	FY 15	\$ 354,600.00

ISSUED

NOT ISSUED

NOT ISSUED

State/FED Estimated Costs

Local Estimated Costs

TOTAL ESTIMATED COUNTY COST:	\$	2,531,058.00	15.48%
TOTAL ESTIMATED PROJECT COST:	\$	16,355,400.00	
COUNTY COSTS NOT INCLUDED IN WORK AUTHORIZATIONS	\$	111,008.00	

* Local Public Agencies (LPA)

SPECIAL MEETING - October 28, 2014

BE IT REMEMBERED, that on this 28th day of October A.D., 2014, there was begun and held a **SPECIAL MEETING** of the Honorable Commissioners' Court of Hidalgo County, Texas, wherein the following members thereof were present, to-wit:

HONORABLE RAMON GARCIA	HIDALGO COUNTY JUDGE
HONORABLE A.C. CUELLAR, JR.	COMMISSIONER, PRECINCT NO. 1
HONORABLE HECTOR "TITO" PALACIOS	COMMISSIONER, PRECINCT NO. 2
HONORABLE JOE M. FLORES	COMMISSIONER, PRECINCT NO. 3
HONORABLE JOSEPH PALACIOS	COMMISSIONER, PRECINCT NO. 4

and **ARTURO GUAJARDO, JR., COUNTY CLERK & EX-OFFICIO CLERK OF THE COMMISSIONERS' COURT** of Hidalgo County, Texas, wherein the following proceedings were had, to-wit:



AGENDA
CC REGULAR CONSENT
COMMISSIONERS' COURT
October 28, 2014
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a **SPECIAL MEETING** of the Commissioners' Court will be held at the Edinburg Council Chambers 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

NOTICE TO THE PUBLIC
CONSENT AGENDA

The following items are of a routine or administrative nature. The Commissioners' Court has been furnished with background and support on each item, and/or it has been discussed at a previous meeting. All items will be acted upon by one vote without being discussed separately unless requested by a Court Commissioner, in which event the item or items will immediately be withdrawn for individual consideration in its normal sequence after the items not requiring separate discussion have been acted upon. The remaining items will be adopted by one vote.

APPROVED

On motion by COMMISSIONER PCT. 1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval for the exception of Items 3.A, 4.E, 14.C, and 14.F to be pulled for discussion.

Vote: 5 - 0 - Unanimously

1. **AI-47186 Approval of check register and payment of claims and bills** - (Payments from Juvenile Probation, Adult Probation, LEOSE Fund, DA Motor Vehicle Theft Fund, DA Bad Check Processing Fund, DA Forfeiture Fund, Sheriff Forfeiture Funds, Constable Forfeiture Funds, HIDTA Forfeiture Funds and VIT Interest Fund are presented for recording purposes only.)
2. **2014 Intradepartmental transfers:**
 - A. **AI-47111** 2014 - County Court at Law # 2 (1100)
 - B. **AI-47160** 2014 - County Judge (1100)
 - C. **AI-47136** 2014 - District Attorney's Office / Autopsies (1100)
 - D. **AI-47137** 2014 - District Attorney's Office (1100)
 - E. **AI-47138** 2014 - District Attorney's Office (1100)
 - F. **AI-47139** 2014 - District Attorney's Office (1222)
 - G. **AI-47134** 2014 - District Attorney's Office / Grand Jury (1100)

- B. AI-46769** 1. Approval of reimbursement in the amount of \$843,242.96 to Blue Cross Blue Shield Insurance Company for claims paid on behalf of Hidalgo County from 09/27/14 to 10/10/14.

09/27-30/14	\$139,139.98
10/01-03/14	\$232,205.51
10/04-10/14	\$471,897.47
TOTAL	\$843,242.96

2. Approval of wire transfer to cover claims paid.

14.

Purchasing Dept:**Notes:**

A. FOR ANY CONTRACTS(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FOWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

- A. AI-47161** Acceptance of proposal submitted by AAMECC, LLC awarded vendor thru County's participation with TIPS /TAPS Contract No. 1042513 for the services of Asbestos Abatement Consulting, including but not limited to preparation of specifications, project air monitoring and air monitoring for final clearance for the project: Facilities Management -Asbestos Abatement at County Clerk's Office in the amount of \$5,695.00. (Project# 2014-373-MSS)
- B. AI-47166** Acceptance and approval of Payment Application #1 for PO#701751 in the amount of \$15,377.47 and Pay Application #1 for PO#701752 in the amount of \$18,233.30 as submitted by Herrera & Hunt Inc. in connection with: "Bullet Proof Windows for Various JP's Offices in Precinct No. 1" as reviewed and approved by Facilities Management.
- C. AI-47172** Acceptance of proposal submitted by AL3 Enterprises, LLC dba Starr Telecom in the amount of \$95,562.00 for Turnkey Installation of Data Drops at the Old Administration Building 1st and 2nd floor thru County Contract No. E-13-321-10-22 (Req. #265971).

Mrs. Marty Salazar stated that they received a better proposal that has been attached to the backup of the Agenda reflecting an amount of \$91,242.00.

On motion by COMMISSIONER PCT.1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval.

Vote: 5 - 0 - Unanimously

- P.** **AI-47105** **APPROVED** Acceptance and approval of Supplemental Agreement No. 1 to Professional Engineering Services Agreement #C-13-336-12-10 & Work Authorization No.1, (to revise project limits as requested by Tx DOT) and as submitted by L & G ENGINEERING in connection to the "professional engineering services" for ongoing project: (FM 1925) from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street) within Hidalgo County Precinct No. 4.

- Q.** **AI-46652** Acceptance and approval of request for Payment Application #1 and Modification #1 for a credit of -\$2,949.20 included for a total payment request amount of \$28,872.18 submitted by Herrera & Hunt Inc., in connection with the project: Hidalgo County Facilities Management - "Sewer Line repairs at the Health Department C.O.", project No. 2013-323-10-30-MSS and PO#701098 with authority for County Treasurer to issue payment after review, audit, and processing procedures are completed by County Auditor
- R.** **AI-47005** Requesting authority to advertise and approval of procurement packet (i.e., specifications/requirements, legal notice and draft requirement agreement etc.) as attached hereto for Hidalgo County-Construction Building Materials & Related Supplies -RFB No.: 2014-002-SMA" including the authority to re-advertise project in the event that no packets are received and/or are rejected and project is still required.
- S.** **AI-47119** Acceptance and approval of Substantial Completion and processing of Pay Application #1 in the amount of \$6,438.45 as submitted by Herrera & Hunt Inc. in connection with the Hidalgo County Facilities Management - "Storefront Doorway Installation at Health Department" (PO#708868) with authority for Hidalgo County Judge Ramon Garcia to sign Substantial Completion.
- T.** **AI-46994** **Sheriff's Office:**
Requesting approval & authority to enter into a 12-month commercial alarm monitoring services and execute the required commercial alarm monitoring agreement with Alan Yoder Enterprises, Inc. d/b/a Superior Alarms for the following department through the requisition 262910 effective upon approval.
- U.** **AI-46576** Acceptance and approval to exercise the County's option to extend the first (1st) year of two (2)-one(1) options under the same rates, terms and conditions for the "Tire Disposal Services" with Texas Land Reclamation.
- V.** **AI-47025** Add Fuel Card Users and Fuel Cards:
1. Sheriff Office - Fuel cards and Users

EXHIBIT “F”
Supplemental Agreement Form

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

**SUPPLEMENTAL AGREEMENT NO. 1
TO WORK AUTHORIZATION NO. 1
TO AGREEMENT FOR PROFESSIONAL SERVICES
C-13-336-12-10**

This **SUPPLEMENTAL AGREEMENT** is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between **HIDALGO COUNTY**, hereinafter called the “**Owner**”, and **L&G ENGINEERING**, professional engineers of Mercedes, Texas, hereinafter called the “**Engineer**”.

WITNESSETH

WHEREAS, the **Owner** and the **Engineer** executed the Main Contract Agreement on the 10 the day of December, 2013 concerning professional engineering services for the “**FM 1925 (from FM 907 (Alamo Road) East to East of SH 68 (Uresti Street)**, (for preparation of the Environmental Assessment, Public Involvement, Schematic and Hydrologic Design) hereinafter referred to as the “**Project**”; and,

WHEREAS, it has become necessary to amend “*Exhibit A – Scope of Services to be provided by the Owner*” and “*Exhibit B – Scope of Services to be provided by the Engineer*” of Work Authorization No. 1, Part 1 of the Agreement – Scope of Work as identified below:

- (1) Revise the project limits as requested by the Texas Department of Transportation to end at Sharp Road including the Re-alignment of Sharp Road (from FM 1925 North approximately 0.5 miles) as identified on the attached *Location Map*.

WHEREAS, it has become necessary to amend “*Exhibit C – Work Schedule*” of the Work Authorization No. 1, Part 5 of the Agreement – Period of Service, to reflect the revised project limits; and,

WHEREAS, it has become necessary to amend “*Exhibit D-1 – Estimated Project Fee Schedule (w/man-hour breakdown)*” of the Work Authorization No. 1, Part 2 of the Agreement – Estimated Cost, to reflect the revised project limits. Work Authorization does not decrease or increase; therefore, the amount of this Work Authorization remains the same.

A. AGREEMENT

NOW THEREFORE, premises considered, the **Owner** and the **Engineer** agree that said **Agreement** is amended as follows:

- I. Sections of the Agreement, LOCATION MAP, EXHIBIT "A" – SERVICES TO BE PROVIDED BY THE OWNER, EXHIBIT "B" – SERVICES TO BE PROVIDED BY THE ENGINEER, EXHIBIT "C" – WORK SCHEDULE, EXHIBIT "D-1" – ESTIMATED PROJECT FEE SCHEDULE are revised to reflect the above listed modifications of this Supplemental.

All other provisions are unchanged and remain in full force and effect.

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the 28th day of October, 2014.

THE ENGINEER:
ENGINEER

BY: [Signature]
Jacinto Garza, P.E., President

THE OWNER:
HIDALGO COUNTY

BY: Ramon Garcia
Ramon Garcia, County Judge

LIST OF EXHIBITS:

LOCATION MAP

EXHIBIT A – "Services to be provided by County"

EXHIBIT B – "Services to be provided by Engineer"

EXHIBIT C – "Work Schedule"

EXHIBIT D-1 – "Estimated Project Fee Schedule (w/man-hour breakdown)"

Approved by Commissioners' Court
on 10/28/14 RJ




EXHIBIT "A"
Services to be provided by the County

1. The County will issue work authorization to initiate all required services and designate the authorized representative of the coordination of each work authorization.
2. The County will provide copies of all subdivision plats of record and/or in the subdivision process.
3. The County will provide the Engineer with on-going guidance, timely reviews, and decisions necessary to complete services required by the work authorization in order to permit the Engineer to maintain an agreed upon project schedule.
4. The County will provide a Purchase Order and process all acceptable requests for payment in a timely manner.
5. The Work Authorization will identify the Notice to Proceed date.

PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: _____

PROJECT/DESCRIPTION: Professional Engineering Services

LENGTH: 2.3 MILES

HIGHWAY: FM 1925 Project

LIMITS: from FM 907 (Alamo Rd) to Sharp Rd. to include
Sharp Rd. Realignment (from FM 1925 North 0.5 Miles)

EXISTING FACILITY

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☐ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

NOTES

NOTE:

**NO REVISIONS WERE MADE TO EXHIBIT "B" BEYOND THIS POINT.
PAGES 1-1, 3-1 THRU 14-2 REMAIN THE SAME IN WORK AUTHORIZATION NO. 1.**

EXHIBIT D-1
ESTIMATED PROJECT FEE SCHEDULE AND MAN-HOUR BREAKDOWN

FM 1925 (SEGMENT II) PROJECT
from FM 907 (Alamo Rd) to Sharp Rd including Sharp Rd Realignment (from FM 1925 N 0.5 mi.)

	MANHOURS														TOTAL HOURS	Sub-Contract Amounts / ROW COST	TOTAL LINE ITEM COST	ROUNDED TOTAL LINE ITEM COST
	Senior Project Manager	Senior Engineer	Senior Environmental Scientist /Specialist	Project Engineer	Design Engineer	ROW Administrator	EIT	Senior Engineer Tech	Environmental Scientist /Specialist	Engineer Tech	CADD Operator / GIS Analyst	Admin / Clerical	Biologist					
CONTRACT RATE	215.40	167.89	136.21	123.54	114.04	107.70	82.36	79.19	79.19	76.02	66.52	57.02	50.68					
WORK AUTHORIZATION NO. 1																		
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN																		
1 Environmental Assessment with TxDOT	60		250						200		245	100	201	1056		\$ 95,000.58	\$ 95,000.00	
2 Public Involvement for Environmental Assessment and 1 Public Meeting	30		35	39		10			28.25		41.25	17	38	238.5		\$ 25,000.66	\$ 25,000.00	
3 Archeological and Historical Research			2						0.5					2.5	\$ 29,692.00	\$ 312.02	\$ 312.00	
4 Engineering Technical Support at Public Meetings with Layouts, etc.	25		44	31		30					44.75	24	24	222.75		\$ 24,000.55	\$ 24,000.00	
5 Schematic for FM 1925	28	30		70	120		79	76.25		100	1496	15	13	2027.25		\$ 154,575.24	\$ 154,575.00	
6 Hydrological Map	14	24	8	65	32		37.75		16	81	163.75	8	6	455.5		\$ 42,000.66	\$ 42,000.00	
7 Schematic for intersecting streets (Sharp Rd)	9	8		8	8		8	9		10	479	10	5	554		\$ 40,000.83	\$ 40,000.00	
8 Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	10	10		30	49		30.25			20	49	7	4	209.25		\$ 21,000.19	\$ 21,000.00	
9 Preliminary Compensable Utility Management Identification on Schematic	10	18		16	19	9	18.25	20		26	34	5	2	177.25		\$ 18,000.25	\$ 18,000.00	
10 Update Schematic based on comments as provided by TxDOT/FHWA	24	24		36	60		44	17		60	101	29	12	407		\$ 39,000.33	\$ 39,000.00	
11 Engineering Technical Support at Public Hearing with Layouts, etc.	24	20	24	36		33	45		32	42	47	31	37	371		\$ 36,000.32	\$ 36,000.00	
12 Public Involvement for 1 Public Hearing	21	17	18	18		19	18.25		22	29	37	32	23	254.25		\$ 25,000.68	\$ 25,000.00	
SUB-TOTAL	255	151	381	349	288	101	280.5	122.25	298.75	368	2737.75	278	365	5975.25	\$ 29,692.00	\$ 519,892.30	\$ 519,887.00	

Subtotal Manhour Fee with Sub-Consultant Costs:	\$	549,584.30
* Total Project Fee:	\$	549,575.00

*Rounded Figure

SPECIAL MEETING - October 28, 2014

BE IT REMEMBERED, that on this 28th day of October A.D., 2014, there was begun and held a **SPECIAL MEETING** of the Honorable Commissioners' Court of Hidalgo County, Texas, wherein the following members thereof were present, to-wit:

HONORABLE RAMON GARCIA	HIDALGO COUNTY JUDGE
HONORABLE A.C. CUELLAR, JR.	COMMISSIONER, PRECINCT NO. 1
HONORABLE HECTOR "TITO" PALACIOS	COMMISSIONER, PRECINCT NO. 2
HONORABLE JOE M. FLORES	COMMISSIONER, PRECINCT NO. 3
HONORABLE JOSEPH PALACIOS	COMMISSIONER, PRECINCT NO. 4

and **ARTURO GUAJARDO, JR., COUNTY CLERK & EX-OFFICIO CLERK OF THE COMMISSIONERS' COURT** of Hidalgo County, Texas, wherein the following proceedings were had, to-wit:



AGENDA
CC REGULAR CONSENT
COMMISSIONERS' COURT
October 28, 2014
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a **SPECIAL MEETING** of the Commissioners' Court will be held at the Edinburg Council Chambers 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

NOTICE TO THE PUBLIC
CONSENT AGENDA

The following items are of a routine or administrative nature. The Commissioners' Court has been furnished with background and support on each item, and/or it has been discussed at a previous meeting. All items will be acted upon by one vote without being discussed separately unless requested by a Court Commissioner, in which event the item or items will immediately be withdrawn for individual consideration in its normal sequence after the items not requiring separate discussion have been acted upon. The remaining items will be adopted by one vote.

APPROVED

On motion by COMMISSIONER PCT. 1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval for the exception of Items 3.A, 4.E, 14.C, and 14.F to be pulled for discussion.

Vote: 5 - 0 - Unanimously

1. **AI-47186 Approval of check register and payment of claims and bills** - (Payments from Juvenile Probation, Adult Probation, LEOSE Fund, DA Motor Vehicle Theft Fund, DA Bad Check Processing Fund, DA Forfeiture Fund, Sheriff Forfeiture Funds, Constable Forfeiture Funds, HIDTA Forfeiture Funds and VIT Interest Fund are presented for recording purposes only.)
2. **2014 Intradepartmental transfers:**
 - A. **AI-47111** 2014 - County Court at Law # 2 (1100)
 - B. **AI-47160** 2014 - County Judge (1100)
 - C. **AI-47136** 2014 - District Attorney's Office / Autopsies (1100)
 - D. **AI-47137** 2014 - District Attorney's Office (1100)
 - E. **AI-47138** 2014 - District Attorney's Office (1100)
 - F. **AI-47139** 2014 - District Attorney's Office (1222)
 - G. **AI-47134** 2014 - District Attorney's Office / Grand Jury (1100)

- B. AI-46769** 1. Approval of reimbursement in the amount of \$843,242.96 to Blue Cross Blue Shield Insurance Company for claims paid on behalf of Hidalgo County from 09/27/14 to 10/10/14.

09/27-30/14	\$139,139.98
10/01-03/14	\$232,205.51
10/04-10/14	\$471,897.47
TOTAL	\$843,242.96

2. Approval of wire transfer to cover claims paid.

14.

Purchasing Dept:

Notes:

A. FOR ANY CONTRACTS(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FOWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

- A. AI-47161** Acceptance of proposal submitted by AAMECC, LLC awarded vendor thru County's participation with TIPS /TAPS Contract No. 1042513 for the services of Asbestos Abatement Consulting, including but not limited to preparation of specifications, project air monitoring and air monitoring for final clearance for the project: Facilities Management -Asbestos Abatement at County Clerk's Office in the amount of \$5,695.00. (Project# 2014-373-MSS)
- B. AI-47166** Acceptance and approval of Payment Application #1 for PO#701751 in the amount of \$15,377.47 and Pay Application #1 for PO#701752 in the amount of \$18,233.30 as submitted by Herrera & Hunt Inc. in connection with: "Bullet Proof Windows for Various JP's Offices in Precinct No. 1" as reviewed and approved by Facilities Management.
- C. AI-47172** Acceptance of proposal submitted by AL3 Enterprises, LLC dba Starr Telecom in the amount of \$95,562.00 for Turnkey Installation of Data Drops at the Old Administration Building 1st and 2nd floor thru County Contract No. E-13-321-10-22 (Req. #265971).

Mrs. Marty Salazar stated that they received a better proposal that has been attached to the backup of the Agenda reflecting an amount of \$91,242.00.

On motion by COMMISSIONER PCT.1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval.

Vote: 5 - 0 - Unanimously

P.

AI-47105

APPROVED

Acceptance and approval of Supplemental Agreement No. 1 to Professional Engineering Services Agreement #C-13-336-12-10 & Work Authorization No.1, (to revise project limits as requested by Tx DOT) and as submitted by L & G ENGINEERING in connection to the "professional engineering services" for ongoing project: (FM 1925) from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street) within Hidalgo County Precinct No. 4.

Q.

AI-46652

Acceptance and approval of request for Payment Application #1 and Modification #1 for a credit of -\$2,949.20 included for a total payment request amount of \$28,872.18 submitted by Herrera & Hunt Inc., in connection with the project: Hidalgo County Facilities Management - "Sewer Line repairs at the Health Department C.O.", project No. 2013-323-10-30-MSS and PO#701098 with authority for County Treasurer to issue payment after review, audit, and processing procedures are completed by County Auditor

R.

AI-47005

Requesting authority to advertise and approval of procurement packet (i.e., specifications/requirements, legal notice and draft requirement agreement etc.) as attached hereto for Hidalgo County-Construction Building Materials & Related Supplies -RFB No.: 2014-002-SMA" including the authority to re-advertise project in the event that no packets are received and/or are rejected and project is still required.

S.

AI-47119

Acceptance and approval of Substantial Completion and processing of Pay Application #1 in the amount of \$6,438.45 as submitted by Herrera & Hunt Inc. in connection with the Hidalgo County Facilities Management - "Storefront Doorway Installation at Health Department" (PO#708868) with authority for Hidalgo County Judge Ramon Garcia to sign Substantial Completion.

T.

AI-46994

Sheriff's Office:

Requesting approval & authority to enter into a 12-month commercial alarm monitoring services and execute the required commercial alarm monitoring agreement with Alan Yoder Enterprises, Inc. d/b/a Superior Alarms for the following department through the requisition 262910 effective upon approval.

U.

AI-46576

Acceptance and approval to exercise the County's option to extend the first (1st) year of two (2)-one(1) options under the same rates, terms and conditions for the "Tire Disposal Services" with Texas Land Reclamation.

V.

AI-47025

Add Fuel Card Users and Fuel Cards:
1. Sheriff Office - Fuel cards and Users

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

AGREEMENT FOR PROFESSIONAL SERVICES
C-13-336-12-10

THIS AGREEMENT is made, by and between **HIDALGO COUNTY**, acting herein by and through the **Commissioner's Court**, hereinafter called the "**Owner**", and **L & G Consulting Engineers Inc. d/b/a L & G Engineering**, Professional Engineers of **Mercedes, Texas**, hereinafter called the "**Engineer**".

WITNESSETH:

WHEREAS, the **Owner** desires to contract with the **Engineer** to provide professional engineering services required for the preparation of the **Environmental Assessment, Public Involvement, Schematic and Hydrologic Design** for the "**FM 1925 (from FM 907 (Alamo Road) East to East of SH68 (Uresti Street)**" project for **Hidalgo County Precinct No. 4** hereinafter referred to as the "**Project**".

NOW, THEREFORE, the **Owner** and the **Engineer** in consideration of the mutual covenants and agreements herein contained do mutually agree as follows:

ARTICLE 1. Employment of Engineer. The **Owner** agrees to employ the **Engineer** and the **Engineer** agrees to perform professional engineering services in connection with the **Project** as stated in the articles to follow and for having rendered such services, the owner agrees to pay the **Engineer** compensation as stated in the articles to follow.

ARTICLE 2. Character and Extent of Services. This Agreement will provide for the development of the **Project** with the following:

2.1 Scope of Work. The **Owner** will furnish items and provide those services for the development of the **Project** and fulfillment of this Agreement, as identified in **EXHIBIT "A"** *Services to be Provided by the Owner*, attached hereto and made a part of this Agreement as identified in **EXHIBIT "B"**- *Services to Provided by the Engineer*, attached hereto and made a part of this agreement.

2.2 Classification of Services For this Agreement, the professional services to be provided by the **Engineer**, as more particularly identified in **EXHIBIT "B"**, attached hereto.

2.3 Schedule of Work. The **Engineer** shall prepare a schedule of work (hereinafter referred to as "**Work Schedule**") in accordance with the terms identified in **EXHIBIT "C" - Work Schedule**, attached hereto and made a part of this Agreement.

ARTICLE 3. Period of Service. Upon execution of this Agreement, the **Engineer** shall proceed with the work outlined under Article 2 hereof.

3.1 Termination Date. This Agreement will be for a period of **one (1) year**, commencing, **December 10, 2013**, expiring, **December 9, 2014** (hereinafter referred to as the "**Termination Date**"), unless extended by written supplemental agreement, as provided in Article 8 hereof, duly executed by the **Engineer** and the **Owner** prior to the **Termination Date**, or otherwise terminated as provided in Article 3.4 herein and below. The **Owner** assumes no liability or obligation for payment to the **Engineer** for work performed or costs incurred by the **Engineer** prior to the date authorized by the **Owner** for the **Engineer** to begin work, during periods when work is suspended, or subsequent to the **Termination Date**.

3.2 Extension of the Termination Date. The **Engineer** shall notify the **Owner** in writing as soon as possible if it is determined, or reasonably anticipated, that the work under this Agreement cannot be completed before the **Termination Date**, and the **Owner** may , at the **Owner's** sole discretion, extend the **Termination Date** by written supplemental agreement as

provided in Article 8 hereof. The **Engineer** shall allow adequate time for review and approval by the **Owner** of the written notice and request by the **Engineer** to extend the **Termination Date**.

3.3 Suspension of Work. Should the **Owner** desire to suspend the work under this Agreement, but not terminate this Agreement, the **Owner** shall provide thirty (30) calendar days verbal notification to the **Engineer**, followed by written confirmation from the **Owner** to the **Engineer** to that effect. The thirty-day notice may be waived as agreed in writing by both the **Owner** and the **Engineer**. The work under this Agreement may be reinstated and resumed in full force and effect within sixty (60) days of receipt of written notice from the **Owner** to the **Engineer**. The sixty-day notice may be waived as agreed in writing by both the **Owner** and the **Engineer**.

If the **Owner** suspends the work, the **Termination Date** as identified above is not affected, and this Agreement will terminate on the date specified, unless extended by written supplemental agreement, as provided in Article 8 hereof, duly executed by the **Engineer** and the **Owner** prior to the **Termination Date**.

3.4 Termination of Agreement. This Agreement may be terminated before the stated **Termination Date** identified in Article 3.1 herein by any of the following conditions:

- (1) **Commitment of Current Revenues.** In the event that, during any term hereof, the **Owner** does not appropriate sufficient funds to meet to the obligations of this Agreement, the **Owner** may terminate this Agreement upon thirty (30) days written notice to the **Engineer**. The **Owner** agrees, however, to use reasonable efforts to secure funds necessary for the continued performance of this Agreement. The parties intend this provision to be a continuing right to terminate this Agreement at the expiration of each budget period of the **Owner** pursuant to the provisions of Tex. Loc. Govt. Code Ann. §271.903 (Vernon Supp. 1995).
- (2) By mutual agreement and consent, in writing, of both the **Engineer** and the **Owner**.
- (3) By the **Owner**, upon failure of the **Engineer** to fulfill the **Engineer's** obligations set forth herein in a satisfactory manner as determined by the

Owner and in sole opinion of the **Owner**, after the **Owner** provides written notice to the **Engineer** of such failure and the **Engineer** has not corrected such failure within (30) days of such written notice by the **Owner**.

- (4) By the **Engineer**, upon failure of the **Owner** to fulfill the **Owner's** obligations set forth herein, after the **Engineer** provides written notice to the **Owner** of such failure and the **Owner** has not corrected such failure within thirty (30) days of such written notice by the **Engineer**.
- (5) By the **Owner** without cause upon thirty (30) days written notice to the **Engineer**.
- (6) By satisfactory completion of all services and obligations described herein.

Should the **Owner** terminate this Agreement as herein provided, no fees other than fees due and payable at the time of termination shall thereafter be paid to the **Engineer** notwithstanding anything herein to the contrary. In determining the value of the work performed by the **Engineer** prior to termination, the **Owner** shall be the sole judge of the value of such work performed. Compensation for work at termination will be based on a percentage of the work completed at that time. Should the **Owner** terminate this Agreement under (5) of the paragraph above, the amount charged during the thirty (30) day notice period shall not exceed the amount charged during the preceding ninety (90) days.

If the termination of this Agreement is due to the failure of the **Engineer** to fulfill the **Engineer's** obligations under this Agreement, the **Owner** may take over the Project and prosecute the work to completion. In such case, the **Engineer** shall be liable to the **Owner** for any additional cost occasioned by the **Owner**.

If the **Engineer** defaults in the performance of this Agreement or if the **Owner** terminates this Agreement for fault on the part of the **Engineer**, the **Owner** will give consideration to payment of an amount in settlement to include: the actual costs incurred by the **Engineer** in performing the work to the date of default, the amount of work required which was satisfactorily completed to

date of default, the value of the work which is usable to the **Owner**, the cost to the **Owner** of employing another consultant and/or firm to complete the work required and the time required to do so, and other factors which affect the value to the **Owner** of the work performed at the time of default. This Agreement shall not be considered as specifying the exclusive remedy for any default by the **Engineer**, but all remedies existing at law and in equity may be availed of by either party and shall be cumulative.

The termination of the Agreement and payment of an amount in settlement as prescribed above shall extinguish all rights, duties, and obligations of the **Owner** and the **Engineer** under this Agreement, except the obligations set forth in Articles 11.2, 12, 13, 15, 16, 17, 18.3, 19, 22 and 26 hereto.

ARTICLE 4. Progress and Coordination. The **Engineer** shall, from time to time during the progress of the work, confer with the **Owner**. The **Engineer** shall prepare and present such information as may be pertinent and necessary, or as may be requested by the **Owner**, in order to evaluate features of the **Engineer's** services and work.

At the request of the **Owner** or the **Engineer**, conferences shall be provided at the **Engineer's** office, the office of the **Owner**, or at other locations designated by the **Owner**. These conferences shall also include evaluation of the **Engineer's** services and work when requested by the **Owner**.

All applicable study reports shall be submitted in preliminary form for approval by the **Owner** before the final report is issued. The **Owner's** comments regarding the **Engineer's** preliminary report will be addressed by the **Engineer** in the final report.

If funds by other agencies or entities are to be used for the development of the project under this Agreement, the **Engineer's** services and work will be subject to periodic review and

approval by other agencies or entities, including those of the city, county, state and/or federal agencies.

Should it be determined that the progress in the production of the **Engineer's** services and work does not satisfy the requirements of the approved **Work Schedule** as provided by **Exhibit "C"**, attached hereto, the **Owner** shall review the approved **Work Schedule** with the **Engineer** to determine the corrective action needed by either the **Owner** or the **Engineer**.

The **Engineer** shall promptly advise the **Owner** in writing of events which have a significant impact upon the progress of the **Engineer's** services and work and the approved **Work Schedule**, including:

- (1) problems, delays, adverse conditions which will materially affect the ability to attain contract objectives, prevent the meeting of time schedules and goals, or preclude the timely completion and submittal of **Project** deliverables by the **Engineer** within established time periods; this disclosure will be accompanied by a statement by the **Engineer** of recommended or immediate action taken, or contemplated, and any **Owner** or other agency or entity assistance needed to resolve the situation: and
- (2) favorable developments or events which enable meeting the **Work Schedule** goals sooner than anticipated.

ARTICLE 5. Compensation and Fees. For and in consideration of the services to be rendered by the Engineer, the Owner shall compensate the Engineer as follows:

5.1 Basic Services. For and in consideration of the **Services** to be rendered by the **Engineer**, as identified in Article 2 and more particularly identified in **EXHIBIT "B"**, attached hereto, the maximum amount payable by the **Owner** to the **Engineer** for **Services**, subject to adjustment in accordance with Article 6.1 herein, will be provided in each work authorization issued. An outline and breakdown of the **Services Fee** is more particularly identified in **EXHIBIT "D1"-Fee Schedule**, attached hereto and made a part of this Agreement. Payments to the

Engineer for **Services** shall be made by the **Owner**, upon presentation by the **Engineer** of the monthly **Request for Payment**, in accordance with the terms and provisions of Article 6 herein.

5.2 Special Services. Those services that may be required to provided by the **Engineer** as **Special Services** are set forth below and more particularly described in **EXHIBIT "B"**, attached hereto. For and in consideration of these **Special Services** rendered as required by the **Engineer**, the **Owner** shall pay the **Engineer** a negotiated lump sum fee (hereafter referred to as "**Special Services Fee**") at the hourly labor rates and non-labor rates (hereinafter referred to as "**Contract Rates**") specified in **EXHIBIT "D" - Contract Rates**, attached hereto and made a part of this Agreement, and as follows:

1. **RESIDENT OR SITE ENGINEER, INSPECTOR** Actual performance of services of project site engineer, resident engineer and/or inspector, if required by **Owner**.
2. **DOCUMENT COPIES** Actual performance and/or providing of additional copies (over 10) of report; additional copies (over 10) of plans (contract drawings), specifications and estimates (PS&E); additional copies (over 10) of bidding documents: additional copies (over 10) of as-built drawings.
3. **EXTRA TRAVEL** Extra travel required of **Engineer** and authorized by **Owner** to points outside of Hidalgo County.
4. **EXPERT WITNESS** Assistance to the **Owner** as expert witness in any litigation with third parties, arising from the development or construction of the **Project**.
5. **MISCELLANEOUS.** Investigations involving detailed consideration of operation, maintenance and overhead expenses and (unless otherwise agreed) the preparation of rate schedules, earning and expense statements; preparation of feasibility studies; environmental document preparation; appraisals, valuations, and material audits; or inventories required for certification of force account construction performed by the **Owner**; preparation of change orders for extra work done by the **Contractor**.

ARTICLE 6. Method of Payment.

6.1 Request for Payment. Payments to the **Engineer** for services rendered will be made while work is in progress as executed through a lump sum fee assigned to each work authorization (hereinafter referred to as "**Work Authorization**") in accordance with **Article 7** herein. For each **Work Authorization**, the **Engineer** shall prepare and submit to the **Owner**

monthly progress reports in sufficient detail to support the progress of the work and in support of a request for payment (hereinafter referred to as "**Request for Payment**"). The progress report shall indicate the percent completion of the work accomplished by the **Engineer** during the billing period and to the date of the **Request for Payment**. On or before noon of the first Monday of each month during the performance of the services, the **Engineer** shall submit to the **Owner** for approval a **Request for Payment**. Payment of the lump sum fee for each **Work Authorization** identified in the **Request for Payment** will be in proportion to the percent completion of the work tasks identified in such **Work Authorizations** together with a detailed breakdown of the amount and the sum of all prior payments. The **Owner** shall review each such **Request for Payment** and may make such exceptions as the **Owner** reasonably deems necessary or appropriate under the circumstances then existing. About ten (10) working days after the Commissioners Court of the **Owner** meets approving such payment, the **Owner** shall make payment to the **Engineer** in the amount approved as aforesaid subject to Article 6.4 herein and below.

If the **Project**, or any portion(s) thereof, are deleted or otherwise not constructed, compensation to the **Engineer** by the **Owner** for the **Project** or such portions of the project shall be only the amounts paid the **Engineer** for actual work performed in accordance with the **Work Authorization(s)** approved by the **Owner**.

6.2 Final Payment. After final completion of the work and acceptance thereof by the **Owner**, the **Engineer** shall submit a final request for payment ("**Final Request for Payment**") which shall set forth all amounts due and remaining unpaid to the **Engineer** and upon approval thereof by the **Owner**, the **Owner** shall pay to the **Engineer** the amount due ("**Final Payment**") under such **Final Request for Payment** in accordance with the provisions of Article 6.1 hereof. The **Final Payment** shall not be made until the **Engineer** delivers to the **Owner** an affidavit that

so far as the **Engineer** has knowledge or information any and all amounts due for materials and services over which the **Engineer** has control have been paid.

6.3 Qualification on Obligations to Pay. Any provision hereof to the contrary notwithstanding, the **Owner** shall not be obligated to make any payment (whether a payment under Article 6.1 hereof or **Final Payment**) to the **Engineer** hereunder if any one or more of the following conditions precedent exist:

- (1) The **Engineer** is in default of any of its obligations hereunder or otherwise is in default under this Agreement or under any contract documents related to this Agreement;
- (2) Any part of such payment is attributable to the **Engineer's** services which are not performed in accordance with this Agreement; provided, however, such payment shall be made as to the part thereof attributable to the **Engineer's** services which were performed in accordance with this Agreement.
- (3) The **Engineer** has failed to make payments promptly to consultants or other third parties used in connection with the **Project** for which the **Owner** has made payment to the **Engineer**;
- (4) If the **Owner**, in good faith judgement, determines that the portion of the compensation then remaining unpaid will not be sufficient to complete the **Engineer's** services in accordance with this Agreement, no additional payments will be due the **Engineer** hereunder unless and until the **Engineer**, at its sole cost, performs a sufficient portion of the **Engineer's** services so that such portion of the compensation then remaining unpaid is determined by the **Owner** to be sufficient to so complete the **Engineer's** services.

6.4 No partial payment made hereunder shall be or construed to be final acceptance or approval of that part of the **Engineer's** services to which such partial payment related or relieves the **Engineer** of any of its obligations hereunder with respect thereto.

6.5 The **Engineer** shall promptly pay all bills for labor and material performed and furnished by others in connection with the performance of the **Engineer's** services.

6.6 Waiver. The making of the **Final Payment** shall constitute a waiver of all claims by the **Owner** except those arising from (1) faulty or defective services of the **Engineer** appearing

after completion of the **Project**. (2) failure of the **Engineer's** services to comply with the requirements of this Agreement or any contracts or Agreements related to the **Project**, or (3) terms of any special warranties required by this Agreement or provided at law or in equity. The acceptance of **Final Payment** shall constitute a waiver of all claims by the **Engineer** except those previously made in writing and identified by the **Engineer** as unsettled at the time of the **Final Request for Payment**.

ARTICLE 7. Work Authorization. After execution of this Agreement, the **Engineer** shall proceed with the work outlined under Article 2 hereof, only as authorized by the **Owner** through an agreed **Work Authorization** document in the form identified in **EXHIBIT "E"- Work Authorization Form**, attached hereto and made a part of this Agreement. The **Engineer** will identify, as approved by the **Owner**, the needed services for the **Project**, as required through the course of the development to the **Project**. The **Owner** shall authorize the **Engineer** to perform one or more of the agreed tasks identified in **EXHIBIT "B"**, attached hereto, in the form of individual work authorizations. Upon authorization from the **Owner**, the **Engineer** will prepare a **Work Authorization** document, which will include a description of the work to be performed, including a description of the tasks and milestones, a work schedule, and an estimated cost proposal agreed upon by the **Owner** and the **Engineer**. The estimated cost proposal shall set forth in detail the computation of the cost of each work task, at the hourly rates established and identified in **EXHIBIT "D"**, attached hereto. The **Work Authorizations** shall not waive the **Owner's** and the **Engineer's** responsibilities and obligations established in this Agreement.

The estimated cost proposal for each **Work Authorization**, developed by the **Engineer** and approved by the **Owner** shall be used by the **Owner** to appropriate a purchase order for the **Work Authorization**. Each executed **Work Authorization** shall become a part of this **Agreement**. Upon satisfactory completion of the **Work Authorization**, the **Engineer** shall submit

the **Project's** deliverables as specified in the executed **Work Authorization** to the **Owner** for review and acceptance.

Work included in a **Work Authorization** shall not begin until the **Owner** and the **Engineer** have signed the **Work Authorization**. All work must be completed on or before the completion date specified in the **Work Authorization**, unless extended by written agreement by the **Engineer** and the **Owner**. The **Engineer** shall promptly notify the **Owner** of any event that will affect completion of the **Work Authorization**. All **Work Authorizations** must be executed and completed by both the **Engineer** and the **Owner** within the period established for this Agreement as specified in Article 3 hereof.

The final acceptance by the **Owner** of each **Work Authorization** for the **Project** shall serve as evidence of completion, on the part of the **Engineer**, of all services under this Agreement insofar as they pertain to that portion of work on the **Project** identified in the applicable work authorization.

ARTICLE 8. Supplemental Agreements. The terms of this Agreement may be amended by supplemental agreement if the Owner determines that (1) there is a need to extend the **Termination Date** identified in Article 3.1 hereof, (2) there has been a significant change in the scope, complexity or character of the services to be performed by the **Engineer**, and/or (3) for any other reason agreeable to the **Owner** and the Engineer. All supplemental agreements will be developed in the form identified in **EXHIBIT "F" - Supplemental Agreement Form**, attached hereto and made a part of this Agreement, and incorporated herein by reference as "**Supplemental Agreement**".

If determined appropriate by the **Owner**, additional compensation to the **Engineer** for (1), (2) and/or (3) above shall be paid as a negotiated lump sum fee at the **Contract Rates** specified

in **EXHIBIT "D"**, attached hereto. The negotiated lump sum fee shall be incorporated into the **Supplemental Agreement**.

Any **Supplemental Agreement** must be executed by both the **Engineer** and the **Owner** prior to the **Termination Date** specified in Article 3 hereof.

It is distinctly understood and agreed that no claim by the **Engineer** for additional work, as identified in Article 9 hereof, or changes or revisions in work, as identified in Article 10 hereof, shall be made by the **Engineer** until full execution of the **Supplemental Agreement** and authorization to proceed is granted by the **Owner**. The **Owner** reserves the right to withhold payment to the **Engineer** pending verification of satisfactory work performed by the **Engineer**.

ARTICLE 9. Additional Work. If the **Engineer** is of the opinion that any work it has been directed to perform is beyond the scope of this Agreement and constitutes extra work, the **Engineer** shall promptly notify the **Owner** in writing. In the event the **Owner** finds that such work does constitute extra work, the **Owner** shall so advise the **Engineer** and a written supplemental agreement will be executed between the **Owner** and the **Engineer** as provided herein. The **Engineer** shall not perform any proposed additional work or incur any additional cost prior to the execution by both the **Engineer** and the **Owner** of a supplemental agreement. Additional compensation from the **Owner** to the **Engineer** shall be paid as a negotiated lump sum fee at the Contract Rates specified in **EXHIBIT "D"** attached hereto. The negotiated lump sum fee shall be incorporated into the supplemental agreement as specified in Article 8 hereof. The **Owner** shall not be liable or under any obligation to compensate the **Engineer** for work performed or costs incurred by the **Engineer** relating to additional work not directly associated with the performance of the work authorized in this Agreement or as amended through supplemental agreement.

ARTICLE 10. Changes or Revisions in Work. If the **Owner** finds it necessary to request changes to the work, and the changes are within the applications of sound engineering principles, the **Engineer** shall make such revisions if requested and directed by the **Owner**.

10.1 Preliminary Work. The **Engineer** will make, without expense to the **Owner**, such revisions of any preliminary reports or drawings as may be required to meet the needs of the **Owner** and the applications of sound engineering principles.

10.2 Previously Approved or Satisfactorily Completed Work. If the **Owner** funds it necessary to request the **Engineer** to make changes to work previously approved by the **Owner** or work satisfactorily completed for which the **Owner** approves or, after a definite plan has been approved by the **Owner**, if a decision is subsequently made by the **Owner**, which for proper execution involves extra services and expenses for changes in or additions to the drawings specifications or other documents, this will be considered as additional work, and compensation from the **Owner** to the Engineer will be in accordance with Article 9 hereof.

10.3 Project Delays. If the **Engineer** is required to perform additional work due to delays by the imposition of causes not within the **Engineer's** control, such as by the re-advertisement of bids or by the delinquency or insolvency of contractors, such work associated with these delays shall be considered additional work, and the **Engineer** shall be compensated by the **Owner** for such extra services and expense in accordance with Article 9 hereof.

10.4 Reduction of Project Cost. Notwithstanding any provision herein to the contrary, in the event it is necessary for the **Owner** to require changes in the final plan of the **Project** to enable it to reduce the construction cost of the **Project** to an amount within the sum estimated by the **Engineer**, the **Engineer** will be required to make such revisions or changes. These changes will only be considered additional work by the **Engineer**, if the **Engineer** previously provided these same changes as options to the **Owner** at the stage of preliminary work or prior to

the approval of the final plan for the Project, and the option or options were not selected or approved by the **Owner** to be incorporated into the final plan of the Project. Payment for this additional work will then be made to the **Engineer** in accordance with Article 9 hereof. If the **Engineer** failed to provide these changes as an option or options to the **Owner** at the stage of preliminary work or prior to the approval of the final plan of the **Project**, these changes will not be considered additional work and no additional compensation will be made to the **Engineer**.

ARTICLE 11. Ownership and Release of Documents.

11.1 Ownership of Documents. Original drawings and specifications are the property of the **Engineer** however the **Project** is the property of the **Owner**, and the **Engineer** may not use the drawings and specifications thereof for any purpose not relating to the **Project** with the **Owner's** consent. The **Owner** shall be furnished with such reproductions of drawings and specifications as the **Owner** may reasonably require. Upon completion of the work or any earlier termination of this Agreement under Article 3.4 hereof, the **Engineer** will revise drawings to reflect changes made during construction and will promptly furnish the **Owner** with one complete set of reproducible record prints. Prints shall be furnished by the **Engineer**, as an additional service, at any other time requested by **Owner**. All such reproductions shall be the property of the **Owner** who may use them without the **Engineer's** permission for any proper purpose relating to the **Project**, including but not limited to additions to or completion of the **Project**. Any additions or revisions by the **Owner** to a drawing signed, sealed, and dated by a registered professional engineer, shall be made in accordance with the Texas Engineering practice Act and the Rules of the State Board of Registration for Professional Engineers.

All documents furnished to the **Engineer** by the **Owner** shall be delivered to the **Owner** upon completion or termination of this Agreement. The **Engineer**, at the **Engineer's** own expense, may retain copies of such documents or any other data under this Agreement.

11.2 Release of Documents or Information. Release of information to the public or others regarding the **Project** will be accordance with the Texas Public Information Act.

ARTICLE 12 Discounts, Rebates, Refunds. In connection with procurement services rendered by the **Engineer**, if procurement services are required of the **Engineer** hereunder, all discounts, rebates and refunds shall accrue to the **Owner**. For some purchases, the **Engineer** may deem that payment within the discount period is not safe; and/or inspection, guarantees, or other considerations may dictate delay. In such cases, the **Engineer** shall promptly notify the **Owner** so that a course of action may be mutually agreed upon by the **Owner** and the **Engineer**.

ARTICLE 13. Records, Accounting, Inspection. The **Engineer** shall keep full and detailed records and accounts in a manner approved by the **Owner**. The **Engineer** shall afford the **Owner's** authorized personnel and independent auditors, if any, full access to the work performed by the **Engineer** regarding the **Project** and to all of the **Engineer's** books, records, correspondence, instructions, drawings, receipts, vouchers and other documents relating to such work under this Agreement and the **Engineer** shall preserve all such records for three (3) years after final payment. The **Engineer** shall deliver to the **Owner** upon completion of such work, a statement of the cost of such work detailed according to the accounting procedure and requirements of the **Owner**.

ARTICLE 14. Subcontracting and Assignment. The **Engineer** shall not assign, subcontract or transfer the **Engineer's** interest in this Agreement without the prior written consent of the **Owner**. The **Engineer** shall bind every subconsultant by written subcontract to observe all the terms of this Agreement to the extent that they may be applicable to each subconsultant. No subcontract relieves the **Engineer** of any responsibilities under this Agreement.

The **Engineer**, and the **Owner**, do hereby bind themselves, their successors, executors, administrators and assigns to each other party of this Agreement and to the successors,

executors, administrators, and assigns of such other party in respect to all covenants of this contract.

ARTICLE 15. Patents. The **Engineer** shall indemnify and save the **Owner** harmless from all liability for alleged or actual infringement of any patent resulting from the use of apparatus or equipment furnished or designed by the **Engineer** or from the use of any process designed by the **Engineer** or effected by said apparatus or equipment, and the **Engineer** shall indemnify and save the **Owner** harmless from and against all costs, legal fees, expenses and liabilities incurred in or about any claim of or action for such infringement: provided, however, that the **Owner** shall promptly transmit to the **Engineer** all papers served on the **Owner** in any suit involving such claim of infringement, and provided further, that the **Owner** permits the **Engineer** to have entire charge and control of the defense of any such suit. If because of actual infringement the use of such apparatus, equipment, or process is enjoined, the **Engineer** shall refund the purchase price thereof in proportion to the length of service uncompleted, the life of such apparatus or equipment being assumed as five years. The **Engineer** hereby grants to the **Owner** a non-exclusive, royalty-free license under patents now or hereafter owned by the **Engineer** covering any machines, apparatus, processes, articles, or products included in the **Engineer's** work hereunder.

ARTICLE 16. Confidential Information, Inventions and Other Restrictions.

16.1 Confidential Information. The **Engineer** shall not use in any way, commercial or otherwise, except to the extent required by the proper performance of this Agreement; and shall hold in confidence and not disclose to any person, for any reason or at any time, any information relating to the secret processes, products, compositions, machinery, apparatus or trade secrets of the **Owner**, or any other confidential information given to the **Engineer** by any of the **Owner's** commissioners, elected officials, employees, or representatives or acquired by the **Engineer** during the term of or as a result of this Agreement. Any information not generally available to the

public shall be considered secret and confidential for the foregoing purposes; provided, however, that any technical information which was lawfully in the **Engineer's** possession prior to such disclosure to the **Engineer** by the **Owner** or which is or shall lawfully be published or become part of general knowledge from sources other than the **Engineer** or which otherwise shall lawfully become available to the **Engineer** from a source other than the **Owner**, shall not be subject to these provisions. All the foregoing stipulations shall apply to such information and work hereunder as well as to any information and ideas originated or developed by the **Engineer** in performing such work. Such information may, of course, be disclosed to the proper officials or employees of the **Owner** if necessary to perform the work hereunder. The **Engineer** shall, however, inform each of its employees who receive such information of these restrictions and the **Engineer** shall take all reasonable precautions and exert all reasonable efforts to assure conformance with such restrictions by all of its officers, employees, and agents, obtaining from them if necessary, agreements satisfactory to the **Owner**, effectuating the purposes of this Article.

16.2 Inventions. The **Engineer** shall communicate to the **Owner** at once, and require the **Engineer's** employees assigned to this **Project** to communicate to the **Owner** all inventions and improvements which any of the **Engineer's** employees, either alone or in conjunction with any of the **Owner's** employees may conceive, make or discover during the course of or as a result of work on this **Project** under this or any ensuing agreement with the **Owner** that relates to the processes, products, compositions, machinery or plants of the **Owner**, or relating in any way to any of the operations in which the **Owner** may be obligated to pay to the **Engineer** as compensation for services rendered by the **Engineer** under contract with the **Owner**. The **Engineer** shall require its employees to execute patent applications and assignments thereof to the **Owner** or its nominees, and powers of attorney relating thereto for any country the **Owner** may designate, and shall take all other actions as the **Owner** may request to maintain and protect such

inventions and improvements. The **Owner** shall pay all costs or charges incurred in protecting such inventions and improvements if the **Owner** desires to protect them. Before assigning any of the **Engineer's** employees to work under any contract with the **Owner** concerning this **Project**, the **Engineer** shall obtain from them agreements satisfactory to **Owner** complying in all respects with the terms and provisions of this Article.

16.3 The rights and obligations set forth in Article 16 shall survive the performance of this Agreement, or any termination, discharge or cancellation thereof

ARTICLE 17. Engineer's Seal, Responsibility and Warranties.

17.1 Engineer's Seal. The **Engineer** shall assign a responsible engineer or engineers licensed to practice in the State of Texas, who shall sign, seal and date all appropriate engineering submissions to the **Owner** in accordance with the Texas Engineering Practice Act and the Rules of the State Board of Registration for Professional Engineers.

17.2 Engineer's Responsibility. The **Engineer** shall be responsible for the accuracy of the work for the **Project** and shall promptly make necessary revisions or corrections resulting from errors, omissions, or negligent acts by the **Engineer**. No additional compensation will be made to the **Engineer** for any necessary revisions or corrections resulting from errors, omissions, or negligent acts by the **Engineer**.

The **Engineer's** responsibility for all questions arising from design errors and/or omissions will be determined by the **Owner** or a designee appointed by the **Owner**. The **Engineer** will not be relieved of the responsibility for subsequent correction of any such errors or omissions or for clarification of any ambiguities until after the construction phase of the **Project** has been completed.

17.3 Warranties.

(a) The **Engineer** warrants that engineering design work performed by the **Engineer** hereunder shall be in accordance with sound engineering design practices and in conformance with applicable code and standards established for such work.

(b) Notwithstanding anything to the contrary contained in this Agreement, the **Owner** and the **Engineer** agree and acknowledge that the **Owner** is entering into this Agreement in reliance on the **Engineer's** experience and abilities with respect to performing the **Engineer's** services hereunder. The **Engineer** accepts the relationship of trust and confidence established between it and the **Owner** by this Agreement. The **Engineer** covenants with the **Owner** to use the **Engineer's** best efforts, skill, judgement and abilities to design the **Project** and to further the interests of the **Owner** in accordance with the **Owner's** requirements and procedures, in accordance with all professional standards, and in compliance with all applicable national, federal, state, county and municipal laws, regulations, codes, ordinances, orders and with those of any other body having jurisdiction. If the development of plans, specifications and estimates (hereinafter referred to as "**PS&E**") are identified in this Agreement under Article 2 hereof or **EXHIBIT "B"**, attached hereto, as part of the services to be provided by the **Engineer** for the **Project**, prior to the commencement of construction, the **Engineer** shall certify in writing to the **Owner** that the **PS&E** for the **Project**, and the improvements when built in accordance therewith, conform to all applicable governmental regulations, statutes and ordinances then in effect. The **Engineer** represents covenants and agrees that there are no obligations, commitments or impediments of any kind that will limit or prevent performance of the **Engineer's** services.

(c) The **Engineer** represents, covenants and agrees that all of **Engineer's** services to be furnished by the **Engineer** under or pursuant to this Agreement from the inception of the Agreement until the **Project** has been fully completed, shall be of the standard and quality which prevail among engineers of similar experience, knowledge, skill and ability engaged in engineering

practice throughout Texas under the same or similar circumstances involving the design and construction of **Project**.

(d) The **Engineer** represents, covenants and agrees that the **Engineer's** special talent, training and experience cause the **Engineer** to be the prime professional on the **Project**; that because of such talent and training, the **Engineer** envisions the construction of the **Project** in its entirety and possesses the special skills which enable the **Engineer** to recognize dangerous conditions that a reasonable, prudent engineer having such special skills could anticipate may arise from the proper use of the **Project** after acceptance by **Owner**; and that the **Engineer** recognizes that any commissioners, elected officials, employees and agents of the **Owner**, plus residents and owners of property within the area affected by the **Project** are within a class of foreseeable persons who will be relying on the project being designed in a professional and safe manner.

(e) If the development of **PS&E** is identified in this Agreement under Article 2 hereof or **EXHIBIT "B"**, attached hereto, as part of the services to be provided by the **Engineer** for the **Project**, the **Engineer** represents, covenants and agrees that the **PS&E** of the **Project** will be accurate and free from any material errors. The **Engineer** additionally represents, covenants and agrees to the following: that the design of the **Project** will conform to its foreseeable use as a **Project** with all the amenities as set forth in any **PS&E** developed by the **Engineer** for the **Project**; that the result of such **PS&E**, if built in accordance therewith, will be suitable for purposes for which the **Project** is designed; and the **Project** will be inspected in a workmanlike, professional manner and will be suitable for the **Project's** intended purpose. The **Engineer's** responsibilities as set forth herein shall at no time be in any way diminished by reason of any approval by the **Owner** of any **PS&E** developed by the **Engineer** for the **Project**, nor shall the **Engineer** be released from

any liability by reason of such approval by the **Owner**, it being understood that the **Owner** at all times is ultimately relying upon the **Engineer's** skill and knowledge in preparing such **PS&E**.

(f) In connection with the **Engineer's** performance of procurement services hereunder, if any, the **Engineer** use its best efforts to obtain from all vendors of equipment and materials, fullest possible warranties against defective materials and workmanship for the benefit of the **Owner**.

ARTICLE 18. Engineer's Resources. The **Engineer** shall furnish and maintain, at the **Engineer's** own expense, office space for the performance of all services, skilled and sufficient personnel, as well as adequate and sufficient equipment to perform the services as required under this Agreement.

18.1 Project Manager. The **Engineer** shall provide a manager (**Project Manager**) for the **Project** that is a registered professional engineer in the State of Texas. The **Project** manager shall have such knowledge and experience as will enable that **Project Manager** during the course of the **Project** without prior consent of the **Owner**. If, due to situations beyond the control of the **Engineer**, the **Engineer** must change the **Project Manager** prior to the completion and acceptance of the **Project**, the **Engineer** will submit a request to change the **Project Manager** to the **Owner** for approval.

18.2 Employees of the Engineer. All employees of the **Engineer** shall have such knowledge and experience as will enable them to perform the duties assigned to them and required for the services under this Agreement. Any employee of the **Engineer** who, in the opinion of the **Owner**, is incompetent, or whose conduct becomes detrimental to the work required under this Agreement, shall immediately be removed from association with the **Project** when so instructed by the **Owner**. The **Engineer** certifies that the **Engineer** presently has employed

sufficient and qualified personnel, and will maintain sufficient and qualified personnel for performance of the services under this Agreement.

18.3 Documents/Information Exchange The purpose of this Article is to define the required automated resources, format for graphics files, and information exchange pertaining to the **Project**. Taking into consideration that the **Owner** has a significant investment in the development of the **Project**, there is a need for the **Engineer** to provide consistency in document development for information exchange. Consistency in document development for information exchange and production will help facilitate an economically efficient **Project**. Therefore, the **Engineer** shall provide the **Owner** with documents and information in accordance with the special requirement outlined in **EXHIBIT "B"** attached hereto.

ARTICLE 19. Indemnification. To the fullest extent permitted by applicable law, the **Engineer** and its agents, partners, subcontractors, and consultants (collectively "**Indemnitors**") shall and do agree to indemnify, and hold harmless the **Owner**, the **Owner's** respective directors, elected officials, employees and agents (collectively "**Indemnitees**") from and against all claims, damages, losses, liens, causes of action, suits, judgments and expenses, including attorney fees, of any nature, kind or description (collectively "**Liabilities**") of any person or entity whomsoever arising out of, caused by or resulting from the negligent performance of the **Engineer's** services through activities of the **Engineer**, its agents, partners, subcontractors and/or consultants performed under this Agreement, and which are caused by or result from error, omission, or negligent act of the **Engineer** or of any person employed or contracted by the **Engineer** provided that any such **Liabilities** (1) are attributable to bodily injury, personal injury, sickness, disease or death of any person, or to the injury to or destruction of tangible personal property including the loss of use and consequential damages resulting there from and (2) are caused in whole or in part by any negligent act or omission of the **Engineer**, anyone directly or indirectly employed by the

Engineer or anyone for whose acts the **Engineer** may be legally liable. The **Engineer** shall also save harmless the **Owner** from any and all expense, including but not limited to, attorney fees which may be incurred by the **Owner** in litigation or otherwise resisting said claim or liabilities which may be imposed on the **Owner** as a result of such activities by the **Engineer**, its agents partners, subcontractors and/or consultants. In this connection, it is agreed and understood that the **Engineer** shall not be responsible for any portion of the liability proximately caused by the **Owner's** negligence.

ARTICLE 20. Joint and Several Liability. In the event more than one of the **Indemnitors** are connected with an accident or occurrence covered by the indemnification in Article 19 hereof, then each of such **Indemnitors** shall be jointly and severally responsible to the **Indemnitees** for indemnification and the ultimate responsibility among such **Indemnitors** for the loss and expense of any such indemnification shall be settled by separate proceedings and without jeopardy to any **Indemnitee**. The provisions of this Article shall not be construed to eliminate or reduce any other indemnification or right which the **Owner** or any of the **Indemnitees** has by law.

ARTICLE 21. Insurance. The **Engineer** shall obtain and maintain insurance in the limits of liability for each of the types of insurance coverage identified as follows.

- (1) **Workers' Compensation**, endorsed with a waiver of subrogation in favor of the **Owner** in accordance with the statutory obligations imposed by Worker's Compensation or Occupational Disease laws under the Texas Workers' Compensation Law ("**Statutory Texas**")
- (2) **Commercial General Liability**, endorsed with the **Owner** as an additional insured and endorsed with a waiver of subrogation in favor of the **Owner** *all to the extent of the liabilities assumed by the Engineer under Article 19 and Article 20* herein, in limits of liability not less than one million dollars (\$1,000,000) combined single limit each occurrence and in the aggregate for bodily injury and property damage.

- (3) **Texas Business Automobile Policy**, endorsed with the **Owner** as an additional insured and endorsed with a waiver of subrogation in favor of the **Owner** *all to the extent of the liabilities assumed by the Engineer under Article 19 and Article 20 herein*, in limits of liability not less than two hundred fifty thousand dollars (**\$250,000**) each person for bodily injury, five hundred thousand dollars (**\$500,000**) each occurrence for bodily injury, and one hundred thousand dollars (**\$100,000**) each occurrence for property damage.
- (4) **Professional Liability** in limits of **\$1,000,000** each claim and aggregate.

The **Engineer** covenants and agrees to maintain an insurance policy in the minimum limits of liability for each of the types of insurance coverage identified above. The **Engineer** shall furnish the **Owner** with a certificate of insurance (**Hidalgo County Certificate of Insurance**) showing the said policy to be in full force and effect during the period of service, identified in Article 3 hereto, for this Agreement. The completed Hidalgo County Certificate of Insurance shall be attached hereto and identified as **EXHIBIT "G"- Hidalgo County Certificate of Insurance**. The **Engineer** will be considered in breach of contract should the **Engineer** fail to maintain an insurance policy in the minimum limits of liability and requirements identified above while performing services for and under this Agreement, and will be subject to default and termination of the Agreement as outlined in Article 3.4 hereto. Additionally, the **Engineer** covenants and agrees to use its best efforts to maintain an insurance policy in the minimum limits of liability and requirements identified above until one year following the date of the acceptance of the **Project** by **Owner**.

ARTICLE 22. Compliance with Laws. The **Engineer** shall comply with all applicable Federal, State and local laws, statutes, codes, ordinances, rules and regulations and the orders and decrees of any court, or administrative bodies or tribunals in any manner affecting the performance of this Agreement including, without limitation, worker's compensation laws, minimum

and maximum salary and wage statutes and regulations and licensing laws and regulations. When required the **Engineer** shall furnish the **Owner** with satisfactory proof of its compliance therewith.

ARTICLE 23. Non-collusion. The **Engineer** warrants that the **Engineer** has not employed or retained any company or persons, other than a bona fide employee working solely for the **Engineer**, to solicit or secure this Agreement, and that the **Engineer** has not paid or agreed to pay any company, engineer or any other person or entity any fee, commission, percentage, brokerage fee, gifts or any other consideration contingent upon or resulting from the award or execution of this Agreement. For breach or violation of this warranty the **Owner** shall have the right to annul this Agreement without liability or, in the **Owner's** discretion, to deduct from the *Services Fee*, or otherwise recover, the full amount of each fee, commission, percentage, brokerage fee, gift or contingent fee.

ARTICLE 24. Gratuities. The **Owner** mandates that employees of the **Owner** shall not accept any benefits, gifts or favors from any person doing business or who reasonably speaking may do business with the **Owner** under this Agreement; the only exceptions allowed are ordinary business meals. Any person doing business with or who may reasonably seeking to do business with the **Owner** under this Agreement may not make any offer of benefits, gifts or favors to **Owner** employees, except as mentioned herein above. Failure on the part of the **Engineer** to adhere to this provision may result in the termination of this Agreement.

ARTICLE 25. Payment of Franchise Tax. The **Engineer** hereby certifies that the **Engineer** is not delinquent in Texas franchise tax payments, or that the **Engineer** is exempt from, or not subject to, such as tax. A false statement concerning corporation's franchise tax status shall constitute grounds for termination of the Agreement at the sole option of the **Owner**.

ARTICLE 26. Disputes. The **Engineer** shall be responsible for the settlement of all contractual and administrative issues arising out of any procurement made by the **Engineer** in support of the services under this Agreement.

ARTICLE 27. Severability. In the event any one or more of the provisions contained in this Agreement shall for any reason, be held to be invalid, illegal, or unenforceable in any respect such invalidity, illegality or unenforceability shall not affect any other provision thereof and this Agreement shall be construed as if such invalid, illegal or unenforceable provision had never been contained herein .

ARTICLE 28. Notices. All notices to either party by the other required under this Agreement shall be personally delivered or mailed to such party at the following respective addresses:

OWNER
Hidalgo County
1615 S. Closner, Suite J
Edinburg, Texas 78539

ENGINEER
L & G Consulting Engineers , Inc.
2100 West Expressway 83
Mercedes, Texas 78570

The Address may be changed by either party by written notice and notice so mailed shall be effective upon mailing.

ARTICLE 29. Miscellaneous Provisions.

(a) This Agreement constitutes the entire Agreement between the **Engineer** and the **Owner** relating to the work herein described and supersedes any prior understanding or written or oral contracts between the parties respecting the subject matter defined herein. These are no previous or contemporary representations or warranties of the **Owner** or the **Engineer** not set forth herein.

(b) Except as specifically provided herein no modification, waiver, termination, rescission, discharge or cancellation of this Agreement or of any terms thereof shall be binding on

the **Owner** unless in writing and executed by an officer or employee of the **Owner** specifically authorized to do so.

(c) No waiver of any provision of or a default under this Agreement shall affect the right of the **Owner** thereafter to enforce said provision or to exercise any right or remedy in the event of any other default whether or not similar.

(d) No modification, waiver, termination, discharge or cancellation of this Agreement or of any terms thereof shall impair the **Owner's** right with respect to any liabilities whether or not liquidated of the **Engineer** to the **Owner** theretofore accrued.

(e) All rights and remedies of the **Owner** specified in this Agreement are in addition to the Owner's other rights and remedies.

(f) The **Engineer** shall remain an independent contractor and shall have no power nor shall the **Engineer** represent that the **Engineer** has any power to bind the **Owner** or to assume or to create any obligation express or implied on behalf of the **Owner** except as specifically authorized in advance by the **Owner**.

(g) The Agreement shall be construed under the laws of the State of Texas and is performable in Hidalgo County, Texas.

(h) This Agreement may only be amended by a written document executed by the Owner and the **Engineer** as provided by Article 8 herein.

ARTICLE 30. Signatory Warranty The undersigned signatory or signatories for the **Engineer** hereby represent and warrant that the signatory is an officer of the organization for which he or she has executed this Agreement and that he or she has full and complete authority to enter into this Agreement on behalf of the **Engineer**. The above-stated representations and warranties are made for the purpose of inducing the **Owner** to enter into this Agreement.

WITNESS WHEREOF, the **Engineer** and the **Owner** have caused this **Agreement for Professional Services** to be effective as of the 10th day of December, 2013.

ENGINEER:
L & G CONSULTING ENGINEERS INC.
d/b/a **L & G ENGINEERING**

BY: Jacinto Garza
Jacinto Garza, P.E./President

OWNER:
HIDALGO COUNTY

BY: Ramon Garcia
Hon. Ramon Garcia, County Judge

ATTEST:

Arturo Guajardo, Jr.
Arturo Guajardo, Jr., County Clerk

Approved by Commissioners' Court
on 12/10/13

Approved on Commissioners' Court: December 10, 2013.

APPROVED AS TO FORM:
Atlas & Hall, L.L.P.

By: AH

ATTACHMENTS:

LOCATION MAP

EXHIBIT A –Scope of Services to be provided by the Owner

EXHIBIT B –Scope of Services to be provided by the Engineer

EXHIBIT C –Work Schedule

EXHIBIT D –Contract Rates

EXHIBIT D1 – Fee Schedule

EXHIBIT E –Work Authorization Form

EXHIBIT F –Supplemental Agreement Form

EXHIBIT G –Certificate of Insurance (*Hidalgo County*)




EXHIBIT "A"
Services to be provided by the County

1. The County will issue work authorization to initiate all required services and designate the authorized representative of the coordination of each work authorization.
2. The County will provide copies of all subdivision plats of record and/or in the subdivision process.
3. The County will provide the Engineer with on-going guidance, timely reviews, and decisions necessary to complete services required by the work authorization in order to permit the Engineer to maintain an agreed upon project schedule.
4. The County will provide a Purchase Order and process all acceptable requests for payment in a timely manner.
5. The Work Authorization will identify the Notice to Proceed date.

GENERAL INSTRUCTIONS

ENGINEER shall mean L&G Engineering.

STATE shall mean Texas Department of Transportation.

COUNTY shall mean the Hidalgo County.

PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: _____

PROJECT/DESCRIPTION: Professional Engineering Services

LENGTH: VARIABLE

HIGHWAY: FM 1925

LIMITS: from FM 907 (ALAMO ROAD) EAST TO URESTI STREET

EXISTING FACILITY

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☐ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

NOTES

ROUTE AND DESIGN STUDIES
(Function Code 110)

Services
Provided By:
ENGINEER COUNTY

—	—	1. Route Location Studies*
—	—	2. Level of Service Analysis
—	—	3. Traffic Evaluations and Projections
—	—	4. Develop Roadway Design Criteria
—	—	5. Preliminary Cost Estimates
—	—	6. Design Schematic (See Section 7, page 7-1 for schematic layout requirements)
—	—	7. Preliminary Right-of-Way Requirements
—	—	8. Design Concept Conference
—	—	9. Soil Core Hole Drilling
—	—	a. Pavement (See Section 7, pages 7-3 thru 7-4 for requirements)
—	—	b. Retaining Walls (See Section 10, page 10-1 thru 10-2 for requirements)
—	—	c. Miscellaneous Structures (See Section 10, page 10-4 for requirements)
—	—	d. Bridges (See Section 11, page 11-3 for requirements)
- * The Phase I or better survey for hazardous material should be included as a determining factor of route selection. Projects which do not require additional right of way should be considered separately from an expansion or new location.

NOTES**SOCIAL, ECONOMIC AND ENVIRONMENTAL STUDIES AND PUBLIC INVOLVEMENT**

(Function Code 120)

Services

Provided By:

ENGINEER COUNTY

1. Environmental Reports

All Environmental Reports shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations, Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.

a. Environmental Assessments

(1) An Environmental Assessment shall be prepared, anticipating a Categorical Exclusion.

(2) An Environmental Assessment shall be prepared, anticipating a Finding of No Significant Impact.

(3) An Environmental Assessment shall be prepared, anticipating the need for a Draft Environmental Impact Statement.

b. Environmental Impact Statement

(1) A Draft Environmental Impact Statement shall be prepared. After appropriate interagency and public reviews within time limits prescribed by the Code of Federal Regulations, Title 23, Part 771 and 43 Texas Administrative Code 2.40-2.51, a Final Environmental Impact Statement shall be prepared.

(2) A Section 4(f) Statement (Department of Transportation Act) shall be provided by the ENGINEER. The format and content of the statement is found in FHWA Technical Advisory T6640.8A.

2. Public Involvement

All public involvement procedures shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.

a. A public involvement meeting(s)/hearing(s) shall be scheduled, coordinated and conducted.*

b. Technical assistance, meeting(s)/hearing(s) preparation, maintenance of contracts lists, minutes of meeting(s), exhibit preparation, and other tasks outlined by the COUNTY, shall be provided.

3. Cultural Resources

Formal consultation with the State Historic Preservation Office (SHPO) and the Texas Historical Commission (THC) will be conducted by the COUNTY.

a. Historic Structure Studies

A records search and reconnaissance survey shall be performed, and documentation prepared regarding identification efforts, National Register eligibility and potential impacts to historic properties in accordance with the state's historic structure requirements.

b. Archeological Studies

(1) Files searches shall be conducted to determine if known archeological sites are present; to identify whether these sites have been listed or determined eligible for the National Register of Historic Places or have been designated State Archeological Landmarks; and to identify the need (if any) to perform additional archeological investigations.

(2) Archeological reconnaissance will be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.

(3) Archeological survey shall be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.

Services
Provided By:
ENGINEER COUNTY

4. Noise and Air Quality Analyses

a. Noise Analysis

A noise analysis shall be prepared, including predicted noise levels and the consideration and evaluation of noise mitigation, in accordance with the STATE'S Noise Guidelines. The noise analysis report shall be prepared and submitted to TxDOT for review and results shall be made part of the administratively complete document.

b. Air Quality Analysis

An air quality analysis shall be prepared in accordance with the STATE'S Air Quality Guidelines. The air quality analysis or a summary of the air quality shall be included in the administratively complete document for the project.

5. Ecological Investigations

A wetland survey and if necessary, a wetland delineation shall be conducted and a "wetland finding" shall be provided if necessary.

A determination should be made if there are potential federally listed endangered or threatened species that could be impacted. The District will be notified as soon as possible that Section 7 or 10 consultations may be required. Supporting data will be furnished to the district when consultation with the U.S. Fish and Wildlife Service is undertaken.

6. Hazardous Materials

The consultant shall prepare a Hazardous Materials Technical report shall be submitted to TxDOT for review and approval. The results shall be made part of the administratively complete document perform an Environmental Site Assessment for hazardous materials impact in accordance with the American Society for Testing and Materials (ASTM) 1528.93 (Transaction Screen Process).

7. General Guidelines for Preparation of Environmental Documents

- a. The Biological Impact Evaluation Report shall be prepared and submitted electronically to TxDOT.
- b. All cultural resource reports (i.e. Archeological and Historical Project Coordination Requests (PCRs), background and reconnaissance surveys) will be submitted electronically to TxDOT.
- c. The draft administratively complete document will be submitted to TxDOT electronically through their FTP site.
- d. The administratively complete document will be prepared in accordance with the content and format of FHWA Technical Advisory T6640.8A and the TxDOT Administrative Code 43 TAC §2.44.
- e. The administratively complete document will be submitted to TxDOT electronically through their FTP site.
- f. Upon completion and approval of the administratively and technically complete document, the Engineer will provide one (1) hard copy to the Client, one (1) hardcopy to the district, and (3) hardcopies to TxDOT ENV.
- g. Exhibits in the administratively complete document shall be color copies and text shall be black and white.

RIGHT-OF-WAY DATA
(Function Code 130)

Services
Provided By:
ENGINEER COUNTY

NOTE: No work involving right-of-way (ROW) data is to be performed until the COUNTY has given the ENGINEER written approval of the final location of the proposed ROW lines as approved by TxDOT.

_____	_____	1. Ownership Data in a .dgn file
		a. The entire project limits.
		b. Compensable utility ownership that has property rights on ROW shall be researched and provided.
		c. For each drainage outfall property
		d. For each irrigation structure pipe.
_____	_____	2. Parcel plats & Right-of-Way Map
		a. A ROW map, parcel plats and field notes shall be prepared and furnished.
		b. All plats and field notes must be signed and sealed by a Registered Professional Land Surveyor (RPLS).
		c. ROW map must depict all improvements affecting ROW.
_____	_____	3. Utilities (Compensable)
		a. Property ownership with recording information shall be shown on ROW Map and Parcel Plats with distance ties to property corners in an effort to locate utility.
_____	_____	4. Field Notes
		a. Field notes and plats, signed and sealed by a Registered Professional Land Surveyor, for all parcels on the ROW Map
		b. Computation Sheets for Survey Closure and Area for Each Parcel.
		c. Ground surveys and preparation of parcel maps, legal descriptions, and right of way maps.
_____	_____	5. Survey and Stake Right-of-Way
_____	_____	6. Records as Required by the County and State
		a. Records used to establish ownership
_____	_____	7. General Guidelines for Preparation of Right-of-Way Maps
		<i>(Sample ROW Maps and Parcel Plats and field notes attached)</i>

GENERAL SPECIFICATIONS

- a. All data submitted by the surveyor will be legible, organized and well documented.
- b. The surveyor shall provide temporary signs and shall control traffic near surveying operations adequately to comply with provisions of the MUTCD; a copy of which the Surveyor acknowledges has been furnished to him. All signs, flags, and safety equipment are to be provided by the surveyor.
- c. Permission to enter private property for surveying (Right-Of-Entry) shall be the sole responsibility of the surveyor.
- d. The surveyor will be held responsible for the correctness of his services. The surveyor will be responsible for the completion of his services.
- e. The surveyor will be required to complete the attached "Right-of-Way Map Checklist" and submit along with the completed R.O.W. map. All requirements of attached R.O.W. map checklist must be complete, accurate and also considered to be essential and is a part of this contract.

PROJECT SPECIFIC SCOPE OF SERVICES

FC 130 – RIGHT-OF-WAY DATA – Abstract analysis, development of ROW Map sheets including parcel plats and field notes with Metes & Bounds field descriptions, and Title Commitments.

FC 150 – FIELD SURVEYING FOR PARCEL MAPPING – Recover horizontal & vertical control, locate and field tie existing ROW and boundary corners. Update topography, and reestablish corners for ROW map revisions.

SURVEYING SCOPE OF SERVICES FOR PARCEL MAPPING

FC 130 – RIGHT-OF-WAY DATA

Right-of-Way Documents - The SURVEYOR will utilize State examples and provide the following:

GENERAL

- a. Abstracting: The SURVEYOR will determine Ownership Data.
- b. Prepare individual parcel maps and field notes as needed to properly describe the right-of-way the State is to acquire.
- c. All procedures involving right-of-way maps will be in accordance with the STATE'S Right-of-Way Book I and Book II, the State's local operating procedures and according to the Texas Board of Professional Land Surveying Practices Act.
- d. All required documents will be in English units.
- e. The SURVEYOR will monument all corners with a 5/8 inch iron rod with a Surveyor's plastic cap on all parcel boundary corners.
- f. The SURVEYOR will provide to the STATE a copy of Instruments of Record.
- g. The SURVEYOR will attach graphics files compatible with the latest version of Micro-Station graphics software.
- h. The SURVEYOR will attach documents or text files compatible with the latest version of Word software.

PARCEL PLATS

- a. A parcel plat will be prepared for each parcel of land to be acquired. The STATE has developed standard formats for parcel plats, copies of which the SURVEYOR will request and secure for all purposes
- b. Parcel boundary lines will be delineated with appropriate bearings, distances, and curve data.
- c. Private property lines will be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired.
- d. League lines and survey lines will be shown and identified by name and abstract number.
- e. A north arrow will be shown on each sheet and, if possible, in the upper right hand corner.
- f. Monumentation set or found will be shown and described as to material and size.
- g. A station and offset will be shown for each PC, PT, and angle point in the proposed right-of-way lines and the existing right-of-way lines in areas of no proposed acquisition.
- h. Intersecting streets will be shown and identified by name and right-of-way width.
- i. A parent tract inset will be shown for each parent tract.
- j. A note will be included on each map sheet stating the basis of bearings, coordinates, and datum used.
- k. Appropriate notes will be included on the title sheet stating the following:
 - a. Month(s) and year abstracting was performed upon which the map is based.
 - b. Month(s) and year field surveys were conducted upon which the map is based.
 - c. Month and year map was completed by the SURVEYOR.
- l. The right-of-way account number and R.O.W. CSJ if available will be shown on each parcel map sheet.

- m. All parcel maps should be 8-1/2" x 11" signed and sealed by a Registered Professional Land Surveyor and note referencing legal description.
- n. The acreage of the part taken should be shown to three decimal places, rounded.

FIELD NOTE DESCRIPTIONS

A field note description will be prepared for each parcel of land to be acquired. Field note descriptions will include, but need not be limited to, the following:

- a. The field note description will begin with a general description that will include, as a minimum:
 - (1) State, county, and city within which the proposed parcel of land to be acquired is located.
 - (2) A reference to unrecorded and recorded subdivisions by name, lot, block, and recording data to the extent applicable.
 - (3) A reference, by name, to the grantor and grantee, date, and recording data of the most current instrument(s) of conveyance describing the parent tract.
- b. The field note description will continue with a metes and bounds description that will include, as a minimum:
 - (1) A point of commencing (outside property corner).
 - (2) A point of beginning on proposed R.O.W. line.
 - (3) A series of courses, identified by number and proceeding in a clockwise direction, describing the perimeter of the parcel of land to be acquired, and delineated with appropriate bearings, distances, and curve data.
 - (4) A description (8-1/2" x 11") of all monumentation set or found to include, as a minimum, size and material.
 - (5) All field note descriptions will be signed and sealed by a Registered Professional Land Surveyor.
 - (6) Note referencing parcel plat.

PHARR DISTRICT
ROW MAP CHECKLIST

Consultant: _____
Contract/WA# _____
Responsible Office: _____
TXDOT Project Manager: _____
County: _____
Highway: _____
RCSJ: _____
CCSJ: _____

As the responsible consultant project manager, I hereby certify that the attached ROW Map has undergone a QA/QC review, with the following applicable items specifically checked for accuracy, completeness and constructability (as noted by Checkmarks)

Signature Date

Printed Name

(This Checklist must be signed by the RPLS and turned in with all proposed ROW Projects. Pharr District ROW will not accept project without this checklist.)

MAP

GENERAL

- ___ All documents have been proofread and are accurate.
- ___ Title Commitments for each individual parcel.
- ___ Graphics files compatible with Microstation and Word software are provided.
- ___ Photos of proposed ROW staking included.
- ___ Field notes and Parcel Plats are numbered continuous.
- ___ Scale shall be 1"=50' or 1"=100".

TITLE SHEET REQUIREMENTS

- ___ Title and description of project including county, limits, etc....
- ___ Vicinity map with beginning and ending station
- ___ Equations and Exceptions
- ___ Index
- ___ Legend
- ___ Title block completely filled out with Construction and R.O.W. CSJ's
- ___ List all Major Utilities from Station to Station

INDIVIDUAL MAP SHEET REQUIREMENTS

- ___ Sheet size 34" X 22"
- ___ Text legible when reduced to half-scale.
- ___ Title block completely filled out with R.O.W. CSJ
- ___ Matchlines
- ___ Project layout sheet
- ___ Existing utility lines and easements, deed reference, as shown on Schedule "B" of the Title Commitment, and defined on parcel plats

EXISTING INFORMATION

- ___ R.O.W. lines
- ___ Whole property or whole property inset
- ___ Roadways

- ☐ Survey, county, and city limit lines shown and labeled
- ☐ Improvements shown and labeled (*see below*)
- ☐ Monumentation i.e. P.C., P.T., Break Points
- ☐ North arrow
- ☐ Scale
- ☐ Property lines
- ☐ Property descriptions i.e., lot, block, tract, subdivision, etc...
- ☐ Identify existing and proposed access denial locations (*if applicable*)

PROPOSED INFORMATION

- ☐ Type II Monumentation i.e. P.C., P.T., Break Points and 1500' intervals
- ☐ Survey and R.O.W. lines
- ☐ Basis of bearings
- ☐ Parcel bearings and distances correspond with traverse sheet
- ☐ Outside ties (P.O.C.) corresponds with field notes
- ☐ Point of beginning (P.O.B.) established on proposed R.O.W. line
- ☐ Parcel tied to baseline
- ☐ Baseline information shown i.e. Stationing, bearings, curve data, etc...
- ☐ Conveyance information shown in tables i.e. parcel number, grantors name, amount of take, remainder etc...
- ☐ Math checked on remainder

IMPROVEMENTS

- ☐ Improvements bisected or within 25' of proposed R.O.W. line are shown on map with stationing and distance from proposed R.O.W. line. Buildings are labeled and dimensioned.
- ☐ Off-premise outdoor advertising signs within proposed R.O.W. are shown and labeled.

UTILITIES

- ☐ All utilities within or crossing existing and proposed right of way are shown and labeled as to size, easement or fee width, and recording data of instrument.
- ☐ Location of underground storage tanks and/or filler caps are shown and labeled

*** DO NOT SEAL MAP**

FIELD NOTES HEADING

- ☐ County
- ☐ Highway
- ☐ Parcel number
- ☐ R.O.W. CSJ
- ☐ Construction CSJ

GENERAL DESCRIPTION OR "PREAMBLE"

- ☐ Area of parcel to be acquired is shown in acreage (0.000) for rural land and/or square feet (to nearest whole sq. ft.) for urban land or smaller parcels

PARENT TRACT DATA IS SHOWN

- ☐ Size of parent tract
- ☐ Survey data or lot, block, and subdivision
- ☐ Name of last recorded seller and buyer
- ☐ Date, volume and page or document number of last recorded conveyance
- ☐ Records and county of last recorded conveyance

BEGINNING DESCRIPTION

- ☐ Point of commencement is on outside tie and is described accurately by bearings and distances as it leads to the point of beginning.
- ☐ Point of beginning is on proposed R.O.W. line

PARTICULAR DESCRIPTION

- ☐ Traverse calls are clockwise sequence
- ☐ Bearings and distances correspond exactly with map, parcel sketch, and traverse sheet
- ☐ Bearings are to nearest whole second and distances are to the nearest one-hundredth of a foot
- ☐ Calls are numbered
- ☐ Denial of access shall be described from beginning to end (*if applicable*)

CLOSING DESCRIPTION

- ☐ Last call leads back to P.O.B.
- ☐ Restates area of parcel
- ☐ Establishes taking in existing road R.O.W. (*if applicable*)
- ☐ Legal description is referenced to Plat
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)

PARCEL SKETCH

- ☐ Shows P.O.B. and P.O.C.
- ☐ All data corresponds exactly with Map and Field Notes
- ☐ Sheet size is no larger than 8 1/2" x 11"
- ☐ Plat closely matches example provided
- ☐ Plat referenced to legal description
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)
- ☐ Existing utility lines and easements (deed reference, if available);

TRAVERSE SHEET

- ☐ Computations show area to be acquired in sq. ft. or acres, whichever is applicable
- ☐ Computations show area that is existing road R.O.W. (*if applicable*)
- ☐ Traverse calls are in clockwise sequence
- ☐ Error of closure meets the following:

Secondary rural	.0003
Primary rural - secondary urban	.0002
Urban or industrial	.00013

FIELD SURVEYING AND PHOTOGRAMMETRY

(Function Code 150)

Services
Provided By:
ENGINEER COUNTY

1. Field Surveying

a. Primary Project Control – 3 to 5 miles spacing

Precision shall be 1 part in 20,000 or better, unless otherwise directed by the District Engineer.

(1) Establish horizontal control points

(2) Establish vertical control points

NOTE: ALL BEARING AND DISTANCE SHALL BE BASED ON THE STATE PLANE COORDINATE SYSTEM NAD 1983, SOUTH ZONE.

ALL DISTANCES AND COORDINATES SHALL BE SURFACE AND MAY BE CONVERTED TO GRID BY MULTIPLYING BY A COMBINED SCALE FACTOR OF 0.999960

b. Secondary Project Control – Surveyor shall recover and/or reset H&V Control Points as provided by the Engineer and create Survey Data Sheets for inclusion in the Project Plans.

- No traverse should exceed 25 angle points. Planimetrics shall be 20 ft Lt & Rt from the proposed ROW as per the schematic provided by the Engineer.

- The unadjusted angular error should not exceed 2 seconds per angle, plus 14 seconds.

- The unadjusted ratio of precision should be one part in 10,000 or better. (The ratio of precision is the total length of the traverse divided by the total error.)

- The unadjusted vertical error should not exceed 0.03 foot per mile of traverse.

(1) Project control base lines

(2) Photogrammetric ground control

(a) Establish horizontal control

(b) Establish vertical control points

(c) Place and maintain control point targets

c. Other Field Surveying

(1) **The limit of the Design surveys shall be 500-ft before and after the limits of the project as identified by the Project Engineer on the schematic. Establish horizontal and vertical control.** Set benchmarks at 1000-ft intervals along the project proposed right-of-way. Provide x, y, z for each Benchmark. Provide a BM along each outfall identified on the Hydrologic Map. The BM's shall be #5 I.R. 2-ft in depth set in concrete. **The surveyor shall provide an H&V Book (a Sample shall be provided by the Engineer to the Surveyor).** The Surveyor will provide a 3-pt reference sketch with ties to the BMs for inclusion the existing H&V Control Book. Establish benchmark circuit throughout the project with a tolerance of 0.03'/ft per mile error vertically.

(2) Complete topographic and cross section survey, data processing, and CADD mapping (2D & 3D) for the limits of the project.

(3) Locate all visible utilities, data processing and CADD mapping (2D & 3D) including irrigation lines. Follow sample provided by the Engineer.

(4) Field locate cross culverts, driveway culverts, inverts, irrigation lines, within the project limits, data processing and CADD mapping (2D & 3D).

(5) Right of Entry, Right of Way Research, and Appraisal District Records is the responsibility of the Surveyor.

Services
Provided By:
ENGINEER COUNTY

- —
- c. Other Field Surveying (*continued*)
- (6) The Surveyor shall also paint the proposed centerline on the existing pavement as approved by Engineer. (500-ft stations and a tick mark at 100 ft. stations –12 inches long with approved paint by Engineer) before construction for the purpose of utility adjustments and project location.
- (7) Profile and cross section intersecting streets for ties into project (500-ft. beyond the proposed ROW per schematic and 20-ft wider than the existing ROW of intersecting street). Reference missing voids as per CD provided by the Engineer.
- (8) Cross section irrigation crossings for a distance of 20-ft beyond the proposed ROW at 100-ft intervals in a DTM file. Provide a complete description of irrigation appurtenances as identified by the engineer sample layout.
- (9) Tie Horizontally and Vertically the existing storm drain system that lies within the existing proposed ROW including the elevation of the outfall of said recovered existing storm drain systems.
- (10) Tie to existing underground and overhead utilities (location, elevation and direction)
Horizontally – The surveyor shall call the 1-800 number for the utilities to be marked on the ground as well as any city water and sewer lines. He shall tie all visible utility crossings with name, address and Phone #'s of utility companies. The engineer will coordinate with the utility companies and jointly the Surveyor and the Engineer will identify which utilities were missed and need to be tied down.
Vertically – The engineer shall identify all utilities that are potential conflicts and that need to be tied vertically. The engineer will advise the surveyor in writing of the needed vertical ties and the surveyor will tie the lines vertically once the surveyor has coordinated the exposure and provide the information to the engineer.
- (11) Additional Field Surveying as shown below:
- (a) IRRIGATION LINES – The surveyor will meet with the engineer before he ties down any irrigation lines. The Engineer will provide him the existing Irrigation District Maps and the A&M Data of existing irrigation lines that are identified of record. He will follow the sample given to him by the engineer and tie the structures horizontally and vertically and provide Field Books to the engineer.
- (b) OUTFALLS – The surveyor will provide a complete 2D & 3D File including utilities of the outfall identified on the Hydrologic Map.
- (12) Driveways and Turnouts
- (a) Inventory commercial entrances, public roads and side streets separately.
- (b) Obtain centerline station. (Width at ROW, PAV'T and existing radius.
- (c) Inventory by type (dirt, caliche, gravel or paved). If paved, indicate condition in terms of no patches, has patches or has potholes.
- (d) Obtain width at R.O.W. line.
- (e) Obtain elevations at both edges of the driveway or turnout in line with the side drain.
- (13) ROW staking (Existing and Proposed @ 1,000 ft. stations PC's PT's and Angle points as per ROW Map)
- (14) Soil core hole staking.
- (15) Determine changes in topography from voids and outdated maps due to development, erosion, etc.
- (16) Profiles of existing drainage facilities.
- (17) Measurement of hydraulic opening under existing bridges.
- (18) Obtain elevations of manholes and valves of utilities
- —
— —
— —
— —
— —
— —

Services
Provided By:
ENGINEER COUNTY

—	—	c. Other Field Surveying (<i>continued</i>)
—	—	(19) Provide temporary signs, traffic control, flags, safety equipment, etc.
—	—	(20) Ties to existing bridges or culverts that may conflict with new construction.
—	—	(21) Bridge widening top of deck and/or top of cap elevations at the Profile Grade Line (PGL) and the edges of slab at bent locations.
—	—	(22) Inventory signs, mailboxes, and driveways
—	—	(23) Survey controlled data sheets per TxDOT guidelines.
—	—	2. Photogrammetric Products
		a. Uncontrolled Photography
		(1) Contact Prints
		(2) Mosaics
		(3) Digital ortho plots
		b. Mapping
		(1) Planimetric Maps
		(2) Contour Maps
		(3) Cross Sections
		(4) Profiles
		(5) Digital Terrain Models (DTM)

ROADWAY DESIGN CONTROLS

(Function Code 160)

Services
Provided By:
ENGINEER COUNTY

1. Geometric Design

a. Horizontal and Vertical Alignment

b. Schematic Layout

- (1) The location of interchanges, main lanes, grade separations, frontage roads and ramps.
- (2) Develop vertical and horizontal alignment of main lanes, ramps and cross roads at proposed interchanges or grade separations. Frontage road alignment data need not be shown on the schematic; however, it should be developed in sufficient detail to determine ROW needs. The degree of horizontal curves and vertical curve data, including "K" values, shall also be shown for ease of checking.
- (3) For freeways, show the location and text of the proposed main lane guide signs. Lane lines and/or arrows indicating the number of lanes shall also be shown.
- (4) A complete explanation of the sequence and methods of stage construction, if proposed, including the initial and ultimate proposed treatment of crossovers and ramps.
- (5) The tentative ROW limits.
 - (a) Provide a roadway Design System (RDS) or (GEOPAK) computer tape of the preliminary earthwork to verify ROW requirements.
 - (b) Provide a graphics file containing the approved schematic.
- (6) The geometric (pavement cross slopes, lane and shoulder widths, slope rates for fills and cuts) of the typical sections of proposed highway main lanes, ramps, frontage roads, and cross roads.
- (7) The current and projected traffic volumes as provided by the TxDOT (20 year traffic projection, unless otherwise determined by the District Engineer).
- (8) The control of access lines if Interstate or designated under House Bill 179.
- (9) Direction of traffic flow on all roadways.
- (10) Location and width of median openings for highway without access control.
- (11) The geometric of speed change (acceleration, deceleration, climbing) lanes.

2. General Guidelines for Project Development

- a. Prior to preparing detailed plans for a proposed project, a preliminary schematic layout shall be prepared which indicates the general geometric features and location requirements peculiar to the project. An uncontrolled aerial mosaic will be provided for this use. Four copies of the schematic layout shall be submitted through the district to the Design Division for approval and subsequent coordination with the Federal Highway Administration (FHWA) where applicable. The layout shall be submitted for two-lane arterial highway projects on new locations and for all multi-lane highway projects. **No geometric design is to be performed until the COUNTY has given the engineer written approval of the preliminary schematic layout.**
- b. All geometric design shall be in conformance with the State's Design Division, Operations and Procedures Manual, except where variances are permitted in writing by the STATE.
- c. The schematic layout shall include basic information which is necessary for the proper review and evaluation including the items listed above in the checklist for schematic layout.
- d. Handling of traffic during construction shall be a consideration in the development of preliminary designs.

Services
Provided By:
ENGINEER COUNTY

2. General Guidelines for Project Development (*continued*)

- e. Upon approval of the schematic layout by Design Division (FHWA on Federal-aid projects), it shall be the basis for an exhibit at any required public hearing prior to final development of the project. If there are any changes to the schematic after the Design Division and FHWA approval and before the public hearing, four copies of the revised schematic, as displayed at the hearing, shall be submitted either prior to or accompanying the public hearing data. If there are no changes in the schematic as displayed at the hearing, only photographs of the schematic and other displays shall be submitted with the public hearing data.
- f. For all freeway construction projects, these schematics shall show the location and text of the proposed main lane guide signs. A schematic layout shall be submitted through the district to the Traffic Operations Division, Traffic Safety Section for approval and subsequent coordination with the FHWA. All signing shall be in conformance with the Texas MUTCD.
- g. On complex projects, informal contact through the district with the Design Division and FHWA personnel is encouraged with regard to development of preliminary design prior to official schematic submission.
- h. The engineer shall furnish a project tape that is compatible with the STATE's computer system, a project listing, and a cross section plot showing the original design sections containing the earthwork input and original cross sections for the project. **Accuracy of the earthwork design is of utmost importance since it is the basis for contractor payments and construction staking.**

3. Exhibit for Airway/Highway Clearance Permits

4. Grading Design

- a. Refine the horizontal and vertical alignment of main lanes, frontage roads, ramps, cross roads and direct connectors based upon the approved schematic layout. Determine vertical clearances at grade separations and overpasses, taking into account the appropriate super elevation rate.
- b. Typical Sections
- c. Design Cross Sections
- d. Determine Cut and Fill Quantities
- e. Slope Stability Analysis
- f. Embankment Foundation Stability Analysis
- g. Embankment Settlement Analysis

5. Pavement Design

- a. Prior to initiating detailed plan preparations for a project, a preliminary investigation shall be made to determine the approximate section and pavement type to be used for the pavement structure. The Flexible Pavement Design Manual for flexible pavement, "Appendix F" of the Design Division, Operations and Procedures Manual, and the current AASHTO Guide for the Design of Pavement Structures, may be used for this purpose.
 - b. The typical section shall also reflect proposed geometric including pavement cross slopes, lane and shoulder widths, and slope rates whenever this data have not been previously shown on a schematic submission.
 - c. Embankment and Subgrade
 - (1) Soil Core Holes (Show cost estimate with Function Code 110)
 - (a) Along center line
 - (b) Along center line of each roadway
- The location and minimum number of soil core holes required for this project are as follows: (To be determined when schematic is being completed)

Services
Provided By:
ENGINEER COUNTY

_____	_____	5. Pavement Design (<i>continued</i>)
_____	_____	c. Embankment and Subgrade (<i>continued</i>)
_____	_____	(2) Identify, interpret and summarize geologic features that affect engineering design
_____	_____	(PI, Sulfate content, % of lime)
_____	_____	d. Traffic Data for Pavement Design by STATE
_____	_____	e. Basic Design Criteria
_____	_____	f. Life Cycle Cost Analysis(es)
_____	_____	g. Cost Data
_____	_____	h. Pavement Material Properties
_____	_____	i. Rehabilitation Investigations
_____	_____	(1) Core Hole Survey (Show cost estimate with Function Code 110)
		(a) Determine type and depth of existing material, pavement, etc. The Engineer
		will determine whether to salvage ACP and FLEXBASE as well as their
		properties and provide this information to TxDOT.

DRAINAGE
(Function Code 161)

Services
Provided By:
ENGINEER COUNTY

All hydraulic design shall be in accordance with the TxDOT's Hydraulic Manual, except where variances are permitted in writing by the COUNTY.

___	___	1. Hydrologic Studies, Discharges
___	___	a. Drainage area maps showing existing conditions and proposed improvements.
		b. Hydrologic data/discharge determination
		2. Hydraulic Drainage Study and Documentation
		a. Hydraulic computations
___	___	(1) Storm water detention available within the ROW (linear ft. along side drain ditch).
___	___	(2) Storm water detention required outside the ROW (as per HCDD#1)
___	___	(3) Culverts
___	___	(4) Bridge waterways
___	___	(5) Channels
___	___	(6) Storm sewers/inlets
___	___	(7) Pump stations
___	___	(8) Storm Water Management facilities
___	___	(9) Other
		(a) Irrigation Canals/Siphons
___	___	b. Hydraulic report(s)
___	___	c. Federal Emergency Management Agency (FEMA) floodway requirements
___	___	d. Determine impact of proposed drainage plan on the following receiving stream(s)
		(1) Hidalgo County Drainage District Outfalls
		(2) All Irrigation District Outfalls impacted
		3. Layout, Structural Design and Detailing of Drainage Features
		a. Culverts
___	___	(1) New culverts
___	___	(2) Culvert widening and/or lengthening
___	___	(3) Culvert replacements
		b. Storm sewers
___	___	(1) New storm sewers
___	___	(2) Modify existing storm sewers
___	___	(3) Inlets
___	___	(4) Manholes
___	___	(5) Trunk lines
		c. Pump stations
___	___	d. Subsurface drainage at retaining walls
___	___	e. Outfall channel(s) within the ROW
___	___	f. Outfall channel(s) outside the ROW
___	___	g. Detention Pond(s) within the ROW
___	___	h. Detention Pond(s) outside the ROW
___	___	i. Summary of Quantities
___	___	j. Storm Water Management facilities
___	___	4. Storm Water Pollution Prevention Plan (SW3P)
___	___	5. Scour Evaluation - Waterway Structures only (to be completed by Bridge Engineer under FC 170.

SIGNING, MARKINGS AND SIGNALIZATION

(Function Code 162)

Services
Provided By:
ENGINEER COUNTY

—	—	1. Signing and Markings Layout
		a. Requirements (Separate Layout)
		(1) Roadway layout
		(2) Center line with station numbering
		(3) ROW lines
		(4) Culverts and other structures that present a hazard to traffic
		(5) Location of utilities, if not shown on plan and profile
		(6) Existing signs to remain, to be removed, to be relocated
		(7) Proposed signs (illustrated and numbered)
		(8) Existing overhead sign bridges to remain, to be revised, removed or relocated
		(9) Proposed overhead sign bridges indicating location by plan layout (electrical details need not be shown on this layout)
		(10) Proposed markings (illustrated and quantified) which include pavement markings, object markings and delineation
		(12) Quantities of existing pavement markings to be removed
		(13) Proposed delineators and object markers
		b. For projects involving freeway to freeway or other types of directional interchanges, projects including left-hand ramps or connections, the following information must be provided:
		(1) The location of interchanges, main lanes, grade separations, frontage roads and ramps
		(2) complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps
		(3) The number of lanes in each section of proposed highway and the location of changes in numbers of lanes
		(4) The projected traffic volumes as provided by the STATE (20 year traffic projection, unless otherwise determined by the District Engineer)
		(5) Tentative ROW limits
		(6) Direction of traffic flow on all roadways
		(7) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations
—	—	2. Summary of Small Signs Tabulation
—	—	3. Summary of Large Signs Tabulation including all Guide Signs
—	—	4. Sign Detail Sheets
		a. All signs except route markers
		b. Design details for large guide signs
		c. Dimensions of letters, shields, borders, corner radii etc.
		d. Designation of shields attached to guide signs
		e. Designation of arrow used on exit direction signs

Services
Provided By:
ENGINEER COUNTY

5. Traffic Signals

a. Development of Justification (Warrant) Data

(1) Location Map

Relationship of proposed installation to other traffic signals, highways, business areas and traffic generators

(2) Photographs as appropriate

(3) Accident data as appropriate

(4) Vehicle volumes (provided by TxDOT)

(a) Existing

(b) Estimated

(c) Projected

(d) Pedestrian

(5) Traffic Survey - Count Analysis

(6) Recommendation based on above data

b. Layout

(1) Title Sheet (when applicable)

(a) Describe the location

(b) Type of installation

(c) Area map with project limits for each location

(d) Index of sheets

(e) Space for official signatures

(2) Estimate and quantity sheet (when applicable)

(a) List of all bid items

(b) Bid item quantities

(c) Specification item number

(d) Paid item description and unit of measure

(3) Basis of estimate sheet (list of materials)

(4) General notes and specification data sheet

(5) Condition diagram

(a) Highway and intersection design features

(b) Roadside development

(c) Traffic control including illumination

(6) Plan sheet(s)

(a) Existing traffic control that will remain (signs and markings)

(b) Existing utilities

(c) Proposed highway improvements

(d) Proposed installation

(e) Proposed additional traffic controls

(f) When applicable, proposed conduit for Railroad interconnect with standard details for runs under tracks.

(g) Proposed illumination attached to signal poles.

(7) Notes for plan layout

(8) Elevation sheet(s) (span wire design)

(9) Phase sequence diagram(s)

(a) Signal locations

(b) Signal indications

(c) Phase diagram

(d) Signal sequence table

(e) Flashing operation (normal and emergency)

(f) Preemption operation (when applicable)

(g) Interval timing, cycle length and offset

Services
Provided By:
ENGINEER COUNTY

5. Traffic Signals (*continued*)

b. Layout (*continued*)

(10) Construction detail sheets(s)

(a) Poles (TxDOT standard sheets)

(b) Detectors

(c) Pull Box and conduit layout

(d) Controller Foundation standard sheet

(11) Marking details (when applicable)

(12) Barricade and warning sign standard sheet and any special details for work zone traffic control for special conditions

(13) Aerial or underground interconnect details (when applicable)

c. General Requirements

(1) Contact local utility company

(a) Confirm power source

(b) Discuss route of aerial or underground interconnect cable (when applicable)

(c) Adjustment of overhead utility lines

(2) Prepare governing specifications and special provisions list

(3) Prepare project estimate

d. Summary of Quantities

MISCELLANEOUS (ROADWAY)

(Function Code 163)

Services
Provided By:
ENGINEER COUNTY

1. Retaining Walls

a. Structural Details

- _____

- (1) Cast-in-Place Cantilever at _____ locations. (TxDOT Standard Retaining Wall)*
 - (2) Tiedback Retaining Wall at _____ location. (TxDOT standard retaining wall)
 - (3) Specialized Retaining Wall at _____ locations (Unique Design).*

b. Alternate Patented Retaining Walls at all locations. (Layouts Only)**

- _____

- (1) Mechanically Stabilized Earth
 - (2) Concrete Block Wall Systems

c. Retaining Wall Layout (PLAN)

- _____

- (1) Designation of reference line
 - (2) Beginning and ending retaining wall stations
 - (3) Station of each retaining wall joint***
 - (4) Offset from reference line
 - (5) Horizontal curve data
 - (6) Number of retaining wall panels and lengths***
 - (7) Total length of wall
 - (8) Indicate face of wall
 - (9) All wall dimensions and alignment relations (alignment data as necessary)
 - (10) Soil core hole locations

d. Retaining Wall Layout (ELEVATION)

- _____

- (1) Top of wall elevations at each joint or intervals***
 - (2) Existing and finished ground line elevations
 - (3) Height of stem at each joint***
 - (4) Wall panel designations***
 - (5) Top of footing elevations***
 - (6) Limits of measurement for payment****
 - (7) Type, limits and anchorage details of railing (If applicable)
 - (8) Top and bottom of wall profiles and soil core hole data plotted at correct station and elevation. The plot shall be at the same scale as the wall profile. Ground water elevations and the observation date shall be shown.

e. Foundation Studies (Show cost estimate with Function Code 110)

- _____

- (1) The soil core holes shall be obtained at approximately 200 foot intervals along retaining wall alignments. The core holes shall extend 25 feet below the footing elevation.

f. Stability Analysis (the ENGINEER shall estimate this task as part of his bid to complete the work).

g. Estimate

h. Summary of Quantities

i. Typical X-section.

j. General Guidelines for Retaining Walls

- _____

- (1) The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. **The designer and checker shall check all calculations and initial each page.**
 - (2) The ground water level should be observed at the water strike.
 - (3) For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
 - (4) Foundation exploration shall conform to the requirements set forth in Administrative Circular No. 25-84, Administrative Circular 33-87 and Administrative Circular No. 25-92.

Services
Provided By:
ENGINEER COUNTY

2. Traffic Control Plan, Detours and Sequence of Construction

Traffic Control Plans (TCP) are required for all projects. A detailed TCP shall be developed when traffic handling during construction involves complications for which a feasible solution is not covered by the Texas MUTCD or the current Barricade and Construction (BC) Standards. The following items are required on all Traffic Control Plan Layouts:

- a. The sequence of construction and method of handling traffic during each phase.
- b. The existing and proposed traffic control devices that will be used to handle traffic during each construction sequence. Include signals, regulatory signs, warning signs, construction warning signs, guide signs, route markers, construction pavement markings, channelizing devices, portable changeable message signs, flashing arrow boards, barricades, barriers, etc.
- c. The proposed traffic control devices (stop signs, signals, flag person, etc.) at grade intersections during each construction sequence.
- d. Where detours are provided, typical cross sections shall be shown.
- e. Road construction work hours shall be developed after an investigation of the traffic volumes has been performed.

3. Illumination

a. Preliminary Roadway Illumination Layout and Circuit Layout

(1) For projects involving freeway to freeway or other types of directional interchanges and projects including left-hand ramps or connections, provide the following:

- (a) The location of interchanges, main lanes, grade separations, frontage roads and ramps
- (b) A complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps
- (c) The number of lanes in each section of proposed highway and the location of changes in the number of lanes
- (d) The projected traffic volumes as provided by the STATE (20 year traffic projection unless otherwise determined by the district engineer)
- (e) Tentative ROW limits
- (f) Direction of traffic flow on all roadways
- (g) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations

b. Final Roadway Illumination and Electrical Circuit Layouts

- (1) Roadway layout showing pavement edges, shoulders, curbs, retaining walls, etc.
- (2) Center line with station numbering.
- (3) ROW lines.
- (4) Symbol legend. Use department standard symbols for lighting and electrical.
- (5) Culverts and other structures that present a hazard to traffic.
- (6) Location of underground utilities, if not shown on plan profile.
- (7) Location of overhead electrical lines, both crossing and parallel to ROW.
- (8) Existing sign lighting circuits and roadway illumination to remain, to be removed, to be relocated.
- (9) Existing service poles, electrical circuits, ground boxes, etc.
- (10) Contact electric utility for service pole locations, voltage characteristics.
- (11) Location of proposed sign lighting circuits and roadway illumination.
- (12) Proposed electrical circuits.
- (13) Tabulation of all quantities including proposed, existing to be relocated, existing to be removed. The layout sheet quantities and lighting summary shall be shown. Tabulations to include estimated quantity with a column for final quantities.

Services
Provided By:
ENGINEER COUNTY

—	—	3. Illumination (<i>continued</i>)
—	—	c. General Guidelines for Illumination (If applicable)
		The ENGINEER shall submit to the COUNTY, well in advance of PS&E due date, the roadway illumination and electrical circuit layout sheets for review by the STATE. Two copies of the layout sheets are to be submitted. One copy will be returned to the Engineer showing corrections that are to be made by the ENGINEER. When final plan submission is made, the ENGINEER shall provide a written statement regarding completion of the corrections.
—	—	4. Miscellaneous Drafting/Standards
—	—	a. Erosion Control
—	—	b. Landscape Development
—	—	5. Compute and Tabulate Quantities
—	—	6. Special Utility Details (Irrigation lines)
		7. Miscellaneous Structures
		a. Type of Structure*
		(1) Overhead Sign Bridges (O.S.B.)
		Modifications or special O.S.B. designs shall be prepared using the same design assumptions that are used for the standard O.S.B structures.
—	—	(a) New O.S.B. structure(s)
—	—	(b) Structural evaluation of existing O.S.B. structure(s) that are to remain in place or to be relocated.
—	—	(2) High Mast Illumination Poles (HMIP)
—	—	(3) Traffic Signal Supports
—	—	(4) Conventional Illumination Poles
—	—	(5) Sound Barrier Walls
—	—	b. Checklist for Layouts
		(1) Reference appropriate O.S.B. standard
		(2) Drilled shaft size and length
		(3) Soil strength used for design {indicate basis and boring(s) used}
		(4) Design height
		(5) Tower heights
		(6) Leg spacings
		(7) Design wind speed
—	—	c. Foundation Studies (Show cost estimate with Function Code 110)
		The soils exploration requirements for miscellaneous structures on this project are as follows: (To be provided by the Engineer on an as-needed basis)
		8. Agreements
—	—	a. Utility Agreements
—	—	b. Exhibits for Utility Agreements
—	—	c. Railroad Agreements
		d. Railroad Exhibits
—	—	(1) Railroad Underpasses
—	—	(2) Railroad Overpasses
—	—	(3) Railroad Grade Crossing (Replanking)
—	—	(4) Railroad Grade Crossing Warning Systems (Signals)
—	—	(5) Other Miscellaneous Sketches for Railroads
—	—	e. Traffic Signal Agreements
—	—	f. Exhibits for Traffic Signal Agreements
—	—	9. Estimate
—	—	10. Specifications and General Notes

BRIDGE DESIGN
(Function Code 170)

Services
Provided By:
ENGINEER COUNTY

			<u>NUMBER REQUIRED</u>
1. Preparation of Structural Details			
a. New Structure(s)			
___	___	(1) Underpass(es)	___
___	___	(2) Overpass(es)	___
___	___	(3) Main Lanes	___
___	___	(4) Direct Connector(s)	___
___	___	(5) Ramp Bridge(s)	___
___	___	(6) Waterway Structure(s)**	___
___	___	(7) Pedestrian Structure(s)	___
___	___	(8) Utility Structure(s)	___
___	___	(9) Railroad Underpass(es)	___
___	___	(10) Railroad Overpass(es)	___
___	___	(11) Bridge Classification Culvert(s)**	___
___	___	(11) Alternate Structural Designs	___
___	___	(12) Alternate Foundation Design	___
Total New Structures =			___
b. Existing Structure(s)			___
___	___	(1) Bridge Widening, Rehabilitation and/or Modification of Existing Structure(s)	___
___	___	(2) Bridge Replacement	___
___	___	(3) Raising Bridge Elevation	___
___	___	(4) Bridge Classification Culvert(s) Widening and/or Modification of Existing Structures(s)	___
___	___	(5) Railroad Overpass(es)	___
___	___	(6) Railroad Underpass(es)	___
Total Existing Structures =			___

* Contour plots of bridge gores are required for projects involving ramps within the main bridge in order to ensure project transition. The Template data and vertical alignment necessary to generate the contour plots are also required.

** In the early stages of a project, it sometimes cannot be determined whether a Waterway Bridge Structure or a Bridge Classification Culvert (20' minimum length) will be required. Therefore, the ENGINEER should be aware that either of these two types of bridges may be reclassified later in the project for the other type when more information is known that would dictate a change in structure classification.

Services
Provided By:
ENGINEER COUNTY

2. Preparation of Bridge Layouts (each bridge)
- a. Bridge Layouts (PLAN)
- (1) Horizontal curve information or bearing of centerline.
 - (2) Including horizontal, vertical, and template information of all roadways or railroads crossed.
 - (3) Bearing of center line or reference line.
 - (4) Skew angle(s).
 - (5) Slope for header banks and approach fills.
 - (6) Control stations at beginning and ending of bridge (with deck elevation), intersections, etc.
 - (7) Approach pavement and crown width.
 - (8) Bridge roadway width and curbs, face of rail, shoulders, or sidewalks.
 - (9) Approach slab and curb returns.
 - (10) Limits and type of riprap.
 - (11) Proposed features under structure.
 - (12) Location of profile grade line.
 - (13) North arrow.
 - (14) Typical bridge roadway section including preliminary proposed beam types and spacings.
 - (15) Cross slope and super elevation data.
 - (16) Minimum horizontal clearances when applicable.
 - (a) Dimensions to features that control clearances. (Calculate and indicate points of minimum vertical and horizontal clearances.
 - (17) Location of soil core holes (station and offset), shown on layout.
 - (18) Bent stations and bearings.
 - (19) Retaining wall locations.
 - (20) Traffic flow directional arrows.
 - (21) Railing types shown.
 - (22) Joint types and seal size, if used.
 - (23) Beam line numbers consistent with span details.
 - (24) Critical horizontal clearances (location of railroad tracks, nearby structures and utilities).
 - (25) Bearings of utilities.
- b. Bridge Layouts (ELEVATION)
- (1) Type of foundation.
 - (2) Finished grade elevations at beginning and end of bridge.
 - (3) Overall length of structure.
 - (4) Length, type of spans and units.
 - (5) Type of railing.
 - (6) Minimum calculated vertical clearance(s).
 - (7) Existing and proposed ground lines clearly marked.
 - (8) Grid elevations and stations.
 - (9) Bent numbers encircled.
 - (10) Stationing of bridge compatible with grid stations.
 - (11) Standard title.
 - (12) Profile grade data.
 - (13) Type of riprap.
 - (14) Soil Core Hole information with penetrometer test data shall be shown on the bridge layout at correct station, elevation and scale.
 - (15) Fixed/expansion condition of all bents.
 - (16) Column "H" heights.
 - (17) Number, size and length of foundations.

Services
Provided By:
ENGINEER COUNTY

- — 2. Preparation of Bridge Layouts (each bridge) *(continued)*
- c. Additional layout requirements for waterway structures and bridge classification culverts.
- (1) Design and 100-year peak discharges.
 - (2) Design and 100-year high water (HW) (Recorded HW and date if available)
 - (3) Natural and through-bridge velocities for design and 100-year floods.
 - (4) Calculated backwater for design and 100-year floods.
 - (5) Direction of flow for waterway crossings.
 - (6) Contours for water crossing.
- — 3. Bridge Classification Culvert, Estimate, Quantities, and Specifications (each bridge)
- — 4. Foundation Studies (Show cost estimate with Function Code 110)
- The minimum number of soil core holes shall be obtained in accordance with Section 1-301 of the Bridges and Structures Foundation Exploration and Design Manual. Soil core holes shall be obtained at approximately (300 foot) intervals along bridge alignments. Texas cone penetrometer (TCP) tests shall be conducted in all soil types encountered at a maximum of (10 foot) intervals. If single column bents with single drilled shafts are planned, TCP values should be taken at close intervals in the upper (15 feet).
- — 5. Bridge Total Quantities and Cost Estimates (each bridge)
- — 6. Bridge Special Provisions and Specifications (each bridge)
- — 7. Bearing seat elevations for each beam or girder. Top of cap elevations for non-beam type structures.
- — 8. General Guidelines for Bridge Design
- a. The ENGINEER shall prepare a bridge layout of each bridge structure for Company's review and approval. The bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures, Detailing Manual. Soil core hole data is not required for submission of the preliminary bridge layout. **No bridge design work is to be performed until the COUNTY has given the engineer written approval of the preliminary bridge layout.**

Several months may be required, after the preliminary bridge layout is submitted, for the district to obtain approval and/or permits from the following:

- TxDOT Design Division, when applicable:
 - Railroad Companies
 - FHWA
 - U.S. Army Corps of Engineers
 - U.S. Coast Guard
 - Bureau of Reclamation
 - Texas Parks and Wildlife
 - Others

Therefore, the bridge layout should be submitted at the earliest possible date and the ENGINEER's design schedule should reflect this.

- b. All bridge superstructure and substructure design will be reviewed by the Design Division for purposes of verifying structural integrity and optimization of design.
- c. The final bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures Detailing Manual.

Services
Provided By:
ENGINEER COUNTY

8. General Guidelines for Bridge Design (*continued*)

- d. The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. All bridge design shall be in conformance with the Texas Department of Transportation Bridges and Structures Operation and Planning Manual, the current American Association of State Highway and Transportation Officials or American Railway Engineers Association Specifications for railway structures, Standard Specifications for Highway Bridges, including applicable interim specifications, and the Bridges and Structures, Foundation Exploration and Design Manual. The ENGINEER shall furnish design calculations to the Design Division. **The designer and checker shall check all calculations and initial each page.**
- e. Structural steel or prestressed concrete shop drawings, form work drawings and false work drawings are not part of the design requirements. However, contract plans shall be in sufficient detail to permit the preparation of complete shop details for fabrication and erection.
- f. Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a metric scale of 1:20 (1/2 inch equals one foot architect scale) or 1:50 (1/4 inch equals one foot architect scale) to provide clear legible drawings when the drawings are reduced. Lettering shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
- g. Standard drawings for beams, diaframs, railings, armor joints, riprap, etc., shall be furnished to the ENGINEER upon request. These standards shall not be redrawn by the ENGINEER nor shall his title block be transferred to the standard drawings. Modifications to the standards, if necessary, shall be clearly identified and designated by "MOD" in the standard title. Specific special drawings prepared by the ENGINEER shall not be identified as standards.
- h. Bridge layout sheets shall have the same vertical and horizontal scale. Usually a metric scale of 1:100 (1 inch = 10 feet) or 1:200 (1 inch = 20 feet) is used. Sections of existing and proposed structures usually have a metric scale of 1:50 (1 inch = 5 feet). Soil core holes shall be positioned and labeled on the bridge layout plan view. The core hole data shall be plotted at the correct station, at the same vertical scale, and at the proper elevation unless otherwise approved by the Design Division.
- i. APPENDIX C, "GENERAL PLAN CHECKLIST", on pages C-1 thru C-5, more specifically relates various sheet types, details, summaries, standards, etc.
- j. For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
- k. Geometry and structural design errors found after acceptance of bridge plans shall be promptly corrected by the consultant at no cost to the Company.

CONSTRUCTION PHASE SERVICES
(Function Code 320)

Services
Provided By:
ENGINEER COUNTY

CONSTRUCTION MANAGEMENT SERVICES:

The ENGINEER will provide engineering, geotechnical testing and support services for and during the construction of the Project or portions of the Project approved by the COUNTY. Specific (basic and special) services for CONSTRUCTION MANAGEMENT AND SUPPORT by the ENGINEER will include the following:

Construction Bidding:

- 1) The ENGINEER will furnish the COUNTY the necessary copies of approved plans, specifications, notices to bidders, and proposals as prepared under PS&E.
- 2) The ENGINEER will assist the COUNTY on the tabulation of bids, recommendations to the Owner as to the proper action on all bid proposals received, and the preparation of formal contract documents for the award of each construction contract.

Construction Contract Administration and Inspection:

- 3) In general, the ENGINEER will provide the management and engineering support/data required for consultation and advisement to the COUNTY and act as the COUNTY's representative as provided in the General Condition of the Construction Contract.
- 4) The ENGINEER will coordinate and conduct a pre-construction conference (if required).
- 5) Defects and Deficiencies. The ENGINEER will use his best efforts to protect the COUNTY against defects and deficiencies in the work of the Contractor. The ENGINEER will promptly notify the COUNTY of any such defect or deficiency, and take all steps possible to require the Contractor to correct the defect or deficiency.
- 6) Contractor Payment. The ENGINEER will review quantities as submitted by the Contractor and will coordinate with the COUNTY for the preparation of the monthly and final estimates for payment to the Contractor.
- 7) The ENGINEER will provide Project site inspection of the authorized construction contract as follows:
 - a) Project Engineer. The ENGINEER will provide visits by the Project Engineer or a competent representative of the ENGINEER to the site of construction for the purpose of monitoring the Contractor's progress and conformance to the construction contract plans and specifications.
 - b) Resident Engineer and/or Construction Inspector(s). The ENGINEER will furnish the services of a Resident Engineer and/or Construction Inspector(s) for on the site inspection construction to monitor/inspect the Contractor's daily progress and conformance to TxDOT's PS&E specifications.

Miscellaneous Technical Activities:

- 8) Shop Drawings. The ENGINEER will review and check all shop or working drawings furnished by the Contractor.

- 9) Control of Materials & Equipment. The ENGINEER will provide inspection of all materials and equipment furnished/used by the Contractor as follows:
 - a) Review and record all laboratory, shop and mill tests of materials and equipment for compliance with the construction contract specifications.
 - b) Observe and/or perform Project record testing and/or independent assurance testing as outlined in the construction contract specifications.
- 10) Change Orders. When applicable the ENGINEER will prepare the engineering data, including plan sheet drawings, specifications, and estimates, for the preparation of construction contract change orders, which may be required due to actual field conditions encountered or new requirements directed by the COUNTY.
- 11) As Built Drawings. The ENGINEER will develop as built drawings to depict the work as actually constructed. The COUNTY will be furnished five (5) set of prints.

CONSTRUCTION MATERIAL TESTING:

The ENGINEER will provide the COUNTY with construction material testing services for the Project. The services to be provided include sampling and testing of all construction materials as required by the project plans and specifications. All sampling frequencies and test procedures will be performed in general accordance with the Texas Department of Transportation TEX methods (or ASTM methods as required) as outlined in the Guide Schedule for Sampling and Testing (11/07). The construction material testing includes, but is not limited to the following:

- (a) Sampling and laboratory testing of soils and base materials proposed for use in the construction of Project (Roads/Bridges/Misc.) to determine compliance of these materials with project plans and specifications.
- (b) Field density testing of soils and base materials to ensure proper compaction as required by project plans and specifications.
- (c) Field sampling and testing of fresh concrete, and laboratory testing of hardened concrete to determine compliance with project plans and specifications.
- (d) Field compaction testing of asphalt to ensure proper compaction during lay down operations.
- (e) Field inspection, sampling and laboratory testing of asphalt materials to determine their material properties and their compliance with project plans and specifications.
- (f) The ENGINEER will be responsible for concrete batching as well as the asphalt testing at the plants to insure delivery of acceptable material to the job site.
- (g) Any additional laboratory testing as required/requested by the COUNTY and the project plans and specifications.
- (h) Providing accurate and timely reports to the COUNTY and all/other recipients as designated by the COUNTY.
- (i) The ENGINEER will verify the concrete and asphalt designs to assure it is in accordance with TxDOT specifications to be developed by the contractor.

FC 600 – ACQUISITION PROVIDER SERVICES
(for EST. 0 PARCELS, 0 EASEMENTS AND 0 RELOCATIONS/DISPLACEMENTS)
(Services to be provided by L&G Engineering)

Services
Provided By:
ENGINEER COUNTY

1) PROJECT ADMINISTRATION

- — a) Negotiation of Scope of Services for Work Authorization
 i) Acquisition Provider will visit project site with COUNTY personnel if necessary.
- — b) Project Presence at L&G Consultant Office Headquarters
 i) Full Project Office
 (1) No Joint Use of COUNTY or TxDOT facilities
 (2) Open during normal COUNTY and State work hours
 (3) Personnel available to answer questions
 (4) Availability of Project Files
 (5) At least one office staff member is required to be a current commissioned notary public.
- — c) Overhead Costs
 i) Administrative costs
- — d) Communication
 i) Provide monthly progress reports with invoice.
 ii) Participate in project review meetings as determined by the COUNTY.
 iii) Prepare initial property owner contact list for use by the COUNTY in distribution of Acquisition Provider introduction letters.
- — e) File Management
 i) Project and parcel files will be kept in the COUNTY's Office, if necessary. Working files will be kept in the Acquisition Provider's project administrative office, but documents generated or received by the Acquisition Provider will be forwarded to the COUNTY office as they are generated or received by the Acquisition Provider, if necessary.
 ii) Prepare payment transmittal request utilizing standard payment submissions forms with supporting documentation.
 iii) Maintain records of all payments including check number, amount, and date paid, etc.
 iv) Provide copies of all incoming and outgoing correspondence as generated if requested by COUNTY at provider conference.
 v) Maintain copies of all correspondence and contacts with property owners.

2) TITLE SERVICES

- — a) Secure preliminary title commitments from the Title Company that will be providing title insurance. Cost of preliminary title commitments will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work for payment and paid as a separate item.
- — b) Secure title commitment updates in accordance with insurance rules and requirements for parcel payment submissions. Cost of title commitment updates will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work and paid as a separate item.
- — c) Secure title insurance for all parcels acquired, insuring acceptable title to COUNTY OF HIDALGO. Written approval by the COUNTY required for any exception.

Services
Provided By:
ENGINEER COUNTY

3) APPRAISAL

- — a) Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list will be available for review at all District offices or at the Right of Way Division Office at 118 E. Riverside Drive, Austin, Texas, upon request.
- — b) Secure written permission (if necessary) from the owner to enter the property from which land is to be acquired. If the Acquisition Provider and/or the fee appraiser, after diligent effort, is unable to secure the necessary letter of permission from the property owner, a waiver must be obtained, in writing from the COUNTY/TxDOT. Maintain permission letters with appraisal reports.
- — c) Prepare (if necessary) pre-appraisal contact with interest owner(s) for each parcel using acceptable COUNTY/TxDOT forms.
- — d) Contact property owners or their designated representative to offer opportunity to accompany the appraiser on the appraiser's inspection of subject property. Maintain record of contact in file.
- — e) Prepare complete appraisal report for each parcel to be acquired utilizing TxDOT Forms No. ROW-A-5 and ROW-A-6 as applicable. These reports shall conform to TxDOT/COUNTY policies and procedures along with the Uniform Standards of Professional Appraisal Practices.
- — f) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation.
- — g) All completed appraisals will be administratively reviewed by L&G Engineering ROW Office and recommended for approval by TxDOT.
- — h) As necessary, the appraiser will appear and or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing /pre-trial meetings as directed by L&G Engineering and/or TxDOT.
- — i) As necessary, the appraiser will coordinate with review appraiser regarding revisions, comments, or additional information that may be required.
- — j) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.

4) APPRAISAL REVIEW

- — a) Review Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list is available for viewing at all District offices or the Right of Way Division office at 118 E. Riverside Drive, Austin, Texas upon request.
- — b) Review all appraisal reports for each parcel to determine consistency of values, supporting documentation related to the conclusion reached and compliance with TxDOT/COUNTY policies and procedures and the Uniform Standards of Professional Appraisal Practices.
- — c) Prepare and submit to TxDOT the Form ROW-RTA-10 "Tabulation of Values", for each appraisal.

Services
Provided By:
ENGINEER COUNTY

- — d) The cost of the review appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the review appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.

5) **APPRAISAL UPDATES**

- — a) Prepare complete appraisal update for the parcel to be acquired utilizing TxDOT Form No. ROW-A-5, which will be furnished to the provider by TxDOT. These reports shall conform to COUNTY/TxDOT policies and procedures along with the Uniform Standards of Professional Appraisal Practices.

- — b) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation. All completed appraisals will be administratively reviewed by L&G Engineering Right of Way Office and recommended for approval by TxDOT.

- — c) As necessary, the appraiser will appear or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing or pre-trial meetings as directed by the TxDOT/COUNTY.

- — d) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.

- — e) As necessary, the appraiser will coordinate with the review appraiser regarding corrections and/or additional information that may be required.

6) **NEGOTIATION, TASKS AND FEES**

- — a) Analyze appraisal and appraisal review reports and confirm the TxDOT's approved value prior to making offer for each parcel.

- — b) Analyze preliminary title report to determine potential title problems, propose methods to cure title deficiencies.

- — c) Prepare the initial offer letter, instruments of conveyance, and any other documents required or requested by COUNTY /TxDOT on applicable COUNTY /TxDOT forms.

- — d) Mail (Certified Mail Return Receipt Requested) initial offer letter, draft deed, Bill of Rights Brochures and Appraisal Reports to address confirmed with the Appraisal District of Hidalgo County. Maintain follow-up contacts and secure the necessary instruments upon acceptance of the offer for the closing.

- — e) Provide a copy of the appraisal report for the subject property exclusively to the property owner or authorized representative at mailing of initial offer. Maintain original signed Receipt of Appraisal. (unless property owner refuses to sign it).

- — f) Respond to property owner inquiries verbally and in writing within two business days.

- — g) Prepare a separate negotiator contact report for each parcel per contact.

Services
Provided By:
ENGINEER COUNTY

- — h) Maintain parcel files of original documentation related to the purchase of the real property or property interests.
- — i) Advise property owner on the Administrative Settlement process. Transmit to TxDOT any written counter offer from property owners including supporting documentation, and provider recommendation with regard to Administrative Settlements in accordance with COUNTY /TxDOT policy and procedures.
- — j) Prepare final offer letter, documents of conveyance as necessary.
- — k) Appear and provide Expert Witness testimony as an Acquisition Provider when requested.
- — l) Meet at the L&G Engineering ROW office in Mission once per week as agreed-upon with the Right of Way Acquisition Manager/Administrator.
- — m) Provide a monthly progress report per parcel by the 25th of the month with invoice.
- — n) The consultant shall, as part of this proposal, estimates 10% of the parcels identified on Page 37 may end up in condemnation. The consultant shall be available for any meeting/hearings as requested by the COUNTY Attorney.

7) **CLOSING SERVICE FEES**

- — a) Coordinate with COUNTY and Title Company to obtain an updated title commitment along with other Forms and certified copy of the instrument of conveyance necessary when requesting the Parcel Payment from the COUNTY.
- — b) Acquisition Provider shall attend closings and provide closing services in conjunction with Title Company.
- — c) Acquisition Provider shall record all original instruments immediately after closing at the respective County Clerk's Office, except for donations which must be forwarded to TxDOT for acceptance by the Texas Transportation Commission.

8) **RELOCATION ASSISTANCE SERVICES (separate Work Authorization will be issued once relocations have been identified, unless noted otherwise).**

- — a) The amount of relocations or displacements as identified. L&G will provide relocation advisory services. L&G will compute replacement housing supplements (owner occupant and/or tenants)
- — b) L&G will provide advisory services to business displacements and relocate them effectively.
- — c) TxDOT will review, approve and pay for all relocation costs as per the Agreement.

9) **CONDEMNATION SUPPORT**

- — a) Pre-Hearing Support
- — i) Upon receipt of a copy of the final offer, request an updated title commitment for Eminent Domain from the Title Company.
- — ii) Prepare a Bisection Clause for the original set of Legal Descriptions supplied by Surveyor if applicable
- — iii) Use the information from the Title Commitment to join all interested parties on the necessary forms. Spouses of owners must also be joined.

Services
Provided By:
ENGINEER COUNTY

- iv) Upon completion of the necessary forms, prepare a packet containing 2 copies each of the following documents: Title Commitment, Negotiator's Reports, Appraisal Acknowledgment, Preappraisal Contact Sheet, signed and sealed property description, and plat, Final Offer Letter, any correspondence from the land owner or representatives, along with one copy of the appraisal report. Submit packet to the COUNTY Office for submission to the COUNTY Attorney's office.
 - v) Upon receipt of concurrence for the Appraisal Witness, request the update of appraisal.
 - vi) Upon receipt of packet prepared by the COUNTY Attorney which will include Petition for Condemnation, Lis Pendens, Order Appointing Special Commissioners, Order Setting Hearing, Oath of Special Commissioner, and Notice of Hearings, developed by the COUNTY Attorney; the attorney shall file the original petition with the COUNTY Court at Law or other appropriate Court for a cause number to be assigned.
 - vii) The COUNTY attorney shall file the Lis Pendens including the cause number with the COUNTY Clerk's Office.
 - viii) Upon assignment of a court, the COUNTY Attorney shall file the Order Appointing Commissioners with the judge retaining a copy of the Order for the files.
 - ix) Following appointment of Special Commissioners by the judge, the COUNTY shall secure the following documents: Oath of Commissioners signed by the Commissioners, Order Setting Hearing, 2 copies of the Notice of Hearing signed by the Commissioners.
 - x) The COUNTY shall file all originals with the court and send copies marked "copy" to L & G Engineering.
 - xi) The COUNTY Attorney shall send a copy of the petition to the Title Company so that the Title Company can make sure the appropriate parties were joined and that no changes in title have occurred.
 - xii) The COUNTY Attorney shall set the Special Commissioners Hearing after the updated appraisal has been submitted, if there is no change in value. If there is an increase in value, COUNTY will approve the new value and the COUNTY's provider will present a revised offer and a final offer letter and submit a copy of the final offer letter.
 - xiii) The COUNTY Attorney shall coordinate a pre-hearing conference prior to the hearing (the day before or earlier) to discuss facts of the case with the COUNTY, Appraiser, and Negotiator.
 - xiv) After the hearing is set, the COUNTY Attorney shall serve Notices of Hearing to the indicated parties at least 11 days prior to the Commissioner's hearing. If it is necessary to join the Federal Government, be advised that they have an additional 60 days to prepare for the Hearing.
 - xv) Once the notices have been served, the COUNTY Attorney shall file the original notices with the court and send copies stamped "copy" to L&G Engineering ROW Office.
 - xvi) The COUNTY's Attorney shall send a reminder letter 2-3 weeks in advance to the COUNTY Administration offices, Acquisition Provider, the three special commissioners and court reporter concerning Hearing dates.
- b) Post Hearing Support (by COUNTY Attorney)
- i) For the hearing, prepare the necessary forms and Special Commissioners time sheets and submit forms to Hidalgo COUNTY clerk's office.
 - ii) Obtain the signatures of Special Commissioners on the Award of Commissioners and file with the court for the judge's signatures within 48 hours of the Hearing.
 - iii) Give timesheets to Judge. The amount paid to the Special Commissioners is determined by the Judge.
 - iv) Obtain and distribute 3 certified copies of the award as follows: 1 certified copy to the title company with a request for a commitment, 1 certified copy to the COUNTY, 1 certified copy to L&G Engineering with the Commitment to request the warrant in the amount of the Special Commissioners Award.

- v) Send the Commitment and the Award to COUNTY, along with individual special commissioner's billing requesting the payment for their fees.
- vi) File COUNTY warrant in the registry of the court. File a Notice of Deposit with the court and send certified copies to each defendant notifying them of the date of the deposit. The Date of Deposit is the Date of Take.
- vii) Take photograph of the interest to be acquired (if necessary) on the day of deposit for relocation verification.
- viii) Send written notices of the date of deposit to the COUNTY Administration office and all interested parties.
- ix) Appear as Expert Witness as requested. Sub-contractors must also appear as Expert Witnesses as requested.
- x) All acquisition negotiations file indicating all "due diligence" provided by the Acquisition Provider will be directed to the COUNTY Attorney's office for his further handling in accordance to the Eminent Domain process by the COUNTY.

10) COMPENSABLE UTILITIES

Utility Accommodation is an integral factor in road construction and design. Coordination of utility adjustments is a necessary function within planning, design, acquisition and construction and requires the administration of property rights issues, utility policy, and reimbursement of eligible utility adjustments. It includes the following tasks:

- a) Preliminary Design Consultations
 - i) Conduct Field Investigation and review Certificate of Convenience and Necessity boundaries to identify utility providers within the project area. Communications through letter, phone calls and email to establish a contact list. Coordinate data gathering by surveyors and design team. Introduce project to utility providers.
- b) Field Observations and Verifications
 - i) Provide maps to Utility providers to "redline" and identify conflicts. Coordinate exposures and data collection by surveyor. Provide and confirm utility data on project maps. Order Utility Location Service.
- c) Exchange of Information with Utility Providers
 - i) Provide project schedule.
 - ii) Request schedules for utility adjustments.
 - iii) Identify who is responsible for utility process.
- d) Confirmation of Property Interests
 - i) Request Documents.
 - ii) Coordination of data on maps and citation of property interest documents.
 - iii) Confirm utilities are within easements.
- e) Coordination of Agreements
 - i) Identify utilities that are compensable.
 - ii) Determine parties and agreements necessary to complete compensable process.
 - iii) Coordinate execution and processing of Standard Utility Agreements.
- f) Utility Meetings throughout project development
 - i) Set up and coordinate utility meetings during planning, design, acquisition and construction phases.
 - ii) Attend and participate in meetings by other parties.

11) PAYMENT SCHEDULE

- a) Project Administration
 - i) Payment and Milestones
 - (a) Full Project Office
 - (1) Lump Sum Basis (assume 1 year project presence)

- (2) Initial payment of 25% upon establishment of a project office with functional phone and utility services.
 - (3) Remainder paid out in equal monthly installments of 15% starting the following month.
 - (4) Monthly billing to COUNTY OF HIDALGO will be required.
- b) Title Services
 - ii) Payment
 - (a) Per Parcel basis.
 - iii) Milestones
 - (a) 100% upon securing initial title commitment.
- c) Appraisal Services
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% paid upon delivery of complete and acceptable appraisal report
- d) Appraisal Review
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon submission of ROW-A-10
- e) Appraisal Update
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon delivery of complete and acceptable appraisal update.
- f) Negotiation, Task, and Fees
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 80% upon presentation of initial offer.
 - (b) 20% upon successful negotiation and all instruments are recorded.
- g) Closing Service Fees
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon recordation of instrument of conveyance.
- h) Relocation Assistance
 - i) Payment
 - (a) Per Relocation
 - ii) Milestones
 - (a) 100% upon issuance of 90-day vacancy letter.
- i) Compensable Utilities
 - i) Payment
 - (a) By percent complete

ADDITIONAL RESONSIBILITIES

Easements, Letters of Permission, Etc.

The ENGINEER shall be responsible for delineating easements. The ENGINEER will be responsible for securing the necessary legal instruments.

Coordination of Utilities

The ENGINEER shall furnish the COUNTY prints of a project layout which will be distributed by ENGINEER to various utility companies to determine which utilities are in the limits of the project. These shall be preliminary layouts. Upon completion of the preliminary drainage plans and U&D sheets, the ENGINEER shall distribute to the various utility companies and request return. Upon return of these prints, the ENGINEER will schedule a meeting with the various utility companies to discuss potential conflicts and conformance with the State's Utility Accommodation Policy. The ENGINEER is responsible for coordination with the various utility companies for exposing potential conflicts and field ties to uncover utilities in potential conflict areas.

Meetings

Meetings will be held with the FHWA, State Officials, local governments, property owners, utility owners, railroad companies, other consulting firms, etc., as needed or required by the COUNTY. The ENGINEER shall coordinate through the COUNTY for the development of this project with any local entity having jurisdiction or interest in the project (i.e., city, county, etc).

Specifications, Special Provisions, Special Specifications

Use the State's standard specifications or previously approved special provisions and/or special specifications. If a special provision and/or special specification is developed for this project, it shall be in the State's format and incorporate references to approved State test procedures.

Project Manager/Engineer Communication

The ENGINEER shall designate one Texas Registered Professional Engineer to be responsible throughout the project for project management and all communications, including billing, with the COUNTY's Director. Any replacements to the ENGINEER's designated Project Manager/Engineer must be approved by the COUNTY.

Engineering documents produced for the department's engineering projects shall be signed, sealed and dated or CADD sealed in accordance with Administrative Order No. 5-89 and Administrative Circular No. 26-91.

Design Responsibilities

The ENGINEER is responsible for design errors and/or omissions that become evident before, during or after construction of the project. The ENGINEER's responsibility for all questions arising from design errors and/or omissions will be determined by the COUNTY and all decisions shall be final and binding. This would include, but not necessarily be limited to:

1. All design errors and/or omissions resulting in additional design work to correct the errors and/or omissions.
2. Preparation of design documents and detail drawings necessary for a field change due to design errors and/or omissions.
3. Revision of original tracings to the extent required for a field change due to design errors and/or omissions.

The ENGINEER shall promptly make necessary revisions or corrections resulting from the ENGINEER's errors, omissions or negligent acts without additional compensation. Acceptance of the work by the COUNTY will not relieve the ENGINEER of the responsibility for subsequent correction of any such errors or omissions or for clarification of any ambiguities.

Document and Information Exchange

Data, Plan Sheets, General Notes and/or Specifications provided to the COUNTY shall be furnished on 8GB USB flash drives. Each 8 GB flash drive shall have a file titled Table of Contents. The Table of Contents shall indicate the locations of files within the directory structure of the documentation.

General Notes and specifications shall be provided in MS Office 2007 format. Plan sheets shall be provided in Microstation DGN or GEOPAK GPK format. PDF copies of plan sheets shall also be provided.

Two copies of the documentation shall be provided to the COUNTY.

If required, the ENGINEER shall provide to the COUNTY, a CD that contains all the plan sheets for the project. The graphics tape shall be compatible with the COUNTY's computer system.

CD Tape Required (YES or NO): YES

Proposal Time

The time indicated in the proposal and the contract shall include time necessary for reviews, approval, etc.

Office Location

The ENGINEER will perform the services to be provided under this agreement out of their office or offices listed below:

<u>Service</u>	<u>Office Location</u>
PS&E	Mission Office
Schematic	Mission Office
Environmental Document	Mercedes Office

The work effort will be managed out of the Mercedes
(City)
office located at 2100 West Expressway 83,
(Address)
Mercedes, Texas.
(City) (State)

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE

1. Title Sheet
Detailed Index of Sheets
2. Typical Sections
3. General Notes and Specifications Data
4. Estimate and Quantity Sheets
5. Storm Water Pollution Prevention Plan (SW3P) Sheets
6. Traffic Control Plans
 - a. Sequence of Construction Layouts
 - b. Detour Plan/Profile/Typical Sections/Quantities
7. Roadway Layouts
 - a. Roadway Plan/Profile Sheets
 - b. Intersection Plan/Profile Sheets
 - c. Intersection Layouts
 - d. Alignment Layouts/Data
 - e. Ramp Layouts/Profiles
 - f. Connection Roads/U-turns Layouts/Profile
8. Roadway Details
 - a. Concrete Pavement Details/Standards
 - b. Concrete Pavement Terminal Anchorage Details/Standards
 - c. Bridge Approach Details/Standards
 - d. Bridge Terminal Anchorage Details/Standards
 - e. Roadway/Median Barrier Details/Standards
 - f. Curb Details
 - g. Driveway Details/Typical Sections/Standards
9. Signing Layouts and Marking Layouts
10. Traffic Signal Layouts
11. Lighting Layouts
12. Illumination Detail Standards (HMID, HMIF, HMIP, RID)
13. Utility Layouts/Profiles
14. Drainage Area Maps and Hydraulic Data
 - a. General Drainage Area Maps
 - b. Stage-Discharge Curves
 - c. Main Cross-Drainage Culvert/Bridge Hydraulic Data
 - d. Drainage Area Maps/Culverts/Storm Sewer
 - e. Hydraulic Data/Culverts/Inlets/Storm Sewer/Pumps
15. Detailed Drainage Plans
 - a. Drainage Plan/Profile Sheets (Storm Sewer Plan/Profile Sheets)
 - b. Channel Plan/Profiles/Typical Sections
 - c. Box Culvert Plan/Profile
 - d. Pipe Sewer/Culvert Cross Sections

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE (Continued)

16. Drainage Structural Details/Standards
 - a. Inlet Details/Standards
 - b. Manhole Details/Standards
 - c. Junction Box Details/Standards
 - d. Safety End Treatment Details/Standards
 - e. Box Culvert Details/Standards
 - f. Culvert Wingwall Details/Standards
 - g. Excavation-Backfill Diaphragms
 - h. Riprap Details/Standards
 - i. Temporary Pollution and Erosion Control Details
17. Pumphouse Layouts
18. Pumphouse Details
19. Pumphouse Standard Details
20. Bridge Layouts/Profile/Typical Sections*
21. Bridge Details*
 - a. Summary of Bridge Quantities
 - b. Abutments
 - c. Interior Bents
 - d. Spans
 - e. Special details for the specific bridge
22. Bridge Standard Details*
23. Bridge Railing Standards
24. Retaining Wall Layouts/Profiles**
25. Retaining Wall Details**
26. Retaining Wall Standard Details**
27. Guard Fence/Standards and Signal Pole Standards
28. Signal/Electrical Details/Standards and Signal Pole Standards
29. Signing/Markers/Striping Details/Standards
30. Barricade/Construction/Beacon Standards
31. Miscellaneous Standards
 - a. Chain Link Fence Standards
 - b. Bridge End Detail/Standards
 - c. Roadway Clearance Details/Standards
 - e. Attenuator Standards

NOTE: Variations of these plan sheet sequence guidelines may be permitted if approved in writing by the County.

APPENDIX B - PLAN PREPARATION PROCEDURES

1. Title Sheet
The ENGINEER shall be responsible for completing the title sheet as required and formatted by the STATE and as discussed in Part V of the Highway Design, Operations and Procedures Manual. Refer to Section K - Plans, 1 - Title Sheets, page 5-24, for the procedure to be used regarding all plans prepared by the ENGINEER.
2. Project Layout
The project layout shall clearly depict the entire project as it is proposed and will usually be drawn at a scale of 1 inch=100 feet or 1 inch=200 feet, depending on the size of the project.
3. Typical Sections
See Part IV of the Highway Design, Operations and Procedures Manual.
4. Sequence of Work Sheets (Traffic Control Plan)
Clarity and completeness should be the rule to follow in preparing these sheets, with particular attention given to location of construction signs and barricades, lane widths, protection of drop offs, etc. For a reference guide use the Texas Department of Transportation, Texas Manual on Uniform Traffic Control Devices. Usual scale of 1 inch=100 feet and/or 1 inch=50 feet for special locations. A narrative sequence shall be included in the special provisions for the project. Staging of structural elements shall be considered. Provisions for drainage shall be considered, included and indicated during all stages of construction operations.
5. Removal Item Sheets
These sheets indicate removal of existing facilities necessary to the proposed construction. (1 inch=40 feet) (use same scale as plan/profile sheets).
6. Summary Sheets
Summary Sheets are required to indicate type, quantity and/or location of work for individual items of the proposed project.
7. Alignment Layout Sheets
These sheets indicate the horizontal alignment with curve data and coordinates usually tabulated thereon. On some projects, depending on size, this information may be included on the plan profile sheets. Usual scale (1 inch=100 feet) or (1 inch=40 feet).
8. Plan Profile Sheet
Clarity and completeness should be the rule to follow in preparation of these sheets. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet), depending on project complexity.
9. Drainage Area Maps
Usual scale (1 inch=100 feet) and/or (1 inch=200 feet) supplemented by large scale area maps as necessary.
10. Drainage Plan Profile Sheets
These sheets may be required on some projects to clearly depict location of inlets, storm sewer lines, and profile of storm sewer lines and laterals. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet). Storm sewer design does include redesign of storm sewers imposed by utility constraints developing after initial reviews by the STATE and consequential redesign and adjustments.
11. Runoff, Inlet, Storm Sewer and Culvert Sheets
Use standard sheets.

APPENDIX B - PLAN PREPARATION PROCEDURES (Continued)

12. Culvert Cross Sections and Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER for modification of special designs.
13. Manhole and Inlet Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER.
14. Miscellaneous Detail
Curb, Sidewalk, Driveways, etc.
15. Intersection Details
16. Marking Layouts and/or Details
Layouts of the entire project with markings depicted thereon. Usual scale 1:500 (1 inch=40 feet or 1 inch=50 feet). On some projects typical details might suffice.
17. Structural Details
Bridge layout sheets shall have the same horizontal and vertical scale. Usually (1 inch = 10 feet) (1 inch = 20 feet). Sections of existing and proposed structures usually have a scale of (1 inch = 5 feet). Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a (1/2 inch = 1 foot) or (1/4 inch equals 1 foot) architect scale to provide clear legible drawings when reduced. Letters shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
18. Overhead Sign Bridge Layouts
A maximum of four structures may be shown on each layout sheet. The reference to the appropriate overhead sign bridge (OSB) standard and the following requirements shall be shown on the layout:
 - (1) Drilled shaft size and length
 - (2) Soil strength used for design {indicate basis and boring(s) used}
 - (3) Design height
 - (4) Tower height
 - (5) Leg spacings and
 - (6) Design wind speed.

The wind speed design map need not be included in the project plans. Designation of tower member size and anchor bolt size shall not be shown. For OSBs which require special design, the design shall be in accordance with the AASHTO sign specifications (see Item 22 of References on page 49) and to the same loading requirements as for normal standard structures. Structures (special or standard) which will have changeable message signs shall be analyzed by the ENGINEER.

APPENDIX C - GENERAL PLAN CHECKLIST

Services
Provided By:
ENGINEER COUNTY

—	—	Title Sheet
—	—	Project Layout
—	—	Sequence of Work
—	—	Detour Layouts & Profiles
—	—	Construction Pavement Markings
—	—	Signing & Barricades
—	—	Construction Sign & Beacons
—	—	Typical Sections
—	—	Shaping & Finishing Sections
—	—	Slopes Adjacent to Shoulders
—	—	Estimate & Quantities
—	—	General Notes & Specification Data
—	—	Grading Summary
—	—	Miscellaneous Summaries (See following "SUMMARIES" heading)
—	—	Horizontal Curve Data & Alignment Layouts
—	—	Drainage Summaries
—	—	Structure Summaries
—	—	Erosion Control Summary & Details
—	—	Plan/Profile Sheets
—	—	Erosion Control Summary & Details
—	—	Pavement Contours
—	—	Superelevation Transition (If Required)
—	—	Grading Contours
—	—	Guard Fence Layouts
—	—	Storm Water Pollution Prevention Plans (SW3P)
—	—	Drainage Area Maps
—	—	Hydraulic Data
—	—	Drainage Sheets
—	—	Bridge Hydrology Sheets
—	—	Inlet & Manhole Details
—	—	Utility Support Details
—	—	Culvert Cross Sections & Details
—	—	Special Culvert Designs
—	—	Special Drainage Details
—	—	Chain Link Fence Locations
—	—	Ramp Details Sheet
—	—	Removal Item Sheet - Including detours (Shown in detour summary, No payment for removal; subsidiary to construction detours)
—	—	Pavement Details
—	—	Pavement Standard Modification for Concrete Shoulder
—	—	Concrete Pavement Continuously Reinforced (CPCR)
—	—	Concrete Pavement Contraction Design (CPCD)
—	—	Concrete Pavement Details - Jointed Reinforced (Steel Bars) (CPJR)
—	—	Bridge Approach Slab Details
—	—	Vehicle Attenuator Details
—	—	Miscellaneous Details
—	—	Wheelchair Ramps
—	—	Pavement Marking Details
—	—	Modified Standards
—	—	List of Standards
—	—	Permanent Signing Plans & Quantities

APPENDIX C - GENERAL PLAN CHECKLIST (continued)

Services
Provided By:
ENGINEER COUNTY

—	—	Permanent Lighting Plans, Quantities & Standards
—	—	Bridge Layout(s)
—	—	Bridge Details
—	—	Retaining Wall Layout(s)
—	—	Retaining Wall Details
—	—	Pumphouse Details
—	—	Underdrain Details (Retaining Walls)
—	—	Culvert Standards
—	—	Soil Profile
—	—	Temporary Traffic Signals
—	—	Design Cross Sections
—	—	Estimate
—	—	List of Standard Specification, Special Provisions & Special Specifications
—	—	Detour Special Provisions (If Required)
—	—	Construction Time Estimate
—	—	Critical Path Method (CPM)
—	—	Unit Price Documentation

Miscellaneous

—	—	Conduit Requirements
—	—	Traffic signal Requirements

Summaries

(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)

—	—	Salvaging and Placing Topsoil
—	—	Prepare ROW
—	—	Remove Old Structures
—	—	Scarify Existing Pavement
—	—	Remove Old Concrete Curb of Curb and Gutter (C&G)
—	—	Remove Old Concrete Pavement
—	—	Remove Old Concrete Riprap
—	—	Remove Metal Beam Guard Fence
—	—	Galvanized steel Beam Guard Fence (12Ga) (GSBGF)
—	—	Temporary Guard Fence (TEMPGF)
—	—	Summary of Concrete Flumes
—	—	Curbs
—	—	Adjust Manholes & Inlets
—	—	Underdrains
—	—	Base and Pavement
—	—	Large Structure
—	—	Concrete Riprap (RR8 & RR9)
—	—	Temporary Portable Concrete Barrier (PCBR)
—	—	Concrete Traffic Barrier
—	—	Vehicle Attenuator
—	—	Guard Rail Energy Absorbing Terminal (Great System)
—	—	Pavement Markings & Blast Cleaning (Thermoplastic)
—	—	Retaining Walls
—	—	Large Structure Summaries
—	—	Small Structure Summaries

APPENDIX C - GENERAL PLAN CHECKLIST (continued)

Services
Provided By:
ENGINEER COUNTY

Summaries		(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)
___	___	Earthwork (Roadway & Channel) & Channel Details
___	___	Culverts
___	___	Detours
___	___	Seeding or Mulch Sod - Quantity Only
___	___	Inlet & Manholes
___	___	Sidewalks
___	___	Construction Pavement Markings
___	___	Driveways
___	___	Concrete Median
___	___	Storm Sewers
___	___	Head Walls & Safety End Treatments
___	___	Curb Openings
___	___	Manholes
___	___	Chain Link Fence, Remove & Replace Chain Link Fence
___	___	Remove & Relay Reinforced Concrete Pipe (RCP) or Pipe Sewer

EXHIBIT "C"

PROJECT WORK SCHEDULE
FM 1925 (Monte Cristo Rd)
From FM 907 (Alamo Road) to East of SH 68 (Uresti St.)
Length = 2.3 miles

TASK AND DESCRIPTION	FIRM	2013	2014												2015												2016												
		DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	
Phase I: EA, Public Involvement, Schematic																																							
Public Involvement																																							
Develop Alternatives & Matrix	L&G																																						
Advertise & Conduct Public Meeting	L&G																																						
Select TPA	L&G																																						
Schematic																																							
Develop Schematic	L&G																																						
Hydrologic Map	L&G																																						
TxDOT Review & Revisions	TxDOT																																						
TxDOT Schematic Approval	TxDOT																																						
Environmental Document																																							
Draft Environmental Document, Field Visits, etc...	L&G																																						
Submit Final Draft Document	L&G																																						
Agency Review & Revisions	TxDOT																																						
Environmental Decision	TxDOT																																						
Phase II: PS&E, ROW Map & Acquisition																																							
PS&E																																							
Design Survey	L&G																																						
Compensable Utility Oversight	L&G																																						
Outfall Coordination with HCDD #1	L&G																																						
30% PS&E Completion	L&G																																						
60% PS&E Completion	L&G																																						
90% PS&E Completion	L&G																																						
95% PS&E Completion	L&G																																						
100% Mylars	L&G																																						
TxDOT Plan Set Approval	TxDOT																																						
ROW Map																																							
Prepare ROW Map	L&G																																						
TXDOT Review & Revisions	TxDOT																																						
TxDOT ROW Map Approval	TxDOT																																						
ROW Acquisition (12 Parcels)																																							
ROW Release (Dependent on Availability of Funds)	TxDOT																																						
Project Administration	L&G																																						
Title Commitments	L&G																																						
Appraisal Reports	L&G																																						
Appraisal Review Reports	L&G																																						
Appraisal Update Reports	L&G																																						
Approved Values by TxDOT	TxDOT																																						
Acquisition Negotiation Offers	L&G																																						
Title Curative Process	L&G																																						
Title Commitment Updates	L&G																																						
Payments for Parcels	L&G																																						
L&G Condemnation Support Process	L&G																																						
Eminent Domain Proceedings by County	COUNTY																																						
Title Insurance Policies	L&G																																						
Consumation of Outstanding Cases	L&G																																						
Phase III: Proposed Letting																																							
Let Project (Est. Earliest Date: May 2016)	TxDOT																																						
(Dependent on Availability of Funds)																																							
EST 18 MONTHS CONSTRUCTION																																							

EST 18 MONTHS CONSTRUCTION

 L&G ENGINEERING TASK
 TxDOT TASK
 COUNTY TASK

EXHIBIT "D-1"
ESTIMATED PROJECT FEE SCHEDULE
FM 1925 PROJECT (SEGMENT II)
(Limits: from FM 907 (Alamo Road) to East of SH68 (Uresti) Street)

ROADWAY PROJECT:	FM 1925	
LIMITS:	from FM 907 (Alamo Road) to East of SH 68 (Uresti Street)	
EXISTING ROADWAY SECTION:	40-ft Rural	
EXISTING ROW WIDTH:	80-Feet	
PROPOSED ROADWAY SECTION:	4-lane divided urban	
PROPOSED ROW WIDTH:	120FT	
ESTIMATED CONSTRUCTION COST:	\$10,305,000.00	
LENGTH FOR 4-LANE ROADWAY	2.3 Miles	
ESTIMATED PROJECT COSTS	STATE/MPO	* LPA
WORK AUTHORIZATION NO. 1		
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN		
Environmental Assessment with TxDOT	\$ -	\$ 95,000.00
Public Involvement for the project with stakeholders and 1 Public Meeting	\$ -	\$ 25,000.00
Archeological and Historical Research	\$ -	\$ 30,000.00
Engineering Technical Support at Public Mtgs with Layouts etc	\$ -	\$ 24,000.00
Schematic for FM 1925	\$ -	\$ 154,575.00
Hydrological Map	\$ -	\$ 42,000.00
Schematic for intersecting streets (Sharp to 3rd Street)	\$ -	\$ 40,000.00
Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	\$ -	\$ 21,000.00
Preliminary Compensable Utilities Identification on Schematic for Approval by TxDOT/FHWA	\$ -	\$ 18,000.00
Update Schematic based on comments as provide by TxDOT/County for schematic and EA update w/ FHWA	\$ -	\$ 39,000.00
Engineering Technical Support at Public Hearing with Layouts etc	\$ -	\$ 36,000.00
Public Involvement and 1 Public Hearing	\$ -	\$ 25,000.00
SUB-TOTAL	\$ -	\$ 549,575.00
WORK AUTHORIZATION NO. 2		
PHASE II- PS&E and CONSTRUCTION OVERSIGHT		
Complete ROW Map (Estimated 12 Parcels)		\$ 48,000.00
Outfall Identification Preliminary Property Ownership and Hydraulics	\$ -	\$ 36,000.00
PS&E Development (7.5% Engineering Fee)		\$ 772,875.00
Engineering Fee to Create sets of Plans and Submit through TxDOT and Austin Letting		\$ 135,000.00
PS&E Development for OUTFALL(S)		\$ 162,000.00
Field Surveys for Design and Construction		\$ 110,000.00
Permitted Utilities Coordination to adjust	\$ -	\$ 90,000.00
ROADWAY CONSTRUCTION COST	\$ 10,305,000.00	
TxDOT Construction Inspection (11%)	\$ 1,133,550.00	
Eng Consultant Construction Management (18 Months)		\$ 162,000.00
SUB-TOTAL	\$ 11,438,550.00	\$ 1,515,875.00
WORK AUTHORIZATION NO. 3		
PHASE III - ROW Acquisition		
Right-of-Way Costs - Acq. Services @ (est 12 Parcels @ \$13,800/Parcel Avg.)		\$ 165,600.00
Estimated County Attorney Costs for Condemnation (\$15,000/Parcel based on 20% total of parcels)		\$ 36,000.00
Estimated Compensable Utility Mgmt for Acq. of Property Rights and Compensate for Utility Adjust(s) (2) High Pressure Gas Lines and One Parallel Irrigation Line and one Parallel Gas Line		\$ 189,000.00
Estimated Roadway Right-of-Way Costs (422,400 sq/ft @ \$4.5/ sq ft) (80/20)	\$ 1,881,792.00	\$ 19,008.00
COMPENSABLE UTILITY COSTS (Est 2-Pipeline Crossings at \$130,000 ea to lower and encase and 1 Parallel Pipeline and 1 Parallel Irrigation Line both at 150,000 each)	\$ 504,000.00	\$ 56,000.00
SUB-TOTAL	\$ 2,385,792.00	\$ 465,608.00
TOTAL	\$ 13,824,342.00	\$ 2,531,058.00

Work Authorization No. 1 Phase I	FY 13	\$ 549,575.00
Work Authorization No. 2 Phase II	FY 14	\$ 1,515,875.00
Work Authorization No. 3 Phase III	FY 15	\$ 354,800.00

NOT ISSUED
NOT ISSUED
NOT ISSUED

State/FED Estimated Costs
Local Estimated Costs

TOTAL ESTIMATED COUNTY COST:	\$ 2,531,058.00	15.48%
TOTAL ESTIMATED PROJECT COST:	\$ 16,355,400.00	
COUNTY COSTS NOT INCLUDED IN WORK AUTHORIZATIONS	\$ 111,008.00	

* Local Public Agencies (LPA)

EXHIBIT "E"

Sample Work Authorization

HIDALGO COUNTY

Professional Engineering Services

Contract # C-

Work Authorization Form

WORK AUTHORIZATION NO. _____

THIS WORK AUTHORIZATION is made pursuant to the terms and conditions of Article I. of the Agreement made by and between HIDALGO COUNTY, action herein by and through the Commissioner's Court, hereinafter called the "Owner," and, L & G Consulting Engineers, Inc. d/b/a L & G Engineering, professional engineers of Mercedes, Texas, hereinafter called "Engineer".

PART 1. SCOPE OF WORK

The purpose of this Work Authorization is for the Engineer to provide

The scope of services to be provided by the Owner is identified in *EXHIBIT "A" - Scope of Services to be provided by the Owner* attached hereto.

The scope of services to be provided by the Engineer is identified in *EXHIBIT "B" - Scope of Services to be provided by the Engineer* attached hereto.

PART 2. ESTIMATED COST

The estimated cost for services under this Work Authorization is \$ _____.

This amount is based upon the costs outlined in the Estimated Cost Proposal attached hereto as *EXHIBIT "D-1" Fee Schedule*.

PART 3. PAYMENT

Compensation and payment to the Engineer for the services established under this Work Authorization shall be made in accordance with Article 6 of the Agreement.

PART 4. FUNDING

This Work Authorization No. 1 shall be funded through funding source:

Account No. _____

Requisition Number _____ (MUST BE INCLUDED AFTER CC APPROVAL)

EXHIBIT "E"

Sample Work Authorization

PART 5. PERIOD OF SERVICE

This Work Authorization shall become effective on the date of final acceptance of the parties hereto, and terminate upon completion of scopes of the work authorization.

PART 6. RESPONSIBILITIES AND OBLIGATIONS

This Authorization does not waive the parties' responsibilities and obligations provided under the Agreement.

PART 7. ACKNOWLEDGEMENT AND CONFIRMATION

Acknowledgement and confirmation by Hidalgo County _____, Commissioner _____ as to content and detail of this Work Authorization No. 1.

HIDALGO COUNTY

COMMISSIONER PRECINCT NO. __

BY: _____

PART 8. ACCEPTANCE AND APPROVAL

This Work Authorization is hereby accepted, approved by Hidalgo County Commissioners' Court on _____ as indicated below.

THE ENGINEER:

L&G ENGINEERING

THE OWNER:

HIDALGO COUNTY

By: Jacinto Garza, P.E.
President

By: Ramon Garcia,
County Judge

ATTEST:

By: Arturo Guajardo, Jr., County Clerk

LIST OF ATTACHMENTS

Location Map

Exhibit A – Services to be provided by Owner

Exhibit B – Services to be provided by Engineer

Exhibit C – Work Schedule

Exhibit D-1 – Fee Schedule

EXHIBIT "F"

Supplemental Agreement Form

THE STATE OF TEXAS §
 §
COUNTY OF HIDALGO §

SUPPLEMENTAL AGREEMENT NO. _____

TO AGREEMENT FOR PROFESSIONAL SERVICES

This SUPPLEMENTAL AGREEMENT is made pursuant to the terms and conditions of Article 8 of the Agreement made by and between HIDALGO COUNTY, acting herein by and through the Commissioner's Court, hereinafter called the "Owner", and _____, Professional Engineers of, _____, Texas, hereinafter called "Engineer".

WITNESSETH

WHEREAS, the Owner and the Engineer executed the Agreement on the ____ day of _____ 2013 concerning engineering for _____ (hereinafter referred to as the "Project"); and,

WHEREAS, Article ____ of the Agreement, (article title), establishes _____; and,

WHEREAS, it has become necessary to amend the contract to

A. AGREEMENT

NOW THEREFORE, premises considered, the Owner and the Engineer agree that said Agreement is amended as follows:

I, Article ____ of the Agreement, (article title), is revised to

~~All other provisions are unchanged and remain in full force and effect.~~

EXHIBIT "F"

Supplemental Agreement Form

IN WITNESS WHEREOF, the Engineer and the Owner have caused this Supplemental Agreement to the Agreement for Professional Services to be executed as of the _____ day of _____, 2013.

THE ENGINEER:
ENGINEER

BY: _____

THE OWNER:
HIDALGO COUNTY

BY: _____
Ramon Garcia, County Judge

LIST OF ATTACHMENTS
(as required)

EXHIBIT "G"

CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
07/24/2013

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an **ADDITIONAL INSURED**, the policy(ies) must be endorsed. If **SUBROGATION IS WAIVED**, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER The Risk Specialty Group LLC 4801 Woodway Drive Suite 300 East Houston TX 77056	CONTACT NAME: PHONE (A/C, No, Ext): (713) 552-1900 FAX (A/C, No): (713) 513-5411 E-MAIL ADDRESS: tlanders@risksspecialtygroup.com														
INSURED L&G Consulting Engineers, Inc. dba L&G Engineering 2100 W. Expressway 83 Mercedes TX 78570	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left;">INSURER(S) AFFORDING COVERAGE</th> <th style="text-align: left;">NAIC #</th> </tr> <tr> <td>INSURER A : Valley Forge Insurance Company</td> <td></td> </tr> <tr> <td>INSURER B : Continental Insurance Company</td> <td></td> </tr> <tr> <td>INSURER C : Continental Casualty Insurance Co.</td> <td></td> </tr> <tr> <td>INSURER D : Endurance American Specialty Ins. Co.</td> <td></td> </tr> <tr> <td>INSURER E :</td> <td></td> </tr> <tr> <td>INSURER F :</td> <td></td> </tr> </table>	INSURER(S) AFFORDING COVERAGE	NAIC #	INSURER A : Valley Forge Insurance Company		INSURER B : Continental Insurance Company		INSURER C : Continental Casualty Insurance Co.		INSURER D : Endurance American Specialty Ins. Co.		INSURER E :		INSURER F :	
INSURER(S) AFFORDING COVERAGE	NAIC #														
INSURER A : Valley Forge Insurance Company															
INSURER B : Continental Insurance Company															
INSURER C : Continental Casualty Insurance Co.															
INSURER D : Endurance American Specialty Ins. Co.															
INSURER E :															
INSURER F :															

COVERAGES	CERTIFICATE NUMBER:	REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSR	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	GENERAL LIABILITY			5095025836	07/19/2013	07/19/2014	EACH OCCURRENCE
	☒ COMMERCIAL GENERAL LIABILITY		DAMAGE TO RENTED PREMISES (Ea occurrence)				
	☐ CLAIMS-MADE ☒ OCCUR		MED EXP (Any one person)				
			PERSONAL & ADV INJURY				
	GEN'L AGGREGATE LIMIT APPLIES PER:						GENERAL AGGREGATE
	☐ POLICY ☒ PROJECT ☐ LOC						PRODUCTS - COMP/OP AGG
B	AUTOMOBILE LIABILITY			5095025884	07/19/2013	07/19/2014	COMBINED SINGLE LIMIT (Ea accident)
	☒ ANY AUTO		BODILY INJURY (Per person)				
	☐ ALL OWNED AUTOS	☐ SCHEDULED AUTOS	BODILY INJURY (Per accident)				
	☒ HIRED AUTOS	☒ NON-OWNED AUTOS	PROPERTY DAMAGE (Per accident)				
C	☒ UMBRELLA LIAB ☒ OCCUR			5095026016	07/15/2013	07/15/2014	EACH OCCURRENCE
	☐ EXCESS LIAB ☐ CLAIMS-MADE		AGGREGATE				
	☐ DED ☒ RETENTION \$ 10,000						
A	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY			5095025920	07/23/2013	07/23/2014	☒ WC STATU-TORY LIMITS ☐ OTH-ER
	ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH)	☐ Y ☐ N	N/A				E.L. EACH ACCIDENT
	If yes, describe under DESCRIPTION OF OPERATIONS below						E.L. DISEASE - EA EMPLOYEE
							E.L. DISEASE - POLICY LIMIT
D	Professional Liability			PPL10004099100	07/19/2013	07/19/2014	Each Claim Limit
	"claims made"						Aggregate Limit

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (Attach ACORD 101, Additional Remarks Schedule, if more space is required)

CCRMA: HNTB Project No. 40619. Hidalgo County and Texas Department of Transportation are automatically included as additional insureds on General Liability and Automobile and are provided with blanket waiver of subrogation in their favor on General Liability, Automobile and Workers Compensation as required by written contract.

CERTIFICATE HOLDER Hidalgo County 724 N Breyfogle Mission, TX 78572	CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE <CC>

© 1988-2010 ACORD CORPORATION. All rights reserved.



AGENDA
HIDALGO COUNTY
COMMISSIONERS COURT MEETING
December 10, 2013
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a SPECIAL MEETING of the Commissioners' Court will be held at Edinburg Council Chambers, 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

- 1. Roll Call**
- 2. Pledge of Allegiance**
- 3. Prayer**
- 4. Approval of Consent Agenda**
- 5. Open Forum**
- 6. County Judge's Office:**
 - A. AI-41991** Discussion, consideration, and action regarding written Resolution and ballot selection of Appraisal District Board of Directors for 2014-2015.
 - B. AI-42138** Discussion, consideration, and approval of Letter of Support for the Rio Grande Regional Water Authority (RGRWA).
- 7. Executive Officer - Valde Guerra:**
 - A.**
 1. Requesting exemption from competitive bidding requirements under the Texas Local Government Code, Section 262.024(A) (4) "a Professional Service" for the "provision of legal services/representation in connection with litigation."
 2. Requesting engagement with the firm of _____ for the "Provision of Legal Services/Representation in connection with Litigation" and authority to submit letter of engagement
 - B.** Presentation for discussion, consideration and action (if necessary) including, but not limited to the following:
 - 1) Renovations to Former Administration Building 1st and 2nd Floors
 - 2) Update on other ongoing county owned building construction and renovation repair projects
 - 3) Emergency situations occurring since last agenda meeting

A. Hidalgo County

1. **AI-42056** Presentation for discussion, consideration and applicable action for the engagement of professional consulting services provider in connection with securing funding from: Settlement BP Deepwater Horizon Restoration Project including, but not limited to, the following options:
 - A. Exemption from competitive bidding requirements under Texas Local Government Code, Chapter, 262.024(a)(4) a professional service to negotiate an agreement;
 - B. Procure a professional consulting services contract by formally publishing/advertising a solicitation for a Request for Proposals (with qualifications) for same.
2. **AI-42119** Acceptance and approval to exercise the option to extend the current inter-local cooperation agreement for an additional one (1) year (as stipulated/detailed in agreement) between Hidalgo County and the City of Edinburg for MSW & Tire disposal services.
3. **AI-42105** Request by lessor, Triple R Medical Facilities (with recommendation from UCP Director to CC to approve) for additional days on the acceptance date of construction of the "Lease of Office Space for Urban County Program" with extension through end of December 2013 through project #C-13-177-07-23.

B.

Pct. 4

1. **AI-42061** a. Requesting approval of a **professional architectural "on call" services agreement** with **RABA-KISTNER, INC.** for the purposes of Repairs/Renovations/Remodeling and/or Additions/Alterations on a "per project basis" for County owned Buildings/Structures located within Hidalgo County Precinct No. 4, through the forms of an AIA Agreement and as selected for negotiations through County's protocol under the "POOL" of Architects.

APPROVED

- 
- b. Requesting approval of a "professional engineering services" agreement with **L&G CONSULTING ENGINEERS, INC. d/b/a L&G ENGINEERING** for: "Professional Engineering Services" in connection to **Job Specific Project: Environmental Assessment, Public Involvement, Schematic and Hydrologic Design** for the "FM 1925 (from FM 907 (Alamo Road) East to East of SH68 (Uresti Street))" located within **Hidalgo County Precinct No. 4;**
 -  c. Pursuant to Article 14 of the "professional engineering services" agreement with **L&G CONSULTING ENGINEERS, INC. d/b/a L&G ENGINEERING**, is requesting approval to engage the services of sub-contractor (**AMATERRA ENVIRONMENTAL, INC.**) with adherence to insurance provisions required by said article;

HIDALGO COUNTY
Professional Engineering Services
Contract # C-13-336-12-10
Work Authorization Form

WORK AUTHORIZATION NO. 1

THIS WORK AUTHORIZATION is made pursuant to the terms and conditions of Article 1 of the Agreement made by and between **HIDALGO COUNTY**, action herein by and through the **Commissioner's Court**, hereinafter called the "**Owner**," and, **L&G Consulting Engineers, Inc. d/b/a L&G Engineering**, professional engineers of Mercedes, Texas hereinafter called "**Engineer**".

PART 1. SCOPE OF WORK

The purpose of this Work Authorization is for the **Engineer** to provide **Engineering Services required for the preparation of Environmental Assessment with TxDOT, Public Involvement, Schematic and Hydrologic Design for the FM 1925 Project from FM 907 (Alamo Road) to East of SH 68 (Uresti Street).**

The scope of services to be provided by the **Owner** is identified in ***EXHIBIT "A" – Scope of Services to be provided by the Owner*** attached hereto.

The scope of services to be provided by the **Engineer** is identified in ***EXHIBIT "B" – Scope of Services to be provided by the Engineer*** attached hereto.

PART 2. ESTIMATED COST

The estimated cost for services under this Work Authorization is **\$549,575.00**. This amount is based upon the costs outlined in the Estimated **Cost Proposal** attached hereto as ***EXHIBIT "D-1" – Estimated Project Fee Schedule and Man-hour Breakdown***.

PART 3. PAYMENT

Compensation and payment to the **Engineer** for the services established under this Work Authorization shall be made in accordance with **Article 6** of the Agreement.

PART 4. FUNDING

This Work Authorization No. 1 shall be funded through funding source:

Account No.: **4-1303-431-00-124-127-0-841**

Requisition Number: **248609** (MUST BE INCLUDED AFTER CC APPROVAL)

PART 5. PERIOD OF SERVICE

This Work Authorization shall become effective on the date of final acceptance of the parties hereto, and shall serve as a Notice to Proceed as per Article 3, Period of Service on the Agreement. This Work Authorization shall terminate **upon completion of scopes of the work authorization**, as identified on ***EXHIBIT "C" – Work Schedule***.


PART 6. RESPONSIBILITIES AND OBLIGATIONS

This Authorization does not waive the parties' responsibilities and obligations provided under the **Agreement**.

PART 7. ACKNOWLEDGEMENT AND CONFIRMATION

Acknowledgement and confirmation by Hidalgo County Precinct No. 4, Commissioner Joseph Palacios as to the content and detail of this **Work Authorization No. 1**.

**HIDALGO COUNTY
COMMISSIONER PRECINCT NO. 4**

BY: 

PART 8. ACCEPTANCE AND APPROVAL

This Work Authorization is hereby accepted, approved by Hidalgo County Commissioners' Court on December 10, 2013 as indicated below.

**THE ENGINEER:
L&G ENGINEERING**


By: Jacinto Garza, P.E./President

**THE OWNER:
HIDALGO COUNTY**


By: Hon. Ramon Garcia, County Judge

ATTEST:


By: Arturo Guajardo, Jr., County Clerk

Approved by Commissioners' Court
on 12-10-13 RO

LIST OF EXHIBITS


Location Map

Exhibit A – Services to be provided by Owner

Exhibit B – Services to be provided by Engineer

Exhibit C – Work Schedule

Exhibit D-1 – Estimated Project Fee Schedule and Man-hour Breakdown



FM 1925 SEGMENT 2 **FROM FM 907 TO URESTI STREET** **LOCATION MAP (APPROX 2.3 MILES)**

L&G Engineering
 Transportation Consultants
 2100 W. Expressway #3
 Mercedes, TX 78570
 Phone : (956) 565-5813
 Fax : (956) 565-9019

EXHIBIT "A"
Services to be provided by the County

1. The County will issue work authorization to initiate all required services and designate the authorized representative of the coordination of each work authorization.
2. The County will provide copies of all subdivision plats of record and/or in the subdivision process.
3. The County will provide the Engineer with on-going guidance, timely reviews, and decisions necessary to complete services required by the work authorization in order to permit the Engineer to maintain an agreed upon project schedule.
4. The County will provide a Purchase Order and process all acceptable requests for payment in a timely manner.
5. The Work Authorization will identify the Notice to Proceed date.

Exhibit B

Generalized Scope of Services for the FM 1925 (Segment II) Project
Exhibit B

Section 1

GENERAL INSTRUCTIONS

ENGINEER shall mean L&G Engineering.

STATE shall mean Texas Department of Transportation.

COUNTY shall mean the Hidalgo County.

PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: _____

PROJECT/DESCRIPTION: Professional Engineering Services

LENGTH: 2.3 MILES

HIGHWAY: FM 1925 Project

LIMITS: from FM 907 (Alamo Rd) to East of SH 68 (Uresti St.)

EXISTING FACILITY

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☐ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

NOTES

ROUTE AND DESIGN STUDIES

(Function Code 110)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1. Route Location Studies
<u>N/A</u>	<u>N/A</u>	2. Level of Service Analysis
<u>N/A</u>	<u>N/A</u>	3. Traffic Evaluations and Projections
<u>YES</u>	<u>N/A</u>	4. Develop Roadway Design Criteria
<u>YES</u>	<u>N/A</u>	5. Preliminary Cost Estimates
<u>YES</u>	<u>N/A</u>	6. Design Schematic (See Section 7, page 7-1 for schematic layout requirements)
<u>YES</u>	<u>N/A</u>	7. Preliminary Right-of-Way Requirements
<u>YES</u>	<u>N/A</u>	8. Design Concept Conference
		9. Soil Core Hole Drilling
<u>N/A</u>	<u>N/A</u>	a. Pavement (See Section 7, pages 7-3 thru 7-4 for requirements)
<u>N/A</u>	<u>N/A</u>	b. Retaining Walls (See Section 10, page 10-1 thru 10-2 for requirements)
<u>N/A</u>	<u>N/A</u>	c. Miscellaneous Structures (See Section 10, page 10-4 for requirements)
<u>N/A</u>	<u>N/A</u>	d. Bridges (See Section 11, page 11-3 for requirements)

NOTES
SOCIAL, ECONOMIC AND ENVIRONMENTAL STUDIES AND PUBLIC INVOLVEMENT
(Function Code 120)

Services
Provided By:
ENGINEER COUNTY

1. Environmental Reports
All Environmental Reports shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations, Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.
 - a. Environmental Assessments
 - (1) An Environmental Assessment shall be prepared, anticipating a Categorical Exclusion.
 - (2) An Environmental Assessment shall be prepared, anticipating a Finding of No Significant Impact.
 - (3) An Environmental Assessment shall be prepared, anticipating the need for a Draft Environmental Impact Statement.
 - b. Environmental Impact Statement
 - (1) A Draft Environmental Impact Statement shall be prepared. After appropriate interagency and public reviews within time limits prescribed by the Code of Federal Regulations, Title 23, Part 771 and 43 Texas Administrative Code 2.40-2.51, a Final Environmental Impact Statement shall be prepared.
 - (2) A Section 4(f) Statement (Department of Transportation Act) shall be provided by the ENGINEER. The format and content of the statement is found in FHWA Technical Advisory T6640.8A.
2. Public Involvement
All public involvement procedures shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.
 - a. A public involvement meeting(s)/hearing(s) shall be scheduled, coordinated and conducted.*
 - b. Technical assistance, meeting(s)/hearing(s) preparation, maintenance of contracts lists, minutes of meeting(s), exhibit preparation, and other tasks outlined by the COUNTY, shall be provided.
3. Cultural Resources
Formal consultation with the State Historic Preservation Office (SHPO) and the Texas Historical Commission (THC) will be conducted by the COUNTY.
 - a. Historic Structure Studies
A records search and reconnaissance survey shall be performed, and documentation prepared regarding identification efforts, National Register eligibility and potential impacts to historic properties in accordance with the state's historic structure requirements.
 - b. Archeological Studies
 - (1) Files searches shall be conducted to determine if known archeological sites are present; to identify whether these sites have been listed or determined eligible for the National Register of Historic Places or have been designated State Archeological Landmarks; and to identify the need (if any) to perform additional archeological investigations.
 - (2) Archeological reconnaissance will be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.
 - (3) Archeological survey shall be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>NO</u>	Noise and Air Quality Analyses a. Noise Analysis A noise analysis shall be prepared, including predicted noise levels and the consideration and evaluation of noise mitigation, in accordance with the STATE'S Noise Guidelines. The noise analysis report shall be prepared and submitted to TxDOT for review and results shall be made part of the administratively complete document.
<u>YES</u>	<u>NO</u>	b. Air Quality Analysis An air quality analysis shall be prepared in accordance with the STATE'S Air Quality Guidelines. The air quality analysis or a summary of the air quality shall be included in the administratively complete document for the project.
<u>YES</u>	<u>NO</u>	5. Ecological Investigations A wetland survey and if necessary, a wetland delineation shall be conducted and a "wetland finding" shall be provided if necessary. A determination should be made if there are potential federally listed endangered or threatened species that could be impacted. The District will be notified as soon as possible that Section 7 or 10 consultations may be required. Supporting data will be furnished to the district when consultation with the U.S. Fish and Wildlife Service is undertaken.
<u>YES</u>	<u>NO</u>	6. Hazardous Materials The consultant shall prepare a Hazardous Materials Technical report shall be submitted to TxDOT for review and approval. The results shall be made part of the administratively complete document perform an Environmental Site Assessment for hazardous materials impact in accordance with the American Society for Testing and Materials (ASTM) 1528.93 (Transaction Screen Process).
<u>YES</u>	<u>NO</u>	7. General Guidelines for Preparation of Environmental Documents a. The Biological Impact Evaluation Report shall be prepared and submitted electronically to TxDOT. b. All cultural resource reports (i.e. Archeological and Historical Project Coordination Requests (PCRs), background and reconnaissance surveys) will be submitted electronically to TxDOT. c. The draft administratively complete document will be submitted to TxDOT electronically through their FTP site. d. The administratively complete document will be prepared in accordance with the content and format of FHWA Technical Advisory T6640.8A and the TxDOT Administrative Code 43 TAC §2.44. e. The administratively complete document will be submitted to TxDOT electronically through their FTP site. f. Upon completion and approval of the administratively and technically complete document, the Engineer will provide one (1) hard copy to the Client, one (1) hardcopy to the district, and (3) hardcopies to TxDOT ENV. g. Exhibits in the administratively complete document shall be color copies and text shall be black and white.

RIGHT-OF-WAY DATA

(Function Code 130)

Services
Provided By:
SURVEYOR COUNTY

NOTE: No work involving right-of-way (ROW) data is to be performed until the COUNTY has given the ENGINEER written approval of the final location of the proposed ROW lines as approved by TxDOT.

A. RIGHT-OF-WAY MAPPING:

1. PURPOSE:

The purpose of right-of-way mapping is to prepare documents suitable for the acquisition of real property interests and the probable issuance of a title policy.

2. DEFINITIONS:

For purposes of this Contract, the following definitions shall apply:

2.1. Abstract Map – A drawing to scale prepared from record documents depicting proposed right-of-way lines, existing right-of-way lines, easement lines, and private property lines with relevant grantee names, recording data, and recording dates.

2.2. Closure/Area Calculation Sheet – A computer generated print-out of the area and the perimeter bearings, distances, curve data, and coordinates of an individual parcel of land to be acquired.

2.3. Access Denial Line – A line which indicates specific location where access to the roadway is denied.

2.4. Property Descriptions – A written metes and bounds description delineating the area and the boundary and describing the location of an individual parcel of land unique to all other parcels of land.

2.5. Owner – The most current title holder of record as determined by a study of the Real Property Records.

2.5. Place Plan – An 8 1/2" inch by 11" inch drawing to scale depicting all the information shown on the right-of-way map regarding an individual parcel of land to be acquired.

2.7. Parent Tract – A unit or contiguous units of land under one ownership, comprising a single marketable tract of land consistent with the principle of highest and best use. A parent tract may be described by a single instrument or several instruments. A single parent tract cannot be severed by a public right-of-way, easement, or separate ownership which destroys unity of use.

2.8. Parent Tract Inset – A small line drawing, to an appropriate scale, of the parent tract perimeter placed upon the right-of-way map in the proximity of the respective parcel. Parent tract insets are used in cases where the parent tract cannot be shown to the same scale as the right-of-way map. Since parent tract insets are used to identify the limits and location of parent tracts, they should include public right-of-ways, utility easements and fee strips, and identifiable water courses which bound the parent tract.

2.9. Point of Beginning (P.O.B.) – A corner of the parcel of land to be acquired, located on the proposed right-of-way line and being the beginning terminus of the first course of the property description.

2.10. Point of Commencing (P.O.C.) – A monumented property corner which can be identified in the Real Property Records and is located outside the proposed right-of-way corridor. For title purposes, the point of commencing should be a monumented back corner of the parent tract. In the event a monumented back corner of the parent tract cannot be recovered, the nearest identifiable monumented property corner located outside the proposed right-of-way corridor may be used.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
SURVEYOR COUNTY

- 2.11. Preliminary Right-of-Way Layout/Abstract Map – A drawing to scale depicting proposed right-of-way lines, existing right-of-way lines, proposed pavement, access denial lines, the proposed centerline alignment, private property lines, easement lines, visible improvements, visible utilities, the station and offset from the centerline alignment to each Point of Curvature (PC), Point of Tangency (PT), and angle point in the proposed right-of-way lines and to each PC, PT, and angle point in the existing right-of-way lines in areas of no proposed acquisition. *(Reference Sample on CD Attached)*
- 2.12. Right-of-Way Maps/Property Description/Parcel Plats – A series of 22 inch by 34 inch and 11 inch by 17 inch drawings to scale depicting the results of relevant elements of records research, field work, analysis, computation, and map making required to determine title, delineate areas and boundaries, locate and describe utilities and improvements to the extent necessary to appraise the value and negotiate the acquisition of individual parcels of private land for a proposed right-of-way project. *(Reference Sample on CD Attached)*

3. **WORK TO BE PERFORMED:**

N/A N/A

3.1. Preliminary Right-of-Way Layout/Abstract Map:

An abstract map shall be prepared sufficient to determine the following:

- 3.1.1. Any and all interests of public record held in the land to be acquired.
- 3.1.2. The total record holdings of an owner contiguous to land to be acquired from that owner.
- 3.1.3. Any and all interests in land to be acquired held in common (shopping mall parking lots, subdivision reserves, etc.)
- 3.1.4. Any and all improvements proposed by other agencies which may have a bearing on project development.
- 3.1.5. All called monuments, bearings, and distances as per recorded information.

N/A N/A

3.2. Right-of-Way Map:

The SURVEYOR shall field locate property corners, existing right-of-way markers, improvements, visible utilities, verify and update the planimetric file, if provided, and as directed by the ENGINEER.

A right-of-way map shall be prepared for each proposed right-of-way project. A right-of-way map shall include a title sheet, an index sheet, a survey control index sheet, a horizontal and vertical control data sheet, and sufficient plan sheets to cover the proposed project, or as directed by the ENGINEER. The STATE has developed standard title sheets, index sheets, and plan sheets, copies of which the SURVEYOR shall request and secure for all purposes of this Contract. Plan sheets shall include, but need not be limited to, the following items of information.

By mutual agreement between the Texas Board of Professional Land Surveying and the TxDOT, right-of-way maps need not be signed and sealed by a Registered Professional Land Surveyor.

- 3.2.1. Proposed right-of-way lines shall be delineated with appropriate bearings, distances, and curve data. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.
- 3.2.2. Existing right-of-way lines shall be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
SURVEYOR COUNTY

- 3.2.3. The proposed project baseline alignment shall be delineated with appropriate bearings, distances, and curve data. Curve data shall include the station of the curve Point of Intersection (PI), radius, delta angle, arc length, tangent length, long chord bearing and distance, and the N and E coordinates of the curve PI. All alignment PCs, PTs, and even 500 foot stations shall be labeled as to station.
- 3.2.4. Proposed paving lines combined with relevant existing paving lines shall be shown to the extent necessary to compile a complete picture of proposed traffic movements. Proposed paving on the final mylars submitted to the ENGINEER shall be shaded with a dot pattern or highlighted by some other means acceptable to the ENGINEER.
- 3.2.5. Access denial lines shall be shown sufficiently to indicate areas where access is to be denied and where access is to be permitted if required by the ENGINEER.
- 3.2.6. Private property lines shall be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.
- 3.2.7. Porción lines, subdivision lines and survey lines shall be shown and identified by name and Porción number.
- 3.2.8. County lines and city limit lines shall be located and identified by name.
- 3.2.9. A north arrow shall be shown on each sheet, and, if possible, located in the upper right corner of the sheet.
- 3.2.10. Monumentation set or found shall be shown and described as to material and size.
- 3.2.11. A station and offset shall be shown for each PC, PT, and angle point in the proposed right-of-way lines. Stations and offsets shall be with respect to the proposed centerline alignment.
- 3.2.12. Intersecting and adjoining public right-of-ways shall be shown and identified by name, right-of-way width, and recording data.
- 3.2.13. Railroads shall be shown and identified by name, right-of-way width, and recording data.
- 3.2.14. Utility corridors shall be identified as to easement or fee and recording information shall be identified.
- 3.2.15. Easements and fee strips shall be shown and identified by width, owner, distance of easement to a property corner of the parent track, and recording data.
- 3.2.16. Building lines or set-back lines shall be shown and identified.
- 3.2.17. Visible improvements located within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be shown and identified.
- 3.2.18. Structures shall be identified as commercial or residential, by number of stories, and as to type (brick, wood frame, etc.).
- 3.2.19. Structures which are severed by a proposed right-of-way line shall be dimensioned to the extent necessary to completely delineate the severed parts.
- 3.2.20. Parking areas, billboards, and other on-premise signs which are severed by a proposed right-of-way line shall be dimensioned to the extent necessary to delineate that portion of the parking area, billboard, or sign which is located within the proposed right-of-way corridor.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
SURVEYOR COUNTY

- 3.2.21. In cases where structures are located outside the proposed right-of-way corridor and within 25 feet of a proposed right-of-way line, the shortest distance between the structure and the proposed right-of-way line shall be shown and field verified.
- 3.2.22. Visible utilities located within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be shown and identified.
- 3.2.23. The location of underground utilities and fuel storage tanks situated within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be determined and shown as required by the ENGINEER. The visible location of stand pipes, vents and filler caps in conjunction with available design and as-built drawings may be used to determine a most probable location and size in the event an actual location is indeterminable.
- 3.2.24. Points of commencing and points of beginning shall be shown and labeled. Points of beginning shall be shown with their respective N and E surface coordinates. As an exception, a point of commencing will not be required in the case of a total taking without a remainder.
- 3.2.25. Each parcel of land to be acquired shall be identified by a parcel number which shall appear in the ownership tabulation and on the right-of-way map in the proximity of the respective parcel. If the SURVEYOR is unfamiliar with the criteria used by the STATE to assign parcel numbers, he shall seek the assistance of the ENGINEER at the time the abstract map is complete. THE SURVEYOR SHALL SEEK ASSISTANCE FROM THE ENGINEER IN DEVELOPING AN OWNERSHIP TABULATION TABLE.
- 3.2.26. An ownership tabulation shall be shown which shall include the parcel number, existing area of the parent tract, lot(s) and block(s) constituting the parent tract when applicable, owner's name, type of conveyance, film code, county clerk's file number, taking area, and remaining area of the parent tract located left and/or right of the centerline alignment. Types of conveyances, film code and file number refer to conveyances into the STATE and will be added to the right-of-way map by the STATE at a later date. Several blank lines shall be provided in the tabulation block to facilitate future map additions.
- 3.2.27. A parent tract inset shall be shown for each parent tract which cannot be shown to scale on the right-of-way map. The use of broken scale lines should be avoided. When parent tract insets are used, the point of commencing with the appropriate bearing and distance to the point of beginning may be shown on the parent tract inset.
- 3.2.28. A note shall be included on the title sheet and each map sheet stating the source of bearings, coordinates, and datum used.
- 3.2.29. Appropriate notes shall be included on the title sheet and each map sheet stating the following:
- Month(s) and year abstracting upon which the map is based.
 - Month(s) and year field surveys were conducted upon which the map is based.
 - Month and year the map was completed by the SURVEYOR.
- 3.2.30. The right-of-way CSJ number, if available, shall be shown on each right-of-way map sheet.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
SURVEYOR COUNTY

3.3. Exhibits:

An Exhibit shall be prepared for each parcel or tract consisting of a property description and a parcel plat.

N/A

NO

3.3.1. Property Description:

A property description shall be prepared for each parcel of land to be acquired. Standard formats for property descriptions, copies of which the SURVEYOR shall request to the ENGINEER and secure for all purposes of this Contract. Property descriptions shall include, but need not be limited to, the following items of information.

All property descriptions shall be signed and sealed by a Registered Professional Land Surveyor. The property description shall begin with a general description which shall include as a minimum:

- a. State, County, and Survey within which the proposed parcel of land to be acquired is located.
- b. A reference to unrecorded and recorded subdivisions by name, lot, block, and recording data to the extent applicable.
- c. A reference by name to the grantor and grantee, date and recording data of the most current instrument(s) of conveyance describing the parent tract. Use execution dates in deed references as opposed to recording or filing dates. In any case, the property description shall make clear which date is being used.

The property description shall continue with a metes and bounds description which shall include as a minimum:

- d. A point of commencing.
- e. A point of beginning with the appropriate N and E surface coordinates.
- f. A series of courses, identified by number and proceeding in a clockwise direction, describing the perimeter of the parcel of land to be acquired, and delineated with appropriate bearings, distances, and curve data.

Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance. Each course shall be identified either as a proposed right-of-way line, and existing right-of-way line, or a property line of the parent tract. Each property line of the parent tract shall be described with an appropriate adjoiner call.

- g. A description of all monumentation set or found shall include, as a minimum, size and material.
- h. A reference to the source of bearings, coordinates, and datum used.

N/A

NO

3.3.2. Parcel Plat:

A parcel plat shall be prepared for each parcel of land to be acquired. The STATE has developed standard formats for parcel plats, copies of which the SURVEYOR shall request from the ENGINEER and secure for all purposes in this Contract. Parcel plats shall include each and every item of information shown on the right-of-way map which concerns the individual parcel. All parcel plats shall be signed and sealed by a Registered Professional Land Surveyor.

Services
Provided By:
SURVEYOR COUNTY

4. DELIVERABLES:

In preparing right-of-way maps, the following is an outline of the work to be submitted (records should be delivered in a binder):

<u>N/A</u>	<u>NO</u>	4.1. An Abstract Map of the current record title holders included in the Preliminary Map showing the proposed schematic and existing right-of-way as per General Specifications.
<u>N/A</u>	<u>NO</u>	4.2. A Right-of-Way map for the project limits under cover of Title Sheet, Index Sheet, Control Data Sheet, and Exhibits of the property descriptions and parcel plats as per General Specifications.
<u>N/A</u>	<u>NO</u>	4.3. Appropriate monuments on the proposed right-of-way lines at intersecting property lines, and at all PCs, PTs, angle points, intersecting right-of-way lines of side streets, and at 1,000 foot stations.
<u>N/A</u>	<u>NO</u>	4.4. Appropriate monuments on the existing right-of-way lines in areas of no acquisition at all PCs, PTs, angle points, and 1,000 foot stations, and as directed by the ENGINEER.
<u>N/A</u>	<u>NO</u>	4.5. A SURVEYOR's report, outlining the approach, reasons or basis for the existing right-of-way determination, and conclusions made.
<u>N/A</u>	<u>NO</u>	4.6. Records used to establish ownership.
<u>N/A</u>	<u>NO</u>	4.7. ROW and parcel filed notes signed and sealed by a RPLS.
<u>N/A</u>	<u>NO</u>	4.8. Computation sheets of survey closures, ground surveys, etc. used to develop plats and meets and bound information.
<u>N/A</u>	<u>NO</u>	4.9. Items indicated under the Automation Requirements Section 6.
<u>N/A</u>	<u>NO</u>	4.10 Completed (Attached) Checklist with submittal of ROW Map etc.

5. GENERAL REQUIREMENTS:

For purposes of this Contract, the following general requirements shall apply:

- NOT INCLUDED IN
WORK AUTHORIZATION NO. 1**
- 5.1. Copies of instruments of record submitted to the ENGINEER shall be indexed by parcel number.
 - 5.2. Coordinates appearing on right-of-way maps, on parcel plats, and in property description shall be surface coordinates based on the Texas State Plane Coordinate System. The combined adjustment factors (sea level factor x scale factor) which have been developed by the STATE for its use are as follows:
 - 5.2.1. In (List Applicable Counties): Counties (----- Zone), grid coordinates are multiplied by a combined adjustment factor of 1.xxxxxx to obtain surface coordinates. For work in Counties other than those listed, the ENGINEER will provide the combine adjustment factor.
 - 5.3. Line and curve tables may be used when necessary.
 - 5.4. The number of centerline alignment stations to be shown on a single plan sheet shall be restricted to the extent necessary to allow approximately 4 inches between match lines and sheet borders for future details and notes.
 - 5.5. A minimum 4 inch by 4 inch space shall be reserved at the bottom right corner of each map sheet for future revision notes.

Services
Provided By:
SURVEYOR COUNTY

6. AUTOMATION REQUIREMENTS:

In addition to standard hard copy plots and mylar copies, the following will be required electronically:

- 6.1. Right-of-way maps and parcel plats shall be prepared using a *Micro Station* software graphics system capable of producing graphics files that can be plotted and viewed without further modification or conversion using the State's *Micro Station V8* graphics system.
- 6.2. It is the intent of the ENGINEER to secure graphics files which have elements of equal integrity, singularity, and attributes as elements prepared using the State's *Micro Station V8* graphics system.
- 6.3. For purposes of clarity, consistency, and ease of utilization, the SURVEYOR shall request and secure standards relevant to right-of-way mapping to the extent necessary to ensure that the needs of the ENGINEER are met. This includes, but may not be limited to, TxDOT seed file and corresponding units.def file, TxDOT font resource file, TxDOT GEOPAK SMD file, TxDOT DGNLIB, associated cell libraries and custom line styles, and other files as deemed appropriate for the project.
- 6.4. Graphics files furnished to the ENGINEER by the SURVEYOR shall be submitted on a Compact Disk CD, DVD or USB, in a format compatible with the STATE's computer system. The SURVEYOR shall confer with the ENGINEER regarding acceptable media and formats before making submissions. The SURVEYOR shall request and secure a Consultant File Index form provided by the ENGINEER, to be completed by the SURVEYOR, and to be submitted to the ENGINEER along with the graphics files.
- 6.5. Property descriptions shall be prepared using a computer word processing system capable of producing data files readable using *Microsoft Office Word Version 2007* word processing software.
- 6.6. Data files furnished to the ENGINEER by the SURVEYOR shall be submitted in ACSII format on a CD, DVD or USB.
- 6.7. Provide to the ENGINEER electronic copies of all instruments of record acquired pursuant to a work authorization.

7. GENERAL SPECIFICATIONS:

For purposes of this Contract, the following general specifications for right-of-way mapping shall apply:

- 7.1. Completed right-of-way maps shall be submitted to the ENGINEER on single or double matte mylar, 22 inches by 34 inches in size with a 21 inch by 32 inch printed border positioned ½ inch from the top, bottom, and right edge of the sheet. Two copies on 11 inch by 17 inch paper will also be supplied to the ENGINEER.
- 7.2. Parcel plats shall be submitted to the ENGINEER on 8 ½ inch by 11 inch bond paper with respective borders of 7 ½ inches by 10 inches, positioned ½ inch from the top, bottom, and right edge of the sheet. Match lines shall be used where more than one sheet is required.
- 7.3. Right-of-way maps shall be drawn to a scale of 1 inch = 50 feet. An appropriate scale other than 1 inch = 50 feet may be used on some proposed right-of-way projects upon prior approval by the ENGINEER.

Services
Provided By:
SURVEYOR COUNTY

- 7.4. Since right-of-way maps are reduced in size by one-half for archiving purposes, the smallest size lettering acceptable on a right-of-way map shall be 1/10 of one inch (Leroy #100). A right-of-way map which contains any lettering smaller than 1/10 of one inch will not be accepted by the ENGINEER.
- 7.5. Parcel plats shall be drawn to a preferred scale of 1 inch = 50 feet. An appropriate scale other than 1 inch = 50 feet may be used on some proposed right-of-way projects upon prior approval by the ENGINEER. In the case of a very large parcel which would be difficult to show with clarity on a single 8 ½ inch by 11 inch sheet, the SURVEYOR shall use multiple 8 ½ inch by 11 inch sheets with matching lines.
- 7.6. The smallest size lettering acceptable on a parcel plat shall be 0.06 of an inch (Leroy #60).
- 7.7. Property descriptions shall be submitted on 8 ½ inch by 11 inch bond paper.
- 7.8. The ENGINEER has encountered a number of mylar products which are considered unacceptable. The SURVEYOR shall confer with the ENGINEER regarding mylar products he intends to use which have not been previously used on State projects.
- 7.9. Zip-A-Tone or other similar stick-on products shall not be used on right-of-way maps or parcel plats.

8. **ADHERENCE TO STANDARDS:**

For purposes of clarity, consistency, and ease of understanding, the COUNTY, as an acquiring agency of private property for public use, has adopted the STATE standards and formats for right-of-way mapping which have proven to facilitate the processes of negotiation, appraisal, relocation assistance, and condemnation. It shall be the responsibility of the SURVEYOR to adhere to these standards and formats to every extent possible to ensure that the needs of the acquiring agency are met.

SAMPLES ATTACHED FC 130:

- PRELIMINARY Right-of-Way Layout / Abstract Map
- Right-of-Way Map, Field Notes, Parcel Sketches and Area Computation Sheets

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

ROW MAP CHECKLIST

Consultant: _____
Contract/WA# _____
Responsible Office: _____
Project Manager: _____
County: _____
Highway: _____
RCSJ: _____
CCSJ: _____

As the responsible consultant project manager, I hereby certify that the attached ROW Map has undergone a QA/QC review, with the following applicable items specifically checked for accuracy, completeness and constructability (as noted by Checkmarks)

Signature Date

Printed Name

**(This Checklist must be signed by
the RPLS and turned in with all
proposed ROW Projects.**

MAP:
General

- ___ All documents have been proofread and are accurate.
- ___ Title Commitments for each individual parcel.
- ___ Graphics files compatible with Micro station and Word software are provided.
- ___ Photos of proposed ROW staking included.
- ___ Field notes and Parcel Plats are numbered continuous.
- ___ Scale shall be 1"=50' or 1"=100".

Title Sheet Requirements

- ___ Title and description of project including county, limits, etc.
- ___ Vicinity map with beginning and ending station
- ___ Equations and Exceptions
- ___ Index
- ___ Legend
- ___ Title block completely filled out with Construction and R.O.W. CSJs'
- ___ List all Major Utilities from Station to Station

Individual Map Sheet Requirements

- ___ Sheet size 34" X 22"
- ___ Text legible when reduced to half-scale.
- ___ Title block completely filled out with R.O.W. CSJ
- ___ Matchlines
- ___ Project layout sheet
- ___ Existing utility lines and easements, deed reference, as shown on Schedule "B" of the Title Commitment, and defined on parcel plats

Existing information:

- ___ R.O.W. lines
- ___ Whole property or whole property inset
- ___ Roadways
- ___ Survey, county, and city limit lines shown and labeled
- ___ Improvements shown and labeled (*see below*)
- ___ Monumentation i.e. P.C., P.T., Break Points
- ___ North arrow
- ___ Scale
- ___ Property lines

- ☐ Property descriptions i.e., lot, block, tract, subdivision, etc...
- ☐ Identify existing and proposed access denial locations (if applicable)

Proposed information:

- ☐ #5- 2-ft iron road set monumentation i.e. P.C., P.T., Break Points and 1000' stations at proposed ROW lines and where existing ROW line is the proposed ROW.
- ☐ Survey and R.O.W. lines
- ☐ Basis of bearings
- ☐ Parcel bearings and distances correspond with traverse sheet
- ☐ Outside ties (P.O.C.) corresponds with field notes
- ☐ Point of beginning (P.O.B.) established on proposed R.O.W. line
- ☐ Parcel tied to baseline
- ☐ Baseline information shown i.e. Stationing, bearings, curve data, etc...
- ☐ Conveyance information shown in tables i.e. parcel number, grantors name, amount of take, remainder etc.
- ☐ Math checked on remainder

Improvements:

- ☐ Improvements bisected or within 25' of proposed R.O.W. line are shown on map with stationing and distance from proposed R.O.W. line. Buildings are labeled and dimensioned.
- ☐ Off-premise outdoor advertising signs within proposed R.O.W. are shown and labeled.

Utilities:

- ☐ All utilities within or crossing existing and proposed right of way are shown and labeled as to size, easement or fee width, and recording data of instrument.
- ☐ Location of underground storage tanks and/or filler caps are shown and labeled

FIELD NOTES - Heading

- ☐ County
- ☐ Highway
- ☐ Parcel number
- ☐ R.O.W. CSJ
- ☐ Construction CSJ

General Description or "preamble"

- ☐ Area of parcel to be acquired is shown in acreage (0.000 for rural land and/or square feet (to nearest whole sq. ft.) for urban land or smaller parcels

Parent tract data is shown:

- ☐ Size of parent tract
- ☐ Survey data or lot, block, and subdivision
- ☐ Name of last recorded seller and buyer
- ☐ Date, volume and page or document number of last recorded conveyance
- ☐ Records and county of last recorded conveyance

Beginning Description

- ☐ Point of commencement is on outside tie and is described accurately by bearings and distances as it leads to the point of beginning.
- ☐ Point of beginning is on proposed R.O.W. line

Particular Description

- ☐ Traverse calls are clockwise sequence
- ☐ Bearings and distances correspond exactly with map, parcel sketch, and traverse sheet
- ☐ Bearings are to nearest whole second and distances are to the nearest one-hundredth of a foot
- ☐ Calls are numbered
- ☐ Denial of access shall be described from beginning to end (if applicable)

Closing Description

- ☐ Last call leads back to P.O.B.
- ☐ Restates area of parcel

- ☐ Establishes taking in existing road R.O.W. if applicable
- ☐ Legal description is referenced to Plat
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)

PARCEL SKETCH:

- ☐ Shows P.O.B. and P.O.C.
- ☐ All data corresponds exactly with Map and Field Notes
- ☐ Sheet size is no larger than 8 1/2" x 11"
- ☐ Plat closely matches example provided
- ☐ Plat referenced to legal description
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)
- ☐ Existing utility lines and easements (deed reference, if available);

TRAVERSE SHEET

- ☐ Computations show area to be acquired in sq. ft. or acres, whichever is applicable
- ☐ Computations show area that is existing road R.O.W. if applicable
- ☐ Traverse calls are in clockwise sequence
- ☐ Error of closure meets the following:

Secondary rural	.0003
Primary rural - secondary urban	.0002
Urban or industrial	.00013

**NOT INCLUDED IN
WORK AUTHORIZATION NO. 1**

FIELD SURVEYING AND PHOTOGRAMMETRY

(Function Code 150)

Services
Provided By:
ENGINEER COUNTY

B. DESIGN AND CONSTRUCTION SURVEYS:

1. PURPOSE:

The purpose of a “design survey” is to provide field information in support of transportation systems design.

The purpose of a “construction survey” is to provide field data in support of highway construction.

2. DEFINITIONS:

A “design survey” is defined as the combined performance of research, field work, analysis, computation, and documentation necessary to provide detailed topographic (3-dimensional) mapping of a project site. A design survey may include, but need not be limited to, cross-sections or data to create cross-sections and Digital Terrain Models (DTM), horizontal and vertical location of utilities and improvements, detailing of bridges and other structures, review of right-of-way maps, establishing control points, etc.

A “construction survey” is defined as the combined performance of reconnaissance, field work, analysis, computation, and documentation necessary to provide the horizontal and vertical position of specific ground points to be used by the construction contractor for determining lines and grades.

3. WORK TO BE PERFORMED:

3.1. Design Surveys:

In performing design surveys, the following will be requested by the ENGINEER on an as needed basis, but need not be limited to:

<u>NO</u>	<u>N/A</u>	3.1.1.	Obtain or collect data to create cross-sections and digital terrain models including any missing voids identified by the ENGINEER.
<u>NO</u>	<u>N/A</u>	3.1.2.	Locate all existing utilities, overhead and underground. <u>Horizontally</u> – The SURVEYOR shall call the 1-800 number for the utilities to be marked on the ground as well as any city water and sewer lines. He shall tie all visible utility crossings with name, address and Phone #'s of utility companies. The ENGINEER will coordinate with the utility companies and jointly the SURVEYOR and the ENGINEER will identify which utilities were missed and need to be tied down. <u>Vertically</u> – The ENGINEER shall identify all utilities that are potential conflicts and that need to be tied vertically and coordinate the exposure. The ENGINEER will advise the SURVEYOR in writing of the needed vertical ties and he will provide the required information to the ENGINEER promptly.
<u>NO</u>	<u>N/A</u>	3.1.3.	Locate topographical features and existing improvements.
<u>NO</u>	<u>N/A</u>	3.1.4.	Provide details of existing bridge structures. The SURVEYOR shall tie the top of deck and/or top of cap elevations at the Profile Grade Line (PGL) and the edges of slab at bent locations.
<u>NO</u>	<u>N/A</u>	3.1.5.	Provide details of existing drainage features, such as culverts, manholes, inlets, etc. The SURVEYOR will tie horizontally and vertically all existing storm drain systems that lie within the existing & proposed ROW including the elevation of the outfall of said recovered existing storm drain systems.
<u>NO</u>	<u>N/A</u>	3.1.6.	Profile and cross section intersecting streets for ties into project (500-ft. beyond the proposed ROW per schematic and 20-ft wider than the existing ROW of intersecting street).

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
<u>NO</u>	<u>N/A</u>	3.1.7. Cross section irrigation crossings for a distance of 20-ft beyond the proposed ROW at 100-ft intervals in a DTM file. Provide a complete description of irrigation appurtenances as identified by the engineer sample layout. The SURVEYOR will meet with the ENGINEER before he ties down any irrigation lines. The ENGINEER will provide him the existing Irrigation District Maps and the A&M Data of existing irrigation lines that are identified of record. He will follow the sample given to him by the ENGINEER and tie the structures horizontally and vertically and include in the field books to be submitted.
<u>NO</u>	<u>N/A</u>	3.1.8. Cross section and profile all outfall channels identified on the Hydrologic Map for a distance of 200-ft beyond the proposed ROW upstream and downstream at 100-ft intervals. The SURVEYOR will provide a complete 2D/3D File including utilities of the outfalls identified.
<u>NO</u>	<u>N/A</u>	3.1.9. Inventory all driveways, commercial entrances, public roads and side streets separately. Obtain centerline station. (Width at ROW, PAV'T and existing radius. Inventory by type (dirt, caliche, gravel or paved). If paved, indicate condition in terms of no patches, has patches or has potholes. Obtain width at R.O.W. line. Obtain elevations at both edges of the driveway or turnout in line with the side drain.
<u>NO</u>	<u>N/A</u>	3.1.10. Inventory signs, mailboxes, and large trees within the proposed ROW.
<u>NO</u>	<u>N/A</u>	3.1.11. Locate wetlands.
<u>NO</u>	<u>N/A</u>	3.1.12. Establish additional control points.
<u>NO</u>	<u>N/A</u>	3.1.13. Locate existing right-of-ways.
<u>NO</u>	<u>N/A</u>	3.1.14. Review right-of-way maps.
<u>NO</u>	<u>N/A</u>	3.1.15. Locate boreholes.
<u>NO</u>	<u>N/A</u>	3.1.16. Perform hydrographic surveys.
<u>NO</u>	<u>N/A</u>	3.1.17. Update existing control data and prepare survey control data sheets, as required by the Design Manual, signed by a Registered Professional Land Surveyor, for inclusion into a construction plan set.
		3.2. <u>Construction Surveys:</u> In performing construction surveys, the following will be requested by the ENGINEER on an as needed basis, but need not be limited to:
<u>NO</u>	<u>N/A</u>	3.2.1. Stake existing and/or proposed right-of-ways.
<u>NO</u>	<u>N/A</u>	3.2.2. Stake existing and/or proposed baseline/centerline.
<u>NO</u>	<u>N/A</u>	3.2.3. Stake proposed bridge structures.
<u>NO</u>	<u>N/A</u>	3.2.4. Stake proposed drainage structures, such as manholes, culverts, etc.
<u>NO</u>	<u>N/A</u>	3.2.5. Set grade stakes.
<u>NO</u>	<u>N/A</u>	3.2.6. Recover and check existing control points.
<u>NO</u>	<u>N/A</u>	3.2.7. Establish additional control points.
<u>NO</u>	<u>N/A</u>	3.2.8. Check elevations and locations of structures.
<u>NO</u>	<u>N/A</u>	3.2.9. Determine and resolve conflicts associated with survey data.
		4. <u>DELIVERABLES:</u> The deliverables to be specified in individual work authorizations for design surveys and construction surveys may be any combination of the following:
<u>NO</u>	<u>N/A</u>	4.1. Digital Terrain Models (DTM) in a format acceptable by the ENGINEER.
<u>NO</u>	<u>N/A</u>	4.2. Final H&V Field Book Binder with all pertinent information obtained in the field for Design Surveys. Maps, plans, or sketches prepared by the SURVEYOR showing the results of field surveys.

<u>NO</u>	<u>N/A</u>	4.3. Computer printouts or other tabulations summarizing the results of field surveys.
<u>NO</u>	<u>N/A</u>	4.4. Digital files or media acceptable by the ENGINEER containing field survey data.
<u>NO</u>	<u>N/A</u>	4.5. Maps, plats, plans, sketches, or other documents acquired from utility companies, private corporations, or other public agencies, the contents of which are relevant to the survey.
<u>NO</u>	<u>N/A</u>	4.6. Field survey notes, as electronic and/or hard copies.
<u>NO</u>	<u>N/A</u>	4.7. An 8 ½ inch by 11 inch survey control data sheet for each construction control point which shall include, but need not be limited to, a location sketch, a physical description of the point including a minimum of two reference ties, surface coordinates, a surface adjustment factor, elevation, and the horizontal and vertical datums used. Survey control data sheets shall be signed and sealed by the supervising Registered Professional Land Surveyor.
<u>NO</u>	<u>N/A</u>	4.8. Final mylar set of 11 inch by 17 inch Survey Control data sheets sign and seal by the RPLS per TxDOT guidelines.
<u>NO</u>	<u>N/A</u>	4.9. A digital and/or hard copy of all computer printouts of horizontal and vertical conventional traverses, GPS analysis and results, data including property descriptions with field notes and plats, right-of-way maps, and survey control data sheets to include in the H&V Field Book Binder.
<u>NO</u>	<u>N/A</u>	4.10. Survey reports in a format requested by the ENGINEER.
<u>NO</u>	<u>N/A</u>	4.11. Items indicated under the Automation Requirements Section 6.

5. GENERAL REQUIREMENTS:

5.1. Design surveys and construction surveys shall be performed under the supervision of a Registered Professional Land Surveyor currently registered with the Texas Board of Professional Land Surveying.

5.2. Horizontal ground control used for design surveys and construction surveys, furnished to the SURVEYOR by the ENGINEER or based on acceptable methods conducted by the SURVEYOR, shall meet the standards of accuracy required by the STATE.

Reference may be made to standards of accuracy for horizontal control traverses, as described in the FGCS Standards and Specifications for Geodetic Control Networks, latest edition, the TxDOT Survey Manual, latest edition, the TxDOT GPS Manual of Practice, latest edition, or the TSPS Manual of Practice for Land Surveying in the State of Texas, as may be applicable.

5.3. Vertical ground control used for design surveys and construction surveys, furnished to the SURVEYOR by the ENGINEER or based on acceptable methods conducted by the SURVEYOR, shall meet the standards of accuracy required by the ENGINEER.

Reference may be made to standards of accuracy for vertical control traverses, as described in the FGCS Standards and Specifications for Geodetic Control Networks, latest edition, the TxDOT Survey Manual, latest edition, the TxDOT GPS Manual of Practice, latest edition, or the TSPS Manual of Practice for Land Surveying in the State of Texas, as may be applicable.

5.4. Side shots or short traverse procedures used to determine horizontal and vertical locations shall meet the following criteria:

5.4.1. Side shots or short traverses shall begin and end on horizontal and vertical ground control as described above.

5.4.2. Standards, procedures, and equipment used shall be such that horizontal locations relative to the control may be reported within the following limits:

- Bridges and other roadway structures: less than 0.1 of one foot.
- Utilities and improvements: less than 0.2 of one foot.
- Cross-sections and profiles: less than 1 foot.
- Bore holes: less than 3 feet.

- 5.4.3. Standards, procedures, and equipment used shall be such that vertical locations relative to the control may be reported within the following limits:
 - a. Bridges and other roadway structures: less than 0.02 of one foot.
 - b. Utilities and improvements: less than 0.1 of one foot.
 - c. Cross-sections and profiles: less than 0.2 of one foot.
 - d. Bore holes: less than 0.5 of one foot.
- 6. **AUTOMATION REQUIREMENTS:**
 - 6.1. Planimetric design files (DGN) shall be fully compatible with the State's *Micro Station V8* graphics program without further modification or conversion.
 - 6.2. Electronically collected and processed field survey data files shall be fully compatible with the State's *CADD* systems without further modification or conversion. All files shall incorporate only those feature codes currently being used by the STATE.
 - 6.3. Digital Terrain Models (DTM) shall be fully compatible with the STATE's *GEOPAK* system without further modification or conversion. All DTM files shall be fully edited and rectified to provide a complete digital terrain model with all necessary break lines.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

ADDITIONAL RESPONSIBILITIES

A. TRAFFIC CONTROL:

The SURVEYOR shall control traffic in and near surveying operations adequately to comply with provisions of the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI and the latest edition of the Occupational Safety Manual both of which can be found on the TxDOT internet site.

In the event field crew personnel must divert traffic or close traveled lanes, a Traffic Control Plan based upon principles outlined in the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI shall be prepared by the SURVEYOR and approved by the ENGINEER prior to commencement of field work. A copy of the approved plan shall be in the possession of field crew personnel on the job site at all times and shall be made available to the ENGINEER for inspection upon request.

B. INVOICING:

Payment requests shall include a SURVEYOR's invoice. With each payment request, the SURVEYOR shall submit a project status report which will, as a minimum, include the percentage of total work complete as of the date of the payment request and a description of current work activity. The percentage of total work complete shall not be based simply on the percentage of funds expended, but shall be based on the best judgment of the SURVEYOR as to the percentage of actual work complete.

C. EASEMENTS, LETTERS OF PERMISSION, ETC.

The SURVEYOR shall be responsible for delineating easements. The SURVEYOR will be responsible for securing the necessary legal instruments and obtaining all Right-of-Entries (ROEs).

D. MEETINGS:

The ENGINEER shall setup the necessary meetings with the SURVEYOR in order to assure all field information is provided on-time and products are delivered in accordance with TxDOT's specifications. SURVEYOR must attend all meetings involving data provided or requested by ENGINEER.

E. PROJECT MANAGER/SURVEYOR COMMUNICATION:

The SURVEYOR shall designate one Texas Registered Professional Land Surveyor (RPLS) to be responsible throughout the project for project surveying coordination and all communications, including billing, with the ENGINEER.

F. OFFICE LOCATION:

The SURVEYOR will perform the services to be provided under this agreement out of a local office and have a crew available to perform requested tasks within 24 hours of request. The coordinating SURVEYOR's Project Manager (RPLS) shall be accessible at all times and working from the local office.

ROADWAY DESIGN CONTROLS

(Function Code 160)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1. Geometric Design
<u>YES</u>	<u>N/A</u>	a. Horizontal and Vertical Alignment (Preliminary based on office surveys)
		b. Schematic Layout
		(1) The location of interchanges, main lanes, grade separations, frontage roads and ramps.
		(2) Develop vertical and horizontal alignment of main lanes, ramps and cross roads at proposed interchanges or grade separations. Frontage road alignment data need not be shown on the schematic; however, it should be developed in sufficient detail to determine ROW needs. The degree of horizontal curves and vertical curve data, including "K" values, shall also be shown for ease of checking.
		(3) For freeways, show the location and text of the proposed main lane guide signs. Lane lines and/or arrows indicating the number of lanes shall also be shown.
		(4) A complete explanation of the sequence and methods of stage construction, if proposed, including the initial and ultimate proposed treatment of crossovers and ramps.
		(5) The tentative ROW limits.
		(a) Provide a roadway Design System (RDS) or (GEOPAK) computer tape of the preliminary earthwork to verify ROW requirements.
		(b) Provide a graphics file containing the approved schematic.
		(6) The geometric (pavement cross slopes, lane and shoulder widths, slope rates for fills and cuts) of the typical sections of proposed highway main lanes, ramps, frontage roads, and cross roads.
		(7) The current and projected traffic volumes as provided by the TxDOT (20 year traffic projection, unless otherwise determined by the District Engineer).
		(8) The control of access lines if Interstate or designated under House Bill 179.
		(9) Direction of traffic flow on all roadways.
		(10) Location and width of median openings for highway without access control.
		(11) The geometric of speed change (acceleration, deceleration, climbing) lanes.
<u>YES</u>	<u>N/A</u>	2. General Guidelines for Project Development
		a. Prior to preparing detailed plans for a proposed project, a preliminary schematic layout shall be prepared which indicates the general geometric features and location requirements peculiar to the project. An uncontrolled aerial mosaic will be provided for this use. Four copies of the schematic layout shall be submitted through the district to the Design Division for approval and subsequent coordination with the Federal Highway Administration (FHWA) where applicable. The layout shall be submitted for two-lane arterial highway projects on new locations and for all multi-lane highway projects. No geometric design is to be performed until the COUNTY has given the engineer written approval of the preliminary schematic layout.
		b. All geometric design shall be in conformance with the State's Design Division, Operations and Procedures Manual, except where variances are permitted in writing by the STATE.
		c. The schematic layout shall include basic information which is necessary for the proper review and evaluation including the items listed above in the checklist for schematic layout.
		d. Handling of traffic during construction shall be a consideration in the development of preliminary designs.

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	2. General Guidelines for Project Development (<i>continued</i>)
		e. Upon approval of the schematic layout by Design Division (FHWA on Federal-aid projects), it shall be the basis for an exhibit at any required public hearing prior to final development of the project. If there are any changes to the schematic after the Design Division and FHWA approval and before the public hearing, four copies of the revised schematic, as displayed at the hearing, shall be submitted either prior to or accompanying the public hearing data. If there are no changes in the schematic as displayed at the hearing, only photographs of the schematic and other displays shall be submitted with the public hearing data.
		f. For all freeway construction projects, these schematics shall show the location and text of the proposed main lane guide signs. A schematic layout shall be submitted through the district to the Traffic Operations Division, Traffic Safety Section for approval and subsequent coordination with the FHWA. All signing shall be in conformance with the Texas MUTCD.
		g. On complex projects, informal contact through the district with the Design Division and FHWA personnel is encouraged with regard to development of preliminary design prior to official schematic submission.
		h. The engineer shall furnish a project tape that is compatible with the STATE's computer system, a project listing, and a cross section plot showing the original design sections containing the earthwork input and original cross sections for the project. Accuracy of the earthwork design is of utmost importance since it is the basis for contractor payments and construction staking.
<u>N/A</u>	<u>N/A</u>	3. Exhibit for Airway/Highway Clearance Permits
<u>NO</u>	<u>N/A</u>	4. Grading Design
		a. Refine the horizontal and vertical alignment of main lanes, frontage roads, ramps, cross roads and direct connectors based upon the approved schematic layout. Determine vertical clearances at grade separations and overpasses, taking into account the appropriate super elevation rate.
<u>NO</u>	<u>N/A</u>	b. Typical Sections
<u>NO</u>	<u>N/A</u>	c. Design Cross Sections
<u>NO</u>	<u>N/A</u>	d. Determine Cut and Fill Quantities
<u>N/A</u>	<u>N/A</u>	e. Slope Stability Analysis
<u>N/A</u>	<u>N/A</u>	f. Embankment Foundation Stability Analysis
<u>N/A</u>	<u>N/A</u>	g. Embankment Settlement Analysis
<u>NO</u>	<u>N/A</u>	5. Pavement Design
		a. Prior to initiating detailed plan preparations for a project, a preliminary investigation shall be made to determine the approximate section and pavement type to be used for the pavement structure. The Flexible Pavement Design Manual for flexible pavement, "Appendix F" of the Design Division, Operations and Procedures Manual, and the current AASHTO Guide for the Design of Pavement Structures, may be used for this purpose.
<u>NO</u>	<u>N/A</u>	b. The typical section shall also reflect proposed geometric including pavement cross slopes, lane and shoulder widths, and slope rates whenever this data have not been previously shown on a schematic submission.
		c. Embankment and Subgrade
		(1) Soil Core Holes (Show cost estimate with Function Code 110)
<u>N/A</u>	<u>N/A</u>	(a) Along center line
<u>N/A</u>	<u>N/A</u>	(b) Along center line of each roadway
		The location and minimum number of soil core holes required for this project are as follows: (To be determined when schematic is being completed)

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	5. Pavement Design (<i>continued</i>)
<u>NO</u>	<u>N/A</u>	c. Embankment and Subgrade (<i>continued</i>)
<u>NO</u>	<u>N/A</u>	(2) Identify, interpret and summarize geologic features that affect engineering design (PI, Sulfate content, % of lime)
<u>NO</u>	<u>N/A</u>	d. Traffic Data for Pavement Design by STATE
<u>NO</u>	<u>N/A</u>	e. Basic Design Criteria
<u>NO</u>	<u>N/A</u>	f. Life Cycle Cost Analysis(es)
<u>NO</u>	<u>N/A</u>	g. Cost Data
<u>NO</u>	<u>N/A</u>	h. Pavement Material Properties
<u>NO</u>	<u>N/A</u>	i. Rehabilitation Investigations
<u>NO</u>	<u>N/A</u>	(1) Core Hole Survey (Show cost estimate with Function Code 110)
		(a) Determine type and depth of existing material, pavement, etc. The Engineer will determine whether to salvage ACP and FLEXBASE as well as their properties and provide this information to TxDOT.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

DRAINAGE
(Function Code 161)

Services
Provided By:
ENGINEER COUNTY

All hydraulic design shall be in accordance with the TxDOT's Hydraulic Manual, except where variances are permitted in writing by the COUNTY.

<u>YES</u>	<u>N/A</u>	1. Hydrologic Studies, Discharges
		a. Drainage area maps showing existing conditions and proposed improvements of outfalls.
<u>YES</u>	<u>N/A</u>	b. Hydrologic data/discharge determination
-
		2. Hydraulic Drainage Study and Documentation
		a. Hydraulic computations
<u>NO</u>	<u>N/A</u>	(1) Storm water detention available within the ROW (linear ft. along side drain ditch).
<u>NO</u>	<u>N/A</u>	(2) Storm water detention required outside the ROW (as per HCDD#1)
<u>NO</u>	<u>N/A</u>	(3) Culverts
<u>NO</u>	<u>N/A</u>	(4) Bridge waterways
<u>NO</u>	<u>N/A</u>	(5) Channels
<u>NO</u>	<u>N/A</u>	(6) Storm sewers/inlets
<u>NO</u>	<u>N/A</u>	(7) Pump stations
<u>NO</u>	<u>N/A</u>	(8) Storm Water Management facilities
<u>NO</u>	<u>N/A</u>	(9) Other
		(a) Irrigation Canals/Siphons
<u>NO</u>	<u>N/A</u>	b. Hydraulic reports
<u>NO</u>	<u>N/A</u>	c. Federal Emergency Management Agency (FEMA) floodway requirements
<u>NO</u>	<u>N/A</u>	d. Determine impact of proposed drainage plan on the following receiving stream(s)
		(1) Hidalgo County Drainage District Outfalls
		(2) All Irrigation District Outfalls impacted
		3. Layout, Structural Design and Detailing of Drainage Features
		a. Culverts
<u>NO</u>	<u>N/A</u>	(1) New culverts
<u>NO</u>	<u>N/A</u>	(2) Culvert widening and/or lengthening
<u>NO</u>	<u>N/A</u>	(3) Culvert replacements
		b. Storm sewers
<u>NO</u>	<u>N/A</u>	(1) New storm sewers
<u>NO</u>	<u>N/A</u>	(2) Modify existing storm sewers
<u>NO</u>	<u>N/A</u>	(3) Inlets
<u>NO</u>	<u>N/A</u>	(4) Manholes
<u>NO</u>	<u>N/A</u>	(5) Trunk lines
<u>NO</u>	<u>N/A</u>	c. Pump stations
<u>NO</u>	<u>N/A</u>	d. Subsurface drainage at retaining walls
<u>NO</u>	<u>N/A</u>	e. Outfall channel(s) within the ROW
<u>NO</u>	<u>N/A</u>	f. Outfall channel(s) outside the ROW
<u>NO</u>	<u>N/A</u>	g. Detention Pond(s) within the ROW
<u>NO</u>	<u>N/A</u>	h. Detention Pond(s) outside the ROW
<u>NO</u>	<u>N/A</u>	i. Summary of Quantities
<u>NO</u>	<u>N/A</u>	j. Storm Water Management facilities
<u>NO</u>	<u>N/A</u>	4. Storm Water Pollution Prevention Plan (SW3P)
<u>NO</u>	<u>N/A</u>	5. Scour Evaluation - Waterway Structures only (to be completed by Bridge Engineer under FC 170.

SIGNING, MARKINGS AND SIGNALIZATION
(Function Code 162)

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	1. Signing and Markings Layout
		a. Requirements (Separate Layout)
		(1) Roadway layout
		(2) Center line with station numbering
		(3) ROW lines
		(4) Culverts and other structures that present a hazard to traffic
		(5) Location of utilities, if not shown on plan and profile
		(6) Existing signs to remain, to be removed, to be relocated
		(7) Proposed signs (illustrated and numbered)
		(8) Existing overhead sign bridges to remain, to be revised, removed or relocated
		(9) Proposed overhead sign bridges indicating location by plan layout (electrical details need not be shown on this layout)
		(10) Proposed markings (illustrated and quantified) which include pavement markings, object markings and delineation
		(12) Quantities of existing pavement markings to be removed
		(13) Proposed delineators and object markers
		b. For projects involving freeway to freeway or other types of directional interchanges, projects including left-hand ramps or connections, the following information must be provided:
		(1) The location of interchanges, main lanes, grade separations, frontage roads and ramps
		(2) complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps
		(3) The number of lanes in each section of proposed highway and the location of changes in numbers of lanes
		(4) The projected traffic volumes as provided by the STATE (20 year traffic projection unless otherwise determined by the District Engineer)
		(5) Tentative ROW limits
		(6) Direction of traffic flow on all roadways
		(7) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations
<u>NO</u>	<u>N/A</u>	2. Summary of Small Signs Tabulation
<u>NO</u>	<u>N/A</u>	3. Summary of Large Signs Tabulation including all Guide Signs
<u>NO</u>	<u>N/A</u>	4. Sign Detail Sheets
		a. All signs except route markers
		b. Design details for large guide signs
		c. Dimensions of letters, shields, borders, corner radii etc.
		d. Designation of shields attached to guide signs
		e. Designation of arrow used on exit direction signs

Services
Provided By:
ENGINEER COUNTY

5. Traffic Signals

a. Development of Justification (Warrant) Data

<u>NO</u>	<u>N/A</u>	(1) Location Map Relationship of proposed installation to other traffic signals, highways, business areas and traffic generators
<u>NO</u>	<u>N/A</u>	(2) Photographs as appropriate
<u>NO</u>	<u>N/A</u>	(3) Accident data as appropriate
<u>N/A</u>	<u>N/A</u>	(4) Vehicle volumes (provided by TxDOT)
<u>N/A</u>	<u>N/A</u>	(a) Existing
<u>N/A</u>	<u>N/A</u>	(b) Estimated
<u>N/A</u>	<u>N/A</u>	(c) Projected
<u>N/A</u>	<u>N/A</u>	(d) Pedestrian
<u>N/A</u>	<u>N/A</u>	(5) Traffic Survey - Count Analysis
<u>N/A</u>	<u>N/A</u>	(6) Recommendation based on above data

b. Layout

- (1) Title Sheet (when applicable)
 - (a) Describe the location
 - (b) Type of installation
 - (c) Area map with project limits for each location
 - (d) Index of sheets
 - (e) Space for official signatures
- (2) Estimate and quantity sheet (when applicable)
 - (a) List of all bid items
 - (b) Bid item quantities
 - (c) Specification item number
 - (d) Paid item description and unit of measure
- (3) Basis of estimate sheet (list of materials)
- (4) General notes and specification data sheet
- (5) Condition diagram
 - (a) Highway and intersection design features
 - (b) Roadside development
 - (c) Traffic control including illumination
- (6) Plan sheet(s)
 - (a) Existing traffic control that will remain (signs and markings)
 - (b) Existing utilities
 - (c) Proposed highway improvements
 - (d) Proposed installation
 - (e) Proposed additional traffic controls
 - (f) When applicable, proposed conduit for Railroad interconnect with standard details for runs under tracks.
 - (g) Proposed illumination attached to signal poles.
- (7) Notes for plan layout
- (8) Elevation sheet(s) (span wire design)
- (9) Phase sequence diagram(s)
 - (a) Signal locations
 - (b) Signal indications
 - (c) Phase diagram
 - (d) Signal sequence table
 - (e) Flashing operation (normal and emergency)
 - (f) Preemption operation (when applicable)
 - (g) Interval timing, cycle length and offset

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	5. Traffic Signals (<i>continued</i>)
		b. Layout (<i>continued</i>)
		(10) Construction detail sheets(s)
		(a) Poles (TxDOT standard sheets)
		(b) Detectors
		(c) Pull Box and conduit layout
		(d) Controller Foundation standard sheet
		(11) Marking details (when applicable)
		(12) Barricade and warning sign standard sheet and any special details for work zone traffic control for special conditions
		(13) Aerial or underground interconnect details (when applicable)
		c. General Requirements
<u>NO</u>	<u>N/A</u>	(1) Contact local utility company
<u>NO</u>	<u>N/A</u>	(a) Confirm power source
<u>N/A</u>	<u>N/A</u>	(b) Discuss route of aerial or underground interconnect cable (when applicable)
<u>NO</u>	<u>N/A</u>	(c) Adjustment of overhead utility lines
<u>NO</u>	<u>N/A</u>	(2) Prepare governing specifications and special provisions list
<u>NO</u>	<u>N/A</u>	(3) Prepare project estimate
<u>NO</u>	<u>N/A</u>	d. Summary of Quantities

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

MISCELLANEOUS (ROADWAY)
(Function Code 163)

Services
Provided By:
ENGINEER COUNTY

1. Retaining Walls
 - a. Structural Details
 - (1) Cast-in-Place Cantilever at _____ locations. (TxDOT Standard Retaining Wall)*
 - (2) Tiedback Retaining Wall at _____ location. (TxDOT standard retaining wall)
 - (3) Specialized Retaining Wall at _____ locations (Unique Design).*
 - b. Alternate Patented Retaining Walls at all locations. (Layouts Only)**
 - (1) Mechanically Stabilized Earth
 - (2) Concrete Block Wall Systems
 - c. Retaining Wall Layout (PLAN)
 - (1) Designation of reference line
 - (2) Beginning and ending retaining wall stations
 - (3) Station of each retaining wall joint***
 - (4) Offset from reference line
 - (5) Horizontal curve data
 - (6) Number of retaining wall panels and lengths***
 - (7) Total length of wall
 - (8) Indicate face of wall
 - (9) All wall dimensions and alignment relations (alignment data as necessary)
 - (10) Soil core hole locations
 - d. Retaining Wall Layout (ELEVATION)
 - (1) Top of wall elevations at each joint or intervals***
 - (2) Existing and finished ground line elevations
 - (3) Height of stem at each joint***
 - (4) Wall panel designations***
 - (5) Top of footing elevations***
 - (6) Limit of measurement for payment****
 - (7) Type, limits and anchorage details of railing (If applicable)
 - (8) Top and bottom of wall profiles and soil core hole data plotted at correct station and elevation. The data shall be at the same scale as the wall profile. Ground water elevations and the observation date shall be shown.
 - e. Foundation Studies (Show cost estimate with Function Code 110)
 - (1) The soil core holes shall be obtained at approximately 200 foot intervals along retaining wall alignments. The core holes shall extend 25 feet below the footing elevation.
 - f. Stability Analysis (the ENGINEER shall estimate this task as part of his bid to complete the work).
 - g. Estimate
 - h. Summary of Quantities
 - i. Typical X-section.
 - j. General Guidelines for Retaining Walls
 - (1) The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. **The designer and checker shall check all calculations and initial each page.**
 - (2) The ground water level should be observed at the water strike.
 - (3) For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
 - (4) Foundation exploration shall conform to the requirements set forth in Administrative Circular No. 25-84, Administrative Circular 33-87 and Administrative Circular No. 25-92.

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	2. Traffic Control Plan, Detours and Sequence of Construction Traffic Control Plans (TCP) are required for all projects. A detailed TCP shall be developed when traffic handling during construction involves complications for which a feasible solution is not covered by the Texas MUTCD or the current Barricade and Construction (BC) Standards. The following items are required on all Traffic Control Plan Layouts: a. The sequence of construction and method of handling traffic during each phase. b. The existing and proposed traffic control devices that will be used to handle traffic during each construction sequence. Include signals, regulatory signs, warning signs, construction warning signs, guide signs, route markers, construction pavement markings, channelizing devices, portable changeable message signs, flashing arrow boards, barricades, barriers, etc. c. The proposed traffic control devices (stop signs, signals, flag person, etc.) at grade intersections during each construction sequence. d. Where detours are provided, typical cross sections shall be shown. e. Road construction work hours shall be developed after an investigation of the traffic volumes has been performed.
<u>N/A</u>	<u>N/A</u>	3. Illumination a. Preliminary Roadway Illumination Layout and Circuit Layout (1) For projects involving freeway to freeway or other types of directional interchanges and projects including left-hand ramps or connections, provide the following: (a) The location of interchanges, main lanes, grade separations, frontage roads and ramps (b) A complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps (c) The number of lanes in each section of proposed highway and the location of changes in the number of lanes (d) The projected traffic volumes as provided by the STATE (20 year traffic projection unless otherwise determined by the district engineer) (e) Tentative ROW limits (f) Direction of traffic flow on all roadways (g) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations b. Final Roadway Illumination and Electrical Circuit Layouts (1) Roadway layout showing pavement edges, shoulders, curbs, retaining walls, etc. (2) Center line with station numbering. (3) ROW lines. (4) Symbol legend. Use department standard symbols for lighting and electrical. (5) Culverts and other structures that present a hazard to traffic. (6) Location of underground utilities, if not shown on plan profile. (7) Location of overhead electrical lines, both crossing and parallel to ROW. (8) Existing sign lighting circuits and roadway illumination to remain, to be removed, to be relocated. (9) Existing service poles, electrical circuits, ground boxes, etc. (10) Contact electric utility for service pole locations, voltage characteristics. (11) Location of proposed sign lighting circuits and roadway illumination. (12) Proposed electrical circuits. (13) Tabulation of all quantities including proposed, existing to be relocated, existing to be removed. The layout sheet quantities and lighting summary shall be shown. Tabulations to include estimated quantity with a column for final quantities.

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	3. Illumination (<i>continued</i>)
		c. General Guidelines for Illumination (If applicable) The ENGINEER shall submit to the COUNTY, well in advance of PS&E due date, the roadway illumination and electrical circuit layout sheets for review by the STATE. Two copies of the layout sheets are to be submitted. One copy will be returned to the Engineer showing corrections that are to be made by the ENGINEER. When final plan submission is made, the ENGINEER shall provide a written statement regarding completion of the corrections.
<u>NO</u>	<u>N/A</u>	4. Miscellaneous Drafting/Standards
<u>N/A</u>	<u>N/A</u>	a. Erosion Control b. Landscape Development
<u>NO</u>	<u>N/A</u>	5. Compute and Tabulate Quantities
<u>NO</u>	<u>N/A</u>	6. Special Utility Details (Irrigation lines)
		7. Miscellaneous Structures
		a. Type of Structure*
		(1) Overhead Sign Bridges (O.S.B.) Modifications or special O.S.B. designs shall be prepared using the same design assumptions that are used for the standard O.S.B. structures.
<u>N/A</u>	<u>N/A</u>	(a) New O.S.B. structure(s)
<u>N/A</u>	<u>N/A</u>	(b) Structural evaluation of existing O.S.B. structure(s) that are to remain in place or to be relocated.
<u>N/A</u>	<u>N/A</u>	(2) High Mast Illumination Poles (HMIP)
<u>N/A</u>	<u>N/A</u>	(3) Traffic Signal Supports
<u>N/A</u>	<u>N/A</u>	(4) Conventional Illumination Pole
<u>N/A</u>	<u>N/A</u>	(5) Sound Barrier Walls
<u>N/A</u>	<u>N/A</u>	b. Checklist for Layouts
		(1) Reference appropriate O.S.B. standard
		(2) Drilled shaft size and length
		(3) Soil strength used for design {indicate basis and boring(s) used}
		(4) Design height
		(5) Tower heights
		(6) Leg spacings
		(7) Design wind speed
<u>N/A</u>	<u>N/A</u>	c. Foundation Studies (Show cost estimate with Function Code 110) The soils exploration requirements for miscellaneous structures on this project are as follows: (To be provided by the Engineer on an as-needed basis)
		8. Agreements
<u>N/A</u>	<u>N/A</u>	a. Utility Agreements
<u>N/A</u>	<u>N/A</u>	b. Exhibits for Utility Agreements
<u>N/A</u>	<u>N/A</u>	c. Railroad Agreements
		d. Railroad Exhibits
<u>N/A</u>	<u>N/A</u>	(1) Railroad Underpasses
<u>N/A</u>	<u>N/A</u>	(2) Railroad Overpasses
<u>N/A</u>	<u>N/A</u>	(3) Railroad Grade Crossing (Replanking)
<u>N/A</u>	<u>N/A</u>	(4) Railroad Grade Crossing Warning Systems (Signals)
<u>N/A</u>	<u>N/A</u>	(5) Other Miscellaneous Sketches for Railroads
<u>N/A</u>	<u>N/A</u>	e. Traffic Signal Agreements
<u>N/A</u>	<u>N/A</u>	f. Exhibits for Traffic Signal Agreements
<u>N/A</u>	<u>N/A</u>	9. Estimate
<u>N/A</u>	<u>N/A</u>	10. Specifications and General Notes

BRIDGE DESIGN
(Function Code 170)

Services
Provided By:
ENGINEER COUNTY

			NUMBER REQUIRED
		1. Preparation of Structural Details	
		a. New Structure(s)	
<u>N/A</u>	<u>N/A</u>	(1) Underpass(es)	
<u>N/A</u>	<u>N/A</u>	(2) Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(3) Main Lanes	
<u>N/A</u>	<u>N/A</u>	(4) Direct Connector(s)	
<u>N/A</u>	<u>N/A</u>	(5) Ramp Bridge(s)	
<u>N/A</u>	<u>N/A</u>	(6) Waterway Structure(s)**	
<u>N/A</u>	<u>N/A</u>	(7) Pedestrian Structure(s)	
<u>N/A</u>	<u>N/A</u>	(8) Utility Structure(s)	
<u>N/A</u>	<u>N/A</u>	(9) Railroad Underpass(es)	
<u>N/A</u>	<u>N/A</u>	(10) Railroad Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(11) Bridge Classification Culvert(s)**	
<u>N/A</u>	<u>N/A</u>	(11) Alternate Structural Designs	
<u>N/A</u>	<u>N/A</u>	(12) Alternate Foundation Design	
		Total New Structures =	
		b. Existing Structure(s)	
<u>N/A</u>	<u>N/A</u>	(1) Bridge Widening, Rehabilitation and/or Modification of Existing Structure(s)	
<u>N/A</u>	<u>N/A</u>	(2) Bridge Replacement	
<u>N/A</u>	<u>N/A</u>	(3) Raising Bridge Elevation	
<u>N/A</u>	<u>N/A</u>	(4) Bridge Classification Culvert(s) Widening and/or Modification of Existing Structures(s)	
<u>N/A</u>	<u>N/A</u>	(5) Railroad Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(6) Railroad Underpass(es)	
		Total Existing Structures =	

* Contour plots of bridge gores are required for projects involving ramps within the main bridge in order to ensure project transition. The Template data and vertical alignment necessary to generate the contour plots are also required.

** In the early stages of a project, it sometimes cannot be determined whether a Waterway Bridge Structure or a Bridge Classification Culvert (20' minimum length) will be required. Therefore, the ENGINEER should be aware that either of these two types of bridges may be reclassified later in the project for the other type when more information is known that would dictate a change in structure classification.

Services
Provided By:
ENGINEER COUNTY

- N/A N/A 2. Preparation of Bridge Layouts (each bridge)
- a. Bridge Layouts (PLAN)
 - (1) Horizontal curve information or bearing of centerline.
 - (2) Including horizontal, vertical, and template information of all roadways or railroads crossed.
 - (3) Bearing of center line or reference line.
 - (4) Skew angle(s).
 - (5) Slope for header banks and approach fills.
 - (6) Control stations at beginning and ending of bridge (with deck elevation), intersections, etc.
 - (7) Approach pavement and crown width.
 - (8) Bridge roadway width and curbs, face of rail, shoulders, or sidewalks.
 - (9) Approach slab and curb returns.
 - (10) Limits and type of riprap.
 - (11) Proposed features under structure.
 - (12) Location of profile grade line.
 - (13) North arrow.
 - (14) Typical bridge roadway section including preliminary proposed beam types and spacings.
 - (15) Cross slope and super elevation data.
 - (16) Minimum horizontal clearances when applicable.
 - (a) Dimensions to features that control clearances. (Calculate and indicate points of minimum vertical and horizontal clearances.
 - (17) Location of soil core holes (station and offset), shown on layout.
 - (18) Bent stations and bearings.
 - (19) Retaining wall locations.
 - (20) Traffic flow directional arrows.
 - (21) Railing type, shown.
 - (22) Joint types and seal size if used.
 - (23) Beam line numbers consistent with span details.
 - (24) Critical horizontal clearances (location of railroad tracks, nearby structures and utilities).
 - (25) Bearings of utilities.
 - b. Bridge Layouts (ELEVATION)
 - (1) Type of foundation.
 - (2) Finished grade elevations at beginning and end of bridge.
 - (3) Overall length of structure.
 - (4) Length, type of spans and units.
 - (5) Type of railing.
 - (6) Minimum calculated vertical clearance(s).
 - (7) Existing and proposed ground lines clearly marked.
 - (8) Grid elevations and stations.
 - (9) Bent numbers encircled.
 - (10) Stationing of bridge compatible with grid stations.
 - (11) Standard title.
 - (12) Profile grade data.
 - (13) Type of riprap.
 - (14) Soil Core Hole information with penetrometer test data shall be shown on the bridge layout at correct station, elevation and scale.
 - (15) Fixed/expansion condition of all bents.
 - (16) Column "H" heights.
 - (17) Number, size and length of foundations.

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	2. Preparation of Bridge Layouts (each bridge) (<i>continued</i>)
		c. Additional layout requirements for waterway structures and bridge classification culverts.
		(1) Design and 100-year peak discharges.
		(2) Design and 100-year high water (HW) (Recorded HW and date if available)
		(3) Natural and through-bridge velocities for design and 100-year floods.
		(4) Calculated backwater for design and 100-year floods.
		(5) Direction of flow for waterway crossings.
		(6) Contours for water crossing.
<u>N/A</u>	<u>N/A</u>	3. Bridge Classification Culvert, Estimate, Quantities, and Specifications (each bridge)
<u>N/A</u>	<u>N/A</u>	4. Foundation Studies (Show cost estimate with Function Code 110)
		The minimum number of soil core holes shall be obtained in accordance with Section 1-301 of the Bridges and Structures Foundation Exploration and Design Manual. Soil core holes shall be obtained at approximately (300 foot) intervals along bridge alignments. Texas cone penetrometer (TCP) tests shall be conducted in all soil types encountered at a maximum of (10 foot) intervals. If single column bents with single drilled shafts are planned, TCP values should be taken at close intervals in the upper (15 feet).
<u>N/A</u>	<u>N/A</u>	5. Bridge Total Quantities and Cost Estimates (each bridge)
<u>N/A</u>	<u>N/A</u>	6. Bridge Special Provisions and Specifications (each bridge)
<u>N/A</u>	<u>N/A</u>	7. Bearing seat elevations for each beam or girder. Top of cap elevations for non-beam type structures.
<u>N/A</u>	<u>N/A</u>	8. General Guidelines for Bridge Design
		a. The ENGINEER shall prepare a bridge layout of each bridge structure for Company's review and approval. The bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures, Detailing Manual. Soil core hole data is not required for submission of the preliminary bridge layout. No bridge design work is to be performed until the COUNTY has given the engineer written approval of the preliminary bridge layout.

Several months may be required, after the preliminary bridge layout is submitted, for the district to obtain approval and/or permits from the following:

- TxDOT Design Division, when applicable:
 - Railroad Companies
 - FHWA
 - U.S. Army Corps of Engineers
 - U.S. Coast Guard
 - Bureau of Reclamation
 - Texas Parks and Wildlife
 - Others

Therefore, the bridge layout should be submitted at the earliest possible date and the ENGINEER's design schedule should reflect this.

- b. All bridge superstructure and substructure design will be reviewed by the Design Division for purposes of verifying structural integrity and optimization of design.
- c. The final bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures Detailing Manual.

Services
Provided By:
ENGINEER COUNTY

8. General Guidelines for Bridge Design (*continued*)

- d. The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. All bridge design shall be in conformance with the Texas Department of Transportation Bridges and Structures Operation and Planning Manual, the current American Association of State Highway and Transportation Officials or American Railway Engineers Association Specifications for railway structures, Standard Specifications for Highway Bridges, including applicable interim specifications, and the Bridges and Structures, Foundation Exploration and Design Manual. The ENGINEER shall furnish design calculations to the Design Division. **The designer and checker shall check all calculations and initial each page.**
- e. Structural steel or prestressed concrete shop drawings, form work drawings and false work drawings are not part of the design requirements. However, contract plans shall be in sufficient detail to permit the preparation of complete shop details for fabrication and erection.
- f. Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a metric scale of 1:20 (1/2 inch equals one foot architect scale) or 1:50 (1/4 inch equals one foot architect scale) to provide clear legible drawings when the drawings are reduced. Lettering shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
- g. Standard drawings for beams, diaframs, railings, armor joints, riprap, etc., shall be furnished to the ENGINEER upon request. These standards shall not be redrawn by the ENGINEER nor shall his title block be transferred to the standard drawings. Modifications to the standards, if necessary, shall be clearly identified and designated by "MOD" in the standard title. Specific special drawings prepared by the ENGINEER shall not be identified as standards.
- h. Bridge layout sheets shall have the same vertical and horizontal scale. Usually a metric scale of 1:100 (1 inch = 10 feet) or 1:200 (1 inch = 20 feet) is used. Sections of existing and proposed structures usually have a metric scale of 1:50 (1 inch = 5 feet). Soil core holes shall be positioned and labeled on the bridge layout plan view. The core hole data shall be plotted at the correct station, at the same vertical scale, and at the proper elevation unless otherwise approved by the Design Division.
- i. APPENDIX C, "GENERAL PLAN CHECKLIST", on pages C-1 thru C-5, more specifically relates various sheet types, details, summaries, standards, etc.
- j. For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
- k. Geometry and structural design errors found after acceptance of bridge plans shall be promptly corrected by the consultant at no cost to the Company.

CONSTRUCTION PHASE SERVICES
(Function Code 320)

Services
Provided By:
ENGINEER COUNTY

N/A N/A **CONSTRUCTION MANAGEMENT SERVICES:**

The ENGINEER will provide engineering, geotechnical testing and support services for and during the construction of the Project or portions of the Project approved by the COUNTY. Specific (basic and special) services for CONSTRUCTION MANAGEMENT AND SUPPORT by the ENGINEER will include the following:

Construction Bidding:

- 1) The ENGINEER will furnish the COUNTY the necessary copies of approved plans, specifications, notices to bidders, and proposals as prepared under PS&E.
- 2) The ENGINEER will assist the COUNTY on the tabulation of bids, recommendations to the Owner as to the proper action on all bid proposals received, and the preparation of formal contract documents for the award of each construction contract.

Construction Contract Administration and Inspection:

- 3) In general, the ENGINEER will provide the management and engineering support/data required for consultation and advisement to the COUNTY and act as the COUNTY's representative as provided in the General Condition of the Construction Contract.
- 4) The ENGINEER will coordinate and conduct a pre-construction conference (if required).
- 5) **NOT INCLUDED IN WORK AUTHORIZATION NO. 1**
Defects and Deficiencies. The ENGINEER will use his best efforts to protect the COUNTY against defects and deficiencies in the work of the Contractor. The ENGINEER will promptly notify the COUNTY of any such defect or deficiency, and take all steps possible to require the Contractor to correct the defect or deficiency.
- 6) Contractor Payment. The ENGINEER will review quantities as submitted by the Contractor and will coordinate with the COUNTY for the preparation of the monthly and final estimates for payment to the Contractor.
- 7) The ENGINEER will provide Project site inspection of the authorized construction contract as follows:
 - a) Project Engineer. The ENGINEER will provide visits by the Project Engineer or a competent representative of the ENGINEER to the site of construction for the purpose of monitoring the Contractor's progress and conformance to the construction contract plans and specifications.
 - b) Resident Engineer and/or Construction Inspector(s). The ENGINEER will furnish the services of a Resident Engineer and/or Construction Inspector(s) for on the site inspection construction to monitor/inspect the Contractor's daily progress and conformance to TxDOT's PS&E specifications.

Miscellaneous Technical Activities:

- 8) Shop Drawings. The ENGINEER will review and check all shop or working drawings furnished by the Contractor.

- 9) Control of Materials & Equipment. The ENGINEER will provide inspection of all materials and equipment furnished/used by the Contractor as follows:
 - a) Review and record all laboratory, shop and mill tests of materials and equipment for compliance with the construction contract specifications.
 - b) Observe and/or perform Project record testing and/or independent assurance testing as outlined in the construction contract specifications.
- 10) Change Orders. When applicable the ENGINEER will prepare the engineering data, including plan sheet drawings, specifications, and estimates, for the preparation of construction contract change orders, which may be required due to actual field conditions encountered or new requirements directed by the COUNTY.
- 11) As Built Drawings. The ENGINEER will develop as built drawings to depict the work as actually constructed. The COUNTY will be furnished five (5) set of prints.

N/A

N/A

CONSTRUCTION MATERIAL TESTING:

The ENGINEER will provide the COUNTY with construction material testing services for the Project. The services to be provided include sampling and testing of all construction materials as required by the project plans and specifications. All sampling frequencies and test procedures will be performed in general accordance with the Texas Department of Transportation TEX methods (or ASTM methods as required) as outlined in the Guide Schedule for Sampling and Testing (11/07). The construction material testing includes, but is not limited to the following:

- (a) Sampling and laboratory testing of soils and base materials proposed for use in the construction of Project (Roads/Bridges/Misc.) to determine compliance of these materials with project plans and specifications.
- (b) Field density testing of soils and base materials to ensure proper compaction as required by project plans and specifications.
- (c) Field sampling and testing of fresh concrete and laboratory testing of hardened concrete to determine compliance with project plans and specifications.
- (d) Field compaction testing of asphalt to ensure proper compaction during lay down operations.
- (e) Field inspection, sampling and laboratory testing of asphalt materials to determine their material properties and their compliance with project plans and specifications.
- (f) The ENGINEER will be responsible for concrete batching as well as the asphalt testing at the plants to insure delivery of acceptable material to the job site.
- (g) Any additional laboratory testing as required/requested by the COUNTY and the project plans and specifications.
- (h) Providing accurate and timely reports to the COUNTY and all/other recipients as designated by the COUNTY.
- (i) The ENGINEER will verify the concrete and asphalt designs to assure it is in accordance with TxDOT specifications to be developed by the contractor.

FC 600 – ACQUISITION PROVIDER SERVICES
(for EST. 0 PARCELS, 0 EASEMENTS AND 0 RELOCATIONS/DISPLACEMENTS)

(Services to be provided by L&G Engineering)

Services
Provided By:
ENGINEER COUNTY

- 1) PROJECT ADMINISTRATION**
- N/A N/A a) Negotiation of Scope of Services for Work Authorization
i) Acquisition Provider will visit project site with COUNTY personnel if necessary.
- N/A N/A b) Project Presence at L&G Consultant Office Headquarters
i) Full Project Office
(1) No Joint Use of COUNTY or TxDOT facilities
(2) Open during normal COUNTY and State work hours
(3) Personnel available to answer questions
(4) Availability of Project Files
(5) At least one office staff member is required to be a current commissioned notary public.
- N/A N/A c) Overhead Costs
i) Administrative costs
- N/A N/A d) Communication
i) Provide monthly progress reports with invoice.
ii) Participate in project review meetings as determined by the COUNTY.
iii) Prepare initial property owner contact list for use by the COUNTY in distribution of Acquisition Provider introduction letters.
- N/A N/A e) File Management
i) Project and parcel files will be kept in the COUNTY's Office, if necessary. Working files will be kept in the Acquisition Provider's project administrative office, but documents generated or received by the Acquisition Provider will be forwarded to the COUNTY office as they are generated or received by the Acquisition Provider if necessary.
ii) Prepare payment transmittal request utilizing standard payment submissions forms with supporting documentation.
iii) Maintain records of all payments including check number, amount, and date paid, etc.
iv) Provide copies of all incoming and outgoing correspondence as generated if requested by COUNTY at provider conference.
v) Maintain copies of all correspondence and contacts with property owners.
- 2) TITLE SERVICES**
- N/A N/A a) Secure preliminary title commitments from the Title Company that will be providing title insurance. Cost of preliminary title commitments will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work for payment and paid as a separate item.
- N/A N/A b) Secure title commitment updates in accordance with insurance rules and requirements for parcel payment submissions. Cost of title commitment updates will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work and paid as a separate item.
- N/A N/A c) Secure title insurance for all parcels acquired, insuring acceptable title to COUNTY OF HIDALGO. Written approval by the COUNTY required for any exception.

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	3) APPRAISAL
		a) Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list will be available for review at all District offices or at the Right of Way Division Office at 118 E. Riverside Drive, Austin, Texas, upon request.
<u>N/A</u>	<u>N/A</u>	b) Secure written permission (if necessary) from the owner to enter the property from which land is to be acquired. If the Acquisition Provider and/or the fee appraiser, after diligent effort, is unable to secure the necessary letter of permission from the property owner, a waiver must be obtained, in writing from the COUNTY/TxDOT. Maintain permission letters with appraisal reports.
<u>N/A</u>	<u>N/A</u>	c) Prepare (if necessary) pre-appraisal contact with interest owner(s) for each parcel using acceptable COUNTY/TxDOT forms.
<u>N/A</u>	<u>N/A</u>	d) Contact property owners or their designated representative to offer opportunity to accompany the appraiser on the appraiser's inspection of subject property. Maintain record of contact in file.
<u>N/A</u>	<u>N/A</u>	e) Prepare complete appraisal report for each parcel to be acquired utilizing TxDOT Forms No. ROW-A-5 and ROW-A-6 as applicable. These reports shall conform to TxDOT/COUNTY policies and procedures along with the Uniform Standards of Professional Appraisal Practices.
<u>N/A</u>	<u>N/A</u>	f) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation.
<u>N/A</u>	<u>N/A</u>	g) All completed appraisals will be administratively reviewed by L&G Engineering ROW Office and recommended for approval by TxDOT.
<u>N/A</u>	<u>N/A</u>	h) As necessary, the appraiser will appear and or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing / pre-trial meetings as directed by L&G Engineering and/or TxDOT.
<u>N/A</u>	<u>N/A</u>	i) As necessary, the appraiser will coordinate with review appraiser regarding revisions, comments, or additional information that may be required.
<u>N/A</u>	<u>N/A</u>	j) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.
		4) APPRAISAL REVIEW
<u>N/A</u>	<u>N/A</u>	a) Review Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list is available for viewing at all District offices or the Right of Way Division office at 118 E. Riverside Drive, Austin, Texas upon request.
<u>N/A</u>	<u>N/A</u>	b) Review all appraisal reports for each parcel to determine consistency of values, supporting documentation related to the conclusion reached and compliance with TxDOT/COUNTY policies and procedures and the Uniform Standards of Professional Appraisal Practices.
<u>N/A</u>	<u>N/A</u>	c) Prepare and submit to TxDOT the Form ROW-RTA-10 "Tabulation of Values", for each appraisal.

Services
Provided By:
ENGINEER COUNTY

N/A N/A d) The cost of the review appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the review appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.

5) APPRAISAL UPDATES

N/A N/A a) Prepare complete appraisal update for the parcel to be acquired utilizing TxDOT Form No. ROW-A-5, which will be furnished to the provider by TxDOT. These reports shall conform to COUNTY/TxDOT policies and procedures along with the Uniform Standards of Professional Appraisal Practices.

N/A N/A b) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation. All completed appraisals will be administratively reviewed by L&G Engineering Right of Way Office and recommended for approval by TxDOT.

N/A N/A c) As necessary, the appraiser will appear or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing or pre-trial meetings as directed by the TxDOT/COUNTY.

N/A N/A d) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.

N/A N/A e) As necessary, the appraiser will coordinate with the review appraiser regarding corrections and/or additional information that may be required.

6) NEGOTIATION TASKS AND FEES

N/A N/A a) Analyze appraisal and appraisal review reports and confirm the TxDOT's approved value prior to making offer for each parcel.

N/A N/A b) Analyze preliminary title report to determine potential title problems, propose methods to cure title deficiencies.

N/A N/A c) Prepare the initial offer letter, instruments of conveyance, and any other documents required or requested by COUNTY /TxDOT on applicable COUNTY /TxDOT forms.

N/A N/A d) Mail (Certified Mail Return Receipt Requested) initial offer letter, draft deed, Bill of Rights Brochures and Appraisal Reports to address confirmed with the Appraisal District of Hidalgo County. Maintain follow-up contacts and secure the necessary instruments upon acceptance of the offer for the closing.

N/A N/A e) Provide a copy of the appraisal report for the subject property exclusively to the property owner or authorized representative at mailing of initial offer. Maintain original signed Receipt of Appraisal. (unless property owner refuses to sign it).

N/A N/A f) Respond to property owner inquiries verbally and in writing within two business days.

N/A N/A g) Prepare a separate negotiator contact report for each parcel per contact.

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	h) Maintain parcel files of original documentation related to the purchase of the real property or property interests.
<u>N/A</u>	<u>N/A</u>	i) Advise property owner on the Administrative Settlement process. Transmit to TxDOT any written counter offer from property owners including supporting documentation, and provider recommendation with regard to Administrative Settlements in accordance with COUNTY /TxDOT policy and procedures.
<u>N/A</u>	<u>N/A</u>	j) Prepare final offer letter, documents of conveyance as necessary.
<u>N/A</u>	<u>N/A</u>	k) Appear and provide Expert Witness testimony as an Acquisition Provider when requested.
<u>N/A</u>	<u>N/A</u>	l) Meet at the L&G Engineering ROW office in Mission once per week as agreed-upon with the Right of Way Acquisition Manager/Administrator.
<u>N/A</u>	<u>N/A</u>	m) Provide a monthly progress report per parcel by the 25th of the month with invoice.
<u>N/A</u>	<u>N/A</u>	n) The consultant shall, as part of this proposal, estimates 10% of the parcels identified on Page 37 may end up in condemnation. The consultant shall be available for any meeting/hearings as requested by the COUNTY Attorney.
		7) CLOSING SERVICE FEES
<u>N/A</u>	<u>N/A</u>	a) Coordinate with COUNTY and Title Company to obtain an updated title commitment along with other Forms and certified copy of the instrument of conveyance necessary when requesting the Parcel Payment from the COUNTY.
<u>N/A</u>	<u>N/A</u>	b) Acquisition Provider shall attend closings and provide closing services in conjunction with Title Company.
<u>N/A</u>	<u>N/A</u>	c) Acquisition Provider shall record all original instruments immediately after closing at the respective County Clerk's Office, except for donations which must be forwarded to TxDOT for acceptance by the Texas Transportation Commission.
		8) RELOCATION ASSISTANCE SERVICES (separate Work Authorization will be issued once relocations have been identified, unless noted otherwise).
<u>N/A</u>	<u>N/A</u>	a) The amount of relocations or displacements as identified. L&G will provide relocation advisory services. L&G will compute replacement housing supplements (owner occupant and/or tenants)
<u>N/A</u>	<u>N/A</u>	b) L&G will provide advisory services to business displacements and relocate them effectively.
<u>N/A</u>	<u>N/A</u>	c) TxDOT will review, approve and pay for all relocation costs as per the Agreement.
		9) CONDEMNATION SUPPORT
<u>N/A</u>	<u>N/A</u>	a) Pre-Hearing Support
		i) Upon receipt of a copy of the final offer, request an updated title commitment for Eminent Domain from the Title Company.
		ii) Prepare a Bisection Clause for the original set of Legal Descriptions supplied by Surveyor if applicable
		iii) Use the information from the Title Commitment to join all interested parties on the necessary forms. <u>Spouses of owners must also be joined.</u>

Services
Provided By:
ENGINEER COUNTY

- iv) Upon completion of the necessary forms, prepare a packet containing 2 copies each of the following documents: Title Commitment, Negotiator's Reports, Appraisal Acknowledgment, Preappraisal Contact Sheet, signed and sealed property description, and plat, Final Offer Letter, any correspondence from the land owner or representatives, along with one copy of the appraisal report. Submit packet to the COUNTY Office for submission to the COUNTY Attorney's office.
- v) Upon receipt of concurrence for the Appraisal Witness, request the update of appraisal.
- vi) Upon receipt of packet prepared by the COUNTY Attorney which will include Petition for Condemnation, Lis Pendens, Order Appointing Special Commissioners, Order Setting Hearing, Oath of Special Commissioner, and Notice of Hearings, developed by the COUNTY Attorney; the attorney shall file the original petition with the COUNTY Court at Law or other appropriate Court for a cause number to be assigned.
- vii) The COUNTY attorney shall file the Lis Pendens including the cause number with the COUNTY Clerk's Office.
- viii) Upon assignment of a court, the COUNTY Attorney shall file the Order Appointing Commissioners with the judge retaining a copy of the Order for the files.
- ix) Following appointment of Special Commissioners by the judge, the COUNTY shall secure the following documents: Oath of Commissioners signed by the Commissioners, Order Setting Hearing, 2 copies of the Notice of Hearing signed by the Commissioners.
- x) The COUNTY shall file all originals with the court and send copies marked "copy" to L & G Engineering.
- xi) The COUNTY Attorney shall send a copy of the petition to the Title Company so that the Title Company can make sure the appropriate parties were joined and that no changes in title have occurred.
- xii) The COUNTY Attorney shall set the Special Commissioners Hearing after the updated appraisal has been submitted, if there is no change in value. If there is an increase in value, COUNTY will approve the new value and the COUNTY's provider will present a revised offer and a final offer letter and submit a copy of the final offer letter.
- xiii) The COUNTY Attorney shall coordinate a pre-hearing conference prior to the hearing the day before or earlier to discuss facts of the case with the COUNTY, Appraiser, and Negotiator.
- xiv) After the hearing is set, the COUNTY Attorney shall serve Notices of Hearing to the indicated parties at least 11 days prior to the Commissioner's hearing. If it is necessary to join the Federal Government, be advised that they have an additional 60 days to prepare for the Hearing.
- xv) Once the notices have been served, the COUNTY Attorney shall file the original notices with the court and send copies stamped "copy" to L&G Engineering ROW Office.
- xvi) The COUNTY's Attorney shall send a reminder letter 2-3 weeks in advance to the COUNTY Administration offices, Acquisition Provider, the three special commissioners and court reporter concerning Hearing dates.

N/A

N/A

- b) Post Hearing Support (by COUNTY Attorney)
 - i) For the hearing, prepare the necessary forms and Special Commissioners time sheets and submit forms to Hidalgo COUNTY clerk's office.
 - ii) Obtain the signatures of Special Commissioners on the Award of Commissioners and file with the court for the judge's signatures within 48 hours of the Hearing.
 - iii) Give timesheets to Judge. The amount paid to the Special Commissioners is determined by the Judge.
 - iv) Obtain and distribute 3 certified copies of the award as follows: 1 certified copy to the title company with a request for a commitment, 1 certified copy to the COUNTY, 1 certified copy to L&G Engineering with the Commitment to request the warrant in the amount of the Special Commissioners Award.

- v) Send the Commitment and the Award to COUNTY, along with individual special commissioner's billing requesting the payment for their fees.
- vi) File COUNTY warrant in the registry of the court. File a Notice of Deposit with the court and send certified copies to each defendant notifying them of the date of the deposit. The Date of Deposit is the Date of Take.
- vii) Take photograph of the interest to be acquired (if necessary) on the day of deposit for relocation verification.
- viii) Send written notices of the date of deposit to the COUNTY Administration office and all interested parties.
- ix) Appear as Expert Witness as requested. Sub-contractors must also appear as Expert Witnesses as requested.
- x) All acquisition negotiations file indicating all "due diligence" provided by the Acquisition Provider will be directed to the COUNTY Attorney's office for his further handling in accordance to the Eminent Domain process by the COUNTY.

10) COMPENSABLE UTILITIES

Utility Accommodation is an integral factor in road construction and design. Coordination of utility adjustments is a necessary function within planning, design, acquisition and construction and requires the administration of property rights issues, utility policy, and reimbursement of eligible utility adjustments. It includes the following tasks:

<u>N/A</u>	<u>N/A</u>	a) Preliminary Design Consultations i) Conduct Field Investigation and review Certificate of Convenience and Necessity boundaries to identify utility providers within the project area. Communications through letter, phone calls and email to establish a contact list. Coordinate data gathering by surveyors and design team. Introduce project to utility providers.
<u>N/A</u>	<u>N/A</u>	b) Field Observations and Verifications i) Provide maps to Utility providers to "redline" and identify conflicts. Coordinate exposures and data collection by surveyor. Provide and confirm utility data on project maps. Order Utility Location Service.
<u>N/A</u>	<u>N/A</u>	c) Exchange of Information with Utility Providers i) Provide project schedule. ii) Request schedules for utility adjustments. iii) Identify who is responsible for utility process.
<u>N/A</u>	<u>N/A</u>	d) Confirmation of Property Interests i) Request Documents. ii) Coordination of data on maps and citation of property interest documents. iii) Confirm utilities are within easements.
<u>N/A</u>	<u>N/A</u>	e) Coordination of Agreements i) Identify utilities that are compensable. ii) Determine parties and agreements necessary to complete compensable process. iii) Coordinate execution and processing of Standard Utility Agreements.
<u>N/A</u>	<u>N/A</u>	f) Utility Meetings throughout project development i) Set up and coordinate utility meetings during planning, design, acquisition and construction phases. ii) Attend and participate in meetings by other parties.

11) PAYMENT SCHEDULE

<u>N/A</u>	<u>N/A</u>	a) Project Administration i) Payment and Milestones (a) Full Project Office (1) Lump Sum Basis (assume 1 year project presence)

- (2) Initial payment of 25% upon establishment of a project office with functional phone and utility services.
- (3) Remainder paid out in equal monthly installments of 15% starting the following month.
- (4) Monthly billing to COUNTY OF HIDALGO will be required.
- b) Title Services
 - ii) Payment
 - (a) Per Parcel basis.
 - iii) Milestones
 - (a) 100% upon securing initial title commitment.
- c) Appraisal Services
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% paid upon delivery of complete and acceptable appraisal report
- d) Appraisal Review
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon submission of ROW-A-10
- e) Appraisal Update
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon delivery of complete and acceptable appraisal update.
- f) Negotiation, Task, and Fees
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 80% upon presentation of initial offer.
 - (b) 20% upon successful negotiation and all instruments are recorded.
- g) Closing Service Fees
 - i) Payment
 - (a) Per Parcel Basis
 - ii) Milestones
 - (a) 100% upon recording of instrument of conveyance.
- h) Relocation Assistance
 - i) Payment
 - (a) Per Relocation
 - ii) Milestones
 - (a) 100% upon issuance of 90-day vacancy letter.
- i) Compensable Utilities
 - i) Payment
 - (a) By percent complete

NOT INCLUDED IN
WORK AUTHORIZATION NO. 1

ADDITIONAL RESPONSIBILITIES

Easements, Letters of Permission, Etc.

The ENGINEER shall be responsible for delineating easements. The ENGINEER will be responsible for securing the necessary legal instruments.

Coordination of Utilities

The ENGINEER shall furnish the COUNTY prints of a project layout which will be distributed by ENGINEER to various utility companies to determine which utilities are in the limits of the project. These shall be preliminary layouts. Upon completion of the preliminary drainage plans and U&D sheets, the ENGINEER shall distribute to the various utility companies and request return. Upon return of these prints, the ENGINEER will schedule a meeting with the various utility companies to discuss potential conflicts and conformance with the State's Utility Accommodation Policy. The ENGINEER is responsible for coordination with the various utility companies for exposing potential conflicts and field ties to uncover utilities in potential conflict areas.

Meetings

Meetings will be held with the FHWA, State Officials, local governments, property owners, utility owners, railroad companies, other consulting firms, etc., as needed or required by the COUNTY. The ENGINEER shall coordinate through the COUNTY for the development of this project with any local entity having jurisdiction or interest in the project (i.e., city, county, etc).

Specifications, Special Provisions, Special Specifications

Use the State's standard specifications or previously approved special provisions and/or special specifications. If a special provision and/or special specification is developed for this project, it shall be in the State's format and incorporate references to approved State test procedures.

Project Manager/Engineer Communication

The ENGINEER shall designate one Texas Registered Professional Engineer to be responsible throughout the project for project management and all communications, including billing, with the COUNTY's Director. Any replacements to the ENGINEER's designated Project Manager/Engineer must be approved by the COUNTY.

Engineering documents produced for the department's engineering projects shall be signed, sealed and dated or CADD sealed in accordance with Administrative Order No. 5-89 and Administrative Circular No. 26-91.

Design Responsibilities

The ENGINEER is responsible for design errors and/or omissions that become evident before, during or after construction of the project. The ENGINEER's responsibility for all questions arising from design errors and/or omissions will be determined by the COUNTY and all decisions shall be final and binding. This would include, but not necessarily be limited to:

1. All design errors and/or omissions resulting in additional design work to correct the errors and/or omissions.
2. Preparation of design documents and detail drawings necessary for a field change due to design errors and/or omissions.
3. Revision of original tracings to the extent required for a field change due to design errors and/or omissions.

The ENGINEER shall promptly make necessary revisions or corrections resulting from the ENGINEER's errors, omissions or negligent acts without additional compensation. Acceptance of the work by the COUNTY will not relieve the ENGINEER of the responsibility for subsequent correction of any such errors or omissions or for clarification of any ambiguities.

Document and Information Exchange

Data, Plan Sheets, General Notes and/or Specifications provided to the COUNTY shall be furnished on 8GB USB flash drives. Each 8 GB flash drive shall have a file titled Table of Contents. The Table of Contents shall indicate the locations of files within the directory structure of the documentation.

General Notes and specifications shall be provided in MS Office 2007 format. Plan sheets shall be provided in Microstation DGN or GEOPAK GPK format. PDF copies of plan sheets shall also be provided.

Two copies of the documentation shall be provided to the COUNTY.

If required, the ENGINEER shall provide to the COUNTY, a CD that contains all the plan sheets for the project. The graphics tape shall be compatible with the COUNTY's computer system.

CD Tape Required (YES or NO): YES

Proposal Time

The time indicated in the proposal and the contract shall include time necessary for reviews, approval, etc.

Office Location

The ENGINEER will perform the services to be provided under this agreement out of their office or offices listed below:

<u>Service</u>	<u>Office Location</u>
PS&E	Mission Office
Schematic	Mission Office
Environmental Document	Mercedes Office

The work effort will be managed out of the Mercedes
(City)
office located at 2100 West Expressway 83,
(Address)
Mercedes, Texas.
(City) (State)

EXHIBIT "D-1"
ESTIMATED PROJECT FEE SCHEDULE
FM 1925 PROJECT (SEGMENT II)
(Limits: from FM 907 (Alamo Road) to East of SH68 (Uresti) Street)

ROADWAY PROJECT:	FM 1925	
LIMITS:	from FM 907 (Alamo Road) to East of SH 68 (Uresti Street)	
EXISTING ROADWAY SECTION:	40-ft Rural	
EXISTING ROW WIDTH:	80-Feet	
PROPOSED ROADWAY SECTION:	4-lane divided urban	
PROPOSED ROW WIDTH:	120FT	
ESTIMATED CONSTRUCTION COST:.....	\$10,305,000.00	
LENGTH FOR 4-LANE ROADWAY	2.3 Miles	
ESTIMATED PROJECT COSTS	STATE/MPO	* LPA
WORK AUTHORIZATION NO. 1		
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN		
Environmental Assessment with TxDOT	\$ -	\$ 95,000.00
Public Involvement for the project with stakeholders and 1 Public Meeting	\$ -	\$ 25,000.00
Archeological and Historical Research	\$ -	\$ 30,000.00
Engineering Technical Support at Public Mtgs with Layouts etc	\$ -	\$ 24,000.00
Schematic for FM 1925	\$ -	\$ 154,575.00
Hydrological Map	\$ -	\$ 42,000.00
Schematic for intersecting streets (Sharp to 3rd Street)	\$ -	\$ 40,000.00
Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	\$ -	\$ 21,000.00
Preliminary Compensable Utilities Identification on Schematic for Approval by TxDOT/FHWA	\$ -	\$ 18,000.00
Update Schematic based on comments as provide by TxDOT/County for schematic and EA update w/ FHWA	\$ -	\$ 39,000.00
Engineering Technical Support at Public Hearing with Layouts etc	\$ -	\$ 36,000.00
Public Involvement and 1 Public Hearing	\$ -	\$ 25,000.00
SUB-TOTAL	\$ -	\$ 549,575.00
WORK AUTHORIZATION NO. 2		
PHASE II- PS&E and CONSTRUCTION OVERSIGHT		
Complete ROW Map (Estimated 12 Parcels)		\$ 48,000.00
Outfall Identification Preliminary Property Ownership and Hydraulics	\$ -	\$ 36,000.00
PS&E Development (7.5% Engineering Fee)		\$ 772,875.00
Engineering Fee to Create sets of Plans and Submit through TxDot and Austin Letting		\$ 135,000.00
PS&E Development for OUTFALL(S)		\$ 162,000.00
Field Surveys for Design and Construction		\$ 110,000.00
Permitted Utilities Coordination to adjust	\$ -	\$ 90,000.00
ROADWAY CONSTRUCTION COST	\$ 10,305,000.00	
TxDOT Construction Inspection (11%)	\$ 1,133,550.00	
Eng Consultant Construction Management (18 Months)		\$ 162,000.00
SUB-TOTAL	\$ 11,438,550.00	\$ 1,515,875.00
WORK AUTHORIZATION NO. 3		
PHASE III - ROW Acquisition		
Right-of-Way Costs - Acq.Services @ (est. 12 Parcels @ \$13,800/Parcel Avg.)		\$ 165,600.00
Estimated County Attorney Costs for Condemnation (\$15,000/Parcel based on 20% total of parcels)		\$ 36,000.00
Estimated Compensable Utility Mgmt for Acq. of Property Rights and Compensate for Utility Adjust(s) (2) High Pressure Gas lines and One Parrallel Irrigation Line and one Parrallel Gas Line		\$ 189,000.00
Estimated Roadway Right-of-Way Costs (422,400 sq/ft @ \$4.5/ sq ft) (80/20)	\$ 1,881,792.00	\$ 19,008.00
COMPENSABLE UTILITY COSTS (Est 2-Pipeline Crossings at \$130,000 ea to lower and encase and 1 Parallel Pipeline and 1 Parralel Irrigation Line both at 150,000 each)	\$ 504,000.00	\$ 56,000.00
SUB-TOTAL	\$ 2,385,792.00	\$ 465,608.00
TOTAL	\$ 13,824,342.00	\$ 2,531,058.00

Work Authorization No. 1 Phase I	FY 13	\$ 549,575.00	PENDING APPROVAL
Work Authorization No. 2 Phase II	FY 14	\$ 1,515,875.00	NOT ISSUED
Work Authorization No. 3 Phase III	FY 15	\$ 354,600.00	NOT ISSUED

State/FED Estimated Costs
Local Estimated Costs

TOTAL ESTIMATED COUNTY COST:	\$ 2,531,058.00	15.48
TOTAL ESTIMATED PROJECT COST:	\$ 16,355,400.00	
COUNTY COSTS NOT INCLUDED IN WORK AUTHORIZATIONS	\$ 111,008.00	

* Local Public Agencies (LPA)

EXHIBIT D-1
ESTIMATED PROJECT FEE SCHEDULE AND MAN-HOUR BREAKDOWN

FM 1925 (SEGMENT II) PROJECT
(from FM 907 (Alamo Road) to East of SH68 (Uresti St.))

	MANHOURS																
	Senior Project Manager	Senior Engineer	Senior Environmental Scientist /Specialist	Project Engineer	Design Engineer	ROW Administrator	EIT	Senior Engineer Tech	Environmental Scientist /Specialist	Engineer Tech	CADD Operator / GISAnalyst	Admin / Clerical	Biologist	TOTAL HOURS	Sub-Contract Amounts / ROW COST	TOTAL LINE ITEM COST	ROUNDED TOTAL LINE ITEM COST
CONTRACT RATE	215.40	167.89	136.21	123.54	114.04	107.70	82.36	79.19	79.19	76.02	66.52	57.02	50.68				
WORK AUTHORIZATION NO. 1																	
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC, DESIGN																	
1 Environmental Assessment with TxDOT	60		250						200		245	100	201	1056		\$ 95,000.58	\$ 95,000.00
2 Public Involvement for Environmental Assessment and 1 Public Meeting	30		35	39		10			28.25		41.25	17	38	238.5		\$ 25,000.66	\$ 25,000.00
3 Archeological and Historical Research			2						0.5					2.5	\$ 29,692.00	\$ 312.02	\$ 312.00
4 Engineering Technical Support at Public Meetings with Layouts, etc.	25		44	31		30					44.75	24	24	222.75		\$ 24,000.55	\$ 24,000.00
5 Schematic for FM 1925	28	30		70	120		79	76.25		100	1496	15	13	2027.25		\$ 154,575.24	\$ 154,575.00
6 Hydrological Map	14	24	8	65	32		37.75		16	81	163.75	8	6	455.5		\$ 42,000.66	\$ 42,000.00
7 Schematic for intersecting streets (Sharp to 3rd Street)	9	8		8	8		8	9		10	479	10	5	554		\$ 40,000.83	\$ 40,000.00
8 Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	10	10		30	49		30.25			20	49	7	4	209.25		\$ 21,000.19	\$ 21,000.00
9 Preliminary Compensable Utility Management Identification on Schematic	10	18		16	19	9	18.25	20		26	34	5	2	177.25		\$ 18,000.25	\$ 18,000.00
10 Update Schematic based on comments as provided by TxDOT/FHWA	24	24		36	60		44	17		60	101	29	12	407		\$ 39,000.33	\$ 39,000.00
11 Engineering Technical Support at Public Hearing with Layouts, etc.	24	20	24	36		33	45		32	42	47	31	37	371		\$ 36,000.32	\$ 36,000.00
12 Public Involvement for 1 Public Hearing	21	17	18	18		19	18.25		22	29	37	32	23	254.25		\$ 25,000.68	\$ 25,000.00
SUB-TOTAL	255	151	381	349	288	101	280.5	122.25	298.75	368	2737.75	278	365	5975.25	\$ 29,692.00	\$ 519,892.30	\$ 519,887.00

Subtotal Manhour Fee with Sub-Consultant Costs:	\$ 549,584.30

* Total Project Fee:	\$ 549,575.00

*Rounded Figure



AGENDA
HIDALGO COUNTY
COMMISSIONERS COURT MEETING
December 10, 2013
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a SPECIAL MEETING of the Commissioners' Court will be held at Edinburg Council Chambers, 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

- 1. Roll Call**
- 2. Pledge of Allegiance**
- 3. Prayer**
- 4. Approval of Consent Agenda**
- 5. Open Forum**
- 6. County Judge's Office:**
 - A. AI-41991** Discussion, consideration, and action regarding written Resolution and ballot selection of Appraisal District Board of Directors for 2014-2015.
 - B. AI-42138** Discussion, consideration, and approval of Letter of Support for the Rio Grande Regional Water Authority (RGRWA).
- 7. Executive Officer - Valde Guerra:**
 - A.**
 1. Requesting exemption from competitive bidding requirements under the Texas Local Government Code, Section 262.024(A) (4) "a Professional Service" for the "provision of legal services/representation in connection with litigation."
 2. Requesting engagement with the firm of _____ for the "Provision of Legal Services/Representation in connection with Litigation" and authority to submit letter of engagement
 - B.** Presentation for discussion, consideration and action (if necessary) including, but not limited to the following:
 - 1) Renovations to Former Administration Building 1st and 2nd Floors
 - 2) Update on other ongoing county owned building construction and renovation repair projects
 - 3) Emergency situations occurring since last agenda meeting

- A. **AI-42139** Discussion and Possible Action to execute the LPA Standard Utility Agreement for FM 681 with Sharyland Water Supply Corporation and AEP Texas Central Co. (AEP-TCC).

16. Precinct #1 - Comm. Cuellar:

- A. **AI-42095** Pct. #1 R&B (1200):
1. Approval of Certification of Revenues as certified by the County Auditor for TxDOT Reimbursement of BCAP Forced Labor - El Mesquite Subdivision and Mid Valley Estates Subdivision.
 2. Approval of 2013 appropriation of funds into Precinct No.1 Road & Maintenance (program 005) in the amount of \$119,246.61.

17. Precinct #2 - Comm. H. Palacios:

- A. **AI-41891**
1. Approval of Interlocal Cooperation Agreement between Military Highway Water Supply Corporation and County of Hidalgo, Texas to extend 10" potable water supply line.
 2. In accordance with Section 791.014 of the Texas Government Code, requesting approval of the interlocal cooperation agreement project to assist the Military Highway Water Supply Corporation in the extension a 10" potable water supply line for the Precinct 2 Equipment & Maintenance Facility Project.

18. Budget & Management - Sergio Cruz:

A. **Budget Appropriations:**

1. **AI-42135** Precinct No.4 Road Project:
 - A. Approval of Certification of Revenues by the County Auditor, for proceeds from the sale of assets to Hidalgo County DD No.1
 - B. Approval of 2013 appropriation of funds in the amount of \$549,575.00 for FM 1925 road project.

19.

Purchasing Department - Marty Salazar:

Notes:

A. FOR ANY CONTRACT(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FOWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

A.

Hidalgo County

1. **AI-42056** Presentation for discussion, consideration and applicable action for the engagement of professional consulting services provider in connection with securing funding from: Settlement BP Deepwater Horizon Restoration Project including, but not limited to, the following options:

A. Exemption from competitive bidding requirements under Texas Local Government Code, Chapter, 262.024(a)(4) a professional service to negotiate an agreement;

B. Procure a professional consulting services contract by formally publishing/advertising a solicitation for a Request for Proposals (with qualifications) for same.
2. **AI-42119** Acceptance and approval to exercise the option to extend the current inter-local cooperation agreement for an additional one (1) year (as stipulated/detailed in agreement) between Hidalgo County and the City of Edinburg for MSW & Tire disposal services.
3. **AI-42105** Request by lessor, Triple R Medical Facilities (with recommendation from UCP Director to CC to approve) for additional days on the acceptance date of construction of the "Lease of Office Space for Urban County Program" with extension through end of December 2013 through project #C-13-177-07-23.

B.

Pct. 4

1. **AI-42061**
 - a. Requesting approval of a **professional architectural "on call" services agreement** with **RABA-KISTNER, INC.** for the purposes of Repairs/Renovations/Remodeling and/or Additions/Alterations on a "per project basis" for County owned Buildings/Structures located within Hidalgo County Precinct No. 4, through the forms of an AIA Agreement and as selected for negotiations through County's protocol under the "POOL" of Architects.

APPROVED



b. Requesting approval of a "professional engineering services" agreement with **L&G CONSULTING ENGINEERS, INC. d/b/a L&G ENGINEERING** for: "Professional Engineering Services" in connection to **Job Specific Project: Environmental Assessment, Public Involvement, Schematic and Hydrologic Design** for the "FM 1925 (from FM 907 (Alamo Road) East to East of SH68 (Uresti Street))" located within **Hidalgo County Precinct No. 4;**



c. Pursuant to Article 14 of the "professional engineering services" agreement with **L&G CONSULTING ENGINEERS, INC. d/b/a L&G ENGINEERING**, is requesting approval to engage the services of sub-contractor (**AMATERRA ENVIRONMENTAL, INC.**) with adherence to insurance provisions required by said article;



d. Requesting approval of Work Authorization No. 1 (\$ 549,575.00) from L&G CONSULTING ENGINEERS, INC. d/b/a L&G ENGINEERING for Professional Engineering Services" in connection to Job Specific Project: Environmental Assessment, Public Involvement, Schematic and Hydrologic Design for the "FM 1925 (from FM 907 (Alamo Road) East to East of SH68 (Uresti Street)" located within Hidalgo County Precinct No. 4.

e. Requesting approval of a "professional surveying services agreement" with **ARANDA & ASSOCIATES, INC.** for the purposes of **(Job Specific)** "Surveying Services" for: **"BREWSTER PARK PROJECT"** located within Hidalgo County Precinct No. 4.

C. Budget & Management

1. **AI-41789** Approval for HC to exercise the first (1st) (of two (2) possible) one (1) year extensions as provided in the RFP #2010-195-09-22-YSI Property & Casualty Insurance with acceptance and approval of detailed schedule of premiums/fees as attached hereto as 2014 Coverage Summary for Property and Casualty Insurance policies in the total amount of \$2,590,729.00 effective January 01, 2014 through January 01, 2015 with authority for County Treasurer to issue payment(s)/check(s) after review, audit and processing procedures completed by County Auditor with the authority for Valde Guerra, HCCC's Executive Officer to sign any applicable documentation.

2. **AI-42088** A. Presentation of scoring grid below (for the purposes of ranking by CC as qualified to continue process) of the responses received and evaluated in connection with RFP No. 13-155-11-20-YSI "Excess Workers' Compensation Insurance" in order to proceed forward with the negotiation portions of the procurement process:

	Montalvo Insurance Agency	The Klement Agency
Evaluator 1	94	DNMS*
Evaluator 2	87	DNMS*
Evaluator 3	87	DNMS*
Average Score	89	DNMS*
CC Rank		-

***Does Not Meet the Specifications/Requirements approved by Hidalgo County**

B. Requesting authority for Purchasing Department to enter into negotiations with the number one (1) ranked proposer/vendor Montalvo Insurance for: Excess Workers' Compensation Insurance.

HIDALGO COUNTY
Professional Engineering Services
Contract # C- 13-336-12-10
Work Authorization Form

WORK AUTHORIZATION NO. 2

THIS WORK AUTHORIZATION is made pursuant to the terms and conditions of Article 1 of the Agreement made by and between HIDALGO COUNTY, action herein by and through the Commissioner's Court, hereinafter called the "Owner," and, L & G Consulting Engineers, Inc. d/b/a L & G Engineering, professional engineers of Mercedes, Texas hereinafter called "Engineer".

PART 1. SCOPE OF WORK

The purpose of this Work Authorization is for the Engineer to provide Engineering Services required for the preparation of the PS&E Development, Right-of-Way Map, Right-of-Way Acquisition Services and Compensable Utility Management for the FM 1925 Segment II project specifically the Sharp Road Realignment Section from FM 1925 North 0.5 Miles.

The scope of services to be provided by the Owner is identified in *EXHIBIT "A" - Scope of Services to be provided by the Owner* attached hereto.

The scope of services to be provided by the Engineer is identified in *EXHIBIT "B" - Scope of Services to be provided by the Engineer* attached hereto.

PART 2. ESTIMATED COST

The estimated cost for services under this Work Authorization is \$406,610.78. This amount is based upon the costs outlined in the Estimated Cost Proposal attached hereto as *EXHIBIT "D-1" - Estimated Project Fee Schedule and Man-hour Breakdown*.

PART 3. PAYMENT

Compensation and payment to the Engineer for the services established under this Work Authorization shall be made in accordance with Article 6 of the Agreement.

PART 4. FUNDING

This Work Authorization No. 2 shall be funded through funding source:

Account No. 5-1345-431-00-124-127-0-721

Requisition Number _____ (MUST BE INCLUDED AFTER CC APPROVAL)

PART 5. PERIOD OF SERVICE

This Work Authorization shall become effective on the date of final acceptance of the parties hereto, and shall serve as a Notice to Proceed as per Article 3, Period of Service on the Agreement. This Work Authorization shall terminate upon completion of scopes of the work authorization, as identified on *EXHIBIT "C" - Work Schedule*.

PART 6. RESPONSIBILITIES AND OBLIGATIONS

This Authorization does not waive the parties' responsibilities and obligations provided under the Agreement.

PART 7. ACKNOWLEDGEMENT AND CONFIRMATION

Acknowledgement and confirmation by Hidalgo County Precinct No. 4, Commissioner Joseph Palacios as to the content and detail of this Work Authorization No. 2.

HIDALGO COUNTY

COMMISSIONER PRECINCT NO. 4

BY: Joseph Palacios

PART 8. ACCEPTANCE AND APPROVAL

This Work Authorization is hereby accepted, approved by Hidalgo County Commissioners' Court on March 31, 2015 as indicated below.

THE ENGINEER:

L&G ENGINEERING

By: Jacinto Garza, P.E.

President

THE OWNER:

HIDALGO COUNTY

By: Ramon Garcia

Ramon Garcia,
County Judge

ATTEST:

By: Arturo Guajardo Jr.

Arturo Guajardo, Jr., County Clerk

LIST OF EXHIBITS


Location Map

Exhibit A - Services to be provided by Owner

Exhibit B - Services to be provided by Engineer

Exhibit C - Work Schedule

Exhibit D-1 - Estimated Project Fee Schedule and Man-hour Breakdown



FM 1925 & SHARP ROAD LOCATION MAP

L & G Engineering
Transportation Consultants
2100 W Expressway #3
Mercedes, TX 78570
Phone : (956) 505-0813
Fax : (956) 505-0018

EXHIBIT "A"
SERVICES TO BE PROVIDED BY THE OWNER

1. The COUNTY will issue work authorization to initiate all required services and designate the authorized representative of the coordination of each work authorization.
2. The COUNTY will provide copies of all subdivision plats of record and/or in the subdivision process.
3. The COUNTY, will provide copies of Engineering, Drainage Studies within or near the project limits
4. The COUNTY will provide the ENGINEER with on-going guidance, timely reviews, and decisions necessary to complete services required by the work authorization in order to permit the ENGINEER to maintain an agreed upon project schedule.
5. The COUNTY will process all acceptable requests for payment in a timely manner.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 1 - PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: _____

PROJECT/DESCRIPTION: PS&E, ROW Mapping & ROW Acquisition for the
FM 1925 (Segment II) Project – Specifically Sharp
Road Realignment Project

LENGTH: 0.5 MILES

HIGHWAY: Sharp Road Realignment

LIMITS: From FM 1925 – Segment II
From FM 1925 (Monte Cristo) North 0.5 Miles

EXISTING FACILITY

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☒ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

ENGINEER shall mean L&G Engineering.

STATE shall mean Texas Department of Transportation.

COUNTY shall mean the Hidalgo County.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

COMPLETED IN WORK AUTHORIZATION NO. 1

SECTION 2 - ROUTE AND DESIGN STUDIES

(Function Code 110)

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	1. Route Location Studies
<u>N/A</u>	<u>N/A</u>	2. Level of Service Analysis
<u>NO</u>	<u>N/A</u>	3. Traffic Evaluations and Projections
<u>NO</u>	<u>N/A</u>	4. Develop Roadway Design Criteria
<u>NO</u>	<u>N/A</u>	5. Preliminary Cost Estimates
<u>NO</u>	<u>N/A</u>	6. Design Schematic (See Section 7, page 7-1 for schematic layout requirements)
<u>NO</u>	<u>N/A</u>	7. Preliminary Right-of-Way Requirements
<u>NO</u>	<u>N/A</u>	8. Design Concept Conference
		9. Soil Core Hole Drilling
<u>N/A</u>	<u>N/A</u>	a. Pavement (See Section 7, pages 7-3 thru 7-4 for requirements)
<u>N/A</u>	<u>N/A</u>	b. Retaining Walls (See Section 10, page 10-1 thru 10-2 for requirements)
<u>N/A</u>	<u>N/A</u>	c. Miscellaneous Structures (See Section 10, page 10-4 for requirements)
<u>N/A</u>	<u>N/A</u>	d. Bridges (See Section 11, page 11-3 for requirements)

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

COMPLETED IN WORK AUTHORIZATION NO. 1

SECTION 3

SOCIAL, ECONOMIC AND ENVIRONMENTAL STUDIES AND PUBLIC INVOLVEMENT

(Function Code 120)

Services
Provided By:
ENGINEER COUNTY

1. Environmental Reports
All Environmental Reports shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations, Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.
 - a. Environmental Assessments
 - (1) An Environmental Assessment shall be prepared, anticipating a Categorical Exclusion.
 - (2) An Environmental Assessment shall be prepared, anticipating a Finding of No Significant Impact.
 - (3) An Environmental Assessment shall be prepared, anticipating the need for a Draft Environmental Impact Statement.
 - b. Environmental Impact Statement
 - (1) A Draft Environmental Impact Statement shall be prepared. After appropriate interagency and public reviews within time limits prescribed by the Code of Federal Regulations, Title 23, Part 771 and 43 Texas Administrative Code 2.40-2.51, a Final Environmental Impact Statement shall be prepared.
 - (2) A Section 4(f) Statement (Department of Transportation Act) shall be provided by the ENGINEER. The format and content of the statement is found in FHWA Technical Advisory T6640.8A.
2. Public Involvement
All public involvement procedures shall be in accordance with 43 Texas Administrative Code (TAC) 2.40-2.51, Code of Federal Regulations Title 23, Part 771 and Highway Design Operations and Procedures Manual, Part II-B.
 - a. A public involvement meeting(s)/hearing(s) shall be scheduled, coordinated and conducted.*
 - b. Technical assistance, meeting(s)/hearing(s) preparation, maintenance of contracts lists, minutes of meeting(s), exhibit preparation, and other tasks outlined by the COUNTY, shall be provided.
3. Cultural Resources
Formal consultation with the State Historic Preservation Office (SHPO) and the Texas Historical Commission (THC) will be conducted by the COUNTY.
 - a. Historic Structure Studies
A records search and reconnaissance survey shall be performed, and documentation prepared regarding identification efforts, National Register eligibility and potential impacts to historic properties in accordance with the state's historic structure requirements.
 - b. Archeological Studies
 - (1) Files searches shall be conducted to determine if known archeological sites are present; to identify whether these sites have been listed or determined eligible for the National Register of Historic Places or have been designated State Archeological Landmarks; and to identify the need (if any) to perform additional archeological investigations.
 - (2) Archeological reconnaissance will be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.
 - (3) Archeological survey shall be performed under a Texas Antiquities Permit (13 TAC 26) signed for the Sponsor by a professional archeologist with the STATE.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	4. Noise and Air Quality Analyses
		a. Noise Analysis A noise analysis shall be prepared, including predicted noise levels and the consideration and evaluation of noise mitigation, in accordance with the STATE'S Noise Guidelines. The noise analysis or a summary of the noise analysis shall be included in the environmental document for the project.
<u>N/A</u>	<u>N/A</u>	b. Air Quality Analysis An air quality analysis shall be prepared in accordance with the STATE'S Air Quality Guidelines. The air quality analysis or a summary of the air quality shall be included in the environmental document for the project.
<u>N/A</u>	<u>N/A</u>	5. Ecological Investigations A wetland survey and if necessary, a wetland delineation shall be conducted and a "wetland finding" shall be provided if necessary. As part of the environmental phase of the project, the consultant should notify the District if it is believed that a Section 404 or Section 9 permit is required, and provide the technical data to the District for application to the U.S. Army Corps of Engineers and/or the U.S. Coast Guard. A determination should be made if there are potential federally listed endangered or threatened species that could be impacted. The District will be notified as soon as possible that Section 7 or 10 consultations may be required. Supporting data will be furnished to the district when consultation with the U.S. Fish and Wildlife Service is undertaken.
<u>N/A</u>	<u>N/A</u>	6. Hazardous Materials The consultant shall perform an Environmental Site Assessment for hazardous materials impact in accordance with the American Society for Testing and Materials (ASTM) 1528.93 (Transaction Screen Process).
<u>N/A</u>	<u>N/A</u>	7. General Guidelines for Preparation of Environmental Documents
		a. The Biological Impact Evaluation Report will be prepared and submitted electronically to TxDOT.
		b. All cultural resource reports (i.e. Archeological and Historical Project Coordination Requests (PCRs), background and reconnaissance surveys) will be submitted electronically to TxDOT.
		c. The draft administratively complete document will be submitted to TxDOT electronically through their FTP site.
		d. The administratively complete document will be prepared in accordance with the content and format of FHWA Technical Advisory T6640.8A and the TxDOT Administrative Code 43 TAC §2.44.
		e. The administratively complete document will be submitted to TxDOT electronically through their FTP site.
		f. Upon completion and approval of the administratively and technically complete document, the Engineer will provide one (1) hard copy to the Client, one (1) hardcopy to the district, and (3) hardcopies to TxDOT ENV.
		g. Exhibits in the environmental document shall be color copies and text shall be black and white.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 4 - RIGHT-OF-WAY DATA
(Function Code 130)

Services
Provided By:
SURVEYOR COUNTY

NOTE: No work involving right-of-way (ROW) data is to be performed until the COUNTY has given the ENGINEER written approval of the final location of the proposed ROW lines.

<u>YES</u>	<u>NO</u>	1. Ownership Data in a .dgn file
		a. The entire project limits.
		b. Compensable utility ownership who have property rights on ROW shall be researched and provided.
		c. For each drainage outfall property
		d. For each irrigation structure pipe.
<u>YES</u>	<u>NO</u>	2. Parcel plats & Right-of-Way Map
		a. A ROW map, parcel plats and field notes shall be prepared and furnished.
		b. All plats and field notes must be signed and sealed by a Registered Professional Land Surveyor (RPLS).
		c. ROW map must depict all improvements affecting ROW.
<u>YES</u>	<u>NO</u>	3. Utilities (Compensable)
		a. Property ownership with recording information shall be shown on ROW Map and Parcel Sketches with distance ties to property corners in an effort to locate utility.
<u>YES</u>	<u>NO</u>	4. Field Notes
		a. Field notes and plats, signed and sealed by a Registered Professional Land Surveyor, for all parcels on the ROW Map
		b. Computation Sheets for Survey Closure and Area for Each Parcel.
		c. Ground surveys and preparation of parcel maps, legal descriptions, and right of way maps.
<u>YES</u>	<u>NO</u>	5. Survey and Stake Right-of-Way (EXISTING AND PROPOSED)
<u>YES</u>	<u>NO</u>	6. Records as Required by the City and State
		a. Records used to establish ownership
<u>YES</u>	<u>NO</u>	7. General Guidelines for Preparation of Right-of-Way Maps (Sample ROW Maps and Parcel Sketches and field notes attached)

General Specifications

- a. All data submitted by the surveyor will be legible, organized and well documented.
- b. The surveyor shall provide temporary signs and shall control traffic near surveying operations adequately to comply with provisions of the MUTCD; a copy of which the Surveyor acknowledges has been furnished to him. All signs, flags, and safety equipment are to be provided by the surveyor.
- c. Permission to enter private property shall be the sole responsibility of the surveyor.
- d. The surveyor will be held responsible for the correctness of his services. The surveyor will be responsible for the completion of his services.
- e. The surveyor will be required to complete the attached "Right-of-Way Map Checklist" and submit along with the completed R.O.W. map. All requirements of attached R.O.W.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

map checklist must be complete, accurate and also considered to be essential and is a part of this contract.

Project specific scope of services

FC 130 – Right of Way Data – Abstract analysis, development of ROW Map sheets including parcel plats and field notes with Metes & Bounds field descriptions, and Title Commitments.

FC 150 – Field Surveying for Parcel Mapping – Recover horizontal & vertical control, locate and field tie existing ROW and boundary corners. Update topography, and reestablish corners for ROW map revisions.

SURVEYING SCOPE OF SERVICES FOR PARCEL MAPPING

RIGHT-OF-WAY DATA

Right-of-Way Documents - The Surveyor will utilize State examples and provide the following:

General

- a. Abstracting: The Surveyor will determine Ownership Data.
- b. Prepare individual parcel maps and field notes as needed to properly describe the right-of-way the State is to acquire.
- c. All procedures involving right-of-way maps will be in accordance with the State's Right-of-Way Book I and Book II, the State's local operating procedures and according to the Texas Board of Professional Land Surveying Practices Act.
- d. All required documents will be in English units.
- e. The Surveyor will monument all corners with a 5/8 inch iron rod with a Surveyor's plastic cap on all parcel boundary corners.
- f. The Surveyor will provide to the State a copy of Instruments of Record.
- g. The Surveyor will attach graphics files compatible with the latest version of Micro-Station graphics software.
- h. The Surveyor will attach documents or text files compatible with the latest version of Word software.

Parcel Plats

- a. A parcel plat will be prepared for each parcel of land to be acquired. The State has developed standard formats for parcel plats, copies of which the Surveyor will request and secure for all purposes
- b. Parcel boundary lines will be delineated with appropriate bearings, distances, and curve data.
- c. Private property lines will be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired.
- d. League lines and survey lines will be shown and identified by name and abstract number.
- e. A north arrow will be shown on each sheet and, if possible, in the upper right hand corner.
- f. Monumentation set or found will be shown and described as to material and size.
- g. A station and offset will be shown for each PC, PT, and angle point in the proposed right-of-way lines and the existing right-of-way lines in areas of no proposed acquisition.
- h. Intersecting streets will be shown and identified by name and right-of-way width.
- i. A parent tract inset will be shown for each parent tract.
- j. A note will be included on each map sheet stating the basis of bearings, coordinates, and datum used.
- k. Appropriate notes will be included on the title sheet stating the following:
 - a. Month(s) and year abstracting was performed upon which the map is based.
 - b. Month(s) and year field surveys were conducted upon which the map is based.
 - c. Month and year map was completed by the Surveyor.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

- l. The right-of-way account number and R.O.W. CSJ if available will be shown on each parcel map sheet.
- m. All parcel maps should be 8-1/2" x 11" signed and sealed by a Registered Professional Land Surveyor and note referencing legal description.
- n. The acreage of the part taken should be shown to three decimal places, rounded.

Field Note Descriptions - A field note description will be prepared for each parcel of land to be acquired. Field note descriptions will include, but need not be limited to, the following:

- a. The field note description will begin with a general description that will include, as a minimum:
 - a. **State**, county, and city within which the proposed parcel of land to be acquired is located.
 - b. A reference to unrecorded and recorded subdivisions by name, lot, block, and recording data to the extent applicable.
 - c. A reference, by name, to the grantor and grantee, date, and recording data of the most current instrument(s) of conveyance describing the parent tract.
- b. The field note description will continue with a metes and bounds description that will include, as a minimum:
 - a. A point of commencing (outside property corner).
 - b. A point of beginning on proposed R.O.W. line.
 - c. A series of courses, identified by number and proceeding in a clockwise direction, describing the perimeter of the parcel of land to be acquired, and delineated with appropriate bearings, distances, and curve data.
 - d. A description (8-1/2" x 11") of all monumentation set or found to include, as a minimum, size and material.
 - e. All field note descriptions will be signed and sealed by a Registered Professional Land Surveyor.
 - f. Note referencing parcel plat.

PHARR DISTRICT ROW MAP CHECKLIST

As the responsible consultant project manager, I hereby certify that the attached ROW Map has undergone a QA/QC review, with the following applicable items specifically checked for accuracy, completeness and constructability (as noted by Checkmarks)

Printed Name _____

MAP

☐ All documents have been proofread and are accurate.
☐ Title Commitments for each individual parcel.
☐ Graphics files compatible with Microstation and Word software are provided.
☐ Photos of proposed ROW staking included.
☐ Field notes and Parcel Plats are numbered continuous.
☐ Scale shall be 1"=50' or 1"=100".

- ___ Title and description of project including county, limits, etc....
- ___ Vicinity map with beginning and ending station
- ___ Equations and Exceptions
- ___ Index
- ___ Legend
- ___ Title block completely filled out with Construction and R.O.W. CSJs'
- ___ List all Major Utilities from Station to Station

_____ Sheet size 34" X 22"
 _____ Text legible when reduced to half-scale.
 _____ Title block completely filled out with R.O.W. CSJ
 _____ Matchlines
 _____ Project layout sheet
 _____ Existing utility lines and easements, deed reference, as shown on Schedule "B" of the Title Commitment, and defined on parcel plats

4-4

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

- ☐ Survey, county, and city limit lines shown and labeled
- ☐ Improvements shown and labeled (*see below*)
- ☐ Monumentation i.e. P.C., P.T., Break Points
- ☐ North arrow
- ☐ Scale
- ☐ Property lines
- ☐ Property descriptions i.e., lot, block, tract, subdivision, etc...
- ☐ Identify existing and proposed access denial locations (*if applicable*)

Proposed information:

- ☐ Type II Monumentation i.e. P.C., P.T., Break Points and 1500' intervals
- ☐ Survey and R.O.W. lines
- ☐ Basis of bearings
- ☐ Parcel bearings and distances correspond with traverse sheet
- ☐ Outside ties (P.O.C.) corresponds with field notes
- ☐ Point of beginning (P.O.B.) established on proposed R.O.W. line
- ☐ Parcel tied to baseline
- ☐ Baseline information shown i.e. Stationing, bearings, curve data, etc...
- ☐ Conveyance information shown in tables i.e. parcel number, grantors name, amount of take, remainder etc...
- ☐ Math checked on remainder

Improvements:

- ☐ Improvements bisected or within 25' of proposed R.O.W. line are shown on map with stationing and distance from proposed R.O.W. line. Buildings are labeled and dimensioned.
- ☐ Off-premise outdoor advertising signs within proposed R.O.W. are shown and labeled.

Utilities:

- ☐ All utilities within or crossing existing and proposed right of way are shown and labeled as to size, easement or fee width, and recording data of instrument.
- ☐ Location of underground storage tanks and/or filler caps are shown and labeled

*** DO NOT SEAL MAP**

FIELD NOTES

Heading

- ☐ County
- ☐ Highway
- ☐ Parcel number
- ☐ R.O.W. CSJ
- ☐ Construction CSJ

General Description or "preamble"

- ☐ Area of parcel to be acquired is shown in acreage (0.000) for rural land and/or square feet (to nearest whole sq. ft.) for urban land or smaller parcels

Parent tract data is shown:

- ☐ Size of parent tract
- ☐ Survey data or lot, block, and subdivision
- ☐ Name of last recorded seller and buyer
- ☐ Date, volume and page or document number of last recorded conveyance
- ☐ Records and county of last recorded conveyance

Beginning Description

- ☐ Point of commencement is on outside tie and is described accurately by bearings and distances as it leads to the point of beginning.
- ☐ Point of beginning is on proposed R.O.W. line

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Particular Description

- ☐ Traverse calls are clockwise sequence
- ☐ Bearings and distances correspond exactly with map, parcel sketch, and traverse sheet
- ☐ Bearings are to nearest whole second and distances are to the nearest one-hundredth of a foot
- ☐ Calls are numbered
- ☐ Denial of access shall be described from beginning to end (*if applicable*)

Closing

Description

- ☐ Last call leads back to P.O.B.
- ☐ Restates area of parcel
- ☐ Establishes taking in existing road R.O.W. if applicable
- ☐ Legal description is referenced to Plat
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)

PARCEL SKETCH

- ☐ Shows P.O.B. and P.O.C.
- ☐ All data corresponds exactly with Map and Field Notes
- ☐ Sheet size is no larger than 8 1/2" x 11"
- ☐ Plat closely matches example provided
- ☐ Plat referenced to legal description
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)
- ☐ Existing utility lines and easements (deed reference, if available);

TRAVERSE SHEET

- ☐ Computations show area to be acquired in sq. ft. or acres, whichever is applicable
- ☐ Computations show area that is existing road R.O.W. if applicable
- ☐ Traverse calls are in clockwise sequence
- ☐ Error of closure meets the following:

Secondary rural	.0003
Primary rural - secondary urban	.0002
Urban or industrial	.00013

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 5 - FIELD SURVEYING AND PHOTOGRAMMETRY

(Function Code 150)

Services
Provided By:
SURVEYOR COUNTY

<u>YES</u> <u>NO</u>	1. Field Surveying
	a. Primary Project Control - 3 to 5 miles spacing Precision shall be 1 part in 20,000 or better, unless otherwise directed by the district engineer. (1) Establish horizontal control points (2) Establish vertical control points
	NOTE: ALL BEARING AND DISTANCE SHALL BE BASED ON THE STATE PLANE COORDINATE SYSTEM NAD 1983, SOUTH ZONE. ALL DISTANCES AND COORDINATES SHALL BE SURFACE AND MAY BE CONVERTED TO GRID BY MULTIPLYING BY A COMBINED SCALE FACTOR OF 0.999960 This project shall be tied to the same H&V on FM 1925. The Engineer shall provide the control points to tie into. The Surveyor shall tie into the H&V Control Points of the FM 1925 Segment II (from FM 907 to Sharp Road including the Sharp Road Realignment (from FM 1925 North 0.5 Miles).
<u>YES</u> <u>NO</u>	b. Secondary Project Control (Surveyor shall recover and/or reset H&V Control Points as provided by the Engineer and create Survey Data Sheets for inclusion in the Project Plans.
	• No traverse should exceed 25 angle points. Planimetrics shall be 20 ft Lt & Rt from the proposed ROW as per the schematic provided by the Engineer. • The unadjusted angular error should not exceed 2 seconds per angle, plus 14 seconds. • The unadjusted ratio of precision should be one part in 10,000 or better. (The ratio of precision is the total length of the traverse divided by the total error.) • The unadjusted vertical error should not exceed 0.03 foot per mile of traverse.
<u>NO</u> <u>NO</u> <u>NO</u> <u>NO</u>	(1) Project control base lines
	(2) Photogrammetric ground control
	(a) Establish horizontal control
	(b) Establish vertical control points
	(c) Place and maintain control point targets
<u>YES</u> <u>NO</u>	c. Other Field Surveying
	(1) The limit of the Design surveys shall be 700-ft before and after the limits of the project as identified by the Project Engineer on the schematic. Establish horizontal and vertical control. Set benchmarks at 1000-ft intervals along the project proposed right-of-way. Provide x,y,z for each Benchmak. Provide a BM along each outfall identified on the Hydrologic Map. The BM's shall be #5 I.R. 2-ft in depth set in concrete. The surveyor shall provide A H&V Book (a Sample shall be provided by the Engineer to the Surveyor). The Surveyor will provide a 3-pt reference sketch with ties to the BMs for inclusion the the existing H&V Control Book. Establish benchmark circuit throughout the project with a tolerance of 0.03'/ft per mile error vertically.
	(2) Complete topographic and cross section survey, data processing, and CADD mapping (2D & 3D) for the limits of the project.
	(3) Locate all visible utilities, data processing and CADD mapping (2D & 3D) including irrigation lines. Follow sample provided by the Engineer.
	(4) Field locate cross culverts, driveway culverts, inverts, irrigation lines, within the project limits, data processing and CADD mapping (2D & 3D).
	(5) Right of Entry, Right of Way Research, and Appraisal District Records is the responsibility of the Surveyor.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
SURVEYOR COUNTY

		(6) The Surveyor shall also paint the proposed centerline on the existing pavement as approved by Engineer. (500-ft stations and a tick mark at 100-ft. stations –12 inches long with approved paint by Engineer) before construction for the purpose of utility adjustments and project location.
		(7) Profile and cross section intersecting streets for ties into project (500-ft. beyond the proposed ROW per schematic and 20-ft wider than the existing ROW of intersecting street). Reference missing voids as per CD provided by the Engineer.
		(8) Cross section irrigation crossings for a distance of 20-ft beyond the proposed ROW at 100-ft intervals in a DTM file. Provide a complete description of irrigation appurtenances as identified by the engineer sample layout.
		(9) Tie Horizontally and Vertically the existing storm drain system that lies within the existing proposed ROW including the elevation of the outfall of said recovered existing storm drain systems.
<u>YES</u>	<u>NO</u>	(10) Tie to existing underground and overhead utilities (location, elevation and direction) <u>Horizontally</u> – the surveyor shall call the 1-800 number for the utilities to be marked on the ground as well as any city water and sewer lines. He shall tie all visible utility crossings with name, address and Phone #'s of utility companies. The engineer will coordinate with the utility companies and jointly the Surveyor and the Engineer will identify which utilities were missed and need to be tied down. <u>Vertically</u> – The engineer shall identify all utilities that are potential conflicts and that need to be tied vertically. The engineer will advise the surveyor in writing of the needed vertical ties and the surveyor will tie the lines vertically once the surveyor has coordinated the exposure and provide the information to the engineer.
<u>YES</u>	<u>NO</u>	(11) Additional Field Surveying as shown below: (A) <u>IRRIGATION LINES</u> – The surveyor will meet with the engineer before he ties down any irrigation lines. The Engineer will provide him the existing Irrigation District Maps and the A&M Data of existing irrigation lines that are identified of record. He will follow the sample given to him by the engineer and tie the structures horizontally and vertically and provide Field Books to the engineer. (B) <u>OUTFALLS</u> – The surveyor will provide a complete 2D & 3D File including utilities of the outfall identified on the Hydrologic Map.
		<u>Driveways and Turnouts</u> (a) Inventory commercial entrances, public roads and side streets separately. (b) Obtain centerline station. (Width at ROW, PAV'T and existing radius. (c) Inventory by type (dirt, caliche, gravel or paved). If paved, indicate condition in terms of no patches, has patches or has potholes. Obtain width at R.O.W. line. (e) Obtain elevations at both edges of the driveway or turnout in line with the side drain.
<u>YES</u>	<u>NO</u>	(12) ROW staking (Existing and Proposed @ 1,000 ft. stations PC's PT's and Angle points as per ROW Map) (#5 I.R. 2-ft.)
<u>NO</u>	<u>NO</u>	(13) Soil core hole staking -
<u>YES</u>	<u>NO</u>	(14) Determine changes in topography from voids and outdated maps due to development, erosion, etc.
<u>YES</u>	<u>NO</u>	(15) Profiles of existing drainage facilities
<u>N/A</u>	<u>NO</u>	(16) Measurement of hydraulic opening under existing bridges
<u>YES</u>	<u>NO</u>	(17) Obtain elevations of manholes and valves of utilities
<u>YES</u>	<u>NO</u>	(18) Provide temporary signs, traffic control, flags, safety equipment, etc.
<u>YES</u>	<u>NO</u>	(19) Ties to existing bridges or culverts that may conflict with new construction.
<u>N/A</u>	<u>N/A</u>	(20) Bridge widening top of deck and/or top of cap elevations at the Profile Grade Line (PGL) and the edges of slab at bent locations.
<u>YES</u>	<u>N/A</u>	(21) Inventory signs, mailboxes, and driveways
<u>YES</u>	<u>N/A</u>	(22) Survey controlled data sheets per TxDOT guidelines.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR County

<u>YES</u>	<u>N/A</u>	(23) Recover and/or re-establish the existing center line and existing Right-of-Way. Have said existing centerline approved by the Engineer. Provide a digital computer dump of both.
<u>YES</u>	<u>N/A</u>	(24) Coordinate with the Engineer to set the existing centerline stationing.
<u>N/A</u>	<u>N/A</u>	2. Photogrammetric Products a. Uncontrolled Photography (1) Contact Prints (2) Mosaics (3) Digital ortho plots b. Mapping (1) Planimetric Maps (2) Contour Maps (3) Cross Sections (4) Profiles (5) Digital Terrain Models (DTM)

EXHIBIT “B”
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

ADDITIONAL RESPONSIBILITIES

A. TRAFFIC CONTROL:

The SURVEYOR shall control traffic in and near surveying operations adequately to comply with provisions of the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI and the latest edition of the Occupational Safety Manual both of which can be found on the TxDOT internet site.

In the event field crew personnel must divert traffic or close traveled lanes, a Traffic Control Plan based upon principles outlined in the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI shall be prepared by the SURVEYOR and approved by the ENGINEER prior to commencement of field work. A copy of the approved plan shall be in the possession of field crew personnel on the job site at all times and shall be made available to the ENGINEER for inspection upon request.

B. INVOICING:

Payment requests shall include a SURVEYOR’s invoice. With each payment request, the SURVEYOR shall submit a project status report which will, as a minimum, include the percentage of total work complete as of the date of the payment request and a description of current work activity. The percentage of total work complete shall not be based simply on the percentage of funds expended, but shall be based on the best judgment of the SURVEYOR as to the percentage of actual work complete.

C. EASEMENTS, LETTERS OF PERMISSION, ETC.

The SURVEYOR shall be responsible for delineating easements. The SURVEYOR will be responsible for securing the necessary legal instruments and obtaining all Right-of-Entries (ROEs).

D. MEETINGS:

The ENGINEER shall setup the necessary meetings with the SURVEYOR in order to assure all field information is provided on-time and products are delivered in accordance with TxDOT’s specifications. SURVEYOR must attend all meetings involving data provided if requested by ENGINEER.

E. PROJECT MANAGER/SURVEYOR COMMUNICATION:

The SURVEYOR shall designate one Texas Registered Professional Land Surveyor (RPLS) to be responsible throughout the project for project surveying coordination and all communications, including billing, with the ENGINEER.

F. OFFICE LOCATION:

The SURVEYOR will perform the services to be provided under this agreement out of a local office and have a crew available to perform requested tasks within 24 hours of request. The coordinating SURVEYOR’s Project Manager (RPLS) shall be accessible at all times and working from the local office.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 6 - ROADWAY DESIGN CONTROLS
(Function Code 160)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1. Geometric Design
<u>YES</u>	<u>N/A</u>	a. Horizontal and Vertical Alignment b. Schematic Layout (UPDATE AS NEEDED) (1) The location of interchanges, main lanes, grade separations, frontage roads and ramps. (2) Develop vertical and horizontal alignment of main lanes, ramps and cross roads at proposed interchanges or grade separations. Frontage road alignment data need not be shown on the schematic; however, it should be developed in sufficient detail to determine ROW needs. The degree of horizontal curves and vertical curve data, including "K" values, shall also be shown for ease of checking. (3) For freeways, show the location and text of the proposed main lane guide signs. Lane lines and/or arrows indicating the number of lanes shall also be shown. (4) A complete explanation of the sequence and methods of stage construction, if proposed, including the initial and ultimate proposed treatment of crossovers and ramps. (5) The tentative ROW limits. (a) Provide a roadway Design System (RDS) or (GEOPAK) computer tape of the preliminary earthwork to verify ROW requirements. (b) Provide a graphics file containing the approved schematic. (6) The geometric (pavement cross slopes, lane and shoulder widths, slope rates for fills and cuts) of the typical sections of proposed highway main lanes, ramps, frontage roads, and cross roads. (7) The current and projected traffic volumes as provided by the TxDOT (20 year traffic projection, unless otherwise determined by the District Engineer). (8) The control of access lines if Interstate or designated under House Bill 179. (9) Direction of traffic flow on all roadways. (10) Location and width of median openings for highway without access control. (11) The geometric of speed change (acceleration, deceleration, climbing) lanes.
<u>YES</u>	<u>N/A</u>	2. General Guidelines for Project Development a. Prior to preparing detailed plans for a proposed project, a preliminary schematic layout shall be prepared which indicates the general geometric features and location requirements peculiar to the project. An uncontrolled aerial mosaic will be provided for this use. Four copies of the schematic layout shall be submitted through the district to the Design Division for approval and subsequent coordination with the Federal Highway Administration (FHWA) where applicable. The layout shall be submitted for two-lane arterial highway projects on new locations and for all multi-lane highway projects. No geometric design is to be performed until the COUNTY has given the engineer written approval of the preliminary schematic layout. b. All geometric design shall be in conformance with the State's Design Division, Operations and Procedures Manual, except where variances are permitted in writing by the STATE. c. The schematic layout shall include basic information which is necessary for the proper review and evaluation including the items listed above in the checklist for schematic layout. d. Handling of traffic during construction shall be a consideration in the development of preliminary designs.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
<u>YES</u>	<u>N/A</u>	2. General Guidelines for Project Development (<i>continued</i>)
		e. Upon approval of the schematic layout by Design Division (FHWA on Federal-aid projects), it shall be the basis for an exhibit at any required public hearing prior to final development of the project. If there are any changes to the schematic after the Design Division and FHWA approval and before the public hearing, four copies of the revised schematic, as displayed at the hearing, shall be submitted either prior to or accompanying the public hearing data. If there are no changes in the schematic as displayed at the hearing, only photographs of the schematic and other displays shall be submitted with the public hearing data.
		f. For all freeway construction projects, these schematics shall show the location and text of the proposed main lane guide signs. A schematic layout shall be submitted through the district to the Traffic Operations Division, Traffic Safety Section for approval and subsequent coordination with the FHWA. All signing shall be in conformance with the Texas MUTCD.
		g. On complex projects, informal contact through the district with the Design Division and FHWA personnel is encouraged with regard to development of preliminary design prior to official schematic submission.
		h. The engineer shall furnish a project tape that is compatible with the STATE's computer system, a project listing, and a cross section plot showing the original design sections containing the earthwork input and original cross sections for the project. Accuracy of the earthwork design is of utmost importance since it is the basis for contractor payments and construction staking.
<u>N/A</u>	<u>N/A</u>	3. Exhibit for Airway/Highway Clearance Permits
<u>NO</u>	<u>N/A</u>	4. Grading Design
		a. Refine the horizontal and vertical alignment of main lanes, frontage roads, ramps, cross roads and direct connectors based upon the approved schematic layout. Determine vertical clearances at grade separations and overpasses, taking into account the appropriate super elevation rate.
<u>YES</u>	<u>N/A</u>	b. Typical Sections
<u>YES</u>	<u>N/A</u>	c. Design Cross Sections
<u>YES</u>	<u>N/A</u>	d. Determine Cut and Fill Quantities
<u>N/A</u>	<u>N/A</u>	e. Slope Stability Analysis
<u>N/A</u>	<u>N/A</u>	f. Embankment Foundation Stability Analysis
<u>N/A</u>	<u>N/A</u>	g. Embankment Settlement Analysis
<u>YES</u>	<u>N/A</u>	5. Pavement Design
		a. Prior to initiating detailed plan preparations for a project, a preliminary investigation shall be made to determine the approximate section and pavement type to be used for the pavement structure. The Flexible Pavement Design Manual for flexible pavement, "Appendix F" of the Design Division, Operations and Procedures Manual, and the current AASHTO Guide for the Design of Pavement Structures, may be used for this purpose.
<u>YES</u>	<u>N/A</u>	b. The typical section shall also reflect proposed geometric including pavement cross slopes, lane and shoulder widths, and slope rates whenever this data have not been previously shown on a schematic submission.
		c. Embankment and Subgrade
		(1) Soil Core Holes (Show cost estimate with Function Code 110)
<u>N/A</u>	<u>N/A</u>	(a) Along center line
<u>N/A</u>	<u>N/A</u>	(b) Along center line of each roadway
		The location and minimum number of soil core holes required for this project are as follows: (To be determined when schematic is being completed)

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	5. Pavement Design (<i>continued</i>)
		c. Embankment and Subgrade (<i>continued</i>)
		(2) Identify, interpret and summarize geologic features that affect engineering design (PI, Sulfate content, % of lime)
<u>YES</u>	<u>N/A</u>	d. Traffic Data for Pavement Design by STATE
<u>YES</u>	<u>N/A</u>	e. Basic Design Criteria
<u>NO</u>	<u>N/A</u>	f. Life Cycle Cost Analysis(es)
<u>YES</u>	<u>N/A</u>	g. Cost Data
<u>YES</u>	<u>N/A</u>	h. Pavement Material Properties
<u>YES</u>	<u>N/A</u>	i. Rehabilitation Investigations
<u>YES</u>	<u>N/A</u>	(1) Core Hole Survey (Show cost estimate with Function Code 110)
		(a) Determine type and depth of existing material, pavement, etc. The Engineer will determine whether to salvage ACP and FLEXBASE as well as their properties and provide this information to TxDOT.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 7 - DRAINAGE

(Function Code 161)

Services
Provided By:
ENGINEER COUNTY

All hydraulic design shall be in accordance with the TxDOT's Hydraulic Manual, except where variances are permitted in writing by the COUNTY.

<u>YES</u>	<u>N/A</u>	1. Hydrologic Studies, Discharges
<u>YES</u>	<u>N/A</u>	a. Drainage area maps showing existing conditions and proposed improvements.
		b. Hydrologic data/discharge determination
		2. Hydraulic Drainage Study and Documentation
<u>YES</u>	<u>N/A</u>	a. Hydraulic computations
		(1) Storm water detention available within the ROW (linear ft. along side drain ditch).
<u>NO</u>	<u>N/A</u>	(2) Storm water detention required outside the ROW (as per HCDD#1)
<u>YES</u>	<u>N/A</u>	(3) Culverts
<u>NO</u>	<u>N/A</u>	(4) Bridge waterways
<u>YES</u>	<u>N/A</u>	(5) Channels
<u>YES</u>	<u>N/A</u>	(6) Storm sewers/inlets
<u>NO</u>	<u>N/A</u>	(7) Pump stations
<u>NO</u>	<u>N/A</u>	(8) Storm Water Management facilities
<u>YES</u>	<u>N/A</u>	(9) Other
		(a) Irrigation Canals/Siphons
<u>NO</u>	<u>N/A</u>	b. Hydraulic report(s)
<u>YES</u>	<u>N/A</u>	c. Federal Emergency Management Agency (FEMA) floodway requirements
<u>YES</u>	<u>N/A</u>	d. Determine impact of proposed drainage plan on the following receiving stream(s)
		(1) Hidalgo County Drainage District Outfalls
		(2) All Irrigation District Outfalls impacted
		3. Layout, Structural Design and Detailing of Drainage Features
<u>YES</u>	<u>N/A</u>	a. Culverts
<u>NO</u>	<u>N/A</u>	(1) New culverts
<u>NO</u>	<u>N/A</u>	(2) Culvert widening and/or lengthening
		(3) Culvert replacements
		b. Storm sewers
<u>NO</u>	<u>N/A</u>	(1) New storm sewers
<u>NO</u>	<u>N/A</u>	(2) Modify existing storm sewers
<u>NO</u>	<u>N/A</u>	(3) Inlets
<u>NO</u>	<u>N/A</u>	(4) Manholes
<u>NO</u>	<u>N/A</u>	(5) Trunk lines
<u>NO</u>	<u>N/A</u>	c. Pump stations
<u>NO</u>	<u>N/A</u>	d. Subsurface drainage at retaining walls
<u>YES</u>	<u>N/A</u>	e. Outfall channel(s) within the ROW
<u>NO</u>	<u>N/A</u>	f. Outfall channel(s) outside the ROW
<u>NO</u>	<u>N/A</u>	g. Detention Pond(s) within the ROW
<u>NO</u>	<u>N/A</u>	h. Detention Pond(s) outside the ROW
<u>YES</u>	<u>N/A</u>	i. Summary of Quantities
<u>NO</u>	<u>N/A</u>	j. Storm Water Management facilities
<u>YES</u>	<u>N/A</u>	4. Storm Water Pollution Prevention Plan (SW3P)
<u>NO</u>	<u>N/A</u>	5. Scour Evaluation - Waterway Structures only (to be completed by Bridge Engineer under FC 170.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 8 - SIGNING, MARKINGS AND SIGNALIZATION

(Function Code 162)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1. Signing and Markings Layout
		a. Requirements (Separate Layout)
		(1) Roadway layout
		(2) Center line with station numbering
		(3) ROW lines
		(4) Culverts and other structures that present a hazard to traffic
		(5) Location of utilities, if not shown on plan and profile
		(6) Existing signs to remain, to be removed, to be relocated
		(7) Proposed signs (illustrated and numbered)
		(8) Existing overhead sign bridges to remain, to be revised, removed or relocated
		(9) Proposed overhead sign bridges indicating location by plan layout (electrical details need not be shown on this layout)
		(10) Proposed markings (illustrated and quantified) which include pavement markings, object markings and delineation
		(12) Quantities of existing pavement markings to be removed
		(13) Proposed delineators and object markers
		b. For projects involving freeway to freeway or other types of directional interchanges, projects including left-hand ramps or connections, the following information must be provided:
		(1) The location of interchanges, main lanes, grade separations, frontage roads and ramps
		(2) complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps
		(3) The number of lanes in each section of proposed highway and the location of changes in numbers of lanes
		(4) The projected traffic volumes as provided by the STATE (20 year traffic projection, unless otherwise determined by the District Engineer)
		(5) Tentative ROW limits
		(6) Direction of traffic flow on all roadways
		(7) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations
<u>YES</u>	<u>N/A</u>	2. Summary of Small Signs Tabulation
<u>YES</u>	<u>N/A</u>	3. Summary of Large Signs Tabulation including all Guide Signs
<u>YES</u>	<u>N/A</u>	4. Sign Detail Sheets
		a. All signs except route markers
		b. Design details for large guide signs
		c. Dimensions of letters, shields, borders, corner radii etc.
		d. Designation of shields attached to guide signs
		e. Designation of arrow used on exit direction signs

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
ENGINEER COUNTY

<u>NO</u> <u>N/A</u> <u>NO</u> <u>N/A</u> <u>NO</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>NO</u> <u>N/A</u>	5. Traffic Signals a. Development of Justification (Warrant) Data (1) Location Map Relationship of proposed installation to other traffic signals, highways, business areas and traffic generators (2) Photographs as appropriate (3) Accident data as appropriate (4) Vehicle volumes (provided by TxDOT) (a) Existing (b) Estimated (c) Projected (d) Pedestrian (5) Traffic Survey - Count Analysis (6) Recommendation based on above data b. Layout (1) Title Sheet (when applicable) (a) Describe the location (b) Type of installation (c) Area map with project limits for each location (d) Index of sheets (e) Space for official signatures (2) Estimate and quantity sheet (when applicable) (a) List of all bid items (b) Bid item quantities (c) Specification item number (d) Paid item description and unit of measure (3) Basis of estimate sheet (list of materials) (4) General notes and specification data sheet (5) Condition diagram (a) Highway and intersection design features (b) Roadside development (c) Traffic control including illumination (6) Plan sheet(s) (a) Existing traffic control that will remain (signs and markings) (b) Existing utilities (c) Proposed highway improvements (d) Proposed installation (e) Proposed additional traffic controls (f) When applicable, proposed conduit for Railroad interconnect with standard details for runs under tracks. (g) Proposed illumination attached to signal poles. (7) Notes for plan layout (8) Elevation sheet(s) (span wire design) (9) Phase sequence diagram(s) (a) Signal locations (b) Signal indications (c) Phase diagram (d) Signal sequence table (e) Flashing operation (normal and emergency) (f) Preemption operation (when applicable) (g) Interval timing, cycle length and offset

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	5. Traffic Signals (<i>continued</i>)
		b. Layout (<i>continued</i>)
		(10) Construction detail sheets(s)
		(a) Poles (TxDOT standard sheets)
		(b) Detectors
		(c) Pull Box and conduit layout
		(d) Controller Foundation standard sheet
		(11) Marking details (when applicable)
		(12) Barricade and warning sign standard sheet and any special details for work zone traffic control for special conditions
		(13) Aerial or underground interconnect details (when applicable)
		c. General Requirements
<u>NO</u>	<u>N/A</u>	(1) Contact local utility company
<u>NO</u>	<u>N/A</u>	(a) Confirm power source
<u>N/A</u>	<u>N/A</u>	(b) Discuss route of aerial or underground interconnect cable (when applicable)
<u>NO</u>	<u>N/A</u>	(c) Adjustment of overhead utility lines
<u>NO</u>	<u>N/A</u>	(2) Prepare governing specifications and special provisions list
<u>NO</u>	<u>N/A</u>	(3) Prepare project estimate
<u>NO</u>	<u>N/A</u>	d. Summary of Quantities

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 9 - MISCELLANEOUS (ROADWAY)

(Function Code 163)

Services
Provided By:
ENGINEER COUNTY

		1. Retaining Walls
		a. Structural Details
<u>N/A</u>	<u>N/A</u>	(1) Cast-in-Place Cantilever at _____ locations. (TxDOT Standard Retaining Wall)*
<u>N/A</u>	<u>N/A</u>	(2) Tiedback Retaining Wall at _____ location. (TxDOT standard retaining wall)
<u>N/A</u>	<u>N/A</u>	(3) Specialized Retaining Wall at _____ locations (Unique Design).*
		b. Alternate Patented Retaining Walls at all locations. (Layouts Only)**
<u>N/A</u>	<u>N/A</u>	(1) Mechanically Stabilized Earth
<u>N/A</u>	<u>N/A</u>	(2) Concrete Block Wall Systems
<u>N/A</u>	<u>N/A</u>	c. Retaining Wall Layout (PLAN)
		(1) Designation of reference line
		(2) Beginning and ending retaining wall stations
		(3) Station of each retaining wall joint***
		(4) Offset from reference line
		(5) Horizontal curve data
		(6) Number of retaining wall panels and lengths***
		(7) Total length of wall
		(8) Indicate face of wall
		(9) All wall dimensions and alignment relations (alignment data as necessary)
		(10) Soil core hole locations
<u>N/A</u>	<u>N/A</u>	d. Retaining Wall Layout (ELEVATION)
		(1) Top of wall elevations at each joint or intervals***
		(2) Existing and finished ground line elevations
		(3) Height of stem at each joint***
		(4) Wall panel designations***
		(5) Top of footing elevations***
		(6) Limits of measurement for payment****
		(7) Type, limits and anchorage details of railing (If applicable)
		(8) Top and bottom of wall profiles and soil core hole data plotted at correct station and elevation. The plot shall be at the same scale as the wall profile. Ground water elevations and the observation date shall be shown.
<u>N/A</u>	<u>N/A</u>	e. Foundation Studies (Show cost estimate with Function Code 110)
<u>N/A</u>	<u>N/A</u>	(1) The soil core holes shall be obtained at approximately 200 foot intervals along retaining wall alignments. The core holes shall extend 25 feet below the footing elevation.
<u>N/A</u>	<u>N/A</u>	f. Stability Analysis (the ENGINEER shall estimate this task as part of his bid to complete the work).
<u>N/A</u>	<u>N/A</u>	g. Estimate
<u>N/A</u>	<u>N/A</u>	h. Summary of Quantities
<u>N/A</u>	<u>N/A</u>	i. Typical X-section.
<u>N/A</u>	<u>N/A</u>	j. General Guidelines for Retaining Walls
		(1) The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. The designer and checker shall check all calculations and initial each page.
		(2) The ground water level should be observed at the water strike.
		(3) For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
		(4) Foundation exploration shall conform to the requirements set forth in Administrative Circular No. 25-84, Administrative Circular 33-87 and Administrative Circular No. 25-92.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	2. Traffic Control Plan, Detours and Sequence of Construction Traffic Control Plans (TCP) are required for all projects. A detailed TCP shall be developed when traffic handling during construction involves complications for which a feasible solution is not covered by the Texas MUTCD or the current Barricade and Construction (BC) Standards. The following items are required on all Traffic Control Plan Layouts: a. The sequence of construction and method of handling traffic during each phase. b. The existing and proposed traffic control devices that will be used to handle traffic during each construction sequence. Include signals, regulatory signs, warning signs, construction warning signs, guide signs, route markers, construction pavement markings, channelizing devices, portable changeable message signs, flashing arrow boards, barricades, barriers, etc. c. The proposed traffic control devices (stop signs, signals, flag person, etc.) at grade intersections during each construction sequence. d. Where detours are provided, typical cross sections shall be shown. e. Road construction work hours shall be developed after an investigation of the traffic volumes has been performed.
<u>N/A</u>	<u>N/A</u>	3. Illumination a. Preliminary Roadway Illumination Layout and Circuit Layout (1) For projects involving freeway to freeway or other types of directional interchanges and projects including left-hand ramps or connections, provide the following: (a) The location of interchanges, main lanes, grade separations, frontage roads and ramps (b) A complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps (c) The number of lanes in each section of proposed highway and the location of changes in the number of lanes (d) The projected traffic volumes as provided by the STATE (20 year traffic projection unless otherwise determined by the district engineer) (e) Tentative ROW limits (f) Direction of traffic flow on all roadways (g) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations b. Final Roadway Illumination and Electrical Circuit Layouts (1) Roadway layout showing pavement edges, shoulders, curbs, retaining walls, etc. (2) Center line with station numbering. (3) ROW lines. (4) Symbol legend. Use department standard symbols for lighting and electrical. (5) Culverts and other structures that present a hazard to traffic. (6) Location of underground utilities, if not shown on plan profile. (7) Location of overhead electrical lines, both crossing and parallel to ROW. (8) Existing sign lighting circuits and roadway illumination to remain, to be removed, to be relocated. (9) Existing service poles, electrical circuits, ground boxes, etc. (10) Contact electric utility for service pole locations, voltage characteristics. (11) Location of proposed sign lighting circuits and roadway illumination. (12) Proposed electrical circuits. (13) Tabulation of all quantities including proposed, existing to be relocated, existing to be removed. The layout sheet quantities and lighting summary shall be shown. Tabulations to include estimated quantity with a column for final quantities.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	3. Illumination (<i>continued</i>)
		c. General Guidelines for Illumination (If applicable) The ENGINEER shall submit to the COUNTY, well in advance of PS&E due date, the roadway illumination and electrical circuit layout sheets for review by the STATE. Two copies of the layout sheets are to be submitted. One copy will be returned to the Engineer showing corrections that are to be made by the ENGINEER. When final plan submission is made, the ENGINEER shall provide a written statement regarding completion of the corrections.
<u>YES</u>	<u>N/A</u>	4. Miscellaneous Drafting/Standards
<u>N/A</u>	<u>N/A</u>	a. Erosion Control
		b. Landscape Development
<u>YES</u>	<u>N/A</u>	5. Compute and Tabulate Quantities
<u>YES</u>	<u>N/A</u>	6. Special Utility Details (Irrigation lines)
		7. Miscellaneous Structures
		a. Type of Structure*
		(1) Overhead Sign Bridges (O.S.B.) Modifications or special O.S.B. designs shall be prepared using the same design assumptions that are used for the standard O.S.B structures.
<u>N/A</u>	<u>N/A</u>	(a) New O.S.B. structure(s)
<u>N/A</u>	<u>N/A</u>	(b) Structural evaluation of existing O.S.B. structure(s) that are to remain in place or to be relocated.
<u>N/A</u>	<u>N/A</u>	(2) High Mast Illumination Poles (HMIP)
<u>N/A</u>	<u>N/A</u>	(3) Traffic Signal Supports
<u>N/A</u>	<u>N/A</u>	(4) Conventional Illumination Poles
<u>N/A</u>	<u>N/A</u>	(5) Sound Barrier Walls
<u>N/A</u>	<u>N/A</u>	b. Checklist for Layouts
		(1) Reference appropriate O.S.B. standard
		(2) Drilled shaft size and length
		(3) Soil strength used for design {indicate basis and boring(s) used}
		(4) Design height
		(5) Tower heights
		(6) Leg spacings
		(7) Design wind speed
<u>N/A</u>	<u>N/A</u>	c. Foundation Studies (Show cost estimate with Function Code 110) The soils exploration requirements for miscellaneous structures on this project are as follows: (To be provided by the Engineer on an as-needed basis)
		8. Agreements
<u>N/A</u>	<u>N/A</u>	a. Utility Agreements
<u>N/A</u>	<u>N/A</u>	b. Exhibits for Utility Agreements
<u>N/A</u>	<u>N/A</u>	c. Railroad Agreements
		d. Railroad Exhibits
<u>N/A</u>	<u>N/A</u>	(1) Railroad Underpasses
<u>N/A</u>	<u>N/A</u>	(2) Railroad Overpasses
<u>N/A</u>	<u>N/A</u>	(3) Railroad Grade Crossing (Replanking)
<u>N/A</u>	<u>N/A</u>	(4) Railroad Grade Crossing Warning Systems (Signals)
<u>N/A</u>	<u>N/A</u>	(5) Other Miscellaneous Sketches for Railroads
<u>N/A</u>	<u>N/A</u>	e. Traffic Signal Agreements
<u>N/A</u>	<u>N/A</u>	f. Exhibits for Traffic Signal Agreements
<u>N/A</u>	<u>N/A</u>	9. Estimate
<u>N/A</u>	<u>N/A</u>	10. Specifications and General Notes

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 10 - BRIDGE DESIGN

(Function Code 170)

Services
 Provided By:
ENGINEER COUNTY

			<u>NUMBER REQUIRED</u>
		1. Preparation of Structural Details	
		a. New Structure(s)	
<u>N/A</u>	<u>N/A</u>	(1) Underpass(es)	
<u>N/A</u>	<u>N/A</u>	(2) Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(3) Main Lanes	
<u>N/A</u>	<u>N/A</u>	(4) Direct Connector(s)	
<u>N/A</u>	<u>N/A</u>	(5) Ramp Bridge(s)	
<u>N/A</u>	<u>N/A</u>	(6) Waterway Structure(s)**	
<u>N/A</u>	<u>N/A</u>	(7) Pedestrian Structure(s)	
<u>N/A</u>	<u>N/A</u>	(8) Utility Structure(s)	
<u>N/A</u>	<u>N/A</u>	(9) Railroad Underpass(es)	
<u>N/A</u>	<u>N/A</u>	(10) Railroad Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(11) Bridge Classification Culvert(s)**	
<u>N/A</u>	<u>N/A</u>	(11) Alternate Structural Designs	
<u>N/A</u>	<u>N/A</u>	(12) Alternate Foundation Design	
Total New Structures =			
		b. Existing Structure(s)	
<u>N/A</u>	<u>N/A</u>	(1) Bridge Widening, Rehabilitation and/or Modification of Existing Structure(s)	
<u>N/A</u>	<u>N/A</u>	(2) Bridge Replacement	
<u>N/A</u>	<u>N/A</u>	(3) Raising Bridge Elevation	
<u>N/A</u>	<u>N/A</u>	(4) Bridge Classification Culvert(s) Widening and/or Modification of Existing Structures(s)	
<u>N/A</u>	<u>N/A</u>	(5) Railroad Overpass(es)	
<u>N/A</u>	<u>N/A</u>	(6) Railroad Underpass(es)	
Total Existing Structures =			

* Countour plots of bridge gores are required for projects involving ramps within the main bridge in order to ensure project transition. The Template data and vertical alignment necessary to generate the contour plots are also required.

** In the early stages of a project, it sometimes cannot be determined whether a Waterway Bridge Structure or a Bridge Classification Culvert (20' minimum length) will be required. Therefore, the ENGINEER should be aware that either of these two types of bridges may be reclassified later in the project for the other type when more information is known that would dictate a change in structure classification.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

- N/A N/A 2. Preparation of Bridge Layouts (each bridge)
- a. Bridge Layouts (PLAN)
 - (1) Horizontal curve information or bearing of centerline.
 - (2) Including horizontal, vertical, and template information of all roadways or railroads crossed.
 - (3) Bearing of center line or reference line.
 - (4) Skew angle(s).
 - (5) Slope for header banks and approach fills.
 - (6) Control stations at beginning and ending of bridge (with deck elevation), intersections, etc.
 - (7) Approach pavement and crown width.
 - (8) Bridge roadway width and curbs, face of rail, shoulders, or sidewalks.
 - (9) Approach slab and curb returns.
 - (10) Limits and type of riprap.
 - (11) Proposed features under structure.
 - (12) Location of profile grade line.
 - (13) North arrow.
 - (14) Typical bridge roadway section including preliminary proposed beam types and spacings.
 - (15) Cross slope and super elevation data.
 - (16) Minimum horizontal clearances when applicable.
 - (a) Dimensions to features that control clearances. (Calculate and indicate points of minimum vertical and horizontal clearances.
 - (17) Location of soil core holes (station and offset), shown on layout.
 - (18) Bent stations and bearings.
 - (19) Retaining wall locations.
 - (20) Traffic flow directional arrows.
 - (21) Railing types shown.
 - (22) Joint types and seal size, if used.
 - (23) Beam line numbers consistent with span details.
 - (24) Critical horizontal clearances (location of railroad tracks, nearby structures and utilities).
 - (25) Bearings of utilities.
 - b. Bridge Layouts (ELEVATION)
 - (1) Type of foundation.
 - (2) Finished grade elevations at beginning and end of bridge.
 - (3) Overall length of structure.
 - (4) Length, type of spans and units.
 - (5) Type of railing.
 - (6) Minimum calculated vertical clearance(s).
 - (7) Existing and proposed ground lines clearly marked.
 - (8) Grid elevations and stations.
 - (9) Bent numbers encircled.
 - (10) Stationing of bridge compatible with grid stations.
 - (11) Standard title.
 - (12) Profile grade data.
 - (13) Type of riprap.
 - (14) Soil Core Hole information with penetrometer test data shall be shown on the bridge layout at correct station, elevation and scale.
 - (15) Fixed/expansion condition of all bents.
 - (16) Column "H" heights.
 - (17) Number, size and length of foundations.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	2. Preparation of Bridge Layouts (each bridge) (<i>continued</i>)
		c. Additional layout requirements for waterway structures and bridge classification culverts.
		(1) Design and 100-year peak discharges.
		(2) Design and 100-year high water (HW) (Recorded HW and date if available)
		(3) Natural and through-bridge velocities for design and 100-year floods.
		(4) Calculated backwater for design and 100-year floods.
		(5) Direction of flow for waterway crossings.
		(6) Contours for water crossing.
<u>N/A</u>	<u>N/A</u>	3. Bridge Classification Culvert, Estimate, Quantities, and Specifications (each bridge)
<u>N/A</u>	<u>N/A</u>	4. Foundation Studies (Show cost estimate with Function Code 110)
		The minimum number of soil core holes shall be obtained in accordance with Section 1-301 of the Bridges and Structures Foundation Exploration and Design Manual. Soil core holes shall be obtained at approximately (300 foot) intervals along bridge alignments. Texas cone penetrometer (TCP) tests shall be conducted in all soil types encountered at a maximum of (10 foot) intervals. If single column bents with single drilled shafts are planned, TCP values should be taken at close intervals in the upper (15 feet).
<u>N/A</u>	<u>N/A</u>	5. Bridge Total Quantities and Cost Estimates (each bridge)
<u>N/A</u>	<u>N/A</u>	6. Bridge Special Provisions and Specifications (each bridge)
<u>N/A</u>	<u>N/A</u>	7. Bearing seat elevations for each beam or girder. Top of cap elevations for non-beam type structures.
<u>N/A</u>	<u>N/A</u>	8. General Guidelines for Bridge Design
		a. The ENGINEER shall prepare a bridge layout of each bridge structure for Company's review and approval. The bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures, Detailing Manual. Soil core hole data is not required for submission of the preliminary bridge layout. No bridge design work is to be performed until the COUNTY has given the engineer written approval of the preliminary bridge layout.

Several months may be required, after the preliminary bridge layout is submitted, for the district to obtain approval and/or permits from the following:

- TxDOT Design Division, when applicable:
 - Railroad Companies
 - FHWA
 - U.S. Army Corps of Engineers
 - U.S. Coast Guard
 - Bureau of Reclamation
 - Texas Parks and Wildlife
 - Others

Therefore, the bridge layout should be submitted at the earliest possible date and the ENGINEER's design schedule should reflect this.

- b. All bridge superstructure and substructure design will be reviewed by the Design Division for purposes of verifying structural integrity and optimization of design.
- c. The final bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures Detailing Manual.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

8. General Guidelines for Bridge Design (*continued*)

- d. The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. All bridge design shall be in conformance with the Texas Department of Transportation Bridges and Structures Operation and Planning Manual, the current American Association of State Highway and Transportation Officials or American Railway Engineers Association Specifications for railway structures, Standard Specifications for Highway Bridges, including applicable interim specifications, and the Bridges and Structures, Foundation Exploration and Design Manual. The ENGINEER shall furnish design calculations to the Design Division. **The designer and checker shall check all calculations and initial each page.**
- e. Structural steel or prestressed concrete shop drawings, form work drawings and false work drawings are not part of the design requirements. However, contract plans shall be in sufficient detail to permit the preparation of complete shop details for fabrication and erection.
- f. Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a metric scale of 1:20 (1/2 inch equals one foot architect scale) or 1:50 (1/4 inch equals one foot architect scale) to provide clear legible drawings when the drawings are reduced. Lettering shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
- g. Standard drawings for beams, diaframs, railings, armor joints, riprap, etc., shall be furnished to the ENGINEER upon request. These standards shall not be redrawn by the ENGINEER nor shall his title block be transferred to the standard drawings. Modifications to the standards, if necessary, shall be clearly identified and designated by "MOD" in the standard title. Specific special drawings prepared by the ENGINEER shall not be identified as standards.
- h. Bridge layout sheets shall have the same vertical and horizontal scale. Usually a metric scale of 1:100 (1 inch = 10 feet) or 1:200 (1 inch = 20 feet) is used. Sections of existing and proposed structures usually have a metric scale of 1:50 (1 inch = 5 feet). Soil core holes shall be positioned and labeled on the bridge layout plan view. The core hole data shall be plotted at the correct station, at the same vertical scale, and at the proper elevation unless otherwise approved by the Design Division.
- i. APPENDIX C, "GENERAL PLAN CHECKLIST", on pages C-1 thru C-5, more specifically relates various sheet types, details, summaries, standards, etc.
- j. For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
- k. Geometry and structural design errors found after acceptance of bridge plans shall be promptly corrected by the consultant at no cost to the Company.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 11 - CONSTRUCTION PHASE SERVICES
(Function Code 320)

Services
Provided By:
ENGINEER COUNTY

NO N/A **CONSTRUCTION MANAGEMENT SERVICES:**

The ENGINEER will provide engineering, geotechnical testing and support services for and during the construction of the Project or portions of the Project approved by the COUNTY. Specific (basic and special) services for CONSTRUCTION MANAGEMENT AND SUPPORT by the ENGINEER will include the following:

Construction Bidding:

- 1) The ENGINEER will furnish the COUNTY the necessary copies of approved plans, specifications, notices to bidders, and proposals as prepared under PS&E.
- 2) The ENGINEER will assist the COUNTY on the tabulation of bids, recommendations to the Owner as to the proper action on all bid proposals received, and the preparation of formal contract documents for the award of each construction contract.

Construction Contract Administration and Inspection:

- 3) In general, the ENGINEER will provide the management and engineering support/data required for consultation and advisement to the COUNTY and act as the COUNTY's representative as provided in the General Condition of the Construction Contract.
- 4) The ENGINEER will coordinate and conduct a pre-construction conference (if required).
- 5) Defects and Deficiencies. The ENGINEER will use his best efforts to protect the COUNTY against defects and deficiencies in the work of the Contractor. The ENGINEER will promptly notify the COUNTY of any such defect or deficiency, and take all steps possible to require the Contractor to correct the defect or deficiency.
- 6) Contractor Payment. The ENGINEER will review quantities as submitted by the Contractor and will coordinate with the COUNTY for the preparation of the monthly and final estimates for payment to the Contractor.
- 7) The ENGINEER will provide Project site inspection of the authorized construction contract as follows:
 - a) Project Engineer. The ENGINEER will provide visits by the Project Engineer or a competent representative of the ENGINEER to the site of construction for the purpose of monitoring the Contractor's progress and conformance to the construction contract plans and specifications.
 - b) Resident Engineer and/or Construction Inspector(s). The ENGINEER will furnish the services of a Resident Engineer and/or Construction Inspector(s) for on the site inspection construction to monitor/inspect the Contractor's daily progress and conformance to TxDOT's PS&E specifications.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

Miscellaneous Technical Activities:

- 8) Shop Drawings. The ENGINEER will review and check all shop or working drawings furnished by the Contractor.
- 9) Control of Materials & Equipment. The ENGINEER will provide inspection of all materials and equipment furnished/used by the Contractor as follows:
 - a) Review and record all laboratory, shop and mill tests of materials and equipment for compliance with the construction contract specifications.
 - b) Observe and/or perform Project record testing and/or independent assurance testing as outlined in the construction contract specifications.
- 10) Change Orders. When applicable the ENGINEER will prepare the engineering data, including plan sheet drawings, specifications, and estimates, for the preparation of construction contract change orders, which may be required due to actual field conditions encountered or new requirements directed by the COUNTY.
- 11) As Built Drawings. The ENGINEER will develop as built drawings to depict the work as actually constructed. The COUNTY will be furnished five (5) set of prints.

NO

N/A

CONSTRUCTION MATERIAL TESTING:

The ENGINEER will provide the COUNTY with construction material testing services for the Project. The services to be provided include sampling and testing of all construction materials as required by the project plans and specifications. All sampling frequencies and test procedures will be performed in general accordance with the Texas Department of Transportation TEX methods (or ASTM methods as required) as outlined in the Guide Schedule for Sampling and Testing (11/07). The construction material testing includes, but is not limited to the following:

- (a) Sampling and laboratory testing of soils and base materials proposed for use in the construction of Project (Roads/Bridges/Misc.) to determine compliance of these materials with project plans and specifications.
- (b) Field density testing of soils and base materials to ensure proper compaction as required by project plans and specifications.
- (c) Field sampling and testing of fresh concrete, and laboratory testing of hardened concrete to determine compliance with project plans and specifications.
- (d) Field compaction testing of asphalt to ensure proper compaction during lay down operations.
- (e) Field inspection, sampling and laboratory testing of asphalt materials to determine their material properties and their compliance with project plans and specifications.
- (f) The ENGINEER will be responsible for concrete batching as well as the asphalt testing at the plants to insure delivery of acceptable material to the job site.
- (g) Any additional laboratory testing as required/requested by the COUNTY and the project plans and specifications.
- (h) Providing accurate and timely reports to the COUNTY and all/other recipients as designated by the COUNTY.
- (i) The ENGINEER will verify the concrete and asphalt designs to assure it is in accordance with TxDOT specifications to be developed by the contractor.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 12 - FC 600 – ACQUISITION PROVIDER SERVICES
(for EST. 5 PARCELS, 1 EASEMENTS AND 0 RELOCATIONS/DISPLACEMENTS)

(Services to be provided by L&G Engineering)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1) PROJECT ADMINISTRATION
		a) Negotiation of Scope of Services for Work Authorization
		i) Acquisition Provider will visit project site with COUNTY personnel if necessary.
<u>YES</u>	<u>N/A</u>	b) Project Presence at L&G Consultant Office Headquarters
		i) Full Project Office
		(1) No Joint Use of COUNTY or TxDOT facilities
		(2) Open during normal COUNTY and State work hours
		(3) Personnel available to answer questions
		(4) Availability of Project Files
		(5) At least one office staff member is required to be a current commissioned notary public.
<u>YES</u>	<u>N/A</u>	c) Overhead Costs
		i) Administrative costs
<u>YES</u>	<u>N/A</u>	d) Communication
		i) Provide monthly progress reports with invoice.
		ii) Participate in project review meetings as determined by the COUNTY.
		iii) Prepare initial property owner contact list for use by the COUNTY in distribution of Acquisition Provider introduction letters.
<u>YES</u>	<u>N/A</u>	e) File Management
		i) Project and parcel files will be kept in the COUNTY's Office, if necessary. Working files will be kept in the Acquisition Provider's project administrative office, but documents generated or received by the Acquisition Provider will be forwarded to the COUNTY office as they are generated or received by the Acquisition Provider, if necessary.
		ii) Prepare payment transmittal request utilizing standard payment submissions forms with supporting documentation.
		iii) Maintain records of all payments including check number, amount, and date paid, etc.
		iv) Provide copies of all incoming and outgoing correspondence as generated if requested by COUNTY at provider conference.
		v) Maintain copies of all correspondence and contacts with property owners.
		2) TITLE SERVICES
<u>YES</u>	<u>N/A</u>	a) Secure preliminary title commitments from the Title Company that will be providing title insurance. Cost of preliminary title commitments will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work for payment and paid as a separate item.
<u>YES</u>	<u>N/A</u>	b) Secure title commitment updates in accordance with insurance rules and requirements for parcel payment submissions. Cost of title commitment updates will be paid by the Acquisition Provider (if requested by the title company) and will be included in the Acquisition Provider's scope of work and paid as a separate item.
<u>YES</u>	<u>N/A</u>	c) Secure title insurance for all parcels acquired, insuring acceptable title to COUNTY OF HIDALGO. Written approval by the COUNTY required for any exception.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	3) APPRAISAL a) Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list will be available for review at all District offices or at the Right of Way Division Office at 118 E. Riverside Drive, Austin, Texas, upon request.
<u>YES</u>	<u>N/A</u>	b) Secure written permission (if necessary) from the owner to enter the property from which land is to be acquired. If the Acquisition Provider and/or the fee appraiser, after diligent effort, is unable to secure the necessary letter of permission from the property owner, a waiver must be obtained, in writing from the COUNTY/TxDOT. Maintain permission letters with appraisal reports.
<u>YES</u>	<u>N/A</u>	c) Prepare (if necessary) pre-appraisal contact with interest owner(s) for each parcel using acceptable COUNTY/TxDOT forms.
<u>YES</u>	<u>N/A</u>	d) Contact property owners or their designated representative to offer opportunity to accompany the appraiser on the appraiser's inspection of subject property. Maintain record of contact in file.
<u>YES</u>	<u>N/A</u>	e) Prepare complete appraisal report for each parcel to be acquired utilizing TxDOT Forms No. ROW-A-5 and ROW-A-6 as applicable. These reports shall conform to TxDOT/COUNTY policies and procedures along with the Uniform Standards of Professional Appraisal Practices.
<u>YES</u>	<u>N/A</u>	f) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation.
<u>YES</u>	<u>N/A</u>	g) All completed appraisals will be administratively reviewed by L&G Engineering ROW Office and recommended for approval by TxDOT.
<u>YES</u>	<u>N/A</u>	h) As necessary, the appraiser will appear and or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing /pre-trial meetings as directed by L&G Engineering and/or TxDOT.
<u>YES</u>	<u>N/A</u>	i) As necessary, the appraiser will coordinate with review appraiser regarding revisions, comments, or additional information that may be required.
<u>YES</u>	<u>N/A</u>	j) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.
<u>YES</u>	<u>N/A</u>	4) APPRAISAL REVIEW a) Review Appraiser may be selected from TxDOT's list of state approved fee appraisers. This list is available for viewing at all District offices or the Right of Way Division office at 118 E. Riverside Drive, Austin, Texas upon request.
<u>YES</u>	<u>N/A</u>	b) Review all appraisal reports for each parcel to determine consistency of values, supporting documentation related to the conclusion reached and compliance with TxDOT/COUNTY policies and procedures and the Uniform Standards of Professional Appraisal Practices.
<u>YES</u>	<u>N/A</u>	c) Prepare and submit to TxDOT the Form ROW-RTA-10 "Tabulation of Values", for each appraisal.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	d) The cost of the review appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the review appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.
<u>YES</u>	<u>N/A</u>	5) APPRAISAL UPDATES a) Prepare complete appraisal update for the parcel to be acquired utilizing TxDOT Form No. ROW-A-5, which will be furnished to the provider by TxDOT. These reports shall conform to COUNTY/TxDOT policies and procedures along with the Uniform Standards of Professional Appraisal Practices.
<u>YES</u>	<u>N/A</u>	b) As necessary, prepare written notification to COUNTY/TxDOT of any environmental concerns associated with the right of way to be acquired which could require environmental remediation. All completed appraisals will be administratively reviewed by L&G Engineering Right of Way Office and recommended for approval by TxDOT.
<u>YES</u>	<u>N/A</u>	c) As necessary, the appraiser will appear or testify as an Expert Witness in eminent domain proceedings and be available for pre-hearing or pre-trial meetings as directed by the TxDOT/COUNTY.
<u>YES</u>	<u>N/A</u>	d) The cost of the appraiser appearing as an expert witness for testimony at special commissioners hearing must be included in the proposed fee schedule for the appraiser. The cost of the appraiser's expert witness testimony for trial is not part of this contract, and shall be paid by the COUNTY.
<u>YES</u>	<u>N/A</u>	e) As necessary, the appraiser will coordinate with the review appraiser regarding corrections and/or additional information that may be required.
<u>YES</u>	<u>N/A</u>	6) NEGOTIATION, TASKS AND FEES a) Analyze appraisal and appraisal review reports and confirm the TxDOT's approved value prior to making offer for each parcel.
<u>YES</u>	<u>N/A</u>	b) Analyze preliminary title report to determine potential title problems, propose methods to cure title deficiencies.
<u>YES</u>	<u>N/A</u>	c) Prepare the initial offer letter, instruments of conveyance, and any other documents required or requested by COUNTY /TxDOT on applicable COUNTY /TxDOT forms.
<u>YES</u>	<u>N/A</u>	d) Mail (Certified Mail Return Receipt Requested) initial offer letter, draft deed, Bill of Rights Brochures and Appraisal Reports to address confirmed with the Appraisal District of Hidalgo County. Maintain follow-up contacts and secure the necessary instruments upon acceptance of the offer for the closing.
<u>YES</u>	<u>N/A</u>	e) Provide a copy of the appraisal report for the subject property exclusively to the property owner or authorized representative at mailing of initial offer. Maintain original signed Receipt of Appraisal. (unless property owner refuses to sign it).
<u>YES</u>	<u>N/A</u>	f) Respond to property owner inquiries verbally and in writing within two business days.
<u>YES</u>	<u>N/A</u>	g) Prepare a separate negotiator contact report for each parcel per contact.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	h) Maintain parcel files of original documentation related to the purchase of the real property or property interests.
<u>YES</u>	<u>N/A</u>	i) Advise property owner on the Administrative Settlement process. Transmit to TxDOT any written counter offer from property owners including supporting documentation, and provider recommendation with regard to Administrative Settlements in accordance with COUNTY /TxDOT policy and procedures.
<u>YES</u>	<u>N/A</u>	j) Prepare final offer letter, documents of conveyance as necessary.
<u>YES</u>	<u>N/A</u>	k) Appear and provide Expert Witness testimony as an Acquisition Provider when requested.
<u>YES</u>	<u>N/A</u>	l) Meet at the L&G Engineering ROW office in Mission once per week as agreed-upon with the Right of Way Acquisition Manager/Administrator.
<u>YES</u>	<u>N/A</u>	m) Provide a monthly progress report per parcel by the 25th of the month with invoice.
<u>YES</u>	<u>N/A</u>	n) The consultant shall, as part of this proposal, estimates 10% of the parcels identified on Page 12-1 may end up in condemnation. The consultant shall be available for any meeting/hearings as requested by the COUNTY Attorney.
7) CLOSING SERVICE FEES		
<u>YES</u>	<u>N/A</u>	a) Coordinate with COUNTY and Title Company to obtain an updated title commitment along with other Forms and certified copy of the instrument of conveyance necessary when requesting the Parcel Payment from the COUNTY.
<u>YES</u>	<u>N/A</u>	b) Acquisition Provider shall attend closings and provide closing services in conjunction with Title Company.
<u>YES</u>	<u>N/A</u>	c) Acquisition Provider shall record all original instruments immediately after closing at the respective County Clerk's Office, except for donations which must be forwarded to TxDOT for acceptance by the Texas Transportation Commission.
8) RELOCATION ASSISTANCE SERVICES (separate Work Authorization will be issued once relocations have been identified, unless noted otherwise).		
<u>YES</u>	<u>N/A</u>	a) The amount of relocations or displacements as identified. L&G will provide relocation advisory services. L&G will compute replacement housing supplements (owner occupant and/or tenants)
<u>YES</u>	<u>N/A</u>	b) L&G will provide advisory services to business displacements and relocate them effectively.
<u>YES</u>	<u>N/A</u>	c) TxDOT will review, approve and pay for all relocation costs as per the Agreement.
9) CONDEMNATION SUPPORT		
<u>YES</u>	<u>N/A</u>	a) Pre-Hearing Support i) Upon receipt of a copy of the final offer, request an updated title commitment for Eminent Domain from the Title Company. ii) Prepare a Bisection Clause for the original set of Legal Descriptions supplied by Surveyor if applicable iii) Use the information from the Title Commitment to join all interested parties on the necessary forms. <u>Spouses of owners must also be joined.</u>

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

- iv) Upon completion of the necessary forms, prepare a packet containing 2 copies each of the following documents: Title Commitment, Negotiator's Reports, Appraisal Acknowledgment, Preappraisal Contact Sheet, signed and sealed property description, and plat, Final Offer Letter, any correspondence from the land owner or representatives, along with one copy of the appraisal report. Submit packet to the COUNTY Office for submission to the COUNTY Attorney's office.
- v) Upon receipt of concurrence for the Appraisal Witness, request the update of appraisal.
- vi) Upon receipt of packet prepared by the COUNTY Attorney which will include Petition for Condemnation, Lis Pendens, Order Appointing Special Commissioners, Order Setting Hearing, Oath of Special Commissioner, and Notice of Hearings, developed by the COUNTY Attorney; the attorney shall file the original petition with the COUNTY Court at Law or other appropriate Court for a cause number to be assigned.
- vii) The COUNTY attorney shall file the Lis Pendens including the cause number with the COUNTY Clerk's Office.
- viii) Upon assignment of a court, the COUNTY Attorney shall file the Order Appointing Commissioners with the judge retaining a copy of the Order for the files.
- ix) Following appointment of Special Commissioners by the judge, the COUNTY shall secure the following documents: Oath of Commissioners signed by the Commissioners, Order Setting Hearing, 2 copies of the Notice of Hearing signed by the Commissioners.
- x) The COUNTY shall file all originals with the court and send copies marked "copy" to L & G Engineering.
- xi) The COUNTY Attorney shall send a copy of the petition to the Title Company so that the Title Company can make sure the appropriate parties were joined and that no changes in title have occurred.
- xii) The COUNTY Attorney shall set the Special Commissioners Hearing after the updated appraisal has been submitted, if there is no change in value. If there is an increase in value, COUNTY will approve the new value and the COUNTY's provider will present a revised offer and a final offer letter and submit a copy of the final offer letter.
- xiii) The COUNTY Attorney shall coordinate a pre-hearing conference prior to the hearing (the day before or earlier) to discuss facts of the case with the COUNTY, Appraiser, and Negotiator.
- xiv) After the hearing is set, the COUNTY Attorney shall serve Notices of Hearing to the indicated parties at least 11 days prior to the Commissioner's hearing. If it is necessary to join the Federal Government, be advised that they have an additional 60 days to prepare for the Hearing.
- xv) Once the notices have been served, the COUNTY Attorney shall file the original notices with the court and send copies stamped "copy" to L&G Engineering ROW Office.
- xvi) The COUNTY's Attorney shall send a reminder letter 2-3 weeks in advance to the COUNTY Administration offices, Acquisition Provider, the three special commissioners and court reporter concerning Hearing dates.

YES

N/A

- b) Post Hearing Support (by COUNTY Attorney)
 - i) For the hearing, prepare the necessary forms and Special Commissioners time sheets and submit forms to Hidalgo COUNTY clerk's office.
 - ii) Obtain the signatures of Special Commissioners on the Award of Commissioners and file with the court for the judge's signatures within 48 hours of the Hearing.
 - iii) Give timesheets to Judge. The amount paid to the Special Commissioners is determined by the Judge.
 - iv) Obtain and distribute 3 certified copies of the award as follows: 1 certified copy to the title company with a request for a commitment, 1 certified copy to the COUNTY, 1 certified copy to L&G Engineering with the Commitment to request the warrant in the amount of the Special Commissioners Award.
 - v)

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
ENGINEER COUNTY

- vi) Send the Commitment and the Award to COUNTY, along with individual special commissioner's billing requesting the payment for their fees.
- vii) File COUNTY warrant in the registry of the court. File a Notice of Deposit with the court and send certified copies to each defendant notifying them of the date of the deposit. The Date of Deposit is the Date of Take.
- viii) Take photograph of the interest to be acquired (if necessary) on the day of deposit for relocation verification.
- ix) Send written notices of the date of deposit to the COUNTY Administration office and all interested parties.
- x) Appear as Expert Witness as requested. Sub-contractors must also appear as Expert Witnesses as requested.
- xi) All acquisition negotiations file indicating all "due diligence" provided by the Acquisition Provider will be directed to the COUNTY Attorney's office for his further handling in accordance to the Eminent Domain process by the COUNTY.

10) COMPENSABLE UTILITIES

Utility Accommodation is an integral factor in road construction and design. Coordination of utility adjustments is a necessary function within planning, design, acquisition and construction and requires the administration of property rights issues, utility policy, and reimbursement of eligible utility adjustments. It includes the following tasks:

<u>YES</u>	<u>N/A</u>	a) Preliminary Design Consultations i) Conduct Field Investigation and review Certificate of Convenience and Necessity boundaries to identify utility providers within the project area. Communications through letter, phone calls and email to establish a contact list. Coordinate data gathering by surveyors and design team. Introduce project to utility providers.
<u>YES</u>	<u>N/A</u>	b) Field Observations and Verifications i) Provide maps to Utility providers to "redline" and identify conflicts. Coordinate exposures and data collection by surveyor. Provide and confirm utility data on project maps. Order Utility Location Service.
<u>YES</u>	<u>N/A</u>	c) Exchange of Information with Utility Providers i) Provide project schedule. ii) Request schedules for utility adjustments. iii) Identify who is responsible for utility process.
<u>YES</u>	<u>N/A</u>	d) Confirmation of Property Interests i) Request Documents. ii) Coordination of data on maps and citation of property interest documents. iii) Confirm utilities are within easements.
<u>YES</u>	<u>N/A</u>	e) Coordination of Agreements i) Identify utilities that are compensable. ii) Determine parties and agreements necessary to complete compensable process. iii) Coordinate execution and processing of Standard Utility Agreements.
<u>YES</u>	<u>N/A</u>	f) Utility Meetings throughout project development i) Set up and coordinate utility meetings during planning, design, acquisition and construction phases. ii) Attend and participate in meetings by other parties.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

11) PAYMENT SCHEDULE

<u>YES</u>	<u>N/A</u>	
		a) Project Administration
		i) Payment and Milestones
		(a) Full Project Office
		(1) Lump Sum Basis (assume 1 year project presence)
		(2) Initial payment of 25% upon establishment of a project office with functional phone and utility services.
		(3) Remainder paid out in equal monthly installments of 15% starting the following month.
		(4) Monthly billing to COUNTY OF HIDALGO will be required.
		b) Title Services
		ii) Payment
		(a) Per Parcel basis.
		iii) Milestones
		(a) 100% upon securing initial title commitment.
		c) Appraisal Services
		i) Payment
		(a) Per Parcel Basis
		ii) Milestones
		(a) 100% paid upon delivery of complete and acceptable appraisal report
		d) Appraisal Review
		i) Payment
		(a) Per Parcel Basis
		ii) Milestones
		(a) 100% upon submission of ROW-A-10
		e) Appraisal Update
		i) Payment
		(a) Per Parcel Basis
		ii) Milestones
		(a) 100% upon delivery of complete and acceptable appraisal update.
		f) Negotiation, Task, and Fees
		i) Payment
		(a) Per Parcel Basis
		ii) Milestones
		(a) 80% upon presentation of initial offer.
		(b) 20% upon successful negotiation and all instruments are recorded.
		g) Closing Service Fees
		i) Payment
		(a) Per Parcel Basis
		ii) Milestones
		(a) 100% upon recordation of instrument of conveyance.
		h) Relocation Assistance
		i) Payment
		(a) Per Relocation
		ii) Milestones
		(a) 100% upon issuance of 90-day vacancy letter.
		i) Compensable Utilities
		i) Payment
		(a) By percent complete

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 13

ADDITIONAL RESONSIBILITIES

Easements, Letters of Permission, Etc.

The ENGINEER shall be responsible for delineating easements. The ENGINEER will be responsible for securing the necessary legal instruments.

Coordination of Utilities

The ENGINEER shall furnish the COUNTY prints of a project layout which will be distributed by ENGINEER to various utility companies to determine which utilities are in the limits of the project. These shall be preliminary layouts. Upon completion of the preliminary drainage plans and U&D sheets, the ENGINEER shall distribute to the various utility companies and request return. Upon return of these prints, the ENGINEER will schedule a meeting with the various utility companies to discuss potential conflicts and conformance with the State's Utility Accommodation Policy. The ENGINEER is responsible for coordination with the various utility companies for exposing potential conflicts and field ties to uncover utilities in potential conflict areas.

Meetings

Meetings will be held with the FHWA, State Officials, local governments, property owners, utility owners, railroad companies, other consulting firms, etc., as needed or required by the COUNTY. The ENGINEER shall coordinate through the COUNTY for the development of this project with any local entity having jurisdiction or interest in the project (i.e., city, county, etc).

Specifications, Special Provisions, Special Specifications

Use the State's standard specifications or previously approved special provisions and/or special specifications. If a special provision and/or special specification is developed for this project, it shall be in the State's format and incorporate references to approved State test procedures.

Project Manager/Engineer Communication

The ENGINEER shall designate one Texas Registered Professional Engineer to be responsible throughout the project for project management and all communications, including billing, with the COUNTY's Director. Any replacements to the ENGINEER's designated Project Manager/Engineer must be approved by the COUNTY.

Engineering documents produced for the department's engineering projects shall be signed, sealed and dated or CADD sealed in accordance with Administrative Order No. 5-89 and Administrative Circular No. 26-91.

Design Responsibilities

The ENGINEER is responsible for design errors and/or omissions that become evident before, during or after construction of the project. The ENGINEER's responsibility for all questions arising from design errors and/or omissions will be determined by the COUNTY and all decisions shall be final and binding. This would include, but not necessarily be limited to:

1. All design errors and/or omissions resulting in additional design work to correct the errors and/or omissions.
2. Preparation of design documents and detail drawings necessary for a field change due to design errors and/or omissions.
3. Revision of original tracings to the extent required for a field change due to design errors and/or omissions.

The ENGINEER shall promptly make necessary revisions or corrections resulting from the ENGINEER's errors, omissions or negligent acts without additional compensation. Acceptance of the work by the COUNTY will not relieve the ENGINEER of the responsibility for subsequent correction of any such errors or omissions or for clarification of any ambiguities.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Document and Information Exchange

Data, Plan Sheets, General Notes and/or Specifications provided to the COUNTY shall be furnished on 8GB USB flash drives. Each 8 GB flash drive shall have a file titled Table of Contents. The Table of Contents shall indicate the locations of files within the directory structure of the documentation.

General Notes and specifications shall be provided in MS Office 2007 format. Plan sheets shall be provided in Microstation DGN or GEOPAK GPK format. PDF copies of plan sheets shall also be provided.

Two copies of the documentation shall be provided to the COUNTY.

If required, the ENGINEER shall provide to the COUNTY, a CD that contains all the plan sheets for the project. The graphics tape shall be compatible with the COUNTY's computer system.

CD Tape Required (YES or NO): YES

Proposal Time

The time indicated in the proposal and the contract shall include time necessary for reviews, approval, etc.

Office Location

The ENGINEER will perform the services to be provided under this agreement out of their office or offices listed below:

<u>Service</u>	<u>Office Location</u>
PS&E	Mission Office
ROW Acquisition	Mission Office

The work effort will be managed out of the _____ Mercedes _____
(City)
office located at _____ 2100 West Expressway 83 _____,
(Address)
_____ Mercedes _____, _____ Texas _____.
(City) (State)

EXHIBIT “B”
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE

1. Title Sheet
Detailed Index of Sheets
2. Typical Sections
3. General Notes and Specifications Data
4. Estimate and Quantity Sheets
5. Storm Water Pollution Prevention Plan (SW3P) Sheets
6. Traffic Control Plans
 - a. Sequence of Construction Layouts
 - b. Detour Plan/Profile/Typical Sections/Quantities
7. Roadway Layouts
 - a. Roadway Plan/Profile Sheets
 - b. Intersection Plan/Profile Sheets
 - c. Intersection Layouts
 - d. Alignment Layouts/Data
 - e. Ramp Layouts/Profiles
 - f. Connection Roads/U-turns Layouts/Profile
8. Roadway Details
 - a. Concrete Pavement Details/Standards
 - b. Concrete Pavement Terminal Anchorage Details/Standards
 - c. Bridge Approach Details/Standards
 - d. Bridge Terminal Anchorage Details/Standards
 - e. Roadway/Median Barrier Details/Standards
 - f. Curb Details
 - g. Driveway Details/Typical Sections/Standards
9. Signing Layouts and Marking Layouts
10. Traffic Signal Layouts
11. Lighting Layouts
12. Illumination Detail Standards (HMID, HMIF, HMIP, RID)
13. Utility Layouts/Profiles
14. Drainage Area Maps and Hydraulic Data
 - a. General Drainage Area Maps
 - b. Stage-Discharge Curves
 - c. Main Cross-Drainage Culvert/Bridge Hydraulic Data
 - d. Drainage Area Maps/Culverts/Storm Sewer
 - e. Hydraulic Data/Culverts/Inlets/Storm Sewer/Pumps
15. Detailed Drainage Plans
 - a. Drainage Plan/Profile Sheets (Storm Sewer Plan/Profile Sheets)
 - b. Channel Plan/Profiles/Typical Sections
 - c. Box Culvert Plan/Profile
 - d. Pipe Sewer/Culvert Cross Sections

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE (Continued)

16. Drainage Structural Details/Standards
 - a. Inlet Details/Standards
 - b. Manhole Details/Standards
 - c. Junction Box Details/Standards
 - d. Safety End Treatment Details/Standards
 - e. Box Culvert Details/Standards
 - f. Culvert Wingwall Details/Standards
 - g. Excavation-Backfill Diaphragms
 - h. Riprap Details/Standards
 - i. Temporary Pollution and Erosion Control Details
17. Pumphouse Layouts
18. Pumphouse Details
19. Pumphouse Standard Details
20. Bridge Layouts/Profile/Typical Sections*
21. Bridge Details*
 - a. Summary of Bridge Quantities
 - b. Abutments
 - c. Interior Bents
 - d. Spans
 - e. Special details for the specific bridge
22. Bridge Standard Details*
23. Bridge Railing Standards
24. Retaining Wall Layouts/Profiles**
25. Retaining Wall Details**
26. Retaining Wall Standard Details**
27. Guard Fence/Standards and Signal Pole Standards
28. Signal/Electrical Details/Standards and Signal Pole Standards
29. Signing/Markers/Striping Details/Standards
30. Barricade/Construction/Beacon Standards
31. Miscellaneous Standards
 - a. Chain Link Fence Standards
 - b. Bridge End Detail/Standards
 - c. Roadway Clearance Details/Standards
 - e. Attenuator Standards

NOTE: Variations of these plan sheet sequence guidelines may be permitted if approved in writing by the County.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX B - PLAN PREPARATION PROCEDURES

1. Title Sheet
The ENGINEER shall be responsible for completing the title sheet as required and formatted by the STATE and as discussed in Part V of the Highway Design, Operations and Procedures Manual. Refer to Section K - Plans, 1 - Title Sheets, page 5-24, for the procedure to be used regarding all plans prepared by the ENGINEER.
2. Project Layout
The project layout shall clearly depict the entire project as it is proposed and will usually be drawn at a scale of 1 inch=100 feet or 1 inch=200 feet, depending on the size of the project.
3. Typical Sections
See Part IV of the Highway Design, Operations and Procedures Manual.
4. Sequence of Work Sheets (Traffic Control Plan)
Clarity and completeness should be the rule to follow in preparing these sheets, with particular attention given to location of construction signs and barricades, lane widths, protection of drop offs, etc. For a reference guide use the Texas Department of Transportation, Texas Manual on Uniform Traffic Control Devices. Usual scale of 1 inch=100 feet and/or 1 inch=50 feet for special locations. A narrative sequence shall be included in the special provisions for the project. Staging of structural elements shall be considered. Provisions for drainage shall be considered, included and indicated during all stages of construction operations.
5. Removal Item Sheets
These sheets indicate removal of existing facilities necessary to the proposed construction. (1 inch=40 feet) (use same scale as plan/profile sheets).
6. Summary Sheets
Summary Sheets are required to indicate type, quantity and/or location of work for individual items of the proposed project.
7. Alignment Layout Sheets
These sheets indicate the horizontal alignment with curve data and coordinates usually tabulated thereon. On some projects, depending on size, this information may be included on the plan profile sheets. Usual scale (1 inch=100 feet) or (1 inch=40 feet).
8. Plan Profile Sheet
Clarity and completeness should be the rule to follow in preparation of these sheets. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet), depending on project complexity.
9. Drainage Area Maps
Usual scale (1 inch=100 feet) and/or (1 inch=200 feet) supplemented by large scale area maps as necessary.
10. Drainage Plan Profile Sheets
These sheets may be required on some projects to clearly depict location of inlets, storm sewer lines, and profile of storm sewer lines and laterals. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet). Storm sewer design does include redesign of storm sewers imposed by utility constraints developing after initial reviews by the STATE and consequential redesign and adjustments.
11. Runoff, Inlet, Storm Sewer and Culvert Sheets
Use standard sheets.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX B - PLAN PREPARATION PROCEDURES (Continued)

12. Culvert Cross Sections and Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER for modification of special designs.
13. Manhole and Inlet Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER.
14. Miscellaneous Detail
Curb, Sidewalk, Driveways, etc.
15. Intersection Details
16. Marking Layouts and/or Details
Layouts of the entire project with markings depicted thereon. Usual scale 1:500 (1 inch=40 feet or 1 inch=50 feet). On some projects typical details might suffice.
17. Structural Details
Bridge layout sheets shall have the same horizontal and vertical scale. Usually (1 inch = 10 feet) (1 inch = 20 feet). Sections of existing and proposed structures usually have a scale of (1 inch = 5 feet). Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a (1/2 inch = 1 foot) or (1/4 inch equals 1 foot) architect scale to provide clear legible drawings when reduced. Letters shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
18. Overhead Sign Bridge Layouts
A maximum of four structures may be shown on each layout sheet. The reference to the appropriate overhead sign bridge (OSB) standard and the following requirements shall be shown on the layout:
 - (1) Drilled shaft size and length
 - (2) Soil strength used for design {indicate basis and boring(s) used}
 - (3) Design height
 - (4) Tower height
 - (5) Leg spacings and
 - (6) Design wind speed.

The wind speed design map need not be included in the project plans. Designation of tower member size and anchor bolt size shall not be shown. For OSBs which require special design, the design shall be in accordance with the AASHTO sign specifications (see Item 22 of References on page 49) and to the same loading requirements as for normal standard structures. Structures (special or standard) which will have changeable message signs shall be analyzed by the ENGINEER.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
—	—	Title Sheet
—	—	Project Layout
—	—	Sequence of Work
—	—	Detour Layouts & Profiles
—	—	Construction Pavement Markings
—	—	Signing & Barricades
—	—	Construction Sign & Beacons
—	—	Typical Sections
—	—	Shaping & Finishing Sections
—	—	Slopes Adjacent to Shoulders
—	—	Estimate & Quantities
—	—	General Notes & Specification Data
—	—	Grading Summary
—	—	Miscellaneous Summaries (See following "SUMMARIES" heading)
—	—	Horizontal Curve Data & Alignment Layouts
—	—	Drainage Summaries
—	—	Structure Summaries
—	—	Erosion Control Summary & Details
—	—	Plan/Profile Sheets
—	—	Erosion Control Summary & Details
—	—	Pavement Contours
—	—	Superelevation Transition (If Required)
—	—	Grading Contours
—	—	Guard Fence Layouts
—	—	Storm Water Pollution Prevention Plans (SW3P)
—	—	Drainage Area Maps
—	—	Hydraulic Data
—	—	Drainage Sheets
—	—	Bridge Hydrology Sheets
—	—	Inlet & Manhole Details
—	—	Utility Support Details
—	—	Culvert Cross Sections & Details
—	—	Special Culvert Designs
—	—	Special Drainage Details
—	—	Chain Link Fence Locations
—	—	Ramp Details Sheet
—	—	Removal Item Sheet - Including detours
—	—	(Shown in detour summary, No payment for removal; subsidiary to construction detours)
—	—	Pavement Details
—	—	Pavement Standard Modification for Concrete Shoulder
—	—	Concrete Pavement Continuously Reinforced (CPCR)
—	—	Concrete Pavement Contraction Design (CPCD)
—	—	Concrete Pavement Details - Jointed Reinforced (Steel Bars) (CPJR)
—	—	Bridge Approach Slab Details
—	—	Vehicle Attenuator Details
—	—	Miscellaneous Details
—	—	Wheelchair Ramps
—	—	Pavement Marking Details
—	—	Modified Standards
—	—	List of Standards
—	—	Permanent Signing Plans & Quantities

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST *(continued)*

Services
Provided By:
ENGINEER COUNTY

___	___	Permanent Lighting Plans, Quantities & Standards
___	___	Bridge Layout(s)
___	___	Bridge Details
___	___	Retaining Wall Layout(s)
___	___	Retaining Wall Details
___	___	Pumphouse Details
___	___	Underdrain Details (Retaining Walls)
___	___	Culvert Standards
___	___	Soil Profile
___	___	Temporary Traffic Signals
___	___	Design Cross Sections
___	___	Estimate
___	___	List of Standard Specification, Special Provisions & Special Specifications
___	___	Detour Special Provisions (If Required)
___	___	Construction Time Estimate
___	___	Critical Path Method (CPM)
___	___	Unit Price Documentation

Miscellaneous

___	___	Conduit Requirements
___	___	Traffic signal Requirements

Summaries

(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)

___	___	Salvaging and Placing Topsoil
___	___	Prepare ROW
___	___	Remove Old Structures
___	___	Scarify Existing Pavement
___	___	Remove Old Concrete Curb of Curb and Gutter (C&G)
___	___	Remove Old Concrete Pavement
___	___	Remove Old Concrete Riprap
___	___	Remove Metal Beam Guard Fence
___	___	Galvanized steel Beam Guard Fence (12Ga) (GSBGF)
___	___	Temporary Guard Fence (TEMPGF)
___	___	Summary of Concrete Flumes
___	___	Curbs
___	___	Adjust Manholes & Inlets
___	___	Underdrains
___	___	Base and Pavement
___	___	Large Structure
___	___	Concrete Riprap (RR8 & RR9)
___	___	Temporary Portable Concrete Barrier (PCBR)
___	___	Concrete Traffic Barrier
___	___	Vehicle Attenuator
___	___	Guard Rail Energy Absorbing Terminal (Great System)
___	___	Pavement Markings & Blast Cleaning (Thermoplastic)
___	___	Retaining Walls
___	___	Large Structure Summaries
___	___	Small Structure Summaries

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST *(continued)*

Services
Provided By:
ENGINEER COUNTY

Summaries

(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)

___	___	Earthwork (Roadway & Channel) & Channel Details
___	___	Culverts
___	___	Detours
___	___	Seeding or Mulch Sod - Quantity Only
___	___	Inlet & Manholes
___	___	Sidewalks
___	___	Construction Pavement Markings
___	___	Driveways
___	___	Concrete Median
___	___	Storm Sewers
___	___	Head Walls & Safety End Treatments
___	___	Curb Openings
___	___	Manholes
___	___	Chain Link Fence, Remove & Replace Chain Link Fence
___	___	Remove & Relay Reinforced Concrete Pipe (RCP) or Pipe Sewer

L&G FUNCTION
ENVIRONMENTAL ASSESSMENT WORK
TXDOT FUNCTION
COUNTY FUNCTION

EXHIBIT "D-1"
ESTIMATED PROJECT FEE SCHEDULE
FM 1925 PROJECT (SEGMENT II)
(Limits: from FM 907 (Alamo Road) to Sharp Road
including the Sharp Road Realignment (from FM 1925 North 0.5 Miles)

ROADWAY PROJECT:	FM 1925	Sharp Road Realignment			
LIMITS:	from FM 907 (Alamo Rd) to Sharp Rd.	from FM 1925 N 0.5 mi. (Project limits incl in Work Auth. No.1) (Time extended 2 years, no addtl money)			
EXISTING ROADWAY SECTION:	40-ft Rural	N/A			
EXISTING ROW WIDTH:	80-Feet	N/A			
PROPOSED ROADWAY SECTION:	4-lane divided urban	2-lane rural			
PROPOSED ROW WIDTH:	120FT	60 FT			
ESTIMATED CONSTRUCTION COST:	\$9,211,522.00	\$1,093,477.00			
LENGTH FOR 4-LANE ROADWAY	1.8 Miles	0.5 Miles			
ESTIMATED PROJECT COSTS	LOCAL %	TOTAL	LOCAL	TOTAL	LOCAL
WORK AUTHORIZATION NO. 1 (INCLUDES FM 1925 & SHARP RD RE-ALIGNMENT)					
PHASE I - EA, PUBLIC INVOLVEMENT, SCHEMATIC DESIGN					
Environmental Assessment with TxDOT	100	\$	-	\$	95,000.00
Public Involvement for the project with stakeholders and 1 Public Meeting	100	\$	-	\$	25,000.00
Archaeological and Historical Research	100	\$	-	\$	30,000.00
Engineering Technical Support at Public Migs with Layouts etc	100	\$	-	\$	24,000.00
Schematic for FM 1925	100	\$	-	\$	154,575.00
Hydrological Map	100	\$	-	\$	42,000.00
Schematic for intersecting streets (Sharp to 3rd Street)	100	\$	-	\$	40,000.00
Office Surveys for Schematic (Preliminary Ownership Identification and Property Rights)	100	\$	-	\$	21,000.00
Preliminary Compensable Utilities Identification on Schematic for Approval by TxDOT/FHWA	100	\$	-	\$	18,000.00
Update	100	\$	-	\$	39,000.00
Engineering Technical Support at Public Hearing with Layouts etc	100	\$	-	\$	36,000.00
Public Involvement and 1 Public Hearing	100	\$	-	\$	25,000.00
SUB-TOTAL	100	\$	-	\$	549,575.00
WORK AUTHORIZATION NO. 2 (SHARP RD RE-ALIGNMENT ONLY)					
PHASE II - PS&E and CONSTRUCTION OVERSIGHT					
Complete ROW Map (Estimated 6 Parcels)	100			\$	25,677.00
PS&E Development (7.5% Engineering Fee)	100			\$	82,010.78
Engineering Fee to Create sets of Plans and Submit through TxDot and Austin Letting	100			\$	72,000.00
PS&E Development for OUTFALL(S)	100			\$	36,000.00
Field Surveys for Design and Construction	100			\$	30,323.00
Permitted Utilities Coordination to adjust	100			\$	37,800.00
TxDOT Review (1.5% of Cost)	100			\$	18,400.00
ROADWAY CONSTRUCTION COST (Off-System 80/20-EDC)	3.4			\$	1,093,477.00
County Construction Inspection (Off-System 80/20-EDC)	3.4			\$	125,750.00
Right-of-Way Costs - Acq.Services @ (est.6 Parcels @ \$13,800/Parcel Avg.)	100			\$	82,800.00
Estimated Compensable Utility Mgmt	100			\$	40,000.00
SUB-TOTAL		\$	-	\$	1,219,227.00
WORK AUTHORIZATION NO. 3 (SHARP RD RE-ALIGNMENT ONLY)					
PHASE III - ROW Acquisition					
Estimated County Attorney Costs for Condemnation (\$15,000/Parcel based on 20% total of parcels)	100			\$	18,000.00
Estimated Roadway Right-of-Way Costs including Comp. Utilities	20			\$	650,000.00
Eng Consultant Construction Management	100			\$	108,000.00
SUB-TOTAL		\$	-	\$	650,000.00
WORK AUTHORIZATION NO. 4 (FM 1925 ONLY)					
PHASE II - PS&E and CONSTRUCTION OVERSIGHT					
Complete ROW Map (Estimated 10 Parcels)	100	\$	-	\$	40,000.00
Outfall Schematic and Hydraulics (Ditch capacities, etc.)	100	\$	-	\$	54,000.00
PS&E Development (7.5% Engineering Fee)	100	\$	-	\$	690,864.15
Engineering Fee to Create sets of Plans and Submit through TxDot and Austin Letting	100	\$	-	\$	135,000.00
PS&E Development for OUTFALL(S)	100	\$	-	\$	162,000.00
Field Surveys for Design and Construction	100	\$	-	\$	99,000.00
Permitted Utilities Coordination to adjust	100	\$	-	\$	90,000.00
ROADWAY CONSTRUCTION COST	0	\$	9,211,522.00	\$	-
TxDOT Construction Inspection	0	\$	549,543.00	\$	-
Eng Consultant Construction Management	100	\$	-	\$	94,500.00
SUB-TOTAL		\$	9,761,065.00	\$	1,365,364.15
WORK AUTHORIZATION NO. 5 (FM 1925 ONLY)					
PHASE III - ROW Acquisition					
Right-of-Way Costs - Acq.Services @ (est.14 Parcels and/or Util Easements @ \$13,800/Parcel Avg.)	100	\$	-	\$	193,200.00
Estimated County Attorney Costs for Condemnation (\$15,000/Parcel based on 20% total of parcels)	100	\$	-	\$	36,000.00
Estimated Compensable Utility Mgmt	100	\$	-	\$	126,000.00
Estimated Roadway Right-of-Way Costs including Comp Utilities (80/20-EDC)	1.7	\$	1,250,000.00	\$	21,250.00
SUB-TOTAL		\$	1,250,000.00	\$	376,450.00
TOTAL		\$	11,011,065.00	\$	2,291,389.15
				\$	1,869,227.00
				\$	720,464.50

	ENGINEER WORK AUTHORIZATION(S)			STATUS	COUNTY COSTS	
FM 1925 / Sharp Rd Realignment	Work Authorization No. 1	FY 13	\$ 549,575.00	ISSUED		
	Suppl. No. 1 to Work Authorization No. 1	FY 14 (to Change Project Limits)	\$ -	ISSUED		
Sharp Rd. Realignment	Work Authorization No. 2	FY 15 BOND FUNDS	\$ 406,610.78	NOT ISSUED	\$	57,853.72
	Work Authorization No. 3	FY 16 SIB FUNDS	\$ 108,000.00	NOT ISSUED	\$	148,000.00
FM 1925	Work Authorization No. 4	FY 15 SIB FUNDS	\$ 1,365,364.15	NOT ISSUED		
	Work Authorization No. 5	FY 16 SIB FUNDS	\$ 319,200.00	NOT ISSUED	\$	57,250.00
			\$ 2,748,749.93		\$	263,103.72

TOTAL ESTIMATED COUNTY COST (FM 1925 / SHARP RD. REALIGNMENT): \$ 3,011,853.65 18.95%

TOTAL ESTIMATED PROJECT COST (FM 1925 / SHARP RD. REALIGNMENT): \$ 15,892,145.65

COUNTY COST NOT INCLUDED IN WORK AUTHORIZATION(S)

EXHIBIT D-1
ESTIMATED PROJECT FEE SCHEDULE AND MAN-HOUR BREAKDOWN

FM 1925 (SEGMENT II) - Sharp Road Realignment PROJECT
from FM 1925 North 0.5 Miles

	MANHOURS														TOTAL HOURS	Sub-Contract Amounts / ROW COST	TOTAL LINE ITEM COST	ROUNDED TOTAL LINE ITEM COST
	Senior Project Manager	Senior Engineer	Senior Environmental Scientist /Specialist	Project Engineer	Design Engineer	ROW Administrator	EIT	Senior Engineer Tech	Environmental Scientist /Specialist	Engineer Tech	CADD Operator / GISAnalyst	Admin / Clerical	Biologist					
CONTRACT RATE	215.40	167.89	136.21	123.54	114.04	107.70	82.36	79.19	79.19	76.02	66.52	57.02	50.68					
WC Work Authorization NO. 2																		
PHASE II - PS&E, ROW ACQUISITION, CONSTRUCTION OVERSIGHT																		
1 Complete ROW Map - SUB (RODS Surveying, Inc.) (Est. 6 Parcels) See Exh D-1 Page 3 of 5														0	\$ 23,340.00	\$ 23,340.00	\$ 23,340.00	
2 L&G Complete and Manage SUB on ROW Map	6		3								7	3		19		\$ 2,337.73	\$ 2,337.73	
3 PS&E Development	62	100	100	80		40			100		180	41	36	739		\$ 82,010.90	\$ 82,010.00	
4 Engineering Fee to create sets of plans and submit through TxDOT & Austin Letting	60	80		120		20			11		399	22		712		\$ 72,001.01	\$ 72,000.00	
5 PS&E Development for Outfall(s)	60		68	40		30					45	26	23	292		\$ 36,000.44	\$ 36,000.00	
6 Field Surveys for Design and Construction - SUB (RODS Surveying, Inc.)															\$ 18,885.00	\$ 18,885.00	\$ 18,885.00	
7 L&G Management of SUB of Field Surveys for Design and Construction - See Exh D-1 Page 4 of 5	8	4		10	10		6	6		60	13	3	2	122		\$ 11,438.24	\$ 11,438.24	
8 Permitted Utilities Coordination to adjust	14	20	10	50	31		30		10	78	162	5	2	412		\$ 37,802.70	\$ 37,800.00	
10 Right-of-Way Acquisition Services (est. 6 Parcels - See Exhibit D-1 Page 5 of 5														0	\$ 82,800.00	\$ 82,800.00	\$ 82,800.00	
11 Compensable Utility Management	9	8		8	8		8	9		10	479	10	5	554		\$ 40,000.83	\$ 40,000.00	
SUB-TOTAL	219	212	181	308	49	90	44	15	121	148	1285	110	68	2850	\$ 125,025.00	\$ 406,616.85	\$ 406,610.97	

Subtotal Manhour Fee with Sub-Consultant Costs:	\$ 406,610.97
* Total Project Fee:	\$ 406,610.97

*Rounded Figure

	TASK DESCRIPTION RIGHT OF WAY MAPPING	3-Person Field Party	RPLS Manager	Survey Tech.	CADD Tech	Clerical	Total Labor Hrs. & Costs	CADD Workstation
	Right of Way Data (FNC 130)							
1	Prepare Ownership Data Map		2	8	10		20	10
2	Prepare Deed Working Sketches for Field		2	6			8	0
3	Analysis of Deed Research & Field Data for Boundaries		4	10			14	0
4	Compute Existing & Proposed ROW Lines (6 Parcels)		4	10			14	0
5	CADD Drafting for ROW Mapping				50		50	50
							0	0
	Field Surveying for ROW Mapping (FNC 150)							
6	Reconnaissance to locate front and back corners	20	2	6			28	
7	Field tie boundary corners	10	2	6			18	
8	Monument proposed ROW lines at PC,PT,PI and 1000' intervals	10	2	2			14	
9	Monument intersecting property lines at proposed ROW	5	1	2			8	
10	Monument intersecting side street ROW lines	5	1	2			8	
11	Deliverables		1	4			5	
	RODS TOTAL LABOR HOURS	50	21	56	60	0	187	60
	LABOR RATE PER HOUR	\$ 160.00	\$ 130.00	\$ 90.00	\$ 90.00	\$ 55.00		\$ 20.00
	TOTAL LABOR COSTS (FNC 130)	\$ 8,000.00	\$ 2,730.00	\$ 5,040.00	\$ 5,400.00	\$ -	\$ 21,170.00	\$ 1,200.00
	DIRECT EXPENSES:							
	Mileage (1,600 mi @ \$0.575/mile)						\$ 920.00	
	CADD Workstation						\$ 1,200.00	
	Reproduction & Delivery						\$ 50.00	
	SUBTOTAL DIRECT EXPENSES:						\$ 2,170.00	
	TOTAL COSTS (FNC 130 & FNC 150)						\$ 23,340.00	

	TASK DESCRIPTION	3-Person Field Party	RPLS Manager	Survey Tech.	CADD Tech	Clerical	Total Labor Hrs. & Costs	CADD Workstation
	CONTROL & TOPOGRAPHIC SURVEY							
	Horizontal-Vertical Control (FNC 150)							
1	Recover and Verify Existing Control	4	2	4				
2	Set and GPS intermediate control as needed	12	2	6			20	
3	Process and analyse data holding Texas State Plane Coordinates, South Zone NAD 83/93 datum and NAVD88.		5	8			13	
4	Provide 11"X 17" Horizontal-Vertical Control Sheets		2	3	8		13	
	Topographic Survey (FNC 150)							
1	Locate and Identify visible utilities & drainage structures	30	2	4	20			20
2	Provide Cross-sections on 500' intervals within the existing ROW	14	2	4	10			10
3	Deliverables			1	2			2
	RODS TOTAL LABOR HOURS	60	15	30	40	0	46	32
	LABOR RATE PER HOUR	\$ 160.00	\$ 130.00	\$ 90.00	\$ 90.00	\$ 55.00		\$ 20.00
	TOTAL LABOR COSTS (FNC 150)	\$ 9,600.00	\$ 1,950.00	\$ 2,700.00	\$ 3,600.00	\$ -	\$ 17,850.00	\$ 640.00
	DIRECT EXPENSES:							
	Mileage (600 mi @ \$0.575/mile)						\$ 345.00	
	CADD Workstation						\$ 640.00	
	Reproduction & Delivery						\$ 50.00	
	SUBTOTAL DIRECT EXPENSES:						\$ 1,035.00	
	TOTAL COSTS (FNC 130 & FNC 150)						\$ 18,885.00	

EXHIBIT "D-1"

FEE SCHEDULE - L&G ENGINEERING's ROW ACQUISITION SERVICES

FM 1925 - Segment II (Sharp Road Realignment) Limits: from FM 1925 North 0.5 Miles

The following is an estimated Parcel No. Cost for completing the subject project's Right-of-Way Acquisition Services as outlined in Exhibit B according to the Exhibit D "Fee Schedule" of the contract. The parcels are estimated from the approved Schematic. **The work and payment, for these services will be accomplished by L&G Engineering and approved and paid for by Hidalgo County Pct. 4- on a percent complete basis as approved by Hidalgo County Pct. 4** L&G Engineering will be completing the work on the approximate schedule provided in Attachment C of this Work Order or as approved by Hidalgo County Pct. 4. The Parcels will be acquired either by completing the entire negotiation of the parcel or by modifying the approved schematic to acquire the parcels. This is a lump sum cost proposal.

RIGHT-OF-WAY ACQUISITION SERVICES

Estimated Number of Parcels	Project Admin (Per Parcel)	Title Services Per Parcel	Appraisal Services Per Parcel	Appraisal Review Per Parcel	Appraisal Update	Negotiation Fees Per Parcel	Closing Services Per Parcel	**Relocation (Residential/ Business)	Grand Total of Task
6	\$5,900.00	\$600.00	\$2,700.00	\$800.00		\$3,500.00	\$200.00	N/A	
Sub Total of Tasks	\$35,400.00	\$3,600.00	\$16,200.00	\$4,800.00	\$600.00 *	\$21,000.00	\$1,200.00		\$82,800.00

(*) Appraisal Updates estimated at 20% of 6 parcels at \$500.00 each.

•Any condemnation support required will be provided by L&G Engineering as part of the administrative costs.

SPECIAL MEETING - March 31, 2015

BE IT REMEMBERED, that on this 31st day of March A.D., 2015, there was begun and held a **SPECIAL MEETING** of the Honorable Commissioners' Court of Hidalgo County, Texas, wherein the following members thereof were present, to-wit:

HONORABLE RAMON GARCIA

HIDALGO COUNTY JUDGE

HONORABLE A.C. CUELLAR, JR.

COMMISSIONER, PRECINCT NO. 1

HONORABLE EDUARDO "EDDIE" CANTU

COMMISSIONER, PRECINCT NO. 2

HONORABLE JOE M. FLORES

COMMISSIONER, PRECINCT NO. 3

and **ARTURO GUAJARDO, JR., COUNTY CLERK & EX-OFFICIO CLERK OF THE COMMISSIONERS' COURT** of Hidalgo County, Texas, wherein the following proceedings were had, to-wit:



AGENDA
CC REGULAR CONSENT
COMMISSIONERS' COURT
March 31, 2015
9:30 A.M.

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a **SPECIAL MEETING** of the Commissioners' Court will be held at the Edinburg Council Chambers 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

NOTICE TO THE PUBLIC
CONSENT AGENDA

The following items are of a routine or administrative nature. The Commissioners' Court has been furnished with background and support on each item, and/or it has been discussed at a previous meeting. All items will be acted upon by one vote without being discussed separately unless requested by a Court Commissioner, in which event the item or items will immediately be withdrawn for individual consideration in its normal sequence after the items not requiring separate discussion have been acted upon. The remaining items will be adopted by one vote.

On motion by COMMISSIONER PCT. 1, A.C. CUELLAR, JR., seconded by COMMISSIONER PCT. 3, JOE M. FLORES
, the Court made a UNANIMOUS vote of approval for the exception of Item 14.E to be pulled for discussion.

Vote: 5 - 0 - Unanimously

1. **Approval of check register and payment of claims and bills -**
(Payments from Juvenile Probation, Adult Probation, LEOSE Fund, DA Motor Vehicle Theft Fund, DA Bad Check Processing Fund, DA Forfeiture Fund, Sheriff Forfeiture Funds, Constable Forfeiture Funds, HIDTA Forfeiture Funds and VIT Interest Fund are presented for recording purposes only.)
2. **2015 Intradepartmental transfers:**
 - A. **AI-49078** 2015 - Co Wide Adm (1100)
 - B. **AI-49066** 2015 - I.T. Department (1100)
 - C. **AI-49044** 2015 - County Clerk (1100)
 - D. **AI-49035** 2015 - District Attorney (1100)
 - E. **AI-48864** 2015 - Constable Pct. 1 (1100)
 - F. **AI-48943** 2015 - Constable Pct. #2 (1100)

- A. **AI-48941** Request for approval of one (1) applicant in the Countywide Area and one (1) applicant in the City of Merced under the Owner-Occupied Housing Rehabilitation Program.

12. Auditor's Office:

- A. **AI-48967** 1. Pursuant to Local Government Code Sections 114.023-.025, requesting approval of Monthly Financial Report for the Month of January 2015.
2. Pursuant to Local Government Code Section 115.0035, requesting approval of the attached reports.

13. Budget & Management:

- A. **AI-48803** 1. Approval of reimbursement in the amount of \$718,236.60 to Blue Cross Blue Shield Insurance Company for claims paid on behalf of Hidalgo County from 03/01/15 to 03/13/15.

03/01-06/15	\$347,845.97
03/07-13/15	\$370,390.63
TOTAL	\$718,236.60

2. Approval of wire transfer to cover claims paid.

- B. **AI-48982** Self-Funded (2202)
Requesting approval of reimbursement of Hidalgo County Workers' Comp. Paying Account for claims paid by Tristar Risk Management for the period of 03/01-15/2015 in the amount of \$40,078.83 and requesting approval of wire transfer.

14.

Purchasing Dept:

Notes:

A. FOR ANY CONTRACTS(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FOWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

- A. **AI-49131** Requesting authority to exercise the **Sixty (60) Day** grace period extension as provided in the current agreement# **E-14-154-05-06** (C-12-321-10-18) for the: **"PEST CONTROL SERVICES"** (on an as needed basis) for Hidalgo County under the same rates, terms and conditions with **Robert Sanchez d/b/a KILL A BUG, effective, 05/13/15 - expiring, 05/12/15** or (upon completion of the procurement process which

- O. AI-48480** Requesting approval of payment for Invoice # 3749 in the amount of \$ 748.20 for professional services submitted by R. Gutierrez Engineering Corporation through Contract C-14-085-04-08 (WA#4) for the Pct. 2 Owassa Road project.
- P. AI-48986** Ratification of fully executed Change Order No. 6 (include 32 additional days) for the "Lowering of Canal Crossing & Road Widening at Eldora & Sgt. Leonel Trevino Roads," to awarded vendor Texas Cordia Construction, LLC, and as submitted by project engineer, Cruz-Hogan Consultants, Inc.

- Q. AI-48957** 1. Requesting approval of Work Authorization No. 3 for (\$883,200.00) as submitted by L&G Consulting Engineers, Inc. d/b/a L&G ENGINEERING for the provision of "professional engineering services" under contract # C-12-126-10-16 for: "job specific" Project: Extension of 10th Street (SH 107 to FM 1925) (ROW Acquisition for 2.5 Miles) located in HC Pct # 4.

APPROVED

2. Requesting approval of Work Authorization No. 2 for (\$406,610.78) as submitted by L&G Consulting Engineers, Inc. d/b/a L&G ENGINEERING for "professional engineering services" under contract # C-13-336-12-10 for the ongoing "job specific" Project: FM 1925 (from FM 907 (Alamo Rd) East of SH 68 (Uresti Street)--(SEG II, SHARP ROAD REALIGNMENT LIMITS N. .5 MILES) within Hidalgo County Precinct No. 4.

3. Requesting approval of Supplemental Agreement No. 1 to Work Authorization No. 2 -Scopes of Work-manage and complete R.O.W. Map to include an additional twelve (12) parcels for an estimated total of sixty four (64) parcels with an (increase of \$ 29,978.60) under contract # C-12-126-10-16 with L&G Consulting Engineering, Inc. for the purposes of (Job Specific) Project: TxDOT has determined that an additional traffic signal (Sugar Avenue) and two (2) flashing beacons (Russell & Rogers Rd.) in connection to the -Project: "Extension of 10th Street (SH 107 to FM 1925)" within Hidalgo County Precinct No. 4.

- R. AI-48888** Planning Department:
1. Requesting authority to enter into an annual software support renewal agreement through our membership/participation with (DIR) Department of Information Resources awarded vendor DLT Solutions, Inc. contract DIR-SDD-1697 for the Planning Department through the following requisition #273402.
 2. Acceptance and approval of the continuation of the services with DLT Sloutions LLC "Software support renewal agreement " through assigned requisition #273402 followed by an approved purchase order including any annual maintenance services renewals through the life term of existing Autodesk AutoCAD Software and any future addtional licenses for Planning Department.
 3. Approval to pay the continuation annual renewal fees.

HIDALGO COUNTY
Professional Engineering Services
Contract # C-13-336-12-10
Work Authorization Form

FILED	AT <u>3:00</u> O'CLOCK <u>P</u> M
SEP 04 2018	
ARTURO GUAJARDO, JR. COUNTY CLERK HIDALGO COUNTY, TEXAS	
BY <u>[Signature]</u>	DEPUTY

WORK AUTHORIZATION NO. 3

THIS WORK AUTHORIZATION is made pursuant to the terms and conditions of Article 7 of the Agreement made by and between **HIDALGO COUNTY**, action herein by and through the **Commissioner's Court**, hereinafter called the "**Owner**," and, **L & G Consulting Engineers, Inc. d/b/a L & G Engineering**, professional engineers of Mercedes, Texas, hereinafter called "**Engineer**".

PART 1. SCOPE OF WORK

The purpose of this Work Authorization is for the **Engineer** to provide the ROW Map, Schematic, PS&E and Consultant Const. Management services needed for the FM 1925 Project (from FM 907 (Alamo Road) to Sharp Road).

The scope of services to be provided by the **Owner** is identified in **EXHIBIT "A" – Scope of Services to be provided by the Owner** attached hereto.

The scope of services to be provided by the **Engineer** is identified in **EXHIBIT "B" – Scope of Services to be provided by the Engineer** attached hereto.

PART 2. ESTIMATED COST

The estimated cost for services under this Work Authorization is **\$1,582,600.00.** This amount is based upon the costs outlined in the Estimated **Cost Proposal** attached hereto as **EXHIBIT "D" Fee Schedule.**

PART 3. PAYMENT

Compensation and payment to the Engineer for the services established under this Work Authorization shall be made in accordance with **Article 5 & 6** of the Agreement.

PART 4. FUNDING

This Work Authorization No. 3 shall be funded through funding source:

Account No. 2018 COS

Requisition Number _____ (**MUST BE INCLUDED AFTER CC APPROVAL**)

PART 5. PERIOD OF SERVICE

This Work Authorization shall become effective on the date of final acceptance of the parties hereto, and terminate upon completion of scopes of the work authorization.

PART 6. RESPONSIBILITIES AND OBLIGATIONS

This Authorization does not waive the parties' responsibilities and obligations provided under the Agreement.

PART 7. ACKNOWLEDGEMENT AND CONFIRMATION

Acknowledgement and confirmation by **Hidalgo County Precinct No. 4**, Commissioner Joseph Palacios, as to content and detail of this **Work Authorization No. 3**.

**HIDALGO COUNTY
COMMISSIONER PRECINCT NO. 4**

BY: Joseph Palacios

PART 8. ACCEPTANCE AND APPROVAL

This Work Authorization is hereby accepted, approved by Hidalgo County Commissioners' Court on August 21, 2018 as indicated below.

**THE ENGINEER:
L&G ENGINEERING**

By: Jacinto Garza, P.E.
President

**THE OWNER:
HIDALGO COUNTY**

By: Ramon Garcia
Ramon Garcia,
County Judge

ATTEST:

By: Arturo Guajardo, Jr. County Clerk



APPROVED BY
COMMISSIONERS' COURT
ON: 8/21/18 me

LIST OF ATTACHMENTS

- Exhibit A – Services to be Provided by the Owner
- Exhibit B – Services to be Provided by the Engineer
- Exhibit C – Work Schedule
- Exhibit D-1 – Man hour Breakdown




EXHIBIT "A"

SCOPE OF SERVICES TO BE PROVIDED BY THE OWNER

The following provides an outline of the services to be provided by the **Owner** in the development of the PS&E for the necessary improvements to FM 1925 located within Hidalgo County, from FM 907 (Alamo Road) to Sharp Road hereinafter denoted as the **Project**.

GENERAL:

The **Owner** will provide to the **Engineer** the following:

- 1) Provide the authorization to proceed with services through coordination with the project consulting and design Engineer.
- 2) Payment for work performed by the **Engineer** and accepted by the **Owner** in accordance with Article 5 of the Agreement.
- 3) Assistance to the **Engineer**, as necessary, to obtain the required data and information from other local, regional, State and Federal agencies the **Engineer** cannot easily obtain.
- 4) Provide any available relevant data the **Owner** may have on file concerning the **Project**.
- 5) Provide timely review and decisions in response to the **Engineer's** request for information and/or required submittals and deliverables, in order for the **Engineer** to maintain the agreed upon work schedule prepared in accordance with Exhibit "C" attached to this Work Authorization.
- 6) Attend and participate in progress meetings as required and as coordinated and conducted by **Engineer**.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 1-PROJECT DESCRIPTION

The services designated herein as "Services provided by the ENGINEER" shall include the performance of all engineering services for the following described facility:

COUNTY/CITY: HIDALGO COUNTY

CONTROL: CSJ: 1803-02-035

PROJECT/DESCRIPTION: ROW Map, Schematic, PS&E & Construction Mgmt.

LENGTH: 1.8 MILES

HIGHWAY: FM 1925

LIMITS: FROM FM 907 TO SHARP ROAD

PROJECT CLASSIFICATION

(Place an "X" in only one Project Classification)

- ☐ Surface Treatment
- ☐ Overlay
- ☐ Rehabilitation Existing Road (Scarify & Reshape)
- ☐ Convert Non-Freeway to Freeway
- ☐ Widen Freeway
- ☒ Widen Non-Freeway
- ☐ New Location Toll Freeway
- ☐ New Location Non-Freeway
- ☐ Interchange (New or Reconstruct)
- ☐ Bridge Widening or Rehabilitation
- ☐ Bridge Replacement
- ☐ Upgrade to Standards - Freeway
- ☐ Upgrade to Standards - Non-Freeway
- ☐ Miscellaneous Studies (Use Function Code 110 for All Tasks)

ENGINEER shall mean L&G Engineering.

STATE shall mean Texas Department of Transportation.

COUNTY shall mean the Hidalgo County.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 5 - RIGHT-OF-WAY DATA

(Function Code 130)

Services
Provided By:
SURVEYOR CITY/COUNTY

NOTE: No work involving right-of-way (ROW) data is to be performed until the ENGINEER has given the SURVEYOR written approval of the final location of the proposed ROW lines as approved by TxDOT and the COUNTY.

A. RIGHT-OF-WAY MAPPING:

1. PURPOSE:

The purpose of right-of-way mapping is to prepare documents suitable for the acquisition of real property interests and the probable issuance of a title policy.

2. DEFINITIONS:

For purposes of this Contract, the following definitions shall apply:

- 2.1. Abstract Map – A drawing to scale prepared from record documents depicting proposed right-of-way lines, existing right-of-way lines, easement lines, and private property lines with relevant grantee names, recording data, and recording dates.
- 2.2. Closure/Area Calculation Sheet – A computer generated print-out of the area and the perimeter bearings, distances, curve data, and coordinates of an individual parcel of land to be acquired.
- 2.3. Access Denial Line – A line which indicates specific location where access to the roadway is denied.
- 2.4. Property Descriptions – A written metes and bounds description delineating the area and the boundary and describing the location of an individual parcel of land unique to all other parcels of land.
- 2.5. Owner – The most current title holder of record as determined by a study of the Real Property Records.
- 2.6. Parcel Plat – An 8 ½ inch by 11 inch drawing to scale depicting all the information shown on the right-of-way map regarding an individual parcel of land to be acquired.
- 2.7. Parent Tract – A unit or contiguous units of land under one ownership, comprising a single marketable tract of land consistent with the principle of highest and best use. A parent tract may be described by a single instrument or several instruments. A single parent tract cannot be severed by a public right-of-way, easement, or separate ownership which destroys unity of use.
- 2.8. Parent Tract Inset – A small line drawing, to an appropriate scale, of the parent tract perimeter placed upon the right-of-way map in the proximity of the respective parcel. Parent tract insets are used in cases where the parent tract cannot be shown to the same scale as the right-of-way map. Since parent tract insets are used to identify the limits and location of parent tracts, they should include public right-of-ways, utility easements and fee strips, and identifiable water courses which bound the parent tract.
- 2.9. Point of Beginning (P.O.B.) – A corner of the parcel of land to be acquired, located on the proposed right-of-way line and being the beginning terminus of the first course of the property description.
- 2.10. Point of Commencing (P.O.C.) – A monumented property corner which can be identified in the Real Property Records and is located outside the proposed right-of-way corridor. For title purposes, the point of commencing should be a monumented back corner of the parent tract. In the event a monumented back corner of the parent tract cannot be recovered, the nearest identifiable monumented property corner located outside the proposed right-of-way corridor may be used.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY

- 2.11. Preliminary Right-of-Way Layout/Abstract Map – A drawing to scale depicting proposed right-of-way lines, existing right-of-way lines, proposed pavement, access denial lines, the proposed centerline alignment, private property lines, easement lines, visible improvements, visible utilities, the station and offset from the centerline alignment to each Point of Curvature (PC), Point of Tangency (PT), and angle point in the proposed right-of-way lines and to each PC, PT, and angle point in the existing right-of-way lines in areas of no proposed acquisition. *(Reference Sample Attached)*
- 2.12. Right-of-Way Maps/Property Description/Parcel Plats – A series of 22 inch by 34 inch and 11 inch by 17 inch drawings to scale depicting the results of relevant elements of records research, field work, analysis, computation, and map making required to determine title, delineate areas and boundaries, locate and describe utilities and improvements to the extent necessary to appraise the value and negotiate the acquisition of individual parcels of private land for a proposed right-of-way project. *(Reference Sample Attached)*

3. WORK TO BE PERFORMED:

YES N/A

3.1. Preliminary Right-of-Way Layout/Abstract Map:

An abstract map shall be prepared sufficient to determine the following:

- 3.1.1. Any and all interests of public record held in the land to be acquired.
- 3.1.2. The total record holdings of an owner contiguous to land to be acquired from that owner.
- 3.1.3. Any and all interests in land to be acquired held in common (shopping mall parking lots, subdivision reserves, etc.)
- 3.1.4. Any and all improvements proposed by other agencies which may have a bearing on project development.
- 3.1.5. All called monuments, bearings, and distances as per recorded information.
- 3.1.6. Preliminary Parcel numbering system.
- 3.1.7. Any and all utilities (permitted or of record)
- 3.1.8. Reference Sample provided.

YES N/A

3.2. Right-of-Way Map:

The SURVEYOR shall field locate property corners, existing right-of-way markers, improvements, visible utilities, verify and update the planimetric file, if provided, and as directed by the ENGINEER.

A right-of-way map shall be prepared for each proposed right-of-way project. A right-of-way map shall include a title sheet, an index sheet, a survey control index sheet, a horizontal and vertical control data sheet, and sufficient plan sheets to cover the proposed project, or as directed by the ENGINEER. The STATE has developed standard title sheets, index sheets, and plan sheets, copies of which the SURVEYOR shall request and secure for all purposes of this Contract. Plan sheets shall include, but need not be limited to, the following items of information.

By mutual agreement between the Texas Board of Professional Land Surveying and the TxDOT, right-of-way maps need not be signed and sealed by a Registered Professional Land Surveyor.

- 3.2.1. Proposed right-of-way lines shall be delineated with appropriate bearings, distances, and curve data. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.
- 3.2.2. Existing right-of-way lines shall be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY
YES N/A

3.2 *Right-of-Way Map Continued (continued)*

- 3.2.3. The proposed project baseline alignment shall be delineated with appropriate bearings, distances, and curve data. Curve data shall include the station of the curve Point of Intersection (PI), radius, delta angle, arc length, tangent length, long chord bearing and distance, and the N and E coordinates of the curve PI. All alignment PCs, PTs, and even 500 foot stations shall be labeled as to station.
- 3.2.4. Proposed paving lines combined with relevant existing paving lines shall be shown to the extent necessary to compile a complete picture of proposed traffic movements. Proposed paving on the final mylars submitted to the ENGINEER shall be shaded with a dot pattern or highlighted by some other means acceptable to the ENGINEER.
- 3.2.5. Access denial lines shall be shown sufficiently to indicate areas where access is to be denied and where access is to be permitted if required by the ENGINEER.
- 3.2.6. Private property lines shall be delineated with appropriate bearings, distances, and curve data to the extent necessary to describe the individual parcels of land to be acquired. Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance.
- 3.2.7. Porción lines, subdivision lines and survey lines shall be shown and identified by name and Porción number.
- 3.2.8. County lines and city limit lines shall be located and identified by name.
- 3.2.9. A north arrow shall be shown on each sheet, and, if possible, located in the upper right corner of the sheet.
- 3.2.10. Monumentation set or found shall be shown and described as to material and size.
- 3.2.11. A station and offset shall be shown for each PC, PT, and angle point in the proposed right-of-way lines. Stations and offsets shall be with respect to the proposed centerline alignment.
- 3.2.12. Intersecting and adjoining public right-of-ways shall be shown and identified by name, right-of-way width, and recording data.
- 3.2.13. Railroads shall be shown and identified by name, right-of-way width, and recording data.
- 3.2.14. Utility corridors shall be identified as to easement or fee and recording information shall be identified.
- 3.2.15. Easements and fee strips shall be shown and identified by width, owner, distance of easement to a property corner of the parent track, and recording data.
- 3.2.16. Building lines or set-back lines shall be shown and identified.
- 3.2.17. Visible improvements located within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be shown and identified.
- 3.2.18. Structures shall be identified as commercial or residential, by number of stories, and as to type (brick, wood frame, etc.).
- 3.2.19. Structures which are severed by a proposed right-of-way line shall be dimensioned to the extent necessary to completely delineate the severed parts.
- 3.2.20. Parking areas, billboards, and other on-premise signs which are severed by a proposed right-of-way line shall be dimensioned to the extent necessary to delineate that portion of the parking area, billboard, or sign which is located within the proposed right-of-way corridor.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY
YES N/A

3.2 *Right-of-Way Map Continued (continued)*

- 3.2.21. In cases where structures are located outside the proposed right-of-way corridor and within 25 feet of a proposed right-of-way line, the shortest distance between the structure and the proposed right-of-way line shall be shown and field verified.
- 3.2.22. Visible utilities located within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be shown and identified.
- 3.2.23. The location of underground utilities and fuel storage tanks situated within the proposed right-of-way corridor or within 50 feet of a proposed right-of-way line shall be determined and shown as required by the ENGINEER. The visible location of stand pipes, vents and filler caps in conjunction with available design and as-built drawings may be used to determine a most probable location and size in the event an actual location is indeterminable.
- 3.2.24. Points of commencing and points of beginning shall be shown and labeled. Points of beginning shall be shown with their respective N and E surface coordinates. As an exception, a point of commencing will not be required in the case of a total taking without a remainder.
- 3.2.25. Each parcel of land to be acquired shall be identified by a parcel number which shall appear in the ownership tabulation and on the right-of-way map in the proximity of the respective parcel. If the SURVEYOR is unfamiliar with the criteria used by the STATE to assign parcel numbers, he shall seek the assistance of the ENGINEER at the time the abstract map is complete. **THE SURVEYOR SHALL SEEK ASSISTANCE FROM THE ENGINEER IN DEVELOPING AN OWNERSHIP TABULATION TABLE.**
- 3.2.26. An ownership tabulation shall be shown which shall include the parcel number, existing area of the parent tract, lot(s) and block(s) constituting the parent tract when applicable, owner's name, type of conveyance, film code, county clerk's file number, taking area, and remaining area of the parent tract located left and/or right of the centerline alignment. Types of conveyance, film code and file numbers refer to conveyances into the STATE and will be added to the right-of-way map by the STATE at a later date. Several blank lines shall be provided in the tabulation block to facilitate future map additions.
- 3.2.27. A parent tract inset shall be shown for each parent tract which cannot be shown to scale on the right-of-way map. The use of broken scale lines should be avoided. When parent tract insets are used, the point of commencing with the appropriate bearing and distance to the point of beginning may be shown on the parent tract inset.
- 3.2.28. A note shall be included on the title sheet and each map sheet stating the source of bearings, coordinates, and datum used.
- 3.2.29. Appropriate notes shall be included on the title sheet and each map sheet stating the following:
- a. Month(s) and year abstracting upon which the map is based.
 - b. Month(s) and year field surveys were conducted upon which the map is based.
 - c. Month and year the map was completed by the SURVEYOR.
- 3.2.30. The right-of-way CSJ number, if available, shall be shown on each right-of-way map sheet.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY

3.3. Exhibits:

An Exhibit shall be prepared for each parcel or tract consisting of a property description and a parcel plat.

YES

N/A

3.3.1. Property Description:

A property description shall be prepared for each parcel of land to be acquired. Standard formats for property descriptions, copies of which the SURVEYOR shall request to the ENGINEER and secure for all purposes of this Contract. Property descriptions shall include, but need not be limited to, the following items of information.

All property descriptions shall be signed and sealed by a Registered Professional Land Surveyor. The property description shall begin with a general description which shall include as a minimum:

- a. State, County, and Survey within which the proposed parcel of land to be acquired is located.
- b. A reference to unrecorded and recorded subdivisions by name, lot, block, and recording data to the extent applicable.
- c. A reference by name to the grantor and grantee, date and recording data of the most current instrument(s) of conveyance describing the parent tract. Use execution dates in deed references as opposed to recording or filing dates. In any case, the property description shall make clear which date is being used.

The property description shall continue with a metes and bounds description which shall include as a minimum:

- d. A point of commencing.
- e. A point of beginning with the appropriate N and E surface coordinates.
- f. A series of courses, identified by number and proceeding in a clockwise direction, describing the perimeter of the parcel of land to be acquired, and delineated with appropriate bearings, distances, and curve data.

Curve data shall include the radius, delta angle, arc length, and long chord bearing and distance. Each course shall be identified either as a proposed right-of-way line, and existing right-of-way line, or a property line of the parent tract. Each property line of the parent tract shall be described with an appropriate adjoiner call.

- g. A description of all monumentation set or found shall include, as a minimum, size and material.
- h. A reference to the source of bearings, coordinates, and datum used.

YES

N/A

3.3.2. Parcel Plat:

A parcel plat shall be prepared for each parcel of land to be acquired. The STATE has developed standard formats for parcel plats, copies of which the SURVEYOR shall request from the ENGINEER and secure for all purposes in this Contract. Parcel plats shall include each and every item of information shown on the right-of-way map which concerns the individual parcel. All parcel plats shall be signed and sealed by a Registered Professional Land Surveyor.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
SURVEYOR CITY/COUNTY

4. DELIVERABLES:

In preparing right-of-way maps, the following is an outline of the work to be submitted (records should be delivered in a binder):

<u>YES</u>	<u>N/A</u>	4.1. An Abstract Map of the current record title holders included in the Preliminary Map showing the proposed schematic and existing right-of-way as per General Specifications defined in 2.11.
<u>YES</u>	<u>N/A</u>	4.2. A Right-of-Way map for the project limits under cover of Title Sheet, Index Sheet, Control Data Sheet, and Exhibits of the property descriptions and parcel plats as per General Specifications defined in 2.12, 3.2 and 3.3. <u>ROW Map Submittal Requirements:</u> 4.2.1. Two (2) paper sets of half-size ROW maps (11"x 17") 4.2.2. One (1) paper set of the full-size ROW maps (22"x 34") 4.2.3. Four (4) sets of original metes & bounds descriptions (field notes) with parcel plats (signed & sealed by the surveyor). <i>Do not include traverse sheet.</i> 4.2.4. City requires one (1) electronic copy of the ROW Map on a CD, and One (1) copy of the DGN electronic file on a CD from the surveyor- Both the electronic copy of the ROW Map and the DGN file can be on one CD. <u>IF Roadway is ON-SYSTEM and after Administrative Approval of the ROW Maps by Division (REVISIONS) Submittal Requirements:</u> 4.2.5. Two (2) paper sets of the half-size of the affected ROW map sheets (11"x17"), detailing the <u>revision</u> 4.2.6. One (1) paper set of the full-size of the affected ROW map sheets (22"x 34"), detailing the <u>revision</u> 4.2.7. Four (4) sets of any <u>revised</u> original metes & bounds descriptions (field notes) with parcel plats (signed & sealed by the surveyor). <i>Do not include traverse sheet.</i> 4.2.8. Division needs one (1) electronic copy of the <u>revised</u> ROW Map sheets on a CD, and 4.2.9. One (1) copy of the DGN electronic file on a CD from the surveyor- detailing the <u>revision</u> -Both the electronic copy of the <u>revised</u> ROW Map sheets and the DGN file can be on one CD.
<u>YES</u>	<u>N/A</u>	4.3. Appropriate monuments on the proposed right-of-way lines at intersecting property lines, and at all PCs, PTs, angle points, intersecting right-of-way lines of side streets, and at 1,000 foot stations of the proposed centerline alignment.
<u>YES</u>	<u>N/A</u>	4.4. Appropriate monuments on the existing right-of-way lines in areas of no acquisition at all PCs, PTs, angle points, and 1,000 foot stations, and as directed by the ENGINEER of the proposed centerline.
<u>YES</u>	<u>N/A</u>	4.5. A SURVEYOR's report, outlining the approach, reasons or basis for the existing right-of-way determination, and conclusions made.
<u>YES</u>	<u>N/A</u>	4.6. Records used to establish ownership.
<u>YES</u>	<u>N/A</u>	4.7. ROW and parcel filed notes signed and sealed by a RPLS.
<u>YES</u>	<u>N/A</u>	4.8. Computation sheets of survey closures, ground surveys, etc. used to develop plats and meets and bound information.
<u>YES</u>	<u>N/A</u>	4.9. Items indicated under the Automation Requirements Section 6.
<u>YES</u>	<u>N/A</u>	4.10 Completed (Attached) Checklist with submittal of ROW Map etc.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY

5. GENERAL REQUIREMENTS:

For purposes of this Contract, the following general requirements shall apply:

YES

N/A

- 5.1. Copies of instruments of record submitted to the ENGINEER shall be indexed by parcel number.
- 5.2. Coordinates appearing on right-of-way maps, on parcel plats, and in property descriptions shall be surface coordinates based on the Texas State Plane Coordinate System. The combined adjustment factors (sea level factor x scale factor) which have been developed by the STATE for its use are as follows:
 - 5.2.1. In (List Applicable Counties): Counties (----- Zone), grid coordinates are multiplied by a combined adjustment factor of 1.xxxxxx to obtain surface coordinates. For work in Counties other than those listed, the ENGINEER will provide the combine adjustment factor.
- 5.3. Line and curve tables may be used when necessary.
- 5.4. The number of centerline alignment stations to be shown on a single plan sheet shall be restricted to the extent necessary to allow approximately 4 inches between match lines and sheet borders for future details and notes.
- 5.5. A minimum 4 inch by 4 inch space shall be reserved at the bottom right corner of each map sheet for future revision notes.

6. AUTOMATION REQUIREMENTS:

In addition to standard hard copy plots and mylar copies, the following will be required electronically:

YES

N/A

- 6.1. Right-of-way maps and parcel plats shall be prepared using a *Micro Station* software graphics system capable of producing graphics files that can be plotted and viewed without further modification or conversion using the State's *Micro Station V8* graphics system.
- 6.2. It is the intent of the ENGINEER to secure graphics files which have elements of equal integrity, singularity, and attributes as elements prepared using the State's *Micro Station V8* graphics system.
- 6.3. For purposes of clarity, consistency, and ease of utilization, the SURVEYOR shall request and secure standards relevant to right-of-way mapping to the extent necessary to ensure that the needs of the ENGINEER are met. This includes, but may not be limited to, TxDOT seed file and corresponding units.def file, TxDOT font resource file, TxDOT GEOPAK SMD file, TxDOT DGNLIB, associated cell libraries and custom line styles, and other files as deemed appropriate for the project.
- 6.4. Graphics files furnished to the ENGINEER by the SURVEYOR shall be submitted on a Compact Disk CD, DVD or USB, in a format compatible with the STATE's computer system. The SURVEYOR shall confer with the ENGINEER regarding acceptable media and formats before making submissions. The SURVEYOR shall request and secure a Consultant File Index form provided by the ENGINEER, to be completed by the SURVEYOR, and to be submitted to the ENGINEER along with the graphics files.
- 6.5. Property descriptions shall be prepared using a computer word processing system capable of producing data files readable using *Microsoft Office Word Version 2007* word processing software.
- 6.6. Data files furnished to the ENGINEER by the SURVEYOR shall be submitted in ACSII format on a CD, DVD or USB.
- 6.7. Provide to the ENGINEER electronic copies of all instruments of record acquired pursuant to a work authorization.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR CITY/COUNTY

7. GENERAL SPECIFICATIONS:

For purposes of this Contract, the following general specifications for right-of-way mapping shall apply:

YES

N/A

- 7.1. Completed right-of-way maps shall be submitted to the ENGINEER on single or double matte mylar, 22 inches by 34 inches in size with a 21 inch by 32 inch printed border positioned ½ inch from the top, bottom, and right edge of the sheet. Two copies on 11 inch by 17 inch paper will also be supplied to the ENGINEER.
- 7.2. Parcel plats shall be submitted to the ENGINEER on 8 ½ inch by 11 inch bond paper with respective borders of 7 ½ inches by 10 inches, positioned ½ inch from the top, bottom, and right edge of the sheet. Match lines shall be used where more than one sheet is required.
- 7.3. Right-of-way maps shall be drawn to a scale of 1 inch = 50 feet. An appropriate scale other than 1 inch = 50 feet may be used on some proposed right-of-way projects upon prior approval by the ENGINEER.
- 7.4. Since right-of-way maps are reduced in size by one-half for archiving purposes, the smallest size lettering acceptable on a right-of-way map shall be 1/10 of one inch (Leroy #100). A right-of-way map which contains any lettering smaller than 1/10 of one inch will not be accepted by the ENGINEER.
- 7.5. Parcel plats shall be drawn to a preferred scale of 1 inch = 50 feet. An appropriate scale other than 1 inch = 50 feet may be used on some proposed right-of-way projects upon prior approval by the ENGINEER. In the case of a very large parcel which would be difficult to show with clarity on a single 8 ½ inch by 11 inch sheet, the SURVEYOR shall use multiple 8 ½ inch by 11 inch sheets with matching lines.
- 7.6. The smallest size lettering acceptable on a parcel plat shall be 0.06 of an inch (Leroy #60).
- 7.7. Property descriptions shall be submitted on 8 ½ inch by 11 inch bond paper.
- 7.8. The ENGINEER has encountered a number of mylar products which are considered unacceptable. The SURVEYOR shall confer with the ENGINEER regarding mylar products he intends to use which have not been previously used on State projects.
- 7.9. Zip-A-Tone or other similar stick-on products shall not be used on right-of-way maps or parcel plats.

8. ADHERENCE TO STANDARDS:

For purposes of clarity, consistency, and ease of understanding, the CITY/COUNTY, as an acquiring agency of private property for public use, has adopted the STATE standards and formats for right-of-way mapping which have proven to facilitate the processes of negotiation, appraisal, relocation assistance, and condemnation. It shall be the responsibility of the SURVEYOR to adhere to these standards and formats to every extent possible to ensure that the needs of the acquiring agency are met.

SAMPLES ATTACHED FC 130:

- PRELIMINARY Right-of-Way Layout / Abstract Map
- Right-of-Way Map, Field Notes, Parcel Sketches and Area Computation Sheets

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER
ROW MAP CHECKLIST

Consultant: _____
Contract/WA# _____
Responsible Office: _____
Project Manager: _____
County: _____
Highway: _____
RCSJ: _____
CCSJ: _____

As the responsible consultant project manager, I hereby certify that the attached ROW Map has undergone a QA/QC review, with the following applicable items specifically checked for accuracy, completeness and constructability (as noted by Checkmarks)

Signature Date

Printed Name

(This Checklist must be signed by the RPLS and turned in with all proposed ROW Projects.)

MAP:

General

- ___ All documents have been proofread and are accurate.
- ___ Title Commitments for each individual parcel.
- ___ Graphics files compatible with Micro station and Word software are provided.
- ___ Photos of proposed ROW staking included.
- ___ Field notes and Parcel Plats are numbered continuous.
- ___ Scale shall be 1"=50' or 1"=100'.

Title Sheet Requirements

- ___ Title and description of project including county, limits, etc....
- ___ Vicinity map with beginning and ending station
- ___ Equations and Exceptions
- ___ Index
- ___ Legend
- ___ Title block completely filled out with Construction and R.O.W. CSJs'
- ___ List all Major Utilities from Station to Station

Individual Map Sheet Requirements

- ___ Sheet size 34" X 22"
- ___ Text legible when reduced to half-scale.
- ___ Title block completely filled out with R.O.W. CSJ
- ___ Matchlines
- ___ Project layout sheet
- ___ Existing utility lines and easements, deed reference, as shown on Schedule "B" of the Title Commitment, and defined on parcel plats

Existing information:

- ___ R.O.W. lines
- ___ Whole property or whole property inset
- ___ Roadways
- ___ Survey, county, and city limit lines shown and labeled
- ___ Improvements shown and labeled (*see below*)
- ___ Monumentation i.e. P.C., P.T., Break Points
- ___ North arrow
- ___ Scale
- ___ Property lines

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

- ☐ Property descriptions i.e., lot, block, tract, subdivision, etc...
- ☐ Identify existing and proposed access denial locations (*if applicable*)

Proposed information:

- ☐ #5- 2-ft iron road set monumentation i.e. P.C., P.T., Break Points and 1000' stations at proposed ROW lines and where existing ROW line is the proposed ROW.
- ☐ Survey and R.O.W. lines
- ☐ Basis of bearings
- ☐ Parcel bearings and distances correspond with traverse sheet
- ☐ Outside ties (P.O.C.) corresponds with field notes
- ☐ Point of beginning (P.O.B.) established on proposed R.O.W. line
- ☐ Parcel tied to baseline
- ☐ Baseline information shown i.e. Stationing, bearings, curve data, etc...
- ☐ Conveyance information shown in tables i.e. parcel number, grantors name, amount of take, remainder etc.
- ☐ Math checked on remainder

Improvements:

- ☐ Improvements bisected or within 25' of proposed R.O.W. line are shown on map with stationing and distance from proposed R.O.W. line. Buildings are labeled and dimensioned.
- ☐ Off-premise outdoor advertising signs within proposed R.O.W. are shown and labeled.

Utilities:

- ☐ All utilities within or crossing existing and proposed right of way are shown and labeled as to size, easement or fee width, and recording data of instrument.
- ☐ Location of underground storage tanks and/or filler caps are shown and labeled

FIELD NOTES - Heading

- ☐ County
- ☐ Highway
- ☐ Parcel number
- ☐ R.O.W. CSJ
- ☐ Construction CSJ

General Description or "preamble"

- ☐ Area of parcel to be acquired is shown in acreage (0.000) for rural land and/or square feet (to nearest whole sq. ft.) for urban land or smaller parcels

Parent tract data is shown:

- ☐ Size of parent tract
- ☐ Survey data or lot, block, and subdivision
- ☐ Name of last recorded seller and buyer
- ☐ Date, volume and page or document number of last recorded conveyance
- ☐ Records and county of last recorded conveyance

Beginning Description

- ☐ Point of commencement is on outside tie and is described accurately by bearings and distances as it leads to the point of beginning.
- ☐ Point of beginning is on proposed R.O.W. line

Particular Description

- ☐ Traverse calls are clockwise sequence
- ☐ Bearings and distances correspond exactly with map, parcel sketch, and traverse sheet
- ☐ Bearings are to nearest whole second and distances are to the nearest one-hundredth of a foot
- ☐ Calls are numbered
- ☐ Denial of access shall be described from beginning to end (*if applicable*)

Closing Description

- ☐ Last call leads back to P.O.B.
- ☐ Restates area of parcel

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

- ☐ Establishes taking in existing road R.O.W. if applicable
- ☐ Legal description is referenced to Plat
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)

PARCEL SKETCH:

- ☐ Shows P.O.B. and P.O.C.
- ☐ All data corresponds exactly with Map and Field Notes
- ☐ Sheet size is no larger than 8 1/2" x 11"
- ☐ Plat closely matches example provided
- ☐ Plat referenced to legal description
- ☐ Sealed and signed
- ☐ Include an access clause whether access is permitted or denied (*if applicable*)
- ☐ Existing utility lines and easements (deed reference, if available);

TRAVERSE SHEET

- ☐ Computations show area to be acquired in sq. ft. or acres, whichever is applicable
- ☐ Computations show area that is existing road R.O.W. if applicable
- ☐ Traverse calls are in clockwise sequence
- ☐ Error of closure meets the following:

Secondary rural	.0003
Primary rural - secondary urban	.0002
Urban or industrial	.00013

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 6 - FIELD SURVEYING AND PHOTOGRAMMETRY

(Function Code 150)

Services
Provided By:
SURVEYOR COUNTY

DESIGN AND CONSTRUCTION SURVEYS:

PURPOSE:

The purpose of a "design survey" is to provide field information in support of transportation systems design.

The purpose of a "construction survey" is to provide field data in support of highway construction.

DEFINITIONS:

A "design survey" is defined as the combined performance of research, field work, analysis, computation, and documentation necessary to provide detailed topographic (3-dimensional) mapping of a project site. A design survey may include, but need not be limited to, cross-sections or data to create cross-sections and Digital Terrain Models (DTM), horizontal and vertical location of utilities and improvements, detailing of bridges and other structures, review of right-of-way maps, establishing control points, etc.

A "construction survey" is defined as the combined performance of reconnaissance, field work, analysis, computation, and documentation necessary to provide the horizontal and vertical position of specific ground points to be used by the construction contractor for determining lines and grades.

YES

N/A

1. Design Surveying

- a. Primary Project Control – 3 to 5 miles spacing
Precision shall be 1 part in 20,000 or better, unless otherwise directed by the District Engineer.
(1) Establish horizontal control points
(2) Establish vertical control points

NOTE: ALL BEARING AND DISTANCE SHALL BE BASED ON THE STATE PLANE COORDINATE SYSTEM NAD 1983, SOUTH ZONE. ALL DISTANCES AND COORDINATES SHALL BE SURFACE AND MAY BE CONVERTED TO GRID BY MULTIPLYING BY A COMBINED SCALE FACTOR OF 0.999960

YES

N/A

- b. Secondary Project Control – Surveyor shall recover and/or reset H&V Control Points as provided by the Engineer and create Survey Control Data Sheets for inclusion in the Construction Project Plans signed and sealed by an R.P.L.S.
(1) No traverse should exceed 25 angle points. Planimetrics shall be 20 ft Lt & Rt from the proposed ROW as per the schematic provided by the Engineer.
(2) The unadjusted angular error should not exceed 2 seconds per angle, plus 14 seconds.
(3) The unadjusted ratio of precision should be one part in 10,000 or better. (The ratio of precision is the total length of the traverse divided by the total error.)
(4) The unadjusted vertical error should not exceed 0.03 foot per mile of traverse.
(5) Project control base lines

NO

N/A

- (6) Photogrammetric ground control
(a) Establish horizontal control
(b) Establish vertical control points
(c) Place and maintain control point targets

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR COUNTY

YES N/A

c. Other Design Surveying

- (1) **The limit of the Design surveys shall be 500-ft before and after the limits of the project as identified by the Project Engineer on the schematic. Establish horizontal and vertical control. Set H&V Control at 1000-ft intervals along the project proposed right-of-way. Provide x, y, z for each H&V Control. Provide an H&V Control along each outfall identified on the Hydrologic Map. The H&V Control shall be #5 I.R. 2-ft in depth set in concrete. The surveyor shall provide an H&V Control Book (a Sample shall be provided by the Engineer to the Surveyor). The Surveyor will provide a 3-pt reference sketch with ties to the BMs for inclusion the existing H&V Control Book. Establish benchmark circuit throughout the project with a tolerance of 0.03'/ft per mile error vertically.**
- (2) Complete topographic and cross section survey, data processing, and CADD mapping (2D & 3D) for the limits of the project.
- (3) Locate all visible utilities, data processing and CADD mapping (2D & 3D) including irrigation lines. Follow sample provided by the Engineer.
- (4) Field locate cross culverts, driveway culverts, inverts, irrigation lines, within the project limits, data processing and CADD mapping (2D & 3D).
- (5) Right of Entry, Right of Way Research, and Appraisal District Records is the responsibility of the Surveyor.
- (6) The Surveyor shall stake the proposed centerline on the existing fields as approved by Engineer before construction for the purpose of utility adjustments and project location.
- (7) Profile and cross section intersecting streets for ties into project (500-ft. beyond the proposed ROW per schematic and 20-ft wider than the existing ROW of intersecting street). Reference missing voids as per CD provided by the Engineer.
- (8) Cross section irrigation crossings for a distance of 20-ft beyond the proposed ROW at 100-ft intervals in a DTM file. Provide a complete description of irrigation appurtenances as identified by the engineer sample layout "EXHIBIT E". The SURVEYOR will meet with the ENGINEER before he ties down any irrigation lines. Jointly the SURVEYOR and the ENGINEER will identify from records such as the Irrigation District Maps and the A&M Data of existing irrigation lines that will need to be tied down. The SURVEYOR will follow the sample given to him by the ENGINEER and tie the structures horizontally and vertically and include in the field books to be submitted.
- (9) Tie Horizontally and Vertically the existing storm drain system that lies within the existing proposed ROW including the elevation of the outfall of said recovered existing storm drain systems.
- (10) Tie to existing underground and overhead utilities (location, elevation and direction)

Horizontally – The surveyor shall call the 1-800 number for the utilities to be marked on the ground as well as any city water and sewer lines. He shall tie all visible utility crossings with name, address and Phone #'s of utility companies. The engineer will coordinate with the utility companies and jointly the Surveyor and the Engineer will identify which utilities were missed and need to be tied down.

Vertically – The engineer shall identify all utilities that are potential conflicts and that need to be tied vertically. The engineer will advise the surveyor in writing of the needed vertical ties and the surveyor will tie the lines vertically once the surveyor has coordinated the exposure and provide the information to the engineer.

EXHIBIT "B" SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER ---

Services
 Provided By:
SURVEYOR COUNTY

<u>YES</u>	<u>N/A</u>	(11) Cross section and profile all outfall channels identified on the Hydrologic Map for a distance of 200-ft beyond the proposed ROW upstream and downstream at 100-ft intervals. The SURVEYOR will provide a complete 2D/3D File including utilities of the outfalls identified.
		(12) Driveways and Turnouts
		(a) Inventory commercial entrances, public roads and side streets separately.
		(b) Obtain centerline station. (Width at ROW, PAV'T and existing radius.
		(c) Inventory by type (dirt, caliche, gravel or paved). If paved, indicate condition in terms of no patches, has patches or has potholes.
		(d) Obtain width at R.O.W. line.
		(e) Obtain elevations at both edges of the driveway or turnout in line with the side drain.
<u>YES</u>	<u>N/A</u>	(13) ROW staking (Existing and Proposed @ 1,000 ft. stations PC's PT's and Angle points as per ROW Map)
<u>N/A</u>	<u>N/A</u>	(14) Soil core hole staking at bridge class structures.
<u>N/A</u>	<u>N/A</u>	(15) Determine changes in topography from voids and outdated maps due to development, erosion, etc.
<u>YES</u>	<u>N/A</u>	(16) Profiles of existing drainage facilities.
<u>N/A</u>	<u>N/A</u>	(17) Measurement of hydraulic opening under existing bridges.
<u>YES</u>	<u>N/A</u>	(18) Obtain elevations of manholes and valves of utilities
<u>YES</u>	<u>N/A</u>	(19) Provide temporary signs, traffic control, flags, safety equipment, etc.
<u>N/A</u>	<u>N/A</u>	(20) Ties to existing bridges railroad rail elevations or culverts that may conflict with new construction.
<u>N/A</u>	<u>N/A</u>	(21) Bridge widening top of deck and/or top of cap elevations at the Profile Grade Line (PGL) and the edges of slab at bent locations.
<u>YES</u>	<u>N/A</u>	(22) Inventory signs, mailboxes, and driveways
<u>N/A</u>	<u>N/A</u>	(23) Locate wetlands.
<u>YES</u>	<u>N/A</u>	(24) Locate existing right-of-ways.

d. Construction Surveys:

In performing construction surveys, the following will be requested by the ENGINEER on an as needed basis, but need not be limited to:

<u>YES</u>	<u>N/A</u>	(1) Stake existing and/or proposed right-of-ways.
<u>YES</u>	<u>N/A</u>	(2) Stake existing and/or proposed baseline/centerline.
<u>N/A</u>	<u>N/A</u>	(3) Stake proposed bridge structures.
<u>YES</u>	<u>N/A</u>	(4) Stake proposed drainage structures, such as manholes, culverts, etc.
<u>N/A</u>	<u>N/A</u>	(5) Set grade stakes.
<u>YES</u>	<u>N/A</u>	(6) Recover and check existing control points.
<u>YES</u>	<u>N/A</u>	(7) Establish additional control points.
<u>YES</u>	<u>N/A</u>	(8) Check elevations and locations of structures.
<u>YES</u>	<u>N/A</u>	(9) Determine and resolve conflicts associated with survey data.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR COUNTY

<u>N/A</u>	<u>N/A</u>	2. Photogrammetric Products a. Uncontrolled Photography (1) Contact Prints (2) Mosaics (3) Digital ortho plots b. Mapping (1) Planimetric Maps (2) Contour Maps (3) Cross Sections (4) Profiles (5) Digital Terrain Models (DTM)
		3. <u>UTILITY SUBSURFACE INVESTIGATION:</u> <u>Utility Quality Levels</u> are in cumulative order (least to greatest) as follows
<u>NO</u>	<u>N/A</u>	3.1. Quality Level C - Existing Records: Utilities are plotted from review of available existing records that will be generated by the Engineer on the schematic and provided to the surveyor for his further creation of a Utility Map which will be turned in as a deliverable as part of this work order.
<u>NO</u>	<u>N/A</u>	3.2. Quality Level B - Surface Visible Feature Survey: The Surveyor shall gather the field tied Utility Information and compare it to the existing records (if any) as provided by the Engineer and correlate with surveyed surface-visible features. The surveyor shall create a Utility Layout Map or plan layout 2D, showing the limits of the proposed project and limits of the work area required for this work authorization; including highway stations, limits within existing or proposed right of way. Correlate utility owner records with designating data and resolve discrepancies using professional judgment. A color-coded composite utility facility plan with utility owner names, quality levels, line sizes and subsurface utility locate (test hole) locations. The Layout Map will include all utilities that have been field tied – 2D Horizontal Utilities. This Layout will be provided to the Engineer and a meeting held with Engineer to identify which utilities will need to be tied down vertically. A note must be placed on the designate deliverable only that states "lines sizes are from best available records". All above ground appurtenance locations must be included in the deliverable to the Engineer. This information will be provided in the latest version of Micro Station or Geopak used by the State. The electronic file will be delivered on C.D. or DVD. A hard copy is required and must be signed, sealed, and dated by the Surveyor. Note: Determine and inform the Engineer of the approximate utility depths at critical locations. This depth indication is understood by the Engineer to be approximate only and is not intended to be used for preparing the construction plans.
<u>YES</u>	<u>N/A</u>	3.3. <u>Subsurface Utility Locate (Test Hole) Service (Quality Level A), THE SURVEYOR SHALL ESTIMATE LOCATING VERICALLY 25 UTILITES PER MILE OR AS IDENTIFIED BY THE ENGINEER.</u> Locate shall mean to obtain precise horizontal and vertical position, material type, condition, size and other data that may be obtainable about the utility facility and its surrounding environment through exposure by non-destructive excavation techniques that ensures the integrity of the utility facility. Subsurface Utility Locate (Test Hole) Services (Quality Level A) are inclusive of Quality Levels B and C. The Surveyor shall: 3.3.1 Review the requested test hole locations that have been identified by the Engineer and Coordinate with utility owner inspectors as may be required by law or utility owner policy.

EXHIBIT "B" SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
SURVEYOR COUNTY

3. *Utility Subsurface (continued)*

- 3.3.2 Measure and record the following data on an appropriately formatted test hole data sheet that has been sealed and dated by the Engineer:
- Elevation of top and/or bottom of utility tied to the datum of the furnished plan.
 - Identify a minimum of two benchmarks utilized. Elevations shall be within an accuracy of 15mm (.591 inches) of utilized benchmarks.
 - Elevation of existing grade over utility at test hole location.
 - Horizontal location referenced to project coordinate datum.
 - Outside diameter of pipe or width of duct banks and configuration of non-encased multi-conduit systems.
 - Utility facility material(s).
 - Utility facility condition.
 - Coating/Wrapping information and condition.
 - Unusual circumstances or field conditions.
- 3.3.3 Excavate test holes in such a manner as to prevent any damage to wrappings, coatings, cathodic protection or other protective coverings and features. Water excavation can only be utilized with written approval from the appropriate State District Office.
- 3.3.4 Back fill all excavations with appropriate material, compact backfill by mechanical means, and restore pavement and surface material. The Engineer shall be responsible for the integrity of the backfill and surface restoration for a period of three years. Install a marker ribbon throughout the backfill.
- 3.3.5 Provide complete restoration of work site and landscape to equal or better condition than before excavation.
- 3.3.6 Plot utility location position information on the Utility Layout sheet and identify the vertical elevation and sealed by the responsible Surveyor. This information will be provided in the latest version of Micro Station or Geopak format used by the State. The electronic file will be delivered on C.D or DVD.

4. **DELIVERABLES:**

The deliverables to be specified in individual work authorizations for design surveys and construction surveys may be any combination of the following:

<u>YES</u>	<u>N/A</u>	4.1. Digital Terrain Models (DTM) in a format acceptable by the ENGINEER.
<u>YES</u>	<u>N/A</u>	4.2. Final H&V Field Book Binder with all pertinent information obtained in the field for Design Surveys. Maps, plans, or sketches prepared by the SURVEYOR showing the results of field surveys.
<u>YES</u>	<u>N/A</u>	4.3. Computer printouts or other tabulations summarizing the results of field surveys.
<u>YES</u>	<u>N/A</u>	4.4. Digital files or media acceptable by the ENGINEER containing field survey data.
<u>YES</u>	<u>N/A</u>	4.5. Maps, plats, plans, sketches, or other documents acquired from utility companies, private corporations, or other public agencies, the contents of which are relevant to the survey.
<u>YES</u>	<u>N/A</u>	4.6. Field survey notes, as electronic and/or hard copies.
<u>YES</u>	<u>N/A</u>	4.7. A H&V Control Book identifying the basis of the Primary and Secondary Control and an 8 1/2 inch by 11 inch survey control data sheet for each construction control point which shall include, but need not be limited to, a location sketch, a physical description of the point including a minimum of two reference ties, surface coordinates, a surface adjustment factor, elevation, and the horizontal and vertical datums used. Survey control data sheets shall be signed and sealed by the supervising Registered Professional Land Surveyor.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
SURVEYOR COUNTY

4. Deliverables (continued)

<u>YES</u> <u>N/A</u>	4.8. Final mylar set of 11 inch by 17 inch Survey Control data sheets sign and seal by the RPLS per TxDOT guidelines.
<u>YES</u> <u>N/A</u>	4.9. A digital and/or hard copy of all computer printouts of horizontal and vertical conventional traverses, GPS analysis and results, data including property descriptions with field notes and plats, right-of-way maps, and survey control data sheets to include in the H&V Field Book Binder.
<u>YES</u> <u>N/A</u>	4.10. Survey reports in a format requested by the ENGINEER.
<u>YES</u> <u>N/A</u>	4.11. Items indicated under the Automation Requirements Section 6.

5. GENERAL REQUIREMENTS:

- 5.1. Design surveys and construction surveys shall be performed under the supervision of a Registered Professional Land Surveyor currently registered with the Texas Board of Professional Land Surveying.
- 5.2. Horizontal ground control used for design surveys and construction surveys, furnished to the SURVEYOR by the ENGINEER or based on acceptable methods conducted by the SURVEYOR, shall meet the standards of accuracy required by the STATE.
- 5.3. Reference may be made to standards of accuracy for horizontal control traverses, as described in the FGCS Standards and Specifications for Geodetic Control Networks, latest edition, the TxDOT Survey Manual, latest edition, the TxDOT GPS Manual of Practice, latest edition, or the TSPS Manual of Practice for Land Surveying in the State of Texas, as may be applicable.
- 5.4. Vertical ground control used for design surveys and construction surveys, furnished to the SURVEYOR by the ENGINEER or based on acceptable methods conducted by the SURVEYOR, shall meet the standards of accuracy required by the ENGINEER.
- 5.5. Reference may be made to standards of accuracy for vertical control traverses, as described in the FGCS Standards and Specifications for Geodetic Control Networks, latest edition, the TxDOT Survey Manual, latest edition, the TxDOT GPS Manual of Practice, latest edition, or the TSPS Manual of Practice for Land Surveying in the State of Texas, as may be applicable.
- 5.6. Side shots or short traverse procedures used to determine horizontal and vertical locations shall meet the following criteria:
 - Side shots or short traverses shall begin and end on horizontal and vertical ground control as described above.
 - Standards, procedures, and equipment used shall be such that horizontal locations relative to the control may be reported within the following limits:
 - Bridges and other roadway structures: less than 0.1 of one foot.
 - Utilities and improvements: less than 0.2 of one foot.
 - Cross-sections and profiles: less than 1 foot.
 - Bore holes: less than 3 feet.
 - Standards, procedures, and equipment used shall be such that vertical locations relative to the control may be reported within the following limits:
 - Bridges and other roadway structures: less than 0.02 of one foot.
 - Utilities and improvements: less than 0.1 of one foot.
 - Cross-sections and profiles: less than 0.2 of one foot.
 - Bore holes: less than 0.5 of one foot.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
SURVEYOR COUNTY

5. **AUTOMATION REQUIREMENTS:**
 - 6.1 Planimetric design files (DGN) shall be fully compatible with the State's *Micro Station V8* graphics program without further modification or conversion.
 - 6.2 Electronically collected and processed field survey data files shall be fully compatible with the State's *CADD* systems without further modification or conversion. All files shall incorporate only those feature codes currently being used by the STATE.
 - 6.3 Digital Terrain Models (DTM) shall be fully compatible with the STATE's GEOPAK system without further modification or conversion. All DTM files shall be fully edited and rectified to provide a complete digital terrain model with all necessary break lines.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

ADDITIONAL RESPONSIBILITIES

A. TRAFFIC CONTROL:

The SURVEYOR shall control traffic in and near surveying operations adequately to comply with provisions of the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI and the latest edition of the Occupational Safety Manual both of which can be found on the TxDOT internet site.

In the event field crew personnel must divert traffic or close traveled lanes, a Traffic Control Plan based upon principles outlined in the latest edition of the TxDOT Manual on Uniform Traffic Control Devices – Part VI shall be prepared by the SURVEYOR and approved by the ENGINEER prior to commencement of field work. A copy of the approved plan shall be in the possession of field crew personnel on the job site at all times and shall be made available to the ENGINEER for inspection upon request.

B. INVOICING:

Payment requests shall include a SURVEYOR's invoice. With each payment request, the SURVEYOR shall submit a project status report which will, as a minimum, include the percentage of total work complete as of the date of the payment request and a description of current work activity. The percentage of total work complete shall not be based simply on the percentage of funds expended, but shall be based on the best judgment of the SURVEYOR as to the percentage of actual work complete.

C. EASEMENTS, LETTERS OF PERMISSION, ETC.

The SURVEYOR shall be responsible for delineating easements. The SURVEYOR will be responsible for securing the necessary legal instruments and obtaining all Right-of-Entries (ROEs).

D. MEETINGS:

The ENGINEER shall setup the necessary meetings with the SURVEYOR in order to assure all field information is provided on-time and products are delivered in accordance with TxDOT's specifications. SURVEYOR must attend all meetings involving data provided if requested by ENGINEER.

E. PROJECT MANAGER/SURVEYOR COMMUNICATION:

The SURVEYOR shall designate one Texas Registered Professional Land Surveyor (RPLS) to be responsible throughout the project for project surveying coordination and all communications, including billing, with the ENGINEER.

F. OFFICE LOCATION:

The SURVEYOR will perform the services to be provided under this agreement out of a local office and have a crew available to perform requested tasks within 24 hours of request. The coordinating SURVEYOR's Project Manager (RPLS) shall be accessible at all times and working from the local office.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 7 - ROADWAY DESIGN CONTROLS

(Function Code 160)

Services
Provided By:
ENGINEER COUNTY

YES
NO

N/A
N/A

1. Geometric Design

- a. Horizontal and Vertical Alignment (Preliminary based on office surveys)
- b. Schematic Layout
 - (1) The location of interchanges, main lanes, grade separations, frontage roads and ramps.
 - (2) Develop vertical and horizontal alignment of main lanes, ramps and cross roads at proposed interchanges or grade separations. Frontage road alignment data need not be shown on the schematic; however, it should be developed in sufficient detail to determine ROW needs. The degree of horizontal curves and vertical curve data, including "K" values, shall also be shown for ease of checking.
 - (3) For freeways, show the location and text of the proposed main lane guide signs. Lane lines and/or arrows indicating the number of lanes shall also be shown.
 - (4) A complete explanation of the sequence and methods of stage construction, if proposed, including the initial and ultimate proposed treatment of crossovers and ramps.
 - (5) The tentative ROW limits.
 - (a) Provide a roadway Design System (RDS) or (GEOPAK) computer tape of the preliminary earthwork to verify ROW requirements.
 - (b) Provide a graphics file containing the approved schematic.
 - (6) The geometric (pavement cross slopes, lane and shoulder widths, slope rates for fills and cuts) of the typical sections of proposed highway main lanes, ramps, frontage roads, and cross roads.
 - (7) The current and projected traffic volumes as provided by the TxDOT (20 year traffic projection, unless otherwise determined by the District Engineer).
 - (8) The control of access lines if Interstate or designated under House Bill 179.
 - (9) Direction of traffic flow on all roadways.
 - (10) Location and width of median openings for highway without access control.
 - (11) The geometric of speed change (acceleration, deceleration, climbing) lanes.

YES

N/A

2. General Guidelines for Project Development

- a. Prior to preparing detailed plans for a proposed project, a preliminary schematic layout shall be prepared which indicates the general geometric features and location requirements peculiar to the project. An uncontrolled aerial mosaic will be provided for this use. Four copies of the schematic layout shall be submitted through the district to the Design Division for approval and subsequent coordination with the Federal Highway Administration (FHWA) where applicable. The layout shall be submitted for two-lane arterial highway projects on new locations and for all multi-lane highway projects. **No geometric design is to be performed until the COUNTY has given the engineer written approval of the preliminary schematic layout.**
- b. All geometric design shall be in conformance with the State's Design Division, Operations and Procedures Manual, except where variances are permitted in writing by the STATE.
- c. The schematic layout shall include basic information which is necessary for the proper review and evaluation including the items listed above in the checklist for schematic layout.
- d. Handling of traffic during construction shall be a consideration in the development of preliminary designs.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
<u>YES</u>	<u>N/A</u>	2. General Guidelines for Project Development (<i>continued</i>)
		e. Upon approval of the schematic layout by Design Division (FHWA on Federal-aid projects), it shall be the basis for an exhibit at any required public hearing prior to final development of the project. If there are any changes to the schematic after the Design Division and FHWA approval and before the public hearing, four copies of the revised schematic, as displayed at the hearing, shall be submitted either prior to or accompanying the public hearing data. If there are no changes in the schematic as displayed at the hearing, only photographs of the schematic and other displays shall be submitted with the public hearing data.
		f. For all freeway construction projects, these schematics shall show the location and text of the proposed main lane guide signs. A schematic layout shall be submitted through the district to the Traffic Operations Division, Traffic Safety Section for approval and subsequent coordination with the FHWA. All signing shall be in conformance with the Texas MUTCD.
		g. On complex projects, informal contact through the district with the Design Division and FHWA personnel is encouraged with regard to development of preliminary design prior to official schematic submission.
		h. The engineer shall furnish a project tape that is compatible with the STATE's computer system, a project listing, and a cross section plot showing the original design sections containing the earthwork input and original cross sections for the project. Accuracy of the earthwork design is of utmost importance since it is the basis for contractor payments and construction staking.
<u>N/A</u>	<u>N/A</u>	3. Exhibit for Airway/Highway Clearance Permits
<u>NO</u>	<u>N/A</u>	4. Grading Design
		a. Refine the horizontal and vertical alignment of main lanes, frontage roads, ramps, cross roads and direct connectors based upon the approved schematic layout. Determine vertical clearances at grade separations and overpasses, taking into account the appropriate super elevation rate.
<u>YES</u>	<u>N/A</u>	b. Typical Sections
<u>YES</u>	<u>N/A</u>	c. Design Cross Sections
<u>YES</u>	<u>N/A</u>	d. Determine Cut and Fill Quantities
<u>N/A</u>	<u>N/A</u>	e. Slope Stability Analysis
<u>N/A</u>	<u>N/A</u>	f. Embankment Foundation Stability Analysis
<u>N/A</u>	<u>N/A</u>	g. Embankment Settlement Analysis
<u>NO</u>	<u>N/A</u>	5. Pavement Design
		a. Prior to initiating detailed plan preparations for a project, a preliminary investigation shall be made to determine the approximate section and pavement type to be used for the pavement structure. The Flexible Pavement Design Manual for flexible pavement, "Appendix F" of the Design Division, Operations and Procedures Manual, and the current AASHTO Guide for the Design of Pavement Structures, may be used for this purpose.
<u>YES</u>	<u>N/A</u>	b. The typical section shall also reflect proposed geometric including pavement cross slopes, lane and shoulder widths, and slope rates whenever this data have not been previously shown on a schematic submission.
		c. Embankment and Subgrade
<u>N/A</u>	<u>N/A</u>	(1) Soil Core Holes (Show cost estimate with Function Code 110)
<u>N/A</u>	<u>N/A</u>	(a) Along center line
		(b) Along center line of each roadway
		The location and minimum number of soil core holes required for this project are as follows: (To be determined when schematic is being completed)

EXHIBIT "B" SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER ---

Services
 Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	5. Pavement Design (<i>continued</i>)
		c. Embankment and Subgrade (<i>continued</i>)
		(2) Identify, interpret and summarize geologic features that affect engineering design (PI, Sulfate content, % of lime)
<u>NO</u>	<u>N/A</u>	d. Traffic Data for Pavement Design by STATE
<u>NO</u>	<u>N/A</u>	e. Basic Design Criteria
<u>NO</u>	<u>N/A</u>	f. Life Cycle Cost Analysis(es)
<u>NO</u>	<u>N/A</u>	g. Cost Data
<u>NO</u>	<u>N/A</u>	h. Pavement Material Properties
<u>NO</u>	<u>N/A</u>	i. Rehabilitation Investigations
<u>NO</u>	<u>N/A</u>	(1) Core Hole Survey (Show cost estimate with Function Code 110)
		(a) Determine type and depth of existing material, pavement, etc. The Engineer will determine whether to salvage ACP and FLEXBASE as well as their properties and provide this information to TxDOT.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 8 - DRAINAGE

(Function Code 161)

Services
Provided By:
ENGINEER COUNTY

All hydraulic design shall be in accordance with the TxDOT's Hydraulic Manual, except where variances are permitted in writing by the COUNTY.

<u>NO</u>	<u>NO</u>	1. Hydrologic Studies, Discharges
<u>YES</u>	<u>N/A</u>	a. Hydrologic map showing drainage areas, contours and drainage Q's.
<u>YES</u>	<u>N/A</u>	b. Drainage area maps showing existing conditions and proposed improvements.
		c. Hydrologic data/discharge determination
		2. Hydraulic Drainage Study and Documentation
<u>NO</u>	<u>N/A</u>	a. Hydraulic computations
<u>YES</u>	<u>N/A</u>	(1) Storm water detention available within the ROW (linear ft. along side drain ditch).
<u>YES</u>	<u>N/A</u>	(2) Storm water detention required outside the ROW (as per HCDD#1)
<u>NO</u>	<u>N/A</u>	(3) Culverts
<u>YES</u>	<u>N/A</u>	(4) Bridge waterways
<u>YES</u>	<u>N/A</u>	(5) Channels
<u>NO</u>	<u>N/A</u>	(6) Storm sewers/inlets
<u>YES</u>	<u>N/A</u>	(7) Pump stations
<u>YES</u>	<u>N/A</u>	(8) Storm Water Management facilities
<u>YES</u>	<u>N/A</u>	(9) Other
		(a) Irrigation Canals/Siphons
<u>NO</u>	<u>N/A</u>	b. Hydraulic report(s)
<u>YES</u>	<u>N/A</u>	c. Federal Emergency Management Agency (FEMA) floodway requirements
<u>YES</u>	<u>N/A</u>	d. Determine impact of proposed drainage plan on the following receiving stream(s)
		(1) Hidalgo County Drainage District Outfalls
		(2) All Irrigation District Outfalls impacted
		3. Layout, Structural Design and Detailing of Drainage Features
<u>YES</u>	<u>N/A</u>	a. Culverts
<u>NO</u>	<u>N/A</u>	(1) New culverts
<u>YES</u>	<u>N/A</u>	(2) Culvert widening and/or lengthening
		(3) Culvert replacements
<u>YES</u>	<u>N/A</u>	b. Storm sewers
<u>NO</u>	<u>N/A</u>	(1) New storm sewers
<u>YES</u>	<u>N/A</u>	(2) Modify existing storm sewers
<u>YES</u>	<u>N/A</u>	(3) Inlets
<u>YES</u>	<u>N/A</u>	(4) Manholes
<u>NO</u>	<u>N/A</u>	(5) Trunk lines
<u>NO</u>	<u>N/A</u>	c. Pump stations
<u>NO</u>	<u>N/A</u>	d. Subsurface drainage at retaining walls
<u>NO</u>	<u>N/A</u>	e. Outfall channel(s) within the ROW
<u>YES</u>	<u>N/A</u>	f. Outfall channel(s) outside the ROW
<u>NO</u>	<u>N/A</u>	g. Detention Pond(s) within the ROW
<u>NO</u>	<u>N/A</u>	h. Detention Pond(s) outside the ROW
<u>YES</u>	<u>N/A</u>	i. Summary of Quantities
<u>NO</u>	<u>N/A</u>	j. Storm Water Management facilities
<u>YES</u>	<u>N/A</u>	4. Storm Water Pollution Prevention Plan (SW3P)
<u>NO</u>	<u>N/A</u>	5. Scour Evaluation - Waterway Structures only (to be completed by Bridge Engineer under FC 170.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 9 - SIGNING, MARKINGS AND SIGNALIZATION

(Function Code 162)

Services
Provided By:
ENGINEER COUNTY

<u>YES</u>	<u>N/A</u>	1. Signing and Markings Layout
		a. Requirements (Separate Layout)
		(1) Roadway layout
		(2) Center line with station numbering
		(3) ROW lines
		(4) Culverts and other structures that present a hazard to traffic
		(5) Location of utilities, if not shown on plan and profile
		(6) Existing signs to remain, to be removed, to be relocated
		(7) Proposed signs (illustrated and numbered)
		(8) Existing overhead sign bridges to remain, to be revised, removed or relocated
		(9) Proposed overhead sign bridges indicating location by plan layout (electrical details need not be shown on this layout)
		(10) Proposed markings (illustrated and quantified) which include pavement markings, object markings and delineation
		(12) Quantities of existing pavement markings to be removed
		(13) Proposed delineators and object markers
		b. For projects involving freeway to freeway or other types of directional interchanges, projects including left-hand ramps or connections, the following information must be provided:
		(1) The location of interchanges, main lanes, grade separations, frontage roads and ramps
		(2) complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps
		(3) The number of lanes in each section of proposed highway and the location of changes in numbers of lanes
		(4) The projected traffic volumes as provided by the STATE (20 year traffic projection, unless otherwise determined by the District Engineer)
		(5) Tentative ROW limits
		(6) Direction of traffic flow on all roadways
		(7) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations
<u>YES</u>	<u>N/A</u>	2. Summary of Small Signs Tabulation
<u>NO</u>	<u>N/A</u>	3. Summary of Large Signs Tabulation including all Guide Signs
<u>YES</u>	<u>N/A</u>	4. Sign Detail Sheets
		a. All signs except route markers
		b. Design details for large guide signs
		c. Dimensions of letters, shields, borders, corner radii etc.
		d. Designation of shields attached to guide signs
		e. Designation of arrow used on exit direction signs

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
 Provided By:
ENGINEER COUNTY

		5. Traffic Signals
		a. Development of Justification (Warrant) Data
<u>YES</u>	<u>N/A</u>	(1) Location Map Relationship of proposed installation to other traffic signals, highways, business areas and traffic generators
<u>YES</u>	<u>N/A</u>	(2) Photographs as appropriate
<u>YES</u>	<u>N/A</u>	(3) Accident data as appropriate
		(4) Vehicle volumes (provided by TxDOT)
<u>N/A</u>	<u>N/A</u>	(a) Existing
<u>N/A</u>	<u>N/A</u>	(b) Estimated
<u>N/A</u>	<u>N/A</u>	(c) Projected
<u>N/A</u>	<u>N/A</u>	(d) Pedestrian
<u>N/A</u>	<u>N/A</u>	(5) Traffic Survey - Count Analysis
<u>N/A</u>	<u>N/A</u>	(6) Recommendation based on above data
<u>NO</u>	<u>N/A</u>	b. Layout
		(1) Title Sheet (when applicable)
		(a) Describe the location
		(b) Type of installation
		(c) Area map with project limits for each location
		(d) Index of sheets
		(e) Space for official signatures
		(2) Estimate and quantity sheet (when applicable)
		(a) List of all bid items
		(b) Bid item quantities
		(c) Specification item number
		(d) Paid item description and unit of measure
		(3) Basis of estimate sheet (list of materials)
		(4) General notes and specification data sheet
		(5) Condition diagram
		(a) Highway and intersection design features
		(b) Roadside development
		(c) Traffic control including illumination
		(6) Plan sheet(s)
		(a) Existing traffic control that will remain (signs and markings)
		(b) Existing utilities
		(c) Proposed highway improvements
		(d) Proposed installation
		(e) Proposed additional traffic controls
		(f) When applicable, proposed conduit for Railroad interconnect with standard details for runs under tracks.
		(g) Proposed illumination attached to signal poles.
		(7) Notes for plan layout
		(8) Elevation sheet(s) (span wire design)
		(9) Phase sequence diagram(s)
		(a) Signal locations
		(b) Signal indications
		(c) Phase diagram
		(d) Signal sequence table
		(e) Flashing operation (normal and emergency)
		(f) Preemption operation (when applicable)
		(g) Interval timing, cycle length and offset

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>NO</u>	<u>N/A</u>	5. Traffic Signals <i>(continued)</i>
		b. Layout <i>(continued)</i>
		(10) Construction detail sheets(s)
		(a) Poles (TxDOT standard sheets)
		(b) Detectors
		(c) Pull Box and conduit layout
		(d) Controller Foundation standard sheet
		(11) Marking details (when applicable)
		(12) Barricade and warning sign standard sheet and any special details for work zone traffic control for special conditions
		(13) Aerial or underground interconnect details (when applicable)
		c. General Requirements
		(1) Contact local utility company
<u>NO</u>	<u>N/A</u>	(a) Confirm power source
<u>NO</u>	<u>N/A</u>	(b) Discuss route of aerial or underground interconnect cable (when applicable)
<u>N/A</u>	<u>N/A</u>	(c) Adjustment of overhead utility lines
<u>NO</u>	<u>N/A</u>	(2) Prepare governing specifications and special provisions list
<u>NO</u>	<u>N/A</u>	(3) Prepare project estimate
<u>NO</u>	<u>N/A</u>	d. Summary of Quantities

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 10 - MISCELLANEOUS (ROADWAY)

(Function Code 163)

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u> <u>N/A</u>	1. Retaining Walls a. Structural Details (1) Cast-in-Place Cantilever at _____ locations. (TxDOT Standard Retaining Wall)* (2) Tiedback Retaining Wall at _____ location. (TxDOT standard retaining wall) (3) Specialized Retaining Wall at _____ locations (Unique Design).* b. Alternate Patented Retaining Walls at all locations. (Layouts Only)** (1) Mechanically Stabilized Earth (2) Concrete Block Wall Systems c. Retaining Wall Layout (PLAN) (1) Designation of reference line (2) Beginning and ending retaining wall stations (3) Station of each retaining wall joint*** (4) Offset from reference line (5) Horizontal curve data (6) Number of retaining wall panels and lengths*** (7) Total length of wall (8) Indicate face of wall (9) All wall dimensions and alignment relations (alignment data as necessary) (10) Soil core hole locations d. Retaining Wall Layout (ELEVATION) (1) Top of wall elevations at each joint or intervals*** (2) Existing and finished ground line elevations (3) Height of stem at each joint*** (4) Wall panel designations*** (5) Top of footing elevations*** (6) Limits of measurement for payment**** (7) Type, limits and anchorage details of railing (If applicable) (8) Top and bottom of wall profiles and soil core hole data plotted at correct station and elevation. The plot shall be at the same scale as the wall profile. Ground water elevations and the observation date shall be shown. e. Foundation Studies (Show cost estimate with Function Code 110) (1) The soil core holes shall be obtained at approximately 200 foot intervals along retaining wall alignments. The core holes shall extend 25 feet below the footing elevation. f. Stability Analysis (the ENGINEER shall estimate this task as part of his bid to complete the work). g. Estimate h. Summary of Quantities i. Typical X-section. j. General Guidelines for Retaining Walls (1) The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. The designer and checker shall check all calculations and initial each page. (2) The ground water level should be observed at the water strike. (3) For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual. (4) Foundation exploration shall conform to the requirements set forth in Administrative Circular No. 25-84, Administrative Circular 33-87 and Administrative Circular No. 25-92.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
<u>YES</u>	<u>N/A</u>	2. Traffic Control Plan, Detours and Sequence of Construction Traffic Control Plans (TCP) are required for all projects. A detailed TCP shall be developed when traffic handling during construction involves complications for which a feasible solution is not covered by the Texas MUTCD or the current Barricade and Construction (BC) Standards. The following items are required on all Traffic Control Plan Layouts: a. The sequence of construction and method of handling traffic during each phase. b. The existing and proposed traffic control devices that will be used to handle traffic during each construction sequence. Include signals, regulatory signs, warning signs, construction warning signs, guide signs, route markers, construction pavement markings, channelizing devices, portable changeable message signs, flashing arrow boards, barricades, barriers, etc. c. The proposed traffic control devices (stop signs, signals, flag person, etc.) at grade intersections during each construction sequence. d. Where detours are provided, typical cross sections shall be shown. e. Road construction work hours shall be developed after an investigation of the traffic volumes has been performed.
<u>N/A</u>	<u>N/A</u>	3. Illumination a. Preliminary Roadway Illumination Layout and Circuit Layout (1) For projects involving freeway to freeway or other types of directional interchanges and projects including left-hand ramps or connections, provide the following: (a) The location of interchanges, main lanes, grade separations, frontage roads and ramps (b) A complete explanation of the sequence and methods of stage construction, where applicable, which would include the initial and ultimate proposed treatment of crossovers and ramps (c) The number of lanes in each section of proposed highway and the location of changes in the number of lanes (d) The projected traffic volumes as provided by the STATE (20 year traffic projection unless otherwise determined by the district engineer) (e) Tentative ROW limits (f) Direction of traffic flow on all roadways (g) Main lane, ramp, frontage road, and necessary cross road profiles at proposed interchanges or grade separations b. Final Roadway Illumination and Electrical Circuit Layouts (1) Roadway layout showing pavement edges, shoulders, curbs, retaining walls, etc. (2) Center line with station numbering. (3) ROW lines. (4) Symbol legend. Use department standard symbols for lighting and electrical. (5) Culverts and other structures that present a hazard to traffic. (6) Location of underground utilities, if not shown on plan profile. (7) Location of overhead electrical lines, both crossing and parallel to ROW. (8) Existing sign lighting circuits and roadway illumination to remain, to be removed, to be relocated. (9) Existing service poles, electrical circuits, ground boxes, etc. (10) Contact electric utility for service pole locations, voltage characteristics. (11) Location of proposed sign lighting circuits and roadway illumination. (12) Proposed electrical circuits. (13) Tabulation of all quantities including proposed, existing to be relocated, existing to be removed. The layout sheet quantities and lighting summary shall be shown. Tabulations to include estimated quantity with a column for final quantities.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services Provided By:		
<u>ENGINEER</u>	<u>COUNTY</u>	
<u>N/A</u>	<u>N/A</u>	3. Illumination (<i>continued</i>)
		c. General Guidelines for Illumination (If applicable)
		The ENGINEER shall submit to the COUNTY, well in advance of PS&E due date, the roadway illumination and electrical circuit layout sheets for review by the STATE. Two copies of the layout sheets are to be submitted. One copy will be returned to the Engineer showing corrections that are to be made by the ENGINEER. When final plan submission is made, the ENGINEER shall provide a written statement regarding completion of the corrections.
<u>YES</u>	<u>N/A</u>	4. Miscellaneous Drafting/Standards
<u>N/A</u>	<u>N/A</u>	a. Erosion Control
		b. Landscape Development
<u>YES</u>	<u>N/A</u>	5. Compute and Tabulate Quantities
<u>YES</u>	<u>N/A</u>	6. Special Utility Details (Irrigation lines)
		7. Miscellaneous Structures
		a. Type of Structure*
		(1) Overhead Sign Bridges (O.S.B.)
		Modifications or special O.S.B. designs shall be prepared using the same design assumptions that are used for the standard O.S.B structures.
<u>N/A</u>	<u>N/A</u>	(a) New O.S.B. structure(s)
<u>N/A</u>	<u>N/A</u>	(b) Structural evaluation of existing O.S.B. structure(s) that are to remain in place or to be relocated.
<u>N/A</u>	<u>N/A</u>	(2) High Mast Illumination Poles (HMIP)
<u>N/A</u>	<u>N/A</u>	(3) Traffic Signal Supports
<u>N/A</u>	<u>N/A</u>	(4) Conventional Illumination Poles
<u>N/A</u>	<u>N/A</u>	(5) Sound Barrier Walls
<u>N/A</u>	<u>N/A</u>	b. Checklist for Layouts
		(1) Reference appropriate O.S.B. standard
		(2) Drilled shaft size and length
		(3) Soil strength used for design {indicate basis and boring(s) used}
		(4) Design height
		(5) Tower heights
		(6) Leg spacings
		(7) Design wind speed
<u>N/A</u>	<u>N/A</u>	c. Foundation Studies (Show cost estimate with Function Code 110)
		The soils exploration requirements for miscellaneous structures on this project are as follows: (To be provided by the Engineer on an as-needed basis)
		8. Agreements
<u>N/A</u>	<u>N/A</u>	a. Utility Agreements
<u>N/A</u>	<u>N/A</u>	b. Exhibits for Utility Agreements
<u>N/A</u>	<u>N/A</u>	c. Railroad Agreements
		d. Railroad Exhibits
<u>N/A</u>	<u>N/A</u>	(1) Railroad Underpasses
<u>N/A</u>	<u>N/A</u>	(2) Railroad Overpasses
<u>N/A</u>	<u>N/A</u>	(3) Railroad Grade Crossing (Replanking)
<u>N/A</u>	<u>N/A</u>	(4) Railroad Grade Crossing Warning Systems (Signals)
<u>N/A</u>	<u>N/A</u>	(5) Other Miscellaneous Sketches for Railroads
<u>N/A</u>	<u>N/A</u>	e. Traffic Signal Agreements
<u>N/A</u>	<u>N/A</u>	f. Exhibits for Traffic Signal Agreements
<u>YES</u>	<u>N/A</u>	9. Estimate
<u>YES</u>	<u>N/A</u>	10. Specifications and General Notes

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

SECTION 11 - BRIDGE DESIGN

(Function Code 170)

Services
 Provided By:
ENGINEER COUNTY

			NUMBER REQUIRED
		1. Preparation of Structural Details	
		a. New Structure(s)	
<u>N/A</u>	<u>N/A</u>	(1) Underpass(es)	_____
<u>N/A</u>	<u>N/A</u>	(2) Overpass(es)	_____
<u>N/A</u>	<u>N/A</u>	(3) Main Lanes	_____
<u>N/A</u>	<u>N/A</u>	(4) Direct Connector(s)	_____
<u>N/A</u>	<u>N/A</u>	(5) Ramp Bridge(s)	_____
<u>N/A</u>	<u>N/A</u>	(6) Waterway Structure(s)**	_____
<u>N/A</u>	<u>N/A</u>	(7) Pedestrian Structure(s)	_____
<u>N/A</u>	<u>N/A</u>	(8) Utility Structure(s)	_____
<u>N/A</u>	<u>N/A</u>	(9) Railroad Underpass(es)	_____
<u>N/A</u>	<u>N/A</u>	(10) Railroad Overpass(es)	_____
<u>N/A</u>	<u>N/A</u>	(11) Bridge Classification Culvert(s)**	_____
<u>N/A</u>	<u>N/A</u>	(11) Alternate Structural Designs	_____
<u>N/A</u>	<u>N/A</u>	(12) Alternate Foundation Design	_____
		Total New Structures =	_____
		b. Existing Structure(s)	_____
<u>N/A</u>	<u>N/A</u>	(1) Bridge Widening, Rehabilitation and/or Modification of Existing Structure(s)	_____
<u>N/A</u>	<u>N/A</u>	(2) Bridge Replacement	_____
<u>N/A</u>	<u>N/A</u>	(3) Raising Bridge Elevation	_____
<u>N/A</u>	<u>N/A</u>	(4) Bridge Classification Culvert(s) Widening and/or Modification of Existing Structures(s)	_____
<u>N/A</u>	<u>N/A</u>	(5) Railroad Overpass(es)	_____
<u>N/A</u>	<u>N/A</u>	(6) Railroad Underpass(es)	_____
		Total Existing Structures =	_____

* Contour plots of bridge gores are required for projects involving ramps within the main bridge in order to ensure project transition. The Template data and vertical alignment necessary to generate the contour plots are also required.

** In the early stages of a project, it sometimes cannot be determined whether a Waterway Bridge Structure or a Bridge Classification Culvert (20' minimum length) will be required. Therefore, the ENGINEER should be aware that either of these two types of bridges may be reclassified later in the project for the other type when more information is known that would dictate a change in structure classification.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

- N/A N/A 2. Preparation of Bridge Layouts (each bridge)
- a. Bridge Layouts (PLAN)
- (1) Horizontal curve information or bearing of centerline.
 - (2) Including horizontal, vertical, and template information of all roadways or railroads crossed.
 - (3) Bearing of center line or reference line.
 - (4) Skew angle(s).
 - (5) Slope for header banks and approach fills.
 - (6) Control stations at beginning and ending of bridge (with deck elevation), intersections, etc.
 - (7) Approach pavement and crown width.
 - (8) Bridge roadway width and curbs, face of rail, shoulders, or sidewalks.
 - (9) Approach slab and curb returns.
 - (10) Limits and type of riprap.
 - (11) Proposed features under structure.
 - (12) Location of profile grade line.
 - (13) North arrow.
 - (14) Typical bridge roadway section including preliminary proposed beam types and spacings.
 - (15) Cross slope and super elevation data.
 - (16) Minimum horizontal clearances when applicable.
 - (a) Dimensions to features that control clearances. (Calculate and indicate points of minimum vertical and horizontal clearances.
 - (17) Location of soil core holes (station and offset), shown on layout.
 - (18) Bent stations and bearings.
 - (19) Retaining wall locations.
 - (20) Traffic flow directional arrows.
 - (21) Railing types shown.
 - (22) Joint types and seal size, if used.
 - (23) Beam line numbers consistent with span details.
 - (24) Critical horizontal clearances (location of railroad tracks, nearby structures and utilities).
 - (25) Bearings of utilities.
- b. Bridge Layouts (ELEVATION)
- (1) Type of foundation.
 - (2) Finished grade elevations at beginning and end of bridge.
 - (3) Overall length of structure.
 - (4) Length, type of spans and units.
 - (5) Type of railing.
 - (6) Minimum calculated vertical clearance(s).
 - (7) Existing and proposed ground lines clearly marked.
 - (8) Grid elevations and stations.
 - (9) Bent numbers encircled.
 - (10) Stationing of bridge compatible with grid stations.
 - (11) Standard title.
 - (12) Profile grade data.
 - (13) Type of riprap.
 - (14) Soil Core Hole information with penetrometer test data shall be shown on the bridge layout at correct station, elevation and scale.
 - (15) Fixed/expansion condition of all bents.
 - (16) Column "H" heights.
 - (17) Number, size and length of foundations.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

<u>N/A</u>	<u>N/A</u>	2. Preparation of Bridge Layouts (each bridge) <i>(continued)</i> c. Additional layout requirements for waterway structures and bridge classification culverts. (1) Design and 100-year peak discharges. (2) Design and 100-year high water (HW) (Recorded HW and date if available) (3) Natural and through-bridge velocities for design and 100-year floods. (4) Calculated backwater for design and 100-year floods. (5) Direction of flow for waterway crossings. (6) Contours for water crossing.
<u>N/A</u> <u>N/A</u>	<u>N/A</u> <u>N/A</u>	3. Bridge Classification Culvert, Estimate, Quantities, and Specifications (each bridge) 4. Foundation Studies (Show cost estimate with Function Code 110) The minimum number of soil core holes shall be obtained in accordance with Section 1-301 of the Bridges and Structures Foundation Exploration and Design Manual. Soil core holes shall be obtained at approximately (300 foot) intervals along bridge alignments. Texas cone penetrometer (TCP) tests shall be conducted in all soil types encountered at a maximum of (10 foot) intervals. If single column bents with single drilled shafts are planned, TCP values should be taken at close intervals in the upper (15 feet).
<u>N/A</u> <u>N/A</u> <u>N/A</u>	<u>N/A</u> <u>N/A</u> <u>N/A</u>	5. Bridge Total Quantities and Cost Estimates (each bridge) 6. Bridge Special Provisions and Specifications (each bridge) 7. Bearing seat elevations for each beam or girder. Top of cap elevations for non-beam type structures.
<u>N/A</u>	<u>N/A</u>	8. General Guidelines for Bridge Design a. The ENGINEER shall prepare a bridge layout of each bridge structure for Company's review and approval. The bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures, Detailing Manual. Soil core hole data is not required for submission of the preliminary bridge layout. No bridge design work is to be performed until the COUNTY has given the engineer written approval of the preliminary bridge layout.

Several months may be required, after the preliminary bridge layout is submitted, for the district to obtain approval and/or permits from the following:

- TxDOT Design Division, when applicable:
 - Railroad Companies
 - FHWA
 - U.S. Army Corps of Engineers
 - U.S. Coast Guard
 - Bureau of Reclamation
 - Texas Parks and Wildlife
 - Others

Therefore, the bridge layout should be submitted at the earliest possible date and the ENGINEER's design schedule should reflect this.

- b. All bridge superstructure and substructure design will be reviewed by the Design Division for purposes of verifying structural integrity and optimization of design.
- c. The final bridge layout shall be in conformance with the Bridges and Structures, Operation and Planning Manual and the Bridges and Structures Detailing Manual.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Services
Provided By:
ENGINEER COUNTY

8. General Guidelines for Bridge Design (*continued*)

- d. The ENGINEER shall make final design calculations and final detail drawings in accordance with standard requirements of the Texas Department of Transportation. All bridge design shall be in conformance with the Texas Department of Transportation Bridges and Structures Operation and Planning Manual, the current American Association of State Highway and Transportation Officials or American Railway Engineers Association Specifications for railway structures, Standard Specifications for Highway Bridges, including applicable interim specifications, and the Bridges and Structures, Foundation Exploration and Design Manual. The ENGINEER shall furnish design calculations to the Design Division. **The designer and checker shall check all calculations and initial each page.**
- e. Structural steel or prestressed concrete shop drawings, form work drawings and false work drawings are not part of the design requirements. However, contract plans shall be in sufficient detail to permit the preparation of complete shop details for fabrication and erection.
- f. Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a metric scale of 1:20 (1/2 inch equals one foot architect scale) or 1:50 (1/4 inch equals one foot architect scale) to provide clear legible drawings when the drawings are reduced. Lettering shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
- g. Standard drawings for beams, diaphragms, railings, armor joints, riprap, etc., shall be furnished to the ENGINEER upon request. These standards shall not be redrawn by the ENGINEER nor shall his title block be transferred to the standard drawings. Modifications to the standards, if necessary, shall be clearly identified and designated by "MOD" in the standard title. Specific special drawings prepared by the ENGINEER shall not be identified as standards.
- h. Bridge layout sheets shall have the same vertical and horizontal scale. Usually a metric scale of 1:100 (1 inch = 10 feet) or 1:200 (1 inch = 20 feet) is used. Sections of existing and proposed structures usually have a metric scale of 1:50 (1 inch = 5 feet). Soil core holes shall be positioned and labeled on the bridge layout plan view. The core hole data shall be plotted at the correct station, at the same vertical scale, and at the proper elevation unless otherwise approved by the Design Division.
- i. APPENDIX C, "GENERAL PLAN CHECKLIST", on pages C-1 thru C-5, more specifically relates various sheet types, details, summaries, standards, etc.
- j. For purposes of uniformity statewide, soil core hole data shall be shown on layouts as illustrated in the Bridges and Structures Foundation Exploration and Design Manual.
- k. Geometry and structural design errors found after acceptance of bridge plans shall be promptly corrected by the consultant at no cost to the Company.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

ADDITIONAL RESONSIBILITIES

Easements, Letters of Permission, Etc.

The ENGINEER shall be responsible for delineating easements. The ENGINEER will be responsible for securing the necessary legal instruments.

Coordination of Utilities

The ENGINEER shall furnish the COUNTY prints of a project layout which will be distributed by ENGINEER to various utility companies to determine which utilities are in the limits of the project. These shall be preliminary layouts. Upon completion of the preliminary drainage plans and U&D sheets, the ENGINEER shall distribute to the various utility companies and request return. Upon return of these prints, the ENGINEER will schedule a meeting with the various utility companies to discuss potential conflicts and conformance with the State's Utility Accommodation Policy. The ENGINEER is responsible for coordination with the various utility companies for exposing potential conflicts and field ties to uncover utilities in potential conflict areas.

Meetings

Meetings will be held with the FHWA, State Officials, local governments, property owners, utility owners, railroad companies, other consulting firms, etc., as needed or required by the COUNTY. The ENGINEER shall coordinate through the COUNTY for the development of this project with any local entity having jurisdiction or interest in the project (i.e., city, county, etc).

Specifications, Special Provisions, Special Specifications

Use the State's standard specifications or previously approved special provisions and/or special specifications. If a special provision and/or special specification is developed for this project, it shall be in the State's format and incorporate references to approved State test procedures.

Project Manager/Engineer Communication

The ENGINEER shall designate one Texas Registered Professional Engineer to be responsible throughout the project for project management and all communications, including billing, with the COUNTY's Director. Any replacements to the ENGINEER's designated Project Manager/Engineer must be approved by the COUNTY.

Engineering documents produced for the department's engineering projects shall be signed, sealed and dated or CADD sealed in accordance with Administrative Order No. 5-89 and Administrative Circular No. 26-91.

Design Responsibilities

The ENGINEER is responsible for design errors and/or omissions that become evident before, during or after construction of the project. The ENGINEER's responsibility for all questions arising from design errors and/or omissions will be determined by the COUNTY and all decisions shall be final and binding. This would include, but not necessarily be limited to:

1. All design errors and/or omissions resulting in additional design work to correct the errors and/or omissions.
2. Preparation of design documents and detail drawings necessary for a field change due to design errors and/or omissions.
3. Revision of original tracings to the extent required for a field change due to design errors and/or omissions.

The ENGINEER shall promptly make necessary revisions or corrections resulting from the ENGINEER's errors, omissions or negligent acts without additional compensation. Acceptance of the work by the COUNTY will not relieve the ENGINEER of the responsibility for subsequent correction of any such errors or omissions or for clarification of any ambiguities.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

Document and Information Exchange

Data, Plan Sheets, General Notes and/or Specifications provided to the COUNTY shall be furnished on 8GB USB flash drives. Each 8 GB flash drive shall have a file titled Table of Contents. The Table of Contents shall indicate the locations of files within the directory structure of the documentation.

General Notes and specifications shall be provided in MS Office 2007 format. Plan sheets shall be provided in Microstation DGN or GEOPAK GPK format. PDF copies of plan sheets shall also be provided.

Two copies of the documentation shall be provided to the COUNTY.

If required, the ENGINEER shall provide to the COUNTY, a CD that contains all the plan sheets for the project. The graphics tape shall be compatible with the COUNTY's computer system.

CD Tape Required (YES or NO): YES

Proposal Time

The time indicated in the proposal and the contract shall include time necessary for reviews, approval, etc.

Office Location

The ENGINEER will perform the services to be provided under this agreement out of their office or offices listed below:

<u>Service</u>	<u>Office Location</u>
PS&E	Mission Office
Schematic	Mission Office
Environmental Document	Mercedes Office

The work effort will be managed out of the _____ Mercedes _____
office located at _____ 2100 West Expressway 83 _____
_____ (Address) _____
_____ Mercedes _____, _____ Texas _____
_____ (City) _____ (State)

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE

1. Title Sheet
Detailed Index of Sheets
2. Typical Sections
3. General Notes and Specifications Data
4. Estimate and Quantity Sheets
5. Storm Water Pollution Prevention Plan (SW3P) Sheets
6. Traffic Control Plans
 - a. Sequence of Construction Layouts
 - b. Detour Plan/Profile/Typical Sections/Quantities
7. Roadway Layouts
 - a. Roadway Plan/Profile Sheets
 - b. Intersection Plan/Profile Sheets
 - c. Intersection Layouts
 - d. Alignment Layouts/Data
 - e. Ramp Layouts/Profiles
 - f. Connection Roads/U-turns Layouts/Profile
8. Roadway Details
 - a. Concrete Pavement Details/Standards
 - b. Concrete Pavement Terminal Anchorage Details/Standards
 - c. Bridge Approach Details/Standards
 - d. Bridge Terminal Anchorage Details/Standards
 - e. Roadway/Median Barrier Details/Standards
 - f. Curb Details
 - g. Driveway Details/Typical Sections/Standards
9. Signing Layouts and Marking Layouts
10. Traffic Signal Layouts
11. Lighting Layouts
12. Illumination Detail Standards (HMID, HMIF, HMIP, RID)
13. Utility Layouts/Profiles
14. Drainage Area Maps and Hydraulic Data
 - a. General Drainage Area Maps
 - b. Stage-Discharge Curves
 - c. Main Cross-Drainage Culvert/Bridge Hydraulic Data
 - d. Drainage Area Maps/Culverts/Storm Sewer
 - e. Hydraulic Data/Culverts/Inlets/Storm Sewer/Pumps
15. Detailed Drainage Plans
 - a. Drainage Plan/Profile Sheets (Storm Sewer Plan/Profile Sheets)
 - b. Channel Plan/Profiles/Typical Sections
 - c. Box Culvert Plan/Profile
 - d. Pipe Sewer/Culvert Cross Sections

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX A - PLAN SHEET SEQUENCE PROCEDURE (Continued)

16. Drainage Structural Details/Standards
 - a. Inlet Details/Standards
 - b. Manhole Details/Standards
 - c. Junction Box Details/Standards
 - d. Safety End Treatment Details/Standards
 - e. Box Culvert Details/Standards
 - f. Culvert Wingwall Details/Standards
 - g. Excavation-Backfill Diaphragms
 - h. Riprap Details/Standards
 - i. Temporary Pollution and Erosion Control Details
17. Pumphouse Layouts
18. Pumphouse Details
19. Pumphouse Standard Details
20. Bridge Layouts/Profile/Typical Sections*
21. Bridge Details*
 - a. Summary of Bridge Quantities
 - b. Abutments
 - c. Interior Bents
 - d. Spans
 - e. Special details for the specific bridge
22. Bridge Standard Details*
23. Bridge Railing Standards
24. Retaining Wall Layouts/Profiles**
25. Retaining Wall Details**
26. Retaining Wall Standard Details**
27. Guard Fence/Standards and Signal Pole Standards
28. Signal/Electrical Details/Standards and Signal Pole Standards
29. Signing/Markers/Striping Details/Standards
30. Barricade/Construction/Beacon Standards
31. Miscellaneous Standards
 - a. Chain Link Fence Standards
 - b. Bridge End Detail/Standards
 - c. Roadway Clearance Details/Standards
 - e. Attenuator Standards

NOTE: Variations of these plan sheet sequence guidelines may be permitted if approved in writing by the County.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX B - PLAN PREPARATION PROCEDURES

1. Title Sheet
The ENGINEER shall be responsible for completing the title sheet as required and formatted by the STATE and as discussed in Part V of the Highway Design, Operations and Procedures Manual. Refer to Section K - Plans, 1 - Title Sheets, page 5-24, for the procedure to be used regarding all plans prepared by the ENGINEER.
2. Project Layout
The project layout shall clearly depict the entire project as it is proposed and will usually be drawn at a scale of 1 inch=100 feet or 1 inch=200 feet, depending on the size of the project.
3. Typical Sections
See Part IV of the Highway Design, Operations and Procedures Manual.
4. Sequence of Work Sheets (Traffic Control Plan)
Clarity and completeness should be the rule to follow in preparing these sheets, with particular attention given to location of construction signs and barricades, lane widths, protection of drop offs, etc. For a reference guide use the Texas Department of Transportation, Texas Manual on Uniform Traffic Control Devices. Usual scale of 1 inch=100 feet and/or 1 inch=50 feet for special locations. A narrative sequence shall be included in the special provisions for the project. Staging of structural elements shall be considered. Provisions for drainage shall be considered, included and indicated during all stages of construction operations.
5. Removal Item Sheets
These sheets indicate removal of existing facilities necessary to the proposed construction. (1 inch=40 feet) (use same scale as plan/profile sheets).
6. Summary Sheets
Summary Sheets are required to indicate type, quantity and/or location of work for individual items of the proposed project.
7. Alignment Layout Sheets
These sheets indicate the horizontal alignment with curve data and coordinates usually tabulated thereon. On some projects, depending on size, this information may be included on the plan profile sheets. Usual scale (1 inch=100 feet) or (1 inch=40 feet).
8. Plan Profile Sheet
Clarity and completeness should be the rule to follow in preparation of these sheets. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet), depending on project complexity.
9. Drainage Area Maps
Usual scale (1 inch=100 feet) and/or (1 inch=200 feet) supplemented by large scale area maps as necessary.
10. Drainage Plan Profile Sheets
These sheets may be required on some projects to clearly depict location of inlets, storm sewer lines, and profile of storm sewer lines and laterals. Usual scale (1 inch=40 feet or 1 inch=50 feet) or (1 inch=20 feet). Storm sewer design does include redesign of storm sewers imposed by utility constraints developing after initial reviews by the STATE and consequential redesign and adjustments.
11. Runoff, Inlet, Storm Sewer and Culvert Sheets
Use standard sheets.

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX B - PLAN PREPARATION PROCEDURES (Continued)

12. Culvert Cross Sections and Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER for modification of special designs.
13. Manhole and Inlet Details
District standard reproducible sheets can be furnished (one each) to the ENGINEER.
14. Miscellaneous Detail
Curb, Sidewalk, Driveways, etc.
15. Intersection Details
16. Marking Layouts and/or Details
Layouts of the entire project with markings depicted thereon. Usual scale 1:500 (1 inch=40 feet or 1 inch=50 feet). On some projects typical details might suffice.
17. Structural Details
Bridge layout sheets shall have the same horizontal and vertical scale. Usually (1 inch = 10 feet) (1 inch = 20 feet). Sections of existing and proposed structures usually have a scale of (1 inch = 5 feet). Elements of the bridge (abutments, bents, slabs, etc.) shall be detailed to a (1/2 inch = 1 foot) or (1/4 inch equals 1 foot) architect scale to provide clear legible drawings when reduced. Letters shall be a minimum size of 4 millimeters (5/32 inch) height for hand lettering and 140 for lettering by computer-aided design and drafting (CADD).
18. Overhead Sign Bridge Layouts
A maximum of four structures may be shown on each layout sheet. The reference to the appropriate overhead sign bridge (OSB) standard and the following requirements shall be shown on the layout:
 - (1) Drilled shaft size and length
 - (2) Soil strength used for design {indicate basis and boring(s) used}
 - (3) Design height
 - (4) Tower height
 - (5) Leg spacings and
 - (6) Design wind speed.

The wind speed design map need not be included in the project plans. Designation of tower member size and anchor bolt size shall not be shown. For OSBs which require special design, the design shall be in accordance with the AASHTO sign specifications (see Item 22 of References on page 49) and to the same loading requirements as for normal standard structures. Structures (special or standard) which will have changeable message signs shall be analyzed by the ENGINEER.

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST

Services
 Provided By:
ENGINEER COUNTY

___	___	Title Sheet
___	___	Project Layout
___	___	Sequence of Work
___	___	Detour Layouts & Profiles
___	___	Construction Pavement Markings
___	___	Signing & Barricades
___	___	Construction Sign & Beacons
___	___	Typical Sections
___	___	Shaping & Finishing Sections
___	___	Slopes Adjacent to Shoulders
___	___	Estimate & Quantities
___	___	General Notes & Specification Data
___	___	Grading Summary
___	___	Miscellaneous Summaries (See following "SUMMARIES" heading)
___	___	Horizontal Curve Data & Alignment Layouts
___	___	Drainage Summaries
___	___	Structure Summaries
___	___	Erosion Control Summary & Details
___	___	Plan/Profile Sheets
___	___	Erosion Control Summary & Details
___	___	Pavement Contours
___	___	Superelevation Transition (If Required)
___	___	Grading Contours
___	___	Guard Fence Layouts
___	___	Storm Water Pollution Prevention Plans (SW3P)
___	___	Drainage Area Maps
___	___	Hydraulic Data
___	___	Drainage Sheets
___	___	Bridge Hydrology Sheets
___	___	Inlet & Manhole Details
___	___	Utility Support Details
___	___	Culvert Cross Sections & Details
___	___	Special Culvert Designs
___	___	Special Drainage Details
___	___	Chain Link Fence Locations
___	___	Ramp Details Sheet
___	___	Removal Item Sheet - Including detours
___	___	(Shown in detour summary, No payment for removal; subsidiary to construction detours)
___	___	Pavement Details
___	___	Pavement Standard Modification for Concrete Shoulder
___	___	Concrete Pavement Continuously Reinforced (CPCR)
___	___	Concrete Pavement Contraction Design (CPCD)
___	___	Concrete Pavement Details - Jointed Reinforced (Steel Bars) (CPJR)
___	___	Bridge Approach Slab Details
___	___	Vehicle Attenuator Details
___	___	Miscellaneous Details
___	___	Wheelchair Ramps
___	___	Pavement Marking Details
___	___	Modified Standards
___	___	List of Standards
___	___	Permanent Signing Plans & Quantities

EXHIBIT "B"

SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST *(continued)*

Services
 Provided By:
ENGINEER COUNTY

___	___	Permanent Lighting Plans, Quantities & Standards
___	___	Bridge Layout(s)
___	___	Bridge Details
___	___	Retaining Wall Layout(s)
___	___	Retaining Wall Details
___	___	Pumphouse Details
___	___	Underdrain Details (Retaining Walls)
___	___	Culvert Standards
___	___	Soil Profile
___	___	Temporary Traffic Signals
___	___	Design Cross Sections
___	___	Estimate
___	___	List of Standard Specification, Special Provisions & Special Specifications
___	___	Detour Special Provisions (If Required)
___	___	Construction Time Estimate
___	___	Critical Path Method (CPM)
___	___	Unit Price Documentation

Miscellaneous

___	___	Conduit Requirements
___	___	Traffic signal Requirements

Summaries

(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)

___	___	Salvaging and Placing Topsoil
___	___	Prepare ROW
___	___	Remove Old Structures
___	___	Scarify Existing Pavement
___	___	Remove Old Concrete Curb of Curb and Gutter (C&G)
___	___	Remove Old Concrete Pavement
___	___	Remove Old Concrete Riprap
___	___	Remove Metal Beam Guard Fence
___	___	Galvanized steel Beam Guard Fence (12Ga) (GSBGF)
___	___	Temporary Guard Fence (TEMPGF)
___	___	Summary of Concrete Flumes
___	___	Curbs
___	___	Adjust Manholes & Inlets
___	___	Underdrains
___	___	Base and Pavement
___	___	Large Structure
___	___	Concrete Riprap (RR8 & RR9)
___	___	Temporary Portable Concrete Barrier (PCBR)
___	___	Concrete Traffic Barrier
___	___	Vehicle Attenuator
___	___	Guard Rail Energy Absorbing Terminal (Great System)
___	___	Pavement Markings & Blast Cleaning (Thermoplastic)
___	___	Retaining Walls
___	___	Large Structure Summaries
___	___	Small Structure Summaries

EXHIBIT "B"
SCOPE OF SERVICES TO BE PROVIDED BY THE ENGINEER

APPENDIX C - GENERAL PLAN CHECKLIST *(continued)*

Services
Provided By:
ENGINEER COUNTY

Summaries		(ALL BELOW YES FOR ENGINEER AND NO FOR COUNTY UNLESS NOTED OTHERWISE)
_____	_____	Earthwork (Roadway & Channel) & Channel Details
_____	_____	Culverts
_____	_____	Detours
_____	_____	Seeding or Mulch Sod - Quantity Only
_____	_____	Inlet & Manholes
_____	_____	Sidewalks
_____	_____	Construction Pavement Markings
_____	_____	Driveways
_____	_____	Concrete Median
_____	_____	Storm Sewers
_____	_____	Head Walls & Safety End Treatments
_____	_____	Curb Openings
_____	_____	Manholes
_____	_____	Chain Link Fence, Remove & Replace Chain Link Fence
_____	_____	Remove & Relay Reinforced Concrete Pipe (RCP) or Pipe Sewer

EXHIBIT "C"

PROJECT WORK SCHEDULE
FM 1925 (Monte Cristo Rd)
From FM 907 (Alamo Road) to Sharp Road
Length = 1.6 miles

TASK AND DESCRIPTION	FIRM	2018						2019												2020											
		JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Work Authorization No. 3																															
Phase II: PS&E & ROW Map																															
PS&E																															
Design Survey	L&G																														
Compensable Utility Oversight	L&G																														
Outfall Coordination with HCDD #1	L&G																														
30% PS&E Completion	L&G																														
60% PS&E Completion	L&G																														
90% PS&E Completion	L&G																														
95% PS&E Completion	L&G																														
100% PS&E Completion	L&G																														
TxDOT Plan Set Approval	TxDOT																														
ROW Map																															
Prepare ROW Map	L&G																														
TxDOT Review & Revisions	TxDOT																														
TxDOT ROW Map Approval	TxDOT																														
Work Authorization No. 5																															
Phase III: ROW Acquisition																															
ROW Acquisition (10 Parcels)																															
ROW Release (Dependent on Availability of Funds)	TxDOT																														
Project Administration	L&G																														
Title Commitments	L&G																														
Appraisal Reports	L&G																														
Appraisal Review Reports	L&G																														
Appraisal Update Reports	L&G																														
Approved Values by TxDOT	TxDOT																														
Acquisition Negotiation Offers	L&G																														
Title Curative Process	L&G																														
Title Commitment Updates	L&G																														
Payments for Parcels	L&G																														
L&G Condemnation Support Process	L&G																														
Eminent Domain Proceedings by County	COUNTY																														
Title Insurance Policies	L&G																														
Consumation of Outstanding Cases	L&G																														
Phase III: Proposed Letting																															
Let Project (Est. Earliest Date: June 2020)	TxDOT																														
(Dependent on Availability of Funds)																															

L&G ENGINEERING TASK
TxDOT TASK
COUNTY TASK

ESTIMATED 18 MONTHS CONSTRUCTION

EXHIBIT D-1
ESTIMATED MAN-HOUR BREAKDOWN

FM 1925 Project
from FM 907 (Alamo Road) East to Sharp Road

		MANHOURS												Sub-Contract Amounts / ROW COST	TOTAL LINE ITEM COST
		Senior Project Manager	Senior Engineer	Project Engineer	Design Engineer	ROW Administrator	EIT	Senior Engineer Tech	Engineer Tech	CADD Operator / GIS Analyst	Admin / Clerical	TOTAL HOURS			
CONTRACT RATE		215.40	167.89	123.54	114.04	107.70	82.36	79.19	76.02	66.52	57.02				
WORK AUTHORIZATION NO. 3															
PHASE II - PS&E, ROW Mapping & Surveying															
1	Coordination and Management of Subconsultant for ROW Map	4	11	11	5	2.00	1.790					35		\$ 5,000.28	
1a	SUB: ROW Mapping (See fee breakdown on Page 2 of 3)												\$ 35,000.00	\$ -	
2	Outfall Hydraulics (Ditch Capacities, etc...)	20	80	116	136		77.96					429.96		\$ 54,000.00	
3	Pavement Design for TxDOT	20	60	90	132		141	180		18.94	642			\$ 67,500.00	
4	Traffic Signal Warrant Design Support ~ Coordination and Management of Subconsultant for Traffic Signal Warrant Design	6	10	20	20		20	10	8	9.93	104			\$ 11,430.66	
4a	SUB: Signal Design, Adjustments, & Warrants (See fee breakdown on Page 3 of 3)											\$ 7,569.57		\$ -	
5	Traffic Signal Design and one Signal Design During Construction	30	60	92	60		50	61	70	3.46	498			\$ 54,000.16	
6	PS&E Development	160	320	480	960		1123	1360	1460	1582	60	7505		\$ 676,800.00	
7	Engineering Fee to Submit Plans Through Letting (Pharr District and Austin Divisions)	52	92	220	235		280	381		20.05	1280			\$ 135,000.00	
8	PS&E Development For Outfalls	40	80	130	200		240	320	363	401	29.95	1803.95		\$ 162,000.00	
9	Coordination and Management of Subconsultant for Field Surveys	28	57	90	60		48	60	68	67.1				\$ 51,899.33	
9a	SUB: Field Surveys for Design and Construction (See fee breakdown on Page 2 of 3)											\$ 64,101.00			
10	Permitted Utilities Coordination to adjust	32	88	254	299		241	240.02			1154			\$ 126,000.00	
11	Engineering Consultant Construction Management (18 Months)	64	120	320	299.98		299				1103			\$ 132,300.00	
SUB-TOTAL		456	978	1823	2406.98	2	2521.75	2612.02	1969	2132.03	132.40	14555	\$ 106,670.57	\$ 1,475,930.44	

Sub-Total Manhours Fee with Subconsultant Fee:	\$ 1,582,601.01

* TOTAL PROJECT FEE:	\$1,582,600.00

* Rounded Figure

Exhibit "D"
BUDGET
LUMP SUM RATE BASIS OF PAYMENT

Work Authorization No. _____

	A	B	C	D	E	F	G	H	I	J	K
1	Highway: FM 1925										
2	County: Hidalgo County, Texas										
3	Limits: FM 907 to Sharp Rd.										
4	Description of Work: ROW Map and Design Survey										
5	TASK AND DESCRIPTION	Survey		Survey	4-man	3-man	2-man		Admin/	Total	Cost
6	FC 130 ROW Map / FC 150 Field Surveying	PM	RPLS	Technician	Survey Crew	Survey Crew	Survey Crew	SUE/per unit	Clerical	Hours	
7	HOURLY RATE	\$124.00	\$125.00	\$82.00	\$175.00	\$155.00	\$130.00	\$500.00	\$50.00		
8	PHASE I - FC 130 (ROW MAP) Lump Sum per Parcel										
9	A. ROW Map, Parcel Description, Metes and Bounds Description, and Title Reports (10 parcels @ \$3,500.00/parcel)										
10	FC 130 Subtotal Cost										\$ 35,000.00
11	PHASE I - FC 150 Field Surveying (Control Hz & Vt)										
12	A. Primary Project Control										
13	a. Establish Primary Control	0	2	2	0	6	0	0	0	10	\$ 1,344.00
14	B. Secondary Project Control										
15	a. Set additional secondary control points as needed	0	4	6	0	5	0	0	0	15	\$ 1,767.00
16	b. Horizontal values established with RTK or VRS	0	2	8	0	6	0	0	0	16	\$ 1,836.00
17	c. Vertical values established with digital level	0	2	4	0	6	0	0	0	12	\$ 1,508.00
18	Subtotal Hours	0	10	20	0	23	0	0	0	53	
19	Subtotal Cost - Phase I	\$0.00	\$1,250.00	\$1,640.00	\$0.00	\$3,565.00	\$0.00	\$0.00	\$0.00		\$ 6,455.00
20	PHASE 2 - DTM Topography and Cross sections (Total Length including side streets, Drain, and Irrigation Crossings=2.1 miles)										
21	C. Setting Benchmarks										
22	1. Setting Benchmarks @ 1000'(ft) intervals	0	0	0	0	20	0	0	0	20	\$ 3,100.00
23	2. Topographic & Crosssections	0	0	10	0	28	0	0	0	38	\$ 5,160.00
24	3. Locate Visible Utilities	0	0	10	0	24	0	0	0	34	\$ 4,540.00
25	4. Cross Culverts, Driveway Culverts, Inverts	0	0	10	0	16	0	0	0	26	\$ 3,300.00
26	5. Right of Entry, ROW Research, Appraisal Dist. Records	0	2	6	0	0	0	0	10	18	\$ 1,242.00
27	6. Proposed Centerline on Existing Pavement Pre-Construction for Utilities	0	2	8	0	8	0	0	0	18	\$ 2,146.00
28	7. Profile and Cross section Intersecting Streets	0	0	6	0	10	0	0	0	16	\$ 2,042.00
29	8. Irrigation Crossings	0	0	8	0	14	0	0	0	22	\$ 2,826.00
30	9. Existing Storm Drain H&V	0	0	2	0	6	0	0	0	8	\$ 1,094.00
31	10. Tie Existing Underground and Overhead Utilities Coordinate with Engineer (No SUE)	0	2	2	0	6	0	0	0	10	\$ 1,344.00
32	11. Additional Field Surveying										
33	a. Irrigation Lines	0	2	3	0	8	0	0	0	13	\$ 1,736.00
34	b. Outfalls	0	2	3	0	8	0	0	0	13	\$ 1,736.00
35	c. Driveways and Turnouts	0	0	3	0	4	0	0	0	7	\$ 866.00
36	15. Profiles of Existing Drainage Facilities	0	0	3	0	6	0	0	0	9	\$ 1,176.00
37	17. Obtain Elevations of Manholes and Valves of Utilities	0	0	3	0	4	0	0	0	7	\$ 866.00
38	18. Provide temp. signs, traffic control, flags, safety equip. etc.	0	0	0	0	4	0	0	0	4	\$ 620.00
39	19. Ties to Existing Bridges or Culverts that may be in conflict with new construction	0	0	3	0	8	0	0	0	11	\$ 1,486.00
40	21. Inventory Signs, mailboxes, and driveways	0	0	3	0	2	0	0	0	5	\$ 556.00
41	22. Survey Control Data Sheets per TxDOT	0	2	3	0	0	0	0	0	5	\$ 496.00
42	23. Recover and Establish Existing CL and ROW	0	0	0	0	0	0	0	0	0	\$ -
43	24. Coordinate with the Engineer for Existing CL Stationing	0	2	0	0	0	0	0	0	2	\$ 250.00
44	25. Right of Way Restaking (Pre Construction)	0	4	4	0	8	0	0	0	16	\$ 2,068.00
45	26. SUE Level A Data Sheets	0	0	0	0	0	0	0	0	0	\$ -
46	Subtotal Hours	0	18	90	0	184	0	0	10	302	
47	Subtotal Cost - Phase 2	\$0.00	\$2,250.00	\$7,380.00	\$0.00	\$28,520.00	\$0.00	\$0.00	\$500.00		\$ 38,650.00
48	PHASE 3- SUBSURFACE UTILITY ENGINEERING										
49	1. Hydro Excavation SUE Level A (30 holes at \$500 each)	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	30.00	\$0.00	\$0.00	
50	Total Cost-Phase 3	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$15,000.00	\$0.00	\$0.00	\$ 15,000.00
51	PHASE 4 - FINAL REPORT & DELIVERABLES										
52	A. CADD file (2D & 3D) for limits of project	0	0	10	0	0	0	0	0	10	\$ 820.00
53	B. Final Report and Deliverables	0	4	10	0	0	0	0	0	14	\$ 1,320.00
54	Subtotal Hours	0	4	20	0	0	0	0	0	24	
55	Subtotal Cost - Phase 4	\$0.00	\$500.00	\$1,640.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00		\$ 2,140.00
56	PROJECT MANAGEMENT & OVERSIGHT										
57	A. Meeting & Coordination w/ Engineers	0	4	0	0	0	0	0	2	6	\$ 600.00
58	B. QC/QA Survey	0	4	8	0	0	0	0	2	14	\$ 1,256.00
59	Subtotal Hours	0	8	8	0	0	0	0	4	64	
60	Subtotal Cost - PM & Oversight	\$0.00	\$1,000.00	\$656.00	\$0.00	\$0.00	\$0.00	\$0.00	\$200.00	0	\$1,856.00
61	Total Fee FC 150	\$0.00	\$5,000.00	\$11,316.00	\$0.00	\$32,085.00	\$0.00	\$0.00	\$700.00	0	\$49,101.00
62	Total SUE										\$15,000.00
63	Total Fee FC 130 & FC 150 & SUE										\$99,101.00

EXHIBIT C "FEE SCHEDULE" - TRAFFIC SIGNAL WARRANT STUDY'
FM 1925 at Sharp Road

Ergonomic Transportation Solutions, Inc.

TRAFFIC SIGNAL WARRANT STUDY			MANHOURS				
			Project Manager	Traffic Engineer	CADD/ Designer	Administrative Assistant	Total
TASK							
	1	Collect Data and Conduct Field Investigations		8	8		16
	2	Assess Collected Data		2	2		4
	3	Accident Analysis		6			6
	4	Collision Diagram		1	4		5
	5	Intersection Exhibits		1	4		5
	6	Signal Warrant Analysis	1	16	2		19
	7	Photo Album			2		2
	8	Recommendations	1	1			2
	9	Traffic Signal Warrant Study Report	1	8	4	2	15
		Subtotal	3	43	26	2	74

Total Sheets/Labor Hours		3	43	26	2	74
Contract Rates		\$ 68.00	\$ 34.00	\$ 23.00	\$ 19.00	
Direct Salary Cost		\$ 204.00	\$ 1,462.00	\$ 598.00	\$ 38.00	\$ 2,302.00
Overhead Multiplier	165.260%	\$ 337.13	\$ 2,416.10	\$ 988.25	\$ 62.80	\$ 3,804.29
Fixed Fee	12.50%	\$ 67.64	\$ 484.76	\$ 198.28	\$ 12.60	\$ 763.29
Total Labor Costs		\$ 608.77	\$ 4,362.86	\$ 1,784.54	\$ 113.40	\$ 6,869.57


Ergonomic Transportation Solutions, Inc. Expenses

EXPENSES

Printing Reproduction	\$ -
Travel	\$ -
Delivery	\$ -
Collect 12 hr Turning Movement Counts (Outsourced)	\$ 700.00

Total Expenses **\$ 700.00**

ETSI Total Cost **\$ 7,569.57**



June 27, 2018

The Honorable Joseph Palacios
Commissioner, Hidalgo County Pct. No. 4
1051 N. Doolittle Road
McAllen, Texas 78541

RE: FM 1925 Road Project
Contract: C-13-336-12-10
Work Authorization No. 3
Limits: From FM 907 (Alamo Road) to Sharp Road

Dear Commissioner Palacios:

As discussed, attached in duplicate for your review and approval is Work Authorization No. 3 to provide PS&E, Field Surveys, ROW Mapping, Permitted Utilities Coordination, Traffic Signal Warrants and Design and Engineering Consultant Const. Management for the Phase II engineering services of the FM 1925 Road Project.

Work Auth. No. 3 is in the amount of \$1,582,600. The following is the funding breakdown for L&G Engineering and our Sub-Consultants proposed fees associated with this Work Authorization.

• L&G Engineering (<i>PRIME</i>)	\$ 1,475,929.43
• ROW Surveying Services, LLC. (<i>SUB-CONSULTANT</i>)	\$ 99,101.00
• ETSI (<i>SUB-CONSULTANT</i>)	\$ <u>7,569.57</u>
TOTAL	\$ 1,582,600.00

Attached you will find the following:

- 1.) Two (2) signed originals of Work Authorization No. 3 with the following attachments:
 - Project Location Map
 - Exhibit A "Services to be provided by the Owner"
 - Exhibit B "Services to be provided by the Engineer"
 - Exhibit C "Work Schedule"
 - Exhibit D-1 "Estimated Man-hour Breakdown" and attachments

Should you have any questions regarding this submittal, do not hesitate to call me at (956) 585-1909.

Sincerely,

Robert Macheska, P.E.
Project Manager

Attachments



June 27, 2018

Hon. Joseph Palacios
Attn: Maria "Lulu" Mayorga – Executive Assistant
Hidalgo County Precinct No. 4
1051 N. Doolittle Road
Edinburg, Texas 78541

RE: Subcontracting Notice for FM 1925 Project
C-13-336-12-10
Limits: From FM 907 (Alamo Road) to Sharp Road

Dear Commissioner Palacios:

We would like to inform you of the subcontractors that we will be using on the FM 1925 Road Project ~ Work Authorization #3. Please coordinate with your Purchasing Department for Commissioner's Court approval of this notification. These subcontractors will be providing Surveying and Traffic Signal Services for the above referenced project.

Subcontractor:

Surveyor:

Mr. Julio Cerda, P.E.
R.O.W. Surveying Services, LLC.
900 S. Stewart Road, Ste. 13
Mission, Texas 78572
Phone (956)-424-3335

Traffic Signals:

Mr. Harry Simeonidis, P.E.
Ergonomic Transportation Solutions, Inc.
11500 Northwest Freeway, Suite 491
Houston, Texas 77092
Phone (713) 956-9601

Should you have any questions, please feel free to give me a call at 956-585-1909.

Sincerely,

Robert Macheska, P.E., C.F.M.
Project Manager

cc: Hidalgo County Auditor's Office

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

OFFICE USE ONLY CERTIFICATION OF FILING

1 Name of business entity filing form, and the city, state and country of the business entity's place of business.

L&G Consulting Engineers, Inc.
Mercedes , TX United States

Certificate Number:
2018-372242

Date Filed:
06/25/2018

Date Acknowledged:

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10

FM 1925 (FM 907 (Alamo Road) to Sharp Road) WA #3 to provide Engineering Services

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval, Armando	Mercedes , TX United States		X
	Garza , Jacinto	Mercedes , TX United States	X	

5 Check only if there is NO Interested Party.

☐


6 UNSWORN DECLARATION

My name is Jacinto Garza, and my date of birth is 10/23/1961.

My address is 2100 W. Expressway 83, Mercedes, TX, 78570, USA.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in Hidalgo County, State of Texas, on the 27th day of June, 20 18.
(month) (year)



Signature of authorized agent of contracting business entity
(Declarant)

CERTIFICATE OF INTERESTED PARTIES

FORM 1295

1 of 1

Complete Nos. 1 - 4 and 6 if there are interested parties.
Complete Nos. 1, 2, 3, 5, and 6 if there are no interested parties.

**OFFICE USE ONLY
CERTIFICATION OF FILING****1 Name of business entity filing form, and the city, state and country of the business entity's place of business.**

L&G Consulting Engineers, Inc.
Mercedes , TX United States

Certificate Number:
2018-372242

Date Filed:
06/25/2018

Date Acknowledged:
08/17/2018

2 Name of governmental entity or state agency that is a party to the contract for which the form is being filed.

Hidalgo County

3 Provide the identification number used by the governmental entity or state agency to track or identify the contract, and provide a description of the services, goods, or other property to be provided under the contract.

C-13-336-12-10
FM 1925 (FM 907 (Alamo Road) to Sharp Road) WA #3 to provide Engineering Services

4	Name of Interested Party	City, State, Country (place of business)	Nature of interest (check applicable)	
			Controlling	Intermediary
	Sandoval, Armando	Mercedes , TX United States		X
	Garza , Jacinto	Mercedes , TX United States	X	

5 Check only if there is NO Interested Party.☐**6 UNSWORN DECLARATION**

My name is _____, and my date of birth is _____.

My address is _____, _____, _____, _____, _____.
(street) (city) (state) (zip code) (country)

I declare under penalty of perjury that the foregoing is true and correct.

Executed in _____ County, State of _____, on the ____ day of _____, 20____.
(month) (year)

Signature of authorized agent of contracting business entity
(Declarant)

SPECIAL MEETING - August 21, 2018

BE IT REMEMBERED, that on this 21st day of August A.D., 2018, there was begun and held a **SPECIAL MEETING** of the Honorable Commissioners' Court of Hidalgo County, Texas, wherein the following members thereof were present, to-wit:

HONORABLE RAMON GARCIA

HIDALGO COUNTY JUDGE

HONORABLE DAVID FUENTES

COMMISSIONER, PRECINCT NO. 1

HONORABLE EDUARDO "EDDIE" CANTU

COMMISSIONER, PRECINCT NO. 2

HONORABLE JOE M. FLORES

COMMISSIONER, PRECINCT NO. 3

HONORABLE JOSEPH PALACIOS

COMMISSIONER, PRECINCT NO. 4

and **ARTURO GUAJARDO, JR., COUNTY CLERK & EX-OFFICIO CLERK OF THE COMMISSIONERS' COURT** of Hidalgo County, Texas, wherein the following proceedings were had, to-wit:



**AGENDA
CC REGULAR
HIDALGO COUNTY
COMMISSIONERS COURT MEETING
August 21, 2018
9:30 A.M.**

NOTICE is hereby given in accordance with Chapter 551, Texas Government Code, that a SPECIAL MEETING of the Commissioners' Court will be held at the Edinburg Council Chambers 415 W. University Drive, Edinburg, Hidalgo County, Texas. Discussion and possible action relating to the following business will be transacted:

1. Roll Call

Judge Garcia called the meeting to order at 12:01 p.m.

All members of the court were in attendance.

Court recessed at 12:01 p.m.

Court reconvened at 12:02 p.m.

Commissioner Palacios stepped away from the meeting.

2. Pledge of Allegiance

Court recited the Pledge of Allegiance.

3. Prayer

Opening prayer offered by Julia Sullivan.

4. Approval of Consent Agenda

The court moved to approve the consent agenda with the exception of Item.6.A. & B to be pulled for discussion.

5. District Attorney's Office:

- A. AI-66107** DA-Victim Coordinator and Liaison Grant (VCLG) (1281)/Criminal DA (1100):
1. Approval to ratify electronic signature submitted on-line for the Victim Coordinator and Liaison Grant (VCLG) Fiscal Year 2019 contract. (2nd year of a two year contract application)

On motion by COMMISSIONER PCT. 1, DAVID FUENTES, seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval.

On motion by COMMISSIONER PCT. 3, JOE M. FLORES, seconded by COMMISSIONER PCT. 4, JOSEPH PALACIOS, the Court made a UNANIMOUS vote of approval.

Vote: 4 - 0 - Unanimously

Commissioner David L. Fuentes abstained from voting on this item.

Court proceeded back to Item. 16.A.1

D. Budget Appropriations:

1. **AI-66195** CC Records Archive (1100):
Approval of appropriation of funds from the General Fund Restricted Fund Balance - CC Records Archive for CC Records Archive in the amount of \$299,000.00 to fund the preservation of books.

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval.

Vote: 5 - 0 – Unanimously

Court proceeded back to Item. 15.C.

16.

Purchasing Department - Notes:

A. FOR ANY CONTRACT(S) AWARDED AND APPROVED UNDER THIS AGENDA, EXECUTED COPIES OF THE CONTRACT(S) WILL BE AVAILABLE ON THE COUNTY INTRA-NET WEBSITE AND WILL BE FORWARDED VIA E-MAIL, FAX OR HAND DELIVERED TO HIDALGO COUNTY AUDITOR'S OFFICE.

B. ANY AND ALL REQUESTS FOR PAYMENT(S) APPROVED WILL BE SUBJECT TO COUNTY AUDITORS PROCESSING PROCEDURES INCLUDING AUTHORITY FOR COUNTY TREASURER TO ISSUE PAYMENT(S)/CHECK(S).

A. Hidalgo County

1. **AI-66188** Acceptance and approval of a **rebate** check number 2884454 from Office Depot [through awarded contract with The Cooperative Purchasing Network, aka, TCPN/ECOMM] 2017 **rebate 55797022 dated 03/01/18** in the amount of \$ 1,098.31.

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval.

Vote: 5 - 0 – Unanimously

2. **AI-66211** a. Acceptance and approval of Work Authorization No. 2 (with an estimated cost of \$2,257,854.00) as submitted by project engineer, L&G Consulting Engineers, to provide "Engineering Services for preparation for the Traffic Impact Analysis, Environmental Assessment, Public Involvement, Schematic Design, Hydrologic Map, and Disposition of Bus 281 ROW at Courthouse Square for the Roadway and Drainage Improvement assoc. with the Bus 281/SH 107 Intersection Project,"

through Contract# C-16-199-07-19.

b. Pursuant to current contract with L&G Engineering (Article 14), a request by engineer approving the subcontracting of R.O.W. Surveying Services, LLC. and Ergonomic Transportation Solutions, Inc. in connection with Work Authorization No. 2 for the "Engineering Services for preparation for the Traffic Impact Analysis, Environmental Assessment, Public Involvement, Schematic Design, Hydrologic Map, and Disposition of Bus 281 ROW at Courthouse Square for the Roadway and Drainage Improvement assoc. with the Bus 281/SH 107 Intersection Project."

No action taken on Item.16.A.2.A & B.

B. Pct. 2

1. **AI-66206** Pursuant to Texas Constitution, Article 3, Sect. 52, requesting acceptance and approval of "Public Purpose" for the purchase of miscellaneous items [i.e. printed materials, supplies and other related items] which assist in the Precinct's efforts in disseminating information on road conditions, closures, paving/drainage improvements, educational and health awareness, public safety services and programs affecting the community including, but not limited to, the following upcoming events:
- A. Ribbon Cutting for Pct. #2 - Regional Linear Park Project-Phase I;
 - B. Groundbreaking for Pct. #2 - Swimming Pool Project
 - C. Precinct Project Update Expo
 - D. P2 Comes 2 You Outreach Event
 - E. Community Resource Center's - Numerous Events

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 3, JOE M. FLORES, the Court made a UNANIMOUS vote of approval on A to E.

Vote: 5 - 0 – Unanimously

C. Pct. 4

1. **AI-66205** a. Acceptance and approval of Work Authorization No. 3 (with an estimated cost of \$ 1,582.600.00) as submitted by project engineer, L&G Engineering to provide [ROW Map, Schematic, PS&E and Consultant Construction Management Services] as required for ongoing Project Specific: "FM 1925 (from FM 907 (Alamo Rd) East to East of SH 68 (Uresti Street)--(SEG II, Sharp Road Realignment Limits North 5 Miles)" in Hidalgo County Precinct No. 4, under agreement# C-13-336-12-10.

APPROVED

On motion by COMMISSIONER PCT. 4, JOSEPH PALACIOS, seconded by COMMISSIONER PCT. 1, DAVID FUENTES, the Court made a UNANIMOUS vote of approval.

August 21, 2018

Vote: 5 - 0 - Unanimously