URBAN COUNTY PROGRAM

1916 TESORO ST. PHARR, TEXAS 78577 (956) 787-8127 FAX (956) 318-2988 E-MAIL: ucp@co.hidalgo.tx.us

REQUEST FOR QUOTE

Hidalgo County Urban County Program is requesting a quote for the purchase of park equipment outlined in the table below. Project Reference: Lopezville Park located at 509 Minnesota Rd, San Juan, TX 78589.

Vendors may propose equivalent commercial playground equipment meeting or exceeding the requested functional scope. Vendor shall provide the proposed manufacturer, model/design, specifications, dimensions, age range, warranty, and applicable playground safety/certification information.

All quotes must include the price, delivery terms, and a validity period of no less than thirty (30) days. **If you are unable to provide a quote, please notify us in writing.** All equipment shall be procured utilizing BuyBoard contracts.

Buy Board Contract # _____

Contact: Anita Jenny, Hidalgo County Urban County CDBG Division Manager	Phone: (956) 787-8127 Email: jenny.anita@co.hidalgo.tx.us			
Description	**BuyBoard #/ Vendor Item#**	**Qty**	**Unit Price**	**Extended Price**
Landscape Structure – Ages 5–12 Play Booster		1 EA	$	$
16" Pod-Style Climber –or equivalent. Commercial climbing/play component approximately 16 inches high, compatible with the proposed landscape structure and suitable for ages 5–12.		1 EA	$	$
20" Pod-Style Climber –or equivalent. Commercial climbing/play component approximately 20 inches high.		1 EA	$	$
Freight and shipping for the complete playground equipment		LS	$	$
Installation			$	$
Concrete flatwork associated with playground, approximately 336 square feet, including approximately 61 linear feet of drainage and related work required for installation.		LS	$	$
Poured-in-place playground safety surfacing, approximately 336 square feet, approximately 4-inch thickness, 50% black / 50% standard color, or equivalent compliant playground safety surfacing. Vendor shall identify proposed surfacing system.		SF		
Payment and Performance Bond, if required/applicable to the proposed scope.		LS		
TOTAL				$

_____ _____

Representative Name **Date**

_____ _____

Email Address **Phone**

SAMPLE DESIGN





Equal Housing Opportunity
Equal Employment Opportunity Employer

Proposal

Q018740

Please Issue Purchase Order to:
Exerplay, Inc
PO Box 1160, Cedar Crest, NM 87008
fax to 505-281-0155

Proposal Date	Salesperson
10/6/2026	Marissa Pecina 956-358-3972 Marissa@exerplay.com

TX: Hidalgo County: Precinct 2, Lopezville Park
Buyboard Equip - 679-22

Quantity	Item Code	Description	Unit Price	DISC.	Total Extended
		LANDSCAPE STRUCTURES, INC.			
1.00	LSI DESIGN	PlayBooster (5-12 years) Design 000033a	42,825.00	5%	40,683.75
1.00	120711A	Pod Climber® 16", DB	395.00	5%	375.25
1.00	158998A	Pod Climber™ 20", Direct Bury	410.00	5%	389.50
1.00	FREIGHT	Freight/Shipping Charges for Playground (150-26-1009)	5,000.00		5,000.00
300.00	INSTALL	Installation of Additional Play Equipment (08062026)	43.18		12,954.00
		SAFETY SURFACING			
300.00	INSTALL	Additional Concrete Flat Work, 336 SF & 61 LF with Drainage (1055)	19.77		5,931.00
336.00	SURFACING	Additional 336 SF Poured-In-Place Surfacing - 50% Black, 50% Standard Color, 4" thickness (08052026)	20.40	5%	6,511.68
1.00	BOND	Payment/Performance Bond	2,602.93		2,602.93

THIS PROPOSAL IS SUBJECT TO THE ATTACHED TERMS AND CONDITIONS
Taxes subject to change

Proposal prepared by: Mary Croft

Subtotal	74,448.11
Tax Total:	0.00
Total	74,448.11

Accepted by:
Print Name: _____ Signature: _____ Date: _____

Installation Terms:

If installation is included on the quote, the following guidelines must be followed:

1. It is recommended that any Landscape Structures Equipment be installed by a certified Landscape Structures installer, and that all other equipment be installed by a CPSI Certified installer. ExerPlay reserves the right to request proof of certification.
2. Playground equipment MUST be installed over ADA compliant wood fiber or rubber surfacing. This area is not ADA compliant without surfacing and an accessible route up to and into the playground area. Please contact us for more information.
3. Installation price does NOT include prevailing wages, Davis-Bacon wages, or TERO wages unless otherwise specified. Any changes in wage requirements at time of order are subject to updated pricing.
4. Installation price is based on normal soil conditions. Unusual or hard dig soil conditions that require the use of a jack hammer, or other such equipment, will incur additional charges by reason of such conditions and supervisory fee, and for an extension of the time of completion. Installation price does not include removal of anything which may hinder installation of equipment, unless otherwise specified on our quote.
5. If Hard Dig conditions are known, please advise so we can quote accordingly to avoid any delays or additional fees. Hard Dig conditions will be considered anything that cannot be excavated with a standard Bobcat mounted hydraulic auger. Hard Dig conditions will require a change order at a Time & Material rate. If an auger truck is required to complete digging, it will be at the expense of the General Contractor or Owner, if a spoil report is not provided at the time of quoting.

6. Finish grade is to be provided by others prior to arrival of installer.
7. Installer must have free and clear access to the install location(s). The installer is not responsible for damage done to existing surfacing/ landscaping that may occur when equipment & vehicles are being used in the normal course of construction. Reasonable access to the job site for a Bobcat is assumed as a part of this quote.
8. Line-item pricing is for informational purposes only and is based upon being awarded the total project. All items are to be installed concurrently if specific areas are not ready for installation, and an additional mobilization fee will be required via Change order unless otherwise specified on the quote.
9. If any materials need to be unloaded on site by the installer, unloading must be coordinated at the same time as the installation. If special arrangements need to be made, an additional trip charge for unloading may apply.
10. Our installation team will call 811 to conduct a line location service; however, often-times they do not mark lines on the actual property where the installation will be done. The owner is responsible for blue-staking the job site and staking out any underground utilities prior to installation. Owner is responsible should damage occur.
11. Neither ExerPlay nor Installers are responsible for vandalism, theft of equipment or subsequent repairs or replacement. Security fencing can be provided upon request and added to the quote.
12. The job site MUST be ready, and area leveled, when the installer arrives to begin the job, unless specifically noted on the quote. Any downtime or site delays caused by Owner or General Contractor will incur additional fees.
13. If equipment is to be shipped to the installer's yard, it will be held for a maximum of 6 months from delivery, with intent to install in that time frame; otherwise, storage fees may occur.

General Contractor is responsible for:

1. Adequate storage and layout area as well as security of equipment while on site.
2. Water, power, sanitary facilities, and trash container on site.
3. Free and clear vehicle access to site and all areas under the scope of work.
4. Movement of any utilities conflicting with the installation of the equipment (installer is not responsible for landscape irrigation).
5. Once the installers are on site, any delays or additional work incurred by the installation crew and caused by others (owners or other contractors) will be charged on a cost-plus basis.
6. Any additional costs, i.e. demolition, relocation, excavation, surfacing materials, and labor due to abnormal soil conditions, are not included in price.
7. Please notify ExerPlay of any changes immediately. If any changes are made which we are not aware of, and which alter the installation, then all additional costs will be passed on to the GC.