



**CITY OF LA HABRA, CALIFORNIA
CONTRACT CHANGE ORDER NO. 1**

PROJECT: Annual Arterial Street Rehabilitation Fiscal Year 2019-2020, City Project No. 5-R-19

**CONTRACTOR: EBS General Engineering, Inc.
1345 Quarry Street, Ste 101, Corona, CA 92879**

You are hereby directed to make the following changes to the plans and specifications and to do the following described work not included in the plans and specifications.

Description of Change Order: This Change Order provides various concrete improvements, 2” grind and overlay of AC pavement for Euclid Street between La Habra Blvd. and Whittier Blvd. and Beach Blvd near Coyote Creek Channel. The nature of the additional work is similar in scope with the current contract. Attached hereon is the Contractor’s supporting cost breakdown dated 8/23/22. The final amount of the change order will be dependent on the actual description of work and quantity as described in the detailed breakdown.

Note: This change order is not effective until approved by the City Engineer.

Changes requested by: Tony An, Principal Engineer

Date of Issuance: September 19, 2022

DESCRIPTION OF CONTRACT CHANGES:

Item #	Item Description	Actual Quantity	Units	Unit Price	Estimated Cost
1	The work includes various concrete improvements, 2” grind and overlay of AC pavement for Euclid Street between La Habra Blvd. and Whittier Blvd. and Beach Blvd near Coyote Creek Channel. See attached for the breakdown.	1	Itemized	\$ 558,471.00	\$ 558,471.00

ORIGINAL CONTRACT AMOUNT: \$ 2,144,751.00
CURRENT CONTRACT AMOUNT: \$ 2,144,751.00
AMOUNT OF THIS CHANGE ORDER: \$ 558,471.00
REVISED CONTRACT AMOUNT: \$ 2,703,222.00

ORIGINAL START DATE: September 26, 2022
ORINGINAL CONTRACT DURATION: 50 working days
ORIGINAL COMPLETION DATE: December 7, 2022
WORKING DAYS FOR THIS CHANGE: 25
REVISED COMPLETION DATE: January 11, 2022

Contractor: EBS General Engineering, Inc.

By: Luis Morales

Title: Project Manager

Signature: _____

Approved by: Albert Mendoza, P.E.

Title: Deputy Director of Public Works / City Engineer

Signature: _____

**Open Bid Item Prices for : ANNUAL ARTERIAL STREET REHAB FY 19-20
(PRIME)**

EBS General Engineering, Inc LUIS MORALES

09/07/2022

Item	Description	Quantity	U/M	Unit Price	Total Price
02 1	TRAFFIC CONTROL, SAFETY & STORM WATER BEST MANAGEMENT PRACTICE	1.00	LS	\$47,050.00	\$47,050.00
02 4	UNCLASSIFIED EXCAVATION AND DISPOSAL (30 CY OF FULL DEPTH ASPHALT EXCAVATION - 6" MIN VARIABLE DEPTH; 1.5 CY OF DRIVEWAY DEMO, 84 SF)	32.00	CY	\$80.00	\$2,560.00
02 7	CONSTRUCT 2" RUBBERIZED AC OVERLAY ARHM GG-C PG64-16	1,275.00	TN	\$141.60	\$180,540.00
02 7A	CONSTRUCT ARAM SEAL PRIOR TO OVERLAY	11,330.00	SY	\$0.00	\$0.00
02 8	COLDMILL 2" AND DISPOSE EXISTING ASPHALT INCLUDE THE REMOVAL OF ANY FABRIC	11,300.00	SY	\$3.25	\$36,725.00
02 9	SPEED LUMPS, INCLUDING MARKINGS	2.00	EA	\$1,750.00	\$3,500.00
02 10	SAWCUT & REMOVE EXISTING, CONSTRUCT 4" THICK CONCRETE SIDEWALK OVER 3" SAND PER CITY STANDARD DETAIL NO R-14	818.00	SF	\$16.00	\$13,088.00
02 11	SAWCUT & REMOVE EXISTING, CONSTRUCT VARIABLE HEIGHT CONCRETE CURB OR CURB & GUTTER OVER 6" CMB PER CITY STANDARD DETAIL NO R-13, TYPE A 2-8 WITH AC SLOT PATCH(84' OF 138' IS CURB ONLY RECONSTRUCTION)	138.00	LF	\$111.00	\$15,318.00
02 12	SAWCUT & REMOVE CURB RAMP AND SIDEWALK, CONSTRUCT 4" PCC CURB RAMP WITH DETECTABLE WARNING SURFACE OVER 3" SAND PER CALTRANS REVISED STANDARD PLANS A88A (DATED MAY 2018), CASE B UNLESS OTHERWISE NOTED. CONSTRUCT 1' WIDE (8" AC / PCC DEEP LIFT) SLOT PATCH	7.00	EA	\$7,490.00	\$52,430.00
02 15	SAWCUT & REMOVE EXISTING, CONSTRUCT 5" THICK PCC DRIVEWAY APPROACH (INCLUDING CURB AND GUTTER) PER SPPWC STANDARD PLAN 110-2, WITH AC SLOT TRENCH	66.00	SF	\$110.00	\$7,260.00
02 16	INSTALL TRAFFIC STRIPING, CROSSWALKS, CURB PAINTING, MARKINGS AND RAISED PAVEMENT MARKERS	1.00	LS	\$16,150.00	\$16,150.00
02 17	TRAFFIC SIGNAL LOOP DETECTORS	8.00	EA	\$425.00	\$3,400.00
02 18	ADJUST WATER VALVES TO GRADE	28.00	EA	\$736.00	\$20,608.00

**Open Bid Item Prices for : ANNUAL ARTERIAL STREET REHAB FY 19-20
(PRIME)**

EBS General Engineering, Inc LUIS MORALES

09/07/2022

<i>Item</i>	<i>Description</i>	<i>Quantity</i>	<i>U/M</i>	<i>Unit Price</i>	<i>Total Price</i>
02 19	ADJUST SEWER, STORM DRAIN MANHOLE COVERS TO GRADE	14.00	EA	\$546.00	\$7,644.00
02 1A	INSTALL FULL DEPTH AC RECONSTRUCTION AND OVERLAY 6" MIN VARIABLE DEPTH	60.00	TN	\$388.00	\$23,280.00
02 1B	REMOVE AND REPLACE TRAFFIC RATEI UTILITY BOX (CITY OWNED FIBER AND COAXIAL PASS THROUGH BOX) - SEE DETAIL AND PLAN FOR MINIMUM BOX SIZE. CONTRACTOR TO PROTECT IN PLACE CITY COMMUNICATION MEDIUM: - FIBER AND COAXIAL	1.00	EA	\$20,000.00	\$20,000.00
02 1C	COLD MILL GRIND 1" WITH OVERLAY (EAST SIDE OF BEACH BLVD, NOTH OF IMPERIAL HWY) TC INCLUDED.	7,875.00	SF	\$10.00	\$78,750.00
02 1D	COLD MILL GRIND 2" WITH OVERLAY 3 LOCATIONS (LAMBER RD, WEST OF EUCLID)	64.00	SF	\$217.00	\$13,888.00
02 1E	COLD MILL GRIND 2" WITH OVERLAY 2 LOCATIONS (LAMBER RD EAST BOUND LEFT TURN AT CYPRESS) TC INCLUDED	296.00	SF	\$55.00	\$16,280.00
Phase 02 CHANGE ORDER 01		Subtotal			\$558,471.00
BID TOTALS FOR OPEN ITEMS					\$558,471.00