



WWW.Rangeline.Com
 Rangeline Utility Services, LLC
 1150 Blue Mound Road W, Unit 821
 Haslet, Texas 76052

Civil Construction Proposal

Project Name:	12" Valve Replacement	DATE:	08/16/2023
Address:	2600 Red Spruce Dr. Little Elm, Tx	Quote #	RUTS 2023-130
Bid Date/Time:	ASAP		
Quoted To:	City of Little Elm	Drawings	N/A
Att:	Cody Collier	Dated:	N/A
Phone:	940-594-7598	Addendum	N/A
Fax:			
Email:	ccollier@litleelm.org		

RUTS, LLC Proposes to Furnish and Install Complete in Place per Scope of Work below for the Following Price:

\$149,000.00

Item		Unit	Qty	Unit Item Bid	Line Item
	<i>Site Work</i>				
	Mobilization	LS	1	\$ 2,600.00	\$ 2,600.00
	<i>Skilled Labor</i>				
	Excavation, Labor and Backfill to replace 12" Valve. Excavation and labor to locate leak off of 20" water line at the same facility	LS	1	\$ 54,000.00	\$ 54,000.00
	Dual 20" Linestops	LS	1	\$ 46,910.00	\$ 46,910.00
	<i>Equipment</i>				
	Excavator	LS	1	\$ 2,400.00	\$ 2,400.00
	Trench Safety Equipment	LS	1	\$ 2,400.00	\$ 2,400.00
	Compaction Equipment	LS	1	\$ 834.00	\$ 834.00
	<i>Material</i>				
	12" Valve with Appurtenances	LS	1	\$ 5,083.00	\$ 5,083.00
	Concrete thrust blocking	LS	1	\$ 1,200.00	\$ 1,200.00
	20" Valve and Accessories	LS	1	\$ 33,573.00	\$ 33,573.00

Project Inclusions:

Provide all labor, equipment, and material to replace 12" valve
 Install Double 20" Line Stops
 Install 20" Gate Valve
 Work in original scope

Project Exclusions:

Any Permit or Impact Fees
 Excavation deeper than 7'
 Sodding or seeding
 Erosion Control Plan or BMP's
 Liquidated Damages
 Bonding (Add 4%)
 De-Mobilization/Re-Mobilization
 Work not proposed on original scope

Total \$149,000.00

Quotation is valid for 31 days.



Prices are based on

Rangeline will NOT be responsible for any delays due to material shortages or changes

If concrete is required to be removed and replaced, additional cost will be added

Rangeline will provide all material, equipment, and labor to replace (1) 12" valve and appurtenances

Rangeline will install (1) Double 20" line stop to isolate the water and keep the booster pump station on line

Rangeline will also excavate leaking line that is connected to the 20" discharge line from booster pump station. If material is needed to repair leak additional charges will apply (COMPLETED)

Rangeline will contact Dig Test prior to excavating, Rangeline is not responsible for any unmarked lines

Rangeline will not be responsible for any delays due to mismarked utility lines or changes required due to unforeseen utility lines

Rangeline is providing this quote with the estimation that the line stops will be on the pipe for three days or less. If additional days are required due to unforeseen issues or changes, additional line stop charges will apply per day

Net 30 from invoice date

- Please allow **3-4 weeks'** notice for scheduling **after receipt of materials** to ensure availability. **Projects that require shorter lead times may incur additional charges.**
- If the type of pipe changes from what we have quoted above, prices and scheduling may vary. Contractor or Municipality is responsible for verifying the type of pipe and its O.D.
- Concrete Pressure Pipe materials are custom made. Once material order is placed, they are non-returnable.
- Rangeline may require a pre-construction meeting prior to scheduling any services.
- Price does not include "Sales Tax" on supplied material.
- Normal daytime hours (8:00AM- 5:00 PM) Monday through Friday. Technician(s) will have a \$350.00 per hour after hours charge. Additional Expenses will be charged at our cost plus 25%.
- Rangeline will allow (1) Mobilizations/De-Mobilizations to the jobsite for the excavation and construction equipment. Additional trips will be \$4,200.00 per trip.
- Rangeline will allow (1) Mobilizations/De-Mobilizations to the jobsite. Additional trips will be \$1,950.00 per trip.
- Canceling a scheduled project after the technician(s) have left the shop will result in a Cancellation Fee please refer to Terms and Conditions #13 (Page 4). This includes weather related cancellations.
- Stand-by charges will be billed at \$250.00 per hour / per technician during normal daytime hours and \$350.00 per hour / per technician during afterhours. For City/owner Delays
- Stand-by charges for equipment at \$1,250.00/per day. For City/owner Delays
- Any additional feet excavated after 7' is an additional \$1000.00 per foot charge

If you have any questions, please feel free to contact our sales team in your region listed below:

Operations Services Manager

Chris Campbell

940.600.3036

Chris.c@Rangeline.com

Customer
Signature _____

Rangeline
Signature Chris Campbell